


Building Material Catalog No. 102



OUR BINDING GUARANTEE

Every article in this Catalog is guaranteed BRAND NEW, of standard manufacture. Every grade, etc., is backed up by our \$2,000,000.00 guarantee to be exactly as represented or **MONEY REFUNDED**, plus *freight charges both ways at our expense.*

We ship direct from Chicago, from where freight rates are extremely low, all to your benefit.

You can come and inspect your material and see it loaded while you wait.

CAPITAL STOCK
AND SURPLUS
\$2,000,000.00

THE GREAT PRICE WRECKERS

CHICAGO HOUSE WRECKING CO

CHICAGO. U. S. A.

COPYRIGHT, 1913 BY CHICAGO HOUSE WRECKING CO

We Guarantee Prompt Shipment, Safe Delivery and Perfect Satisfaction

ENTIRE SATISFACTION. We guarantee absolute and complete satisfaction. There is no half way about this guarantee. Every purchase you make from us will be exactly as represented, and you will be satisfied in every way or we will make such just amends as are within our power.

NO MISREPRESENTATION. Our descriptions represent straight, honest facts. There is nothing colored about them. We are handling many lines of regular merchandise. Our business is of a varied character. It is necessary for us to give you descriptions in the coldest manner possible. We have no intention of overdrawn facts or playing upon your imagination.

YOUR MONEY REFUNDED. If you buy any Millwork from us and it is not satisfactory to you in every manner, we will either take back such merchandise and refund the full purchase price, or we will make satisfactory adjustments to you. We have faith in the honesty and integrity of our patrons and we will demonstrate it to your entire satisfaction. We will not, however, accept the return of material specially made to order.

CONFIDENCE. We want at all times to enjoy your fullest confidence, and we will gain it by giving you an honest, square deal. Bear that in mind always, and we are sure we will get to know one another much better.

FAIR TREATMENT. We aim to treat every man as though he was the only one we do business with. That is the relationship we are anxious to maintain at all times with you.

DON'T HESITATE. You can purchase with absolute confidence and without hesitation or fear, knowing full well that every dollar's worth of new goods shipped you is covered by a guarantee so binding that no possibility of evasion exists for us.

WRITE US. If upon receipt of your goods you find anything contrary to our representations or not satisfactory, don't get mad and imagine all sorts of things. May be an error has been made. If the fault was ours, we will make good at once. If it is necessary to return the articles, write us the facts in the case and we will furnish you with such necessary shipping instructions. Immediately upon receipt of the goods in question your money will be refunded in full, or the articles will be exchanged for you, subject to your pleasure in the matter.

Our Capital Stock is \$2,000,000.00

The CHICAGO HOUSE WRECKING CO., has a capital stock of two million dollars (\$2,000,000.). We are incorporated under the laws of the State of Illinois. This company has been in existence for over twenty years. Its responsibility is unquestioned.

Ask Any Commercial Agency—Ask Any Publisher of Any Paper Anywhere—Ask Any Bank or Banker—Ask Any Express Company

INDEX	
Adjustable Floor Scraper.....	82
Andirons.....	69
Ash Pit Doors, Iron.....	71
Ash Pit Trap.....	71
Asphalt Mineral Paint.....	140
Axes.....	140
Balusters, Porch.....	41
Barn and Cellar Sash.....	35
Barn Paint.....	84
Barn Siding.....	79
Base.....	44-46
Base Blocks.....	50
Basket Grates.....	71
Bathroom Outfits.....	97
Bath Tubs.....	97
Bed, Hot Sash.....	77
Bells, Electric.....	154
Bevel Siding.....	73
Bills, Stair.....	53, 54
Bin, Floor.....	37
Bits and Braces.....	141-142
Blinds, Outside.....	35
Blocks, Head, Base and Corner.....	53
Boards, Finishing.....	122
Bolts, Carriage.....	132
Bolts, Mixed.....	133
Book Case Columns.....	55
Boxes, Mitre.....	138
Brackets, Porch and Gable.....	41
Brushes.....	82-84
Building Plans.....	4, 5
Byrket's Patent Lath.....	81
Cabinets, Kitchen.....	158
Cabinets, Medicine.....	61
Carriage Bolts.....	132
Casing, Interior.....	44, 49
Ceilings—Metal.....	110
Ceilings—Wood.....	81
Cellar Frames.....	42
Cement Block Machines.....	123
Chandeliers, Gas and Electric.....	152
Chimney Flue Damper.....	71
China Closet Doors.....	60, 61
China Closets.....	143
Chisels.....	101
Closet Outfits.....	55-58
Columnnades.....	38-39
Colored Art Glass.....	40
Colonial Columns, Interior.....	40
Columns, Porch.....	40, 41
Consoles.....	30
Corner Blocks.....	50
Corner Sinks.....	100
Cottage Windows.....	32
Craftsmen.....	12-28
Cupboard Doors.....	37
Dampers, Flue.....	71
Door Screens.....	72
Door Trim, Interior.....	49
Doors.....	10-20
Doors, Cupboard and China Closet.....	37
Doors, Flush or Slab.....	10
Doors, Front.....	10-20
Doors, Glazed.....	11, 14, 16, 20-22
Doors, Hardwood, Panel.....	15
Doors, Iron Ash Pit.....	16
Doors, Mirror.....	22
Doors, Painted and Grained.....	22
Doors, Screen.....	72
Doors, Sliding.....	26

INDEX	
Doors, Soft Pine, Front.....	17, 18, 19
Doors, Store.....	28, 29
Doors, Storm.....	36
Doors, Veneered.....	10-16
Drawer Case.....	37
Drop Siding.....	79
Engines, Gasoline.....	160
Entrance Fronts.....	31
Eureka Plaster Board.....	74
Factory Flooring.....	80, 81
Fencing.....	154-157
Finish, Interior.....	44-50
Fire Doors.....	20, 21
Fire Place Fixtures.....	70, 71
Fire Flooring.....	80
Fire Lumber.....	78
Fixtures, Fire Place.....	70, 71
Flooring, All Kinds.....	80
Floor Paint.....	87
Floor Scraper, Adjustable.....	82
Flour Bin.....	37
Flue Damper.....	71
Frames, Cellar.....	42
Frames, Front Entrance.....	31
Frames, Outside.....	31, 42-43
Freight Information.....	8, 9
Front Doors.....	10-20
Front Entrance Frames.....	31
Front, Entrances.....	31
Fronts, Store.....	28, 29
Gable Brackets.....	41
Galvanized Conductors, Pipes, Gutters, Etc.....	115-116
Galvanized Metal Work.....	115-116
Gas and Electric Chandeliers.....	152, 153
Gas Logs.....	150
Gasoline Engines.....	71
Glass, Colored Art.....	38-39
Glass, Green House.....	77
Glass, Leaded.....	38, 39
Glass, Plate.....	23
Glass, Window.....	11, 14, 16, 20-22
Glass Doors.....	11, 14, 16, 20-22
Gold Medal Roofing.....	112
Grained Doors.....	22, 23
Grate Outfits.....	70-71
Grates, Basket.....	71
Green House Glass.....	77
Green House Material.....	77
Grilles.....	56-59
Hammers.....	137
Handles, Casters, Bolts.....	131
Hand Saws.....	136
Hangers.....	138
Hinges.....	15
Hardwood Flooring.....	81
Hatchets.....	137
Hay Carrier Outfits and Tools.....	150, 151
Head Blocks.....	50
Heating Plants.....	102
Hinges.....	12-28
Hooks.....	127
Hot Bed Sash and Glass.....	77
House Paint.....	36
Inside Door Jambes.....	26
Interior Casing.....	44, 49
Interior Mouldings.....	30
Jambes, Inside Door.....	26
Kitchen Cabinets.....	158
Kalsomine.....	92
Lamps, Incandescent.....	155

INDEX	
Lath, Plaster.....	81
Lap Siding.....	79
Lavatories.....	99
Leaded Glass.....	38-39
Lock Sets.....	124, 125
Logs, Gas.....	71
Lumber, Outside Finish.....	78
Machine Cement.....	123
Magic Wall Board.....	76
Mantel Shelves.....	69
Mantel Tile.....	69
Mantels, Wood.....	62-63
Medicine Cabinets, Built In.....	61
Metal Roofing.....	106-109
Metal Siding.....	106-109
Metal Work, Galvanized.....	115-116
Mineral Asphalt Paint.....	90
Mirror Doors.....	15
Mitre Boxes.....	138
Mixed Bolts.....	133
Mouldings, Interior.....	44-50
Mouldings, Outside.....	51
Nails, Wire.....	113
Newsels, Porch.....	52
Newsels, Stair.....	52
Ornamental Ceilings.....	110
Outfits, Bathroom.....	97
Outfits, Closet.....	101
Outfits, Grate.....	70-71
Outside Blinds.....	35
Outside Finish Lumber.....	78
Outside Frames.....	31, 42-43
Outside Mouldings.....	51
Paint, Barn.....	84
Paint, Floor.....	87
Paint, House.....	86
Paint, Mineral Asphalt.....	90
Patent Lath, Byrket's, Wood.....	81
Pipe.....	104
Plain Rail Windows.....	34, 35
Planes.....	139
Plans for Houses.....	4, 5
Plaster Boards.....	74, 75, 76
Plate Glass.....	28
Plate Rail.....	50
Plate Rail.....	50
Porch Columns and Newsels.....	40, 41
Porch Floor Paint.....	72
Porch Newsels.....	41
Porch Paint.....	87
Porch Railing and Balusters.....	105
Pump Outfits.....	105
Rafter Ends.....	41
Railing, Porch.....	41
Rail Plate.....	50
Rawhide Pebble Coat Roofing.....	113
Refrigerators.....	159
Roofing, Gold Medal.....	106-113
Roofing, Metal.....	106-109
Room Mouldings.....	45, 47
Roofing, Rawhide.....	111, 112, 113
Roofing, Rubber.....	111
Roofing, Sundries.....	114
Rubber Roofing.....	111
Rules.....	147
Sash, Barn and Cellar.....	35
Sash, Hot Bed.....	79
Sash, Stall.....	35

INDEX	
Sash, Storm.....	36
Sash, Transom and Attic.....	35
Saws, Hand.....	132
Screens, Door.....	72
Screen, Window.....	73
Sets, Lock.....	124, 125, 126
Sets, Tool.....	134, 135
Shades, Window.....	96
Sheathing Lath.....	81
Shelves, Mantel.....	69
Shingles.....	81
Shingle Stain.....	88
Side Boards, Built In.....	60, 61
Side Lights.....	27
Siding, Barn.....	79
Siding, Bevel.....	79
Siding, Drop.....	79
Siding, Lap.....	79
Siding, Metal.....	106-109
Siding, Novelty.....	79
Siding, Wood.....	79
Sinks.....	100
Sinks, Corner.....	100
Sink Trim Wood.....	50
Slate Mantel Tile.....	69
Slate Tile.....	69
Sliding Doors and Jambes.....	26
Spark Guard Wire for Fire Place.....	35
Special Windows.....	145
Squares.....	35
Stain Shingle.....	84
Stair Bills.....	53, 54
Stair Newsels, Rails and Balusters.....	52
Stair Treads and Risers.....	53
Stair Treads.....	35
Steel, Structural.....	119-122
Steel Troughs.....	117
Steel Work.....	119-122
Store Doors.....	28, 29
Store Fronts.....	28, 29
Storm Doors.....	36
Storm Sash.....	36
Structural Steel.....	119-122
Tile, Galvanized and Marbleized Slate.....	69
Tile, Slate Mantel.....	69
Tool Sets.....	134, 135
Transoms.....	35
Transom and Attic Sash.....	35
Trap, Ash Pit.....	71
Treads and Risers, Stair.....	53
Trim, Window.....	44-48
Troughs, Steel.....	117
Tubs, Bath.....	97
Varnishes.....	89
Veneered Doors.....	10-16
Wall Board.....	74-76
White Pine Flooring.....	80
Windows, Check-Rail.....	35
Windows, Cottage.....	32, 33
Window Glass.....	77
Windows, Plain Rail.....	34
Window Screen.....	73
Window Shades.....	35
Windows, Special.....	35
Window Trim.....	48
Wire and Fencing.....	156-157
Wire Nails.....	118
Wood Siding.....	79
Yellow Pine Flooring.....	80

PHENOMENAL GROWTH

CAUSED BY

Low Prices and Honest Representation

How We Became the Originators of Lowest Prices on Building Materials of Every Description. Tersely Told in the Following Paragraphs. Read it and Reap the Benefit of the Information.

LOW PRICES

Usually all concerns claim to have the lowest prices. Some will dwell on superior purchasing facilities of some sort or another, others will boldly assert that they control the source of supply, still others emphasize upon a highly organized sales system and a few of them just say their prices are lowest because they are the lowest.

This shows how easily claims can be made—on paper. Seldom are they backed by live, substantial proof and sound logical reasons.

WE ARE THE ORIGINATORS

Our past record is the best proof we can offer you as to our ability to maintain low prices and maintain quality simultaneously. Four and one-half years ago, we began selling New Mill Work and Lumber in a modest way. That was during the height of the late financial stringency. The opportunity was presented to us to become the owners of large stocks, through the inability of the manufacturers to realize on their holdings. We bought it—for spot cash. Their loss was your gain, and while we profited to some extent, you gained the most—not temporarily, but permanently—and for this reason.

These original large purchases formed the nucleus around which we have built our present enormous sales capacity, firmly establishing our entry in this special field on a broad scale. That introduced us to the building fraternity in general and to YOU, small home-builder in particular, as the originators of lowest prices on brand new modern Mill Work and straight, clean cut, first-class Lumber—all NEW.

BRIDGED THE DISTANCE

BETWEEN YOU AND HIGH PRICES

We could have asked much higher prices and still have allowed you a large saving over local dealers' prices who have not the resources at their command to compete with us in a buying capacity or we could have charged prices that some other competitive concerns charged who were then selling direct to consumers but such is not our policy. Every conservative business institution has to figure on a safe margin of profit to do business. We add our margin, but no more, whatever the original cost.

This explains that prior to the launching of our Lumber and Mill Work Department, your savings did not go very far towards the ownership of the coveted cottage or a sorely needed barn or corn crib. You were looking into the distant future. We bridged that distance between you and high prices, not only on Lumber and Mill Work but on all the rest of building materials required to complete your building operations, such as Hardware, Paints, Plumbing and Heating Goods, Furniture, etc., etc. Bargains on every page in this catalog. Consult them.

NOW IS THE TIME TO BUILD

If you have hesitated to begin building operations, we urge you not to delay any longer—for today is the day to buy Lumber and Mill Work. Our forest products are becoming less and less every year, and as quantity diminishes, the prices increase proportionately. This is the natural condition of things, solely governed by the law of supply and demand. Therefore, if you have any intentions of building at all or know of some friend

of yours, now is the time to build. Make up your list as soon as possible and send for our delivered prices. Never mind if the bill is not entirely complete; this can be adjusted later as you may wish to come and see us personally. To delay may not be exactly dangerous, but it might prove decidedly unprofitable to you. The bridge of low prices is still down—cross it while the chance is available. ■■■■

SOME OF OUR PRICES VERY LOW

In pursuance of our policy, only a certain safe percentage of profit added to the original cost will make it clear to you that you will find some of our Material Prices way down low and that some seem smaller than cost of production. Do not be persuaded that such items are below grade unless so described. You can depend upon our descriptions. And you can depend upon all Material as being of a quality brand new, spick and span. Some of these items reflect a saving of from 15 to 60 per cent, all depending upon where you are located.

TO THOSE WHO ARE IN DOUBT

Do not lend willing ears to others (at home or elsewhere), who would dissuade you from getting acquainted with us.

Some will do their level best to discourage you from even corresponding with us. They know that when we once make you prices, they will not be able to sell you. They will make statements contrary to every guarantee printed in this book, for no other reason than to get your order at their price and to maintain high prices continually. No statement too libelous, no method seems to be too low for some dealers and their associations.

We do not have to resort to such means to get our orders. Not one word will you hear from us against any other concern's material unless they have been trying to "do" us. Our proposition is simply good goods, honest grades, low prices, a fair and square deal, and it makes no difference to us whether you are an expert buyer or whether you do not know a thing about it, you can come and buy from us just as cheap. We have one Price, One Treatment and One Policy, which is fair and square to all.

A woman can come here and buy \$1.00 worth of material or a complete house or barn just as cheap as the expert and with a feeling of absolute safety. We have among our satisfied customers many women customers who, owing to circumstances, are compelled to transact their own business.

ENOUGH STOCK TO BUILD A CITY

While the secret of our growth is due largely to taking advantage of special closing out sales, enabling us to buy very much below regular market prices (because that is our long suit), the main reason of our success is owing to the fact that we maintain a larger stock than anyone else engaged in a similar line. When we tell you that we have piled at our 40 acre plant about 20 Million feet of lumber, you know that it is a large amount but when we tell you that this stock will build 2,000 average sized homes and barns, you will have a correct idea of its magnitude. Think of it!—Enough to build two good sized towns with churches and schools, and all complete.

You are neglecting the best opportunity of your life if you fail to promptly take advantage of our extremely low prices.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

We have consistently maintained our position far in the lead.

DO WE MAKE GOOD?

ASK OUR CUSTOMERS.

The following letters are published for the benefit of those who are in doubt as to whether the promises we make in our Catalog are over drawn or not. Read what they say. They speak for themselves. **THEY SPEAK MORE ELOQUENTLY** for us than we would dare speak for ourselves. We are thankful for such letters, as it shows us that our money-saving ability is appreciated by our customers. They are unsolicited and should convince you more than mere advertisements and statements made by would-be competitors to belittle our reputation.

WE HAVE THOUSANDS OF OTHER TESTIMONIALS and photographs and letters from customers who built with our material their own idea and who saved money on their purchases, and can show any customer any quantity of such photographs upon his personal visit to our Plant. We do not ask our customers for testimonials. We feel that every customer has a right to receive material as good better than represented, as well as courteous treatment, prompt shipment, and an immediate adjustment of any complaint. It is our aim to fill each and every order correctly. Every means is taken to prevent errors. Every effort is made to understand correctly a customer's wants.

NOTE.—We do not reproduce the Post Office address of the customers for the reason, first, to prevent unscrupulous would-be competitors and members of the various Lumber Trust Dealers Associations from writing anonymous letters, causing our customers a lot of unnecessary correspondence. Second, to protect our customers from the merely curious. To anyone showing sufficient interest and an honest intention to purchase, we will be pleased to furnish the Post-office addresses of any or all that may be requested.

SAVED \$500.

Chicago House Wrecking Co., Chicago, Illinois.

Dear Sirs:—Today I forward under separate cover, the photographs of my double houses that I built from your Plan No. 143 with variations I utilized the third floor for two sleeping chambers, giving five instead of three chambers to each house.

The Bill of Material was received in good condition. I find that there is a saving of **\$500.00 in a double house like I built** by getting the Material from you or getting the material in a retail way from local dealers also saves many delays and a big lot of worry and poor stock.

If I should build more houses, I shall certainly get the material from Chicago House Wrecking Co.

I wish you could inspect my houses personally; as I fell very proud of them.

Yours very truly,
(Signed), Moses H. Snavely.

BETTER THAN EXPECTED.

Gentlemen:—I received my carload of lumber No. 25484 in good condition and a far better grade of lumber than I expected and I am well satisfied. There have been some of my neighbors here and looked the lumber over and are well pleased with it. I will recommend your lumber to anyone I know who is going to build.

(Signed), Riley Merriman.

SAVED \$200 to \$300.

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—I have got my house ready for the plastering and will say that I am more than pleased with it and I am satisfied that I saved from **\$200 to \$300** by getting my lumber from your firm.

(Signed), Walter Huff.

BARN DESIGN No. 221.



was as you represented it. It was for barn design No. 221.

(Signed), JOHN E. RYLAND.

NOT A NAIL MISSING.

Chicago House Wrecking Co., Chicago, Ill.

Dear Sirs:—Please excuse my delay in writing you in regard to my shipment.

I received the goods last week and I want you to know that I am very pleased with same.

The order was so well filled that I honestly do not believe there was even one nail missing. The lumber was better than most anything I can get around here regardless of price. Also the goods arrived here on time right to the very hour. Now I will close so as not to take up any more of your time. I also wish to say that I think this order will make a pretty good ad around here.

I will send in another order in a few weeks.
Yours respectfully,
John A. Johnson.

"HALF PRICE."

Chicago House Wrecking Co., Chicago, Ill.

Dear Sirs:—I got my car of lumber sometime ago I had ten men to help me haul it and they all say they do not understand how you people can sell such good lumber for half the price that our home dealers ask for it. These men would ask me what I paid for this or that, in fact, I had to tell the price of everything, and when I did they started to laugh and just as much called me a liar, cause they claimed you could not sell lumber that cheap.

That ship lap I got of you is \$27.50 per thousand here, that quarter sawed flooring is \$45.00 per thousand here and so you see I got mine for half the price they ask here. That is what these fellows could not see. One of neighbors is going to build a barn next summer and by the way he talks now he will give you an order for lumber.

Yours truly,
(Signed), Ed. Beaumel.

SAVED 50 PER CENT.

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—The bill of lumber throughout was better than I expected. I shall advertise your lumber to all who intend building as I know they will get a square deal and save at least **50% on their bill**. The lumber you sent me was exactly what I ordered.

(Signed), A. F. Ferris.

"FAIRNESS AND GREAT SAVING."

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—The car of lumber or mill work, both of which I purchased from you arrived. Thanks for your promptness and careful attention of same.

Our dealer had a car right along side mine and unloaded at the same time. Well, gentlemen, you ought to have seen the expression on their faces—amusement. They could scarcely believe what they saw, and when I told them the prices they were dumb founded, while I was all smiles. The first of September my carpenter laid the sills, and such sills! He could scarcely believe it himself, and to work the lumber, he said was like eating pie.

You may use any part of this letter you choose or refer them to me and I will gladly tell all of your kind treatment and fairness and of your great saving to the working man that wants to build himself a home.

(Signed), FRANK J. DIXON.

HOUSE DESIGN No. 130.

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—The car of lumber No. 26,760, N. Y. C. & St. L. (House Design No. 130), arrived here May 12th, and would say as far as I have seen the lumber is **O. K.** I have not had time to check it up but will do so this week, but I do not expect to find any difference between the bill of lading and the bill of material. I saw the Oak trim, ordered special, and will say it is A No. 1.

(Signed), WM. E. CONLON.

SAVED \$1,000.

This customer Built Design No. 6.



Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—My house being completed, and am living in it, I take pleasure to inform you that it is one of the greatest houses in town. I have had over two hundred people side looking at this house. I have given a number your address. No doubt you have heard from some of them. If you have not already, you soon will. I have had men from three other towns looking at it and they all thank it **O. K.**

Everything arrived in good condition. Found everything alright. I saved on the building, including steam heat, and bath room outfit about **\$1,000** as this kind of lumber would be very difficult here. My house is open for inspection at all times.

(Signed), LEWIS YOUNG

SAVED \$100.

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—I received the car of lumber O. K. and everything was all right and came up to my expectations. I consider that you saved me better than **\$100.00** on the car.

Will you please see to it that the Blue Print that I ordered about three weeks ago, is sent forward soon as convenient.

Thanking you for your promptness, I remain
Respectfully yours, (Signed), Claud Smith

HOUSE DESIGN No. 154.



Chicago House Wrecking Co., Chicago, Ill.

Dear Sirs:—Two carloads of material for House Design No. 154, reached here in good condition last Monday morning. It created a great deal of interest in this part of the country being the first shipment of material for a house from the West in this locality. The material is first-class and the finishing material is beautiful all the way through. The contractor said he never had prettier dressed lumber.

You have filled the order with everything which could be desired toward the completion of the house and we find nothing missing and I wish to thank you for the pains you have taken in filling this order.

The contractor and myself will certainly give you a good recommendation. (Signed) Mrs. E. C. Gilman

HIS FOURTH HOUSE.

Chicago House Wrecking Co., Chicago, Ill.

Gentlemen:—Enclosed find order for my fourth house, and wish to say that I am well satisfied with Three already built. Having saved lots of money and find material of the best quality.

Thanking you for past favors, I remain,
A satisfied customer, Michael J. Nick.

TESTIMONIALS CONTINUED ON NEXT PAGE.

DO WE MAKE GOOD?

CONTINUED.

SAVED \$400 to \$500.

Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—Received the material which I telephoned you about also received the back order on my large estimate both arrived in good condition and the quality was of the best. I now have received everything which I ordered of you except the 4x7 rolling door and the nickel plated door set for the bathroom. I trust both will be along as soon as convenient.
I consider I have saved between **four and five hundred dollars by buying my "house"** from you people besides getting a better grade than I possibly could have gotten of my local dealer.
Cecil W. McAtee.

ALL MATERIAL ON HAND.

Chicago House Wrecking Co., Chicago, Ill.
Dear Sirs:—Have just moved in my new house (your design No. 145), built from your materials. I am more than pleased with the materials, and found it very convenient to **have all the material on the place at one time**, it saves time and money. I found your firm very prompt in delivering the goods, also in answering questions accurately. If I ever build another house I shall certainly get all my material from you and also the plans as my little home is so conveniently laid out.
Thanking you for your kind attention and promptness, I am,
Yours very truly,
(Signed), Mrs. Florence L. Young.

"MUCH BETTER THAN EXPECTED"



Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—Have received and unloaded House Design No. 157, now No. 41 and found everything in first-class shape. Not a thing broken or cracked. The lumber is **much better than expected** and the mill work and hardware O. K. Carpenters are rushing the work at present and will sure have it up. I think you will get more orders from here for a number of persons have looked at my place with good intentions and are very much pleased.
Will send you photo and letter to publish later.
Thanking you for past favors, I am sincerely,
(Signed), OTTO A. JENCKS.

MORE THAN SATISFIED.

Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—I would not like you to think that I am not satisfied with the material that I got from you, for I am more than satisfied, and I highly recommend you to everyone that talks about our new home. It takes the eye of everybody. Don't be worried about the putting up part of it for it is put up just as square and plump as any house ever was built. There was plenty of material for the house, nothing was short, for which I think you very much and whenever I can send you a new customer I will gladly do it.
Yours truly,
Wm. G. Hahn.

HOUSE DESIGN No. 138.



Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—Received the crown moulding all right. This now completes the order for **House Design No. 138**.
I wish to state for the benefit of those who contemplate ordering from your house, that I am more than pleased with the quality of the material you sent also with the liberal allowance, you made in sending enough to construct the design.
You are at perfect liberty to use my name if it will aid you any.
(Signed), A. A. CHESMAN.

NEVER BETTER MATERIAL.

Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—I have my House nearly completed and believe your Company is deserving of a word of credit for the treatment you have accorded me. I have built a more expensive house than this one, but in my opinion have never had a better selection of material used than that furnished by you for this House, and will say that everything has been very satisfactory in every respect and I can consistently recommend the Chicago House Wrecking Company to anyone who is anticipating the building of a new home.
I, furthermore, believe I have saved a considerable amount on my house by buying my material from you and if I can be of any further assistance to you, please call on me.
Yours truly,
(Signed), S. M. Scott.

HOUSE DESIGN No. 117.



Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—The car of lumber you sent me was delivered to me at Johnson Station last Saturday, and I had the lumber unloaded Monday and Tuesday, finishing late Tuesday evening.
In regard to the character of the lumber, I want to say to you that I am exceedingly well pleased and satisfied so far as I have been able to inspect it, and so is my carpenter, who, as I explained to you, is probably the best carpenter in the city, and a very good judge of lumber.
(Signed), JOS. H. JONES.

"FRAMES."

Chicago House Wrecking Co., Chicago, Ill.
Dear Sir:—Would say in reply to yours of the Fourth that I am well pleased so far with the material that I received from the House Wrecking Co., the frames were certainly fine stuff and they went together in fine shape. I will be pleased to speak a good word for you. Please make me a price on your best grade of window shades for our house.
Thanking you for past favors, I remain,
Very truly yours,
M. Bullock.

ALL GOOD, HONEST MATERIAL.

Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—I take great pleasure in answering this letter. I want to say you're the fairest and nicest Company to deal with that I ever had anything to do with, and that I appreciate it. I am very sorry that I mentioned not having found that Closet Seat for I have since dug it up. Everything is here to the letter, and all good honest material. I will have the house ready for plaster in another week. It is admired by all who see it and is without doubt an ideal home, good enough for anyone, and I know that I have saved a third of what it would have cost me here. I am,
Very truly yours,
(Signed), D. E. Noblic.

SQUARE DEAL.

Chicago House Wrecking Co., Chicago, Ill.
Dear Sirs:—We received the lumber Monday and have it all hauled. We found it all O. K. There were several parties at the car looking at the lumber, all said it was good lumber. We will order the other goods soon. Thanking you for a square deal, we remain,
Yours respectfully,
T. D. Coleman.

PLEASED WITH IT.

"In regard to your lumber which I received in February, 1911, would say that I am pleased with it and thank you for your prompt attention. Now I am in the market for more lumber."
P. J. Bauman.

HIS THIRD ORDER.

Chicago House Wrecking Co., Chicago, Ill.
Dear Sirs:—I am now building the third House that you have shipped here and I am expecting several more in the near future. I write you for a little information and all the Advertising matter you have to spare as I am having calls every day from people for miles around and I have to answer so many questions that I have to guess at a lot of them besides the Dealers would break my head if they dare.
Now this No. 6 is making a great hit here. The material is No. 1 and so far there is plenty (but none to waste).
In the two of No. 122 there was not one thing lacking; plenty of everything. Now as I am waiting your answer on No. 6 you will soon get another order, possibly two. Thanking you in advance, I remain yours,
A. D. Swick.

TWO HOUSE DESIGNS No. 156. "Business relations delightful."



Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—Everything in save the last small remnant, we have never had dealings with any firm, nor individual where more **perfect satisfaction** has been given. A delight it has been to have business relations with the Chicago House Wrecking Co. Every item of material is **first-class** for its kind or purpose. As soon as building is completed will be pleased to send you a photograph of same.
(Signed), M. S. BROWNE.

"MANTEL."

Chicago House Wrecking Co., Chicago, Ill.
"I bought Mantel No. 10-A-6984, quartered-sawn Oak with tile and grate, price, \$48.50, from you last year, and find it more than I expected. You shall hear from me soon on other orders."
P. J. Crowl.

MILL WORK.

Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—I will write you about the Mill Work you sent Mr. Glarmann. I will say that it is O. K. the best I have used in a long time, even thickness and good work, no waste in cutting to make shortage in estimate.
W. H. Hassler.

SAVED \$700.

Special design made to order for him.



Chicago House Wrecking Co., Chicago, Ill.
Gentlemen:—Enclosed please find proof of house and will send photograph of same as soon as I possibly can.
I will assure you gentlemen, that I am **perfectly satisfied** with all material sent me and that my house has got the best material in it of any on the street. I also wish to state if you have any inquiries from (—) about lumber or heating plants or plumbing, don't be a bit backward in referring them to me as I will do all in my power for the Chicago House Wrecking Co., for the reason that you have done all and if anything more than you agreed to do by me.
I also wish to state that I **saved on house**, seven hundred dollars (\$700.00), and also got better material and a **better house**.
(Signed), JOHN J. DUNN.



DESIGN NO. 163.

Design No. 163 is of the bungalow type, 26x26 feet square. 4 rooms with ample closet space on the first floor, 2 rooms, bath and 3 closets on the second. At the price we are selling the material it can be built for a home or for an investment that will net big returns.

We will furnish the material as explained in detail in our Plan Book for... **\$649.00**



DESIGN NO. 131.

A modern home, size 28x28 feet square, 7 foot porch across the entire front; den, vestibule, living room, dining room, kitchen, pantry and extra large closet on the first floor; 4 big bedrooms, bath and closets on the second. A solid, house, easily built and easily maintained. Investigate further by getting our Plan Book.

We will furnish the material as explained in detail in our Plan Book for... **\$950.00**



DESIGN NO. 6-A.

House Design No. 6-A—23 feet wide by 33 feet 3 inches long. This house has been built over 300 times. A full 2-story house, 7 rooms, bath, pantry, plenty of closet room. It is an ideal home, well lighted, handsome open stairway, cased openings, bay windows, spacious front porch, attractive from any point of view.

We furnish the material as explained in detail in our Plan Book for... **\$759.00**




DESIGN NO. 117.

Design No. 117 is a bungalow in every sense of the word, 6 rooms on one floor, size over all, 39 feet 6 inches wide by 27 feet deep. This is the Design that we built for our Exhibition Building at the Iowa State Fair. It has been built any number of times and is a source of satisfaction and pleasure to the owners, and will prove so to you if the Plan meets with your approval. Our Plan Book gives full details.

We will furnish the material as explained in detail in our Plan Book. for... **\$708.00**

A \$10,000.00



Get
This
Book
Today
ASK FOR
Plan Book
63 B. M.

We are originators of the most unique system of distributing broadcast, a **Modern Book of Plans**, free of charge. We are **pioneers**, were first in the field with our unparalleled system of selling complete Building Material Equipments for Residences, Barns, Hotels, Stores and other Buildings direct to the consumer at a "**one-small-profit**" price.

We have **spent a fortune** in perfecting our Plan Book. The result is the most practical and most accurate book of its kind—an **Ideal Book of Plans**. Our Designs are **so good** that they have been and will be copied, but they never were and **never** will be surpassed and if they are **equalled**, we will not be out-distanced in price of material, and if the price is met, we will out-shine all comers in quality, and if the quality is also maintained, **we can and will beat all others in service.**

We are, you might say, just about alone in the field of service because our Lumber Yards, our Millwork, and Warehouses are located **right here at Chicago** and not scattered hither and thither, everywhere and nowhere keeping you guessing where the material is coming from, and keeping you in suspense about when you are going to get it.

PRICES TRUSTWORTHY AND DEPENDABLE

Prices in our Plan Book are **reliable and fair**. As clearly stated, they are free on board cars, Chicago. If you take for granted that other Planbook quotations mean that the material will be shipped from wherever the offices of the parties issuing same are located you will not only be disappointed in service, but invariably will be subjected to **extra freight and handling expense.**

Can you afford to wait weeks and weeks for your lumber to come from some remote saw mill point? Think of how **inconvenient** it will be to have your order come stringing along in various shipments, Millwork from one place, Hardware from another, something else from somewhere else and the lumber—**THE LUMBER**, which is needed first—arriving after all the other material is on the ground.

In contrast to this state of affairs, **consider our straight-forward proposition.** We do not keep you in the dark regarding our supplies, removing any doubt which you may have about where the material is coming from and how it will be shipped and how long it will take to reach you. You simply must ignore all other proposals **and you will.**

COME AND SEE IT LOADED IN CHICAGO

The material for your Building will be loaded **right here in Chicago** at our 40 Acre Plant, located in the great Central Manufacturing District, where it can be **seen and inspected** under your own supervision, and from where practically **immediate** shipment can be effected.

Do you see the advantage we have? Of course you do.

4 In Working up our Plans, Nothing is Left to Guesswork.

**EXPERT
ESTIMATING**


**CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.**



DESIGN NO. 52-

Here is a perfect beauty of a bungalow, modern in every respect. It has been built again and again with great success and will make a beautiful appearance in any locality. It contains 6 rooms and bath all on one floor, ample room in the attic to finish off additional rooms. A modern City Apartment transformed into a Bungalow. It is a beauty. Our Plan Book gives more detailed information.

We will furnish the material as explained in detail in our Plan Book for... **\$864.00**



DESIGN NO. 152-D

Design 152-C is a class of building rapidly becoming into favor 28x28 Feet square, large living room extending the entire front with French doors, large dining room, kitchen and pantry, enclosed back porch. Second floor can be arranged for either 3 or 4 bedrooms, ample closets and bathroom. Interior can be arranged so as to make a most artistic home. Will furnish material **\$867.00** as explained in detail in our Plan Book for.....

PLAN BOOK FREE!

100 Practical Plans of Modern Houses and Barns

BY

Experienced Architects, Designers and Estimators. Free at Your Command

A GUARANTEE THAT IS A GUARANTEE

We absolutely **guarantee** the material to be **satisfactory** for every purpose specified, and guarantee to furnish every item in **sufficient quantities** to complete the job. We further guarantee that our designs are reliable—**true to detail**, strictly new and modern, conforming to straight and standard rules of construction, resulting in a substantial building in every sense of the word. Does this not make our guarantee **clear and binding** when we say that we unequivocally guarantee to supply sufficient material to complete your proposition according to our representations? Sufficient means **enough** and enough means a **finished** job. Is that not so?

FREE PLANS—AND THEY ARE FREE

Purchasers of our material will find that there is no string attached to our free plan offer and all our Plans are thoroughly practical, the houses having been built again and again **some over 300 times**. Plans are made by men of the widest experience, not alone along architectural lines, but in a contracting and manufacturing capacity as well; **men who have been on the job themselves**. Thus you get the benefit of **years and years** of practical experience in actual building construction. This combination of services is rarely available except at great expense. **We offer it free.**

SKETCH PLANS—PLANS TO ORDER

When you get our Book read our **FREE PLAN OFFER**, read our **SKETCH PLAN OFFER**, as well as our **PLANS MADE TO ORDER OFFER**. Our competent, progressive Architectural Department is ready to serve you in every way and in any and every kind of an architectural problem. **Test it.**

SUBMIT YOUR OWN IDEAS

If you don't find a plan in our book which suits you, send us your rough pencil plans. Our Architectural Department is ready to co-operate with you in developing your own ideas. Our **Guaranteed Material Specification Estimate** offer is something entirely new. It affords positive protection to the builder. We will name you a delivered price on all material furnish by us and **guarantee** sufficient quantities to complete the work. This is information on which you can absolutely depend and that is the kind of information you want when you are trying to find out how much it is going to cost you to build. **Submit Your Ideas.**



DESIGN NO. 50.

An excellent style of square house without bays' angles or unusual projections. Reception room, living room, dining room and kitchen, including pantry, coat closet on the first floor, 4 good sized bedrooms with airing balcony on the second floor also bathroom and ample closet space. A popular design, successfully built many times, and will prove a winner. We will furnish the material as explained in detail in our Plan Book for **\$998.00**



DESIGN NO. 145.

Our Design No. 145 is 21 feet 6 inches wide by 30 feet long, contains 7 rooms and bath. Modern in every respect. A practical, neat and substantial appearing house. Can be built nicely on a 25-foot lot. Will require little or no repairs. A very desirable Plan. The first floor has reception hall, parlor, dining room, kitchen and pantry. Second floor 3 good sized bedrooms with bath and closets. **\$739.00**

**10 to 20 Million
Feet in Stock.**

LUMBER

Order Direct From This Book.

Acres of Lumber for your Personal Inspection and Immediate Shipment. We have the Largest and Best Equipped "DIRECT TO THE CONSUMER" LUMBER YARD in the World. Located in the heart of the great Central Manufacturing District in the City of Chicago, from where hundreds of carloads of material are shipped every day in the year.

[illegible]

WHEN we make the above statement it is not someone else's Lumber Yard that we are talking about, nor is it someone else's Saw Mill Yard, but **our own**, right here in the heart of the great City of Chicago, where you can come and personally select your stock either before or at the time it is being loaded. We carry in stock at all times 10 to 20 million feet of all kinds of Building Lumber, which is ready for **immediate delivery** to our customers. There are no uncertain delays, no uncertain grades, and our stock consists of a complete line of various woods used for all kinds of building purposes, including finishing lumber, siding, flooring, etc., materials of Southern Pine, Northern Soft Pine, Cypress, Poplar, Spruce, Red Cedar, all kinds of flooring—Hard Pine and Oak, White Pine, Spruce, Fir, Maple, etc., etc.—in fact, we carry practically the most complete line of lumber of any Yard, and can meet the reasonable requirements of each and every customer in nearly any section of the United States.

See Our Prices in This Book

In this catalog we can only list a small part of our complete line, such as Flooring, Siding, Ceiling, Lath and Shingles. If you need a complete house or barn bill, then

Send Us at Once Your Order Complete Lumber Bill for Lowest Freight Prepaid Prices.

We guarantee grades, sizes, quality loading and safe arrival of material. We relieve you of all your worry. We aim to give you **unequalled service.**

On the back cover of this catalog we give you a few views of our Mammoth Lumber Yards. Come to Chicago and see for yourself. Our latch-string is always out.

Save Money

Hundreds upon hundreds of customers have purchased our lumber, built fine homes with it and, according to their own statements, have saved from 25 to 50 per cent. **Why not you? ACT TODAY.**

[illegible]

VALUABLE FACTS

INFORMATION ABOUT

FREIGHT, BREAKAGE, TERMS, ETC.

FREIGHT CHARGES

Freight charges are very reasonable on Mill Work whether shipped in small or large quantities. **Freight is the cheapest way of shipping material.** Do not listen to local prophets who claim to know everything about freight, etc. If you have any doubt whatever of what material will cost you delivered at your Station, write us, and we will name you a delivered price promptly, thus there will be no guess-work. If the order is only a small order, it will not be necessary for you to do this.

EXAMPLE

Here is an example of how cheap freight charges really are. Take for instance, the freight charges on 2 windows and 2 doors, weighing about 100 lbs. would be only 60c were they shipped all the way from Chicago to New York City which is nearly a thousand miles.

Our prices are so low that the matter of freight charges is offset at once. **Your local dealer must pay freight also, therefore any argument against high freight rates is knocked out.**

SHIPPING FACILITIES

Unlike practically all our competitors **we do not ship Mill Work from one locality and Lumber from another**, neither of the items coming from the Plant from which they are advertised, but on the contrary, **all our Mill Work and Lumber is shipped right from our Chicago Plant** where you can come and see the material loaded and inspect it while you wait and make your own selection. Chicago shipments not only give you the benefit of the very lowest freight charges, but **saves you making frequent trips to the Depots.** Carpenters and contractors who have suffered experiences of this sort will appreciate this information and act accordingly—if they are wise.

CAPACITY

We have a capacity of handling 50 carloads a day, thousands and thousands less than carload shipments, and where Mill Work is ordered to be shipped with lumber or in large quantities, we have the further advantage of being able to **include in the carload, hardware, paint, furniture, plumbing, heating, merchandise** of all kinds that we handle, so as to get the same rate of freight on all items taking the same classification as lumber and so that all your material will reach you in one car, in good condition and at one time. We have few direct factory shipments, practically the only items being mantles and fireplace fixtures and these are shipped direct from factory to the advantage of the customer as far as price is concerned.

RUSH ORDERS

SPECIAL attention will be paid to customers who **must** have their material shipped at once. Mention the date upon which you wish them and unless the material has to be made up of special stock, we will do **our level best** to see that the material is shipped **in the time specified** by you as we gain absolutely nothing by delaying your order a moment longer than is necessary or a moment longer than is desired by you and we **gain a whole lot** by shipping your order **when you want it**, and therefore we are **anxious** at all times to do the very best we can for you.

OUR EXTENSIVE LINE

While we list in this Mill Work Catalogue a **most complete line** of mill-work of every description, it does not cover by any means all the different kinds of material **that we can supply.** Practically all of the goods listed is **carried in stock**, and material to complete any average home can be selected therefrom without being **limited in choice** or confined to that sameness in style so **much seen** in other catalogues.

TO CARPENTERS AND BUILDERS

We solicit a thorough comparison of our **prices and qualities** by **YOU** who are thoroughly **posted** on values and prices. We have among our customers **many contractors, builders and carpenters** who purchase their own material and we aim to help such customers in every possible manner to transact their business with the **least possible worry**, trouble or delay of any kind and all we want is a **trial order** to prove this.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

SPECIAL OR ODD MILLWORK

While it is **to your interests** to confine your order in all cases to **regular stock** sizes as listed in this catalog sometimes special items cannot be avoided, **nor will we avoid them.** On the contrary we **welcome your request for prices on Specialties**, under the condition that you furnish us an **itemized list** showing just what **you will require**, so that we will have definite information to figure on, enabling us to base our figures right down to **rock-bottom** and thereby secure tangible **results.**

However, we cannot **save you as much money** as on **stock goods**, neither can we offer as **prompt shipments**, nor can anyone else. **Odd stuff** is odd stuff the **entire country** over, and it frequently happens that you have to pay **abnormal prices.** Our **protective price policy** shields you from such overcharges, for you can depend with **absolute safety** upon any **special price** that we quote, as being the lowest you can obtain special mill-work for, because we **understand millwork values** as well as some of the others and **better than most of the others.**

PLAIN PACKING-LABELS

We use plain labels on all our packages. Our name does not appear on same. It is no one's business but your own where your material comes from.

ABOUT BREAKAGE AND DAMAGE IN TRANSIT

Before giving a receipt to the Railroad Company for articles covered by our freight receipt please **examine** every package carefully. In case any articles are missing or broken, report the same to the freight agent before removing goods. When you pay the freight, **require the agent to note the extent of the damage** or of the missing articles on the face of the paid freight bill.

If you believe that an error has been made in weight as shown in the expense bill, ask the agent to weigh the goods, and if it is found that the shipment is billed overweight he will correct the error.

In case of breakage, shortage or overcharge make your claim on the Railroad Company **at once**, as you are the owner of the goods.

If you want us to make claim for you, mail us the **invoice and original paid freight bill**, showing the shortage or breakage noted on such bill. (Get the agent to give you a duplicate of such freight bill, which retain, in case original gets lost in mail.)

If you want to order of us parts to replace damaged goods, or shortage, please state with your order all particulars, and from which shipment, giving date and number of our invoice.

When we agree to **prepay freight**, and shipment arrives at your station with charges to collect, in order to avoid storage charges while corresponding, pay freight charges and return the freight receipt showing the amount paid, and on receipt of same we will send you a check without delay for the amount paid, and assume the claim against the Railroad Company for double collection.

TERMS

Our established terms are cash with order, and where it is at all convenient for a customer to remit in this way, it will mean a saving in time and expense to the customer, as there will be no C. O. D. collection or return charges to be taken care of. If, however, the customer does not feel safe in sending remittance in full, he may send 25% of the amount of order and material will be shipped C. O. D. for the balance. Where Mill Work or lumber is ordered in carload lots we will ship under our **"GUARANTEE PAYMENT SYSTEM"** without one cent down from customer and give him 5 days or more time in which to unload and inspect the stock. This method is **all that can be asked** by any fair-minded customer.

Send us a Trial Order. Let us Convince You.

Freight Charges on Millwork and Lumber are Low

VERY reasonable indeed are the freight rates on building material of every description, as **clearly explained** on this and next page, in easily read, and condensed form, so that any one, no matter where located, can figure very closely and prove to his own satisfaction that freight rates are nominal. As some articles are more costly than others, also as some require greater care in handling, the railroads naturally grade their charges accordingly so that a hundred pounds of common panel doors can be transported **cheaper** to most sections than a hundred pounds of glazed windows. Freight charges also **vary more or less**, depending upon the locality. For instance, common pine doors take fourth class to all points except Eastern territory on which third class rates apply. Therefore, the railroads issue from time to time what they call a tariff or freight classification from which we have compiled the following table, showing four different freight gradings or classes: **West, South, East and Illinois.**

FREIGHT CLASSIFICATION TABLE

ARTICLES	West	East	South	Illinois	ARTICLES	West	East	South	Illinois
Balusters and Spindles.....	3	2	4	4	Glass, boxed, common windows, Plain or colored in packages exceeding 86 United	1	3	3	3
Blinds.....	4	1	4	4	Inch measurements.....	1 1/2	2	1	1
Blocks for interior trim.....	3	3	4	4	Grille Work in white, unfinished.....	DI 1	1	1	1
Building Paper.....	3	3	5	4	Grille Work finished in Oil and varnished.....	2	3	2	2
Brackets (Wood for porches).....	1	2	4	3	Hardware.....	4	4	4	4
Byrkit's Patent Sheathing Lath.....	4	4	4	4	Lath, (Wood) for plaster.....	4	4	4	4
China Closets and Side Boards, Built in, not finished, set up in sections.....	DI 1	1	2	DI 1	Lumber, Common Finish.....	4	4	4	4
Colonade, (Wood).....	3	3	3	3	Mouldings Unfinished.....	3	4	4	4
Columns Built up or Solid.....	4	3	4	4	Nails.....	4	4	6	4
Door Frames K. D.....	3	4	4	4	Newels, porch and stairs.....	3	2	4	4
Doors Common Pine, Glazed Plain or figured glass, (Not Plate).....	3	1	3	4	Paint in cans.....	1	1	2	1
Doors Hard Wood, Glazed Plain or Figured Glass, (Not Plate).....	3	1	3	4	Paint in barrels.....	4	4	4	4
Doors Glazed Leaded Glass.....	DI 1	1	2	1	Porch Columns and Newels Built Up or Solid	4	3	4	4
Doors Glazed Plate Glass.....	1	1	2	4	Sash, glazed with common or plain glass.....	3	1	3	4
Doors Common Pine Paneled, also Sash					Sash Weights in bundles.....	4	4	6	4
Doors without glass.....	4	3	4	4	Screens for doors and windows.....	1	1	2	2
Flooring (Wood).....	4	4	4	4	Shingles (Wood).....	4	4	4	4
Floor Scraper, (Iron).....	1	2	3	2	Siding (Wood).....	4	4	4	4
Frames, Doors and Windows, K. D.....	3	3	4	4	Stair Rail and Porch Rail.....	3	2	4	4
Gable Ornaments (Wood).....	3	1	4	4	Wall Board:—				
Glass colored Enameled or Ground (Leaded)	2	1	3	1	Magic.....	4	3	4	4
Glass Plain or Colored—(Not Leaded) Under					Ceil-Tite.....	3	3	4	3
68 United Inches.....	4	3	3	4	Eureka.....	3	3	4	3
Glass Plain or Colored,—(Not Leaded) Under					Windows (See Sash).....	4	4	6	4
86 inches.....	2	3	3	4	Wire, Barb or Smooth.....	4	3	5	4
					Wire Fencing.....	3	4	5	3

Explanation of table and how to find freight rate to any point shown in rate table on next page.

- 1 denotes First Class.
- 2 denotes Second Class.
- 3 denotes Third Class.
- 4 denotes Fourth Class.
- 5 denotes Fifth Class.
- 6 denotes Sixth Class.

- 1 1/2 denotes 1 1/2 times First Class.
- DI denotes 2 times First Class.
- Note A. Not less than 75c.
- Note B. Not less than 50c.

WEST. The railroads running west, northwest and Southwest from Chicago, use the western classification. Use the classification in column marked "West" if you live in any of the following states: Arizona, Arkansas, California, Colorado, Idaho, Indian Territory, Iowa, Kansas, Louisiana, Minnesota, Missouri, Montana, Nebraska, Nevada, New Mexico, North Dakota, Oklahoma, Oregon, South Dakota, Texas, Utah, Washington, Wisconsin, Wyoming.

EAST. The railroads running east and northeast from Chicago, use the eastern classification. Use the classification in column marked "East" if you live in any of the following states: Connecticut, Delaware, Dis-

trict of Columbia, Indiana, Maryland, Maine, Massachusetts, Michigan, New Hampshire, New Jersey, New York, Ohio, Pennsylvania, Rhode Island, Vermont, Virginia, West Virginia.

SOUTH. The railroads running south and southeast from Chicago, use the southern classification. Use the classification in column marked "South" if you live in any of the following states: Alabama, Florida, Georgia, Kentucky, Mississippi, North Carolina, South Carolina, Tennessee.

ILLINOIS. If you live in Illinois use the column marked "Illinois."

EXAMPLE. Find the rate on two Pine Panel Doors weighing 75 lbs. and one glazed window weighing 25 lbs., making a combined weight of 100 lbs., to Rochester, N. Y., or nearby points. By turning to the **classification table** you will find common Pine Doors in the Eastern column (which column applies to **Rochester**) under the 3rd class and glazed sash in 1st class. Now, turn to the freight rate table on the next page, 1st class rate 56c and 3rd class 37c. By multiplying the number of pounds and the respective rates you arrive at the total of—41c.

NOTE That in all other localities doors are 4th class and that glazed sash in all other localities are rated lower than 1st class.

TABLE OF WEIGHTS

Balusters, porch per 100.....	80 lbs.
Balusters, Stairs per 100.....	120 lbs.
Base Blocks each.....	2 lbs.
Blinds per pair (Average).....	25 lbs.
Corner Blocks each.....	1 lb.
Brackets, porch each.....	1 1/2 lbs.
China Closet Door, glazed.....	25 lbs.
Columns 4x 4-8" each.....	20 lbs.
Columns 5x 5-9" each.....	30 lbs.
Columns 8x 8-8" each.....	32 lbs.
Columns 10x10-9" each.....	45 lbs.
Cupboard Doors (Average).....	18 lbs.
Doors Paneled 2/0x6/0-1 1/4".....	25 lbs.
Doors Paneled 2/6x6/6-1 1/4".....	30 lbs.
Doors Paneled 2/8x6/8-1 1/4".....	40 lbs.
Doors Paneled 3/0x7/0-1 1/4".....	55 lbs.

Doors Plain Glass (Average).....	60 lbs.
Doors Plate Glass (Average).....	100 lbs.
Doors Hardwood, will weigh 40 Per Cent more than Pine Doors.....	
Frames for Windows (Average).....	45 lbs.
Frames for Outside Doors (Average).....	60 lbs.
Frames for Inside Doors (Average).....	20 lbs.
Gable Ornaments.....	12 lbs.
Glass, Common S. S. per box.....	60 lbs.
Glass, Common D. S. per box.....	80 lbs.
Mouldings per 100 Lin. Ft.	
Up to 1 1/2" wide.....	15 lbs.
Up to 3" wide.....	40 lbs.
Up to 4" wide.....	60 lbs.
Up to 5" wide.....	75 lbs.
Up to 8" wide.....	125 lbs.

Porch Rail per foot.....	1 lb.
Sash, Barn or Cellar (Average).....	10 lbs.
Sash, Hotbed.....	30 lbs.
Spindles per 100.....	30 lbs.
Stair Rails per foot.....	2 lbs.
Storm Sash (Average).....	25 lbs.
Wall Board:—	
Magic—Per 100 sq. ft.....	100 lbs.
Ceil-Tite Per 100 sq. ft.....	80 lbs.
Eureka Per 100 sq. ft.....	140 lbs.
Windows—small size.....	20 lbs.
Windows—Medium Size.....	30 lbs.
Windows—Large.....	45 lbs.

8 Carload rates are still lower, most items Lumber and Millwork taking lowest class.

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Freight Rates to All States

SEE PREVIOUS PAGE FOR FULL EXPLANATION

From CHICAGO to	Min. Freight Charge	1st Class Freight per 100 lbs.	2d Class Freight per 100 lbs.	3d Class Freight per 100 lbs.	4th Class Freight per 100 lbs.	5th Class Freight per 100 lbs.	From CHICAGO to	Min. Freight Charge	1st Class Freight per 100 lbs.	2d Class Freight per 100 lbs.	3d Class Freight per 100 lbs.	4th Class Freight per 100 lbs.	5th Class Freight per 100 lbs.
ALABAMA							MISSOURI						
Birmingham	Note B	\$1.14	\$0.99	\$0.80	\$0.62	\$0.53	Chillicothe	.45	.80	.65	.45	.32	.27
Mobile	\$1.10	1.10	.90	.75	.58	.47	Independence	.45	.80	.65	.45	.32	.27
Montgomery	Note B	1.33	1.17	1.00	.77	.63	Kirksville	.40	.67	.55	.40	.27	.25
ARIZONA TER.							Saint Louis	.28	.43	.35	.28	.22	.18
Kingman	\$2.74	3.15	2.74	2.28	1.93	1.62	Sedalia	.42	.75	.61	.42	.29	.24
Tucson	2.51	2.90	2.51	2.09	1.75	1.47	MONTANA						
ARKANSAS							Benton	Note A	2.63	2.23	1.82	1.47	1.22
Arkansas City	Note A	1.30	1.09	.83	.64	.47	Helena	Note A	2.85	2.40	1.98	1.60	1.33
Jonesboro	Note B	1.31	.84	.66	.53	.39	Missoula	Note A	2.96	2.51	2.05	1.67	1.38
Texarkana	Note B	1.47	1.27	1.08	.86	.72	NEBRASKA						
CALIFORNIA							Alliance	1.25	1.81	1.58	1.25	.97	.81
Los Angeles	\$2.60	3.00	2.60	2.20	1.90	1.65	Broken Bow	1.02	1.51	1.29	1.02	.79	.68
Sacramento	2.60	3.00	2.60	2.20	1.90	1.65	Imperial	1.10	1.63	1.41	1.10	.85	.67
San Francisco	2.60	3.00	2.60	2.20	1.90	1.65	Lincoln	.49	.85	.70	.49	.36	.30
COLORADO							NEVADA						
Colorado Springs	1.10	1.80	1.45	1.10	.85	.67	NEW HAMPSHIRE	2.73	3.65	3.28	2.89	2.41	1.94
Grand Junction	2.20	3.20	2.70	2.20	1.60	1.27	Concord	.82	.82	.71	.55	.39	.33
Pueblo	1.10	1.80	1.45	1.10	.85	.67	NEW JERSEY						
CONNECTICUT							Belvidere	.75	.75	.65	.50	.35	.30
To all points	.82	.82	.71	.55	.39	.33	NEW MEXICO						
DELAWARE							Albuquerque	1.80	2.32	2.10	1.80	1.52	1.22
Dover	.75	.75	.65	.50	.35	.30	Roswell	1.47	2.02	1.80	1.47	1.29	1.03
D. C.							Santa Fe	1.80	2.32	2.10	1.80	1.52	1.22
Washington	.72	.72	.62	.47	.32	.27	NEW YORK						
FLORIDA							Albany	.72	.72	.62	.49	.32	.27
Jacksonville	Note A	1.30	1.10	.97	.85	.71	Buffalo	.45	.45	.39	.30	.21	.18
Miami	Note A	2.21	1.97	1.76	1.55	1.31	New York	.75	.75	.65	.50	.35	.30
Pensacola	\$1.10	1.10	.90	.75	.58	.47	Rochester	.56	.68	.58	.48	.37	.22
GEORGIA							Utica	.68	.68	.59	.45	.32	.27
Atlanta	Note A	1.33	1.17	1.00	.78	.65	NORTH CAROLINA						
Gainesville	Note A	1.47	1.35	1.06	.80	.66	Marion	Note A	1.51	1.32	1.08	.82	.68
Macon	Note A	1.38	1.20	1.03	.80	.67	Raleigh	Note A	1.28	1.09	.86	.62	.53
Savannah	Note A	1.30	1.10	.97	.85	.71	NORTH DAKOTA						
IDAHO							Bismarck	Note A	1.60	1.35	1.07	.76	.61
Boise	\$2.00	2.81	2.41	2.00	1.65	1.37	Fargo	Note B	1.17	.99	.77	.54	.42
Twin Falls	1.97	2.77	2.37	1.97	1.62	1.35	Minot	Note A	1.75	1.49	1.20	.89	.72
ILLINOIS							OHIO						
Bloomington	.25	.35	.27	.21	.17	.14	Bellefontaine	.37	.37	.32	.24	.16	.13
Danville	.25	.34	.27	.21	.17	.14	Cleveland	.41	.41	.35	.26	.18	.15
Decatur	.25	.38	.30	.23	.19	.15	Mansfield	.45	.45	.39	.30	.21	.18
Ealingham	.25	.39	.32	.24	.20	.16	Portsmouth	.45	.45	.39	.30	.21	.18
Galesburg	.25	.37	.30	.23	.19	.15	Toledo	.37	.37	.32	.24	.16	.13
Joliet	.25	.21	.17	.14	.11	.08	Youngstown	.44	.44	.38	.29	.19	.17
Mount Vernon	.28	.43	.35	.28	.22	.18	OKLAHOMA						
Ottawa	.25	.29	.24	.19	.14	.11	Guthrie	Note A	1.50	1.29	1.07	.87	.68
Peoria	.25	.37	.29	.22	.18	.15	Lawton	Note A	1.60	1.37	1.14	1.01	.80
Pontiac	.25	.30	.25	.20	.15	.12	Tulsa	Note A	1.35	1.20	.90	.70	.57
Rockford	.25	.29	.24	.20	.14	.11	OREGON						
Waukegan	.25	.21	.17	.14	.11	.08	Baker City	\$2.42	3.00	2.59	2.16	1.79	1.50
INDIANA							Salem	2.85	3.24	2.81	2.38	2.06	1.75
Bedford	.37	.37	.32	.24	.16	.14	PENNSYLVANIA						
Crawfordsville	.30	.30	.25	.20	.14	.11	Erie	.45	.45	.39	.30	.21	.18
Evansville	.40	.40	.34	.25	.17	.15	Harrisburg	.72	.72	.62	.47	.32	.27
Fort Wayne	.29	.29	.25	.20	.14	.11	Newcastle	.44	.44	.38	.29	.19	.17
Indianapolis	.32	.32	.27	.22	.14	.12	Pittsburg	.45	.45	.39	.30	.21	.18
Madison	.40	.40	.34	.25	.17	.15	Scranton	.73	.73	.63	.48	.33	.28
Richmond	.36	.36	.31	.23	.16	.13	RHODE ISLAND						
Terre Haute	.32	.32	.27	.22	.14	.12	Providence	.82	.82	.71	.55	.39	.33
IOWA							SOUTH CAROLINA						
Clinton	.25	.38	.30	.23	.19	.15	Charleston	Note A	1.30	1.10	.97	.85	.71
Dubuque	.25	.38	.31	.24	.19	.15	Sumter	Note A	1.49	1.30	1.06	.80	.65
Fort Dodge	.42	.72	.54	.42	.30	.20	SOUTH DAKOTA						
Muskogee	.25	.39	.31	.24	.19	.16	Alberda	\$0.67	1.14	.95	.67	.50	.37
Oskaloosa	.40	.60	.50	.40	.26	.21	Bellefourche	1.35	1.62	1.42	1.15	1.10	.87
Sioux City	.45	.80	.65	.45	.32	.27	Chamberlain	.80	1.22	1.02	.80	.55	.45
KANSAS							Milbank	.65	.94	.79	.65	.43	.35
Abilene	.83	1.31	1.11	.83	.62	.53	Mitchell	.67	1.05	.94	.67	.47	.37
Dodge City	1.10	1.67	1.43	1.10	.85	.67	Sioux Falls	.47	.83	.68	.47	.34	.28
Emporia	.73	1.24	1.00	.73	.55	.45	TENNESSEE						
Fort Scott	.35	.95	.81	.55	.37	.31	Fayetteville	Note B	1.23	1.08	.90	.73	.64
Independence	.80	1.21	1.03	.80	.57	.45	Jackson	\$1.03	1.03	.86	.73	.59	.46
Stockton	1.02	1.51	1.30	1.02	.81	.68	Memphis	.85	.85	.65	.55	.43	.37
Topeka	.64	1.09	.89	.64	.47	.37	Nashville	Note B	.73	.63	.50	.33	.31
KENTUCKY							TEXAS						
Cattlettsburg	.45	.45	.39	.30	.21	.18	Beaumont	Note A	1.67	1.45	1.16	1.06	.82
Frankfort	.65	.65	.52	.41	.31	.28	Dallas	Note A	1.67	1.45	1.16	1.06	.82
Hickman	.60	.60	.50	.40	.31	.27	El Paso	Note A	1.79	1.54	1.34	1.26	.93
Lotusville	.41	.41	.35	.26	.18	.16	Galveston	Note A	1.07	1.41	1.16	1.06	.82
Owensboro	.48	.48	.41	.30	.22	.18	Houston	Note A	1.67	1.41	1.16	1.06	.82
Richmond	Note A	.78	.67	.53	.40	.36	Livingston	Note A	1.67	1.41	1.16	1.06	.82
LOUISIANA							Paris	Note A	1.67	1.41	1.16	1.06	.82
New Orleans	1.10	1.10	.90	.75	.58	.47	San Diego	Note A	1.79	1.54	1.34	1.26	.95
MAINE							UTAH						
Bangor	.82	.82	.71	.55	.39	.33	Marysval	\$2.20	2.95	2.55	2.18	1.83	1.45
Machias	1.07	1.00	.86	.67	.49	.42	Salt Lake City	1.72	2.45	2.07	1.72	1.39	1.15
MARYLAND							VERMONT						
Baltimore	.72	.72	.62	.47	.32	.27	Newport	.82	.82	.71	.55	.39	.33
MASSACHUSETTS							VIRGINIA						
Boston	.82	.82	.71	.55	.39	.33	Charlottesville	.72	.72	.62	.47	.32	.27
MICHIGAN							Marion	.84	.84	.72	.55	.39	.33
Adrian	.35	.35	.30	.23	.15	.13	Richmond	.72	.72	.62	.47	.32	.27
Alpena	.53	.53	.45	.34	.26	.20	WASHINGTON						
Detroit	.37	.37	.32	.24	.16	.13	Spokane	2.57	3.00	2.51	2.09	1.75	1.47
Grand Rapids	.33	.33	.28	.22	.15	.12	Wenatche	2.72	3.07	2.66	2.21	1.86	1.57
Kalamazoo	.30	.30	.25	.21	.14	.11	WEST VIRGINIA						
Ludington	.47	.47	.41	.31	.23	.18	Charleston	.45	.45	.39	.30	.21	.18
Port Huron	.37	.37	.32	.24	.16	.13	Martinsburg	.72	.72	.62	.47	.32	.27
Saginaw	.37	.37	.32	.24	.16	.13	WISCONSIN						
Sault Ste. Marie	.48	.60	.50	.37	.28	.22	Ashland	.44	.65	.55	.44	.23	.22
MINNESOTA							Fond du Lac	.28	.40	.33	.28	.20	.15
Albert Lea	.40	.60	.50	.40	.25	.20	Madison	.26	.39	.34	.26	.18	.14
Duluth	.44	.65	.55	.44	.28	.22	Milwaukee	.25	.25	.20	.15	.12	.08
International Falls	.69	1.26	1.07	.85	.59	.46	Phillips	.42	.62	.52	.42	.26	.20
Marshall	.54	.77	.67	.54	.38	.29	Sheboygan	.27	.35	.31	.27	.19	.14
Minneapolis	.40	.60	.50	.40	.25	.20	Wausau	.33	.60	.42	.33	.23	.18
Red Wing	.40	.60	.50	.40	.25	.20	WYOMING						
Rochester	.37	.57	.47	.37	.24	.19	Cheyenne	1.10	1.80	1.45	1.10	.85	.67
MISSISSIPPI							New Castle	1.55	2.22	1.92	1.55	1.26	1.06
Jackson	1.18	1.18	.99	.80	.67	.56							
Vicksburg	1.10	1.10	.90	.75	.58	.47							
Winona	1.25	1.25	1.02	.81	.69	.57							

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

If in doubt, send your list for freight prepaid prices.

Modern Flush or Slab Doors


ORIGINAL

Safe, Sane and Sanitary

IMPOSING



TENNYSON



BRYANT



EMERSON

The Sanitary Door—The Door of The Future.

Nothing is so conducive to a pleasant and congenial home atmosphere as artistic harmonious surroundings and while many of the comparatively better class of home-loving folks have learned to arrange successfully the furniture details and garden spots, very few homes there are where the important feature of the **doors, windows and other items of building equipment** has not been neglected. Since the greater majority are not placed in position to acquire the requisite information, it is not due entirely to lack of artistic temperament, but rather because the selection has been made **haphazard** and in many cases left to others, who were either uninterested or not sufficiently familiar with the subject to produce the desired genteel elite effect—subservient to **good taste**.

The "**Tennyson**" should be used mainly as a front door. The "**Bryant**" makes a perfect match for the vestibule but may also be used as a front door. The "**Emerson**" would naturally be used as an interior door exclusively.

Flush doors have a perfectly plain surface, hence the commercial term "**Flush Door**." They present a smooth, even exterior and interior—gathering no dust or dirt, in short—make the **ideal sanitary door**.

The "**Emerson**" door claims exclusive title as the "**Slab Door**", so called because it portrays, to all superficial appearance, nothing but a slab cut from a beautifully grained log, but revealing upon closer inspection the **handicraft of master workmen**, improving upon the work of nature through the stages of evolution aided by modern machinery and labor-saving equipment.

PRICES OF TENNYSON

1 1/2 Inch Thick SIZES				Red Oak		Northern Birch	
Width		Height		10-G-207 Glazed Clear D.S.A.	10-G-213 Glazed Bevel Plate	10-G-239 Glazed Clear D.S.A.	10-G-250 Glazed Bevel Plate
Ft.	In.	Ft.	In.				
2	8	6	8	\$ 9.30	\$10.40	\$8.77	\$ 9.97
2	10	6	10	9.80	10.60	9.37	10.17
2	8	7	0	9.65	10.44	9.22	10.01
2	10	7	0	10.00	10.87	9.57	10.47
3	0	7	0	10.37	11.15	9.94	10.72

PRICES OF BRYANT

1 1/2 Inch Thick SIZES				Red Oak		Northern Birch	
Width		Height		10-G-226 Glazed Clear D.S.A.	10-G-227 Glazed Bevel Plate	10-G-228 Glazed Clear D.S.A.	10-G-229 Glazed Bevel Plate
Ft.	In.	Ft.	In.				
2	8	6	8	\$8.50	\$10.53	\$8.09	\$10.13
2	10	6	10	8.98	11.16	8.56	10.74
2	8	7	0	8.84	11.00	8.44	10.60
3	0	7	0	9.52	12.02	9.10	11.62

PRICES OF EMERSON

1 1/2 Inch Thick SIZES				Red Oak	Yellow Pine	North' Birch
Width		Height		10-G-234	10-G-235	10-G-236
Ft.	In.	Ft.	In.			
2	0	6	8	\$4.98	\$4.65	\$4.66
2	2	6	8	5.22	4.78	4.76
2	4	6	8	5.28	4.93	4.95
2	6	6	8	5.50	5.07	5.05
2	8	6	8	5.70	5.29	5.31
2	10	6	8	5.98	5.42	5.41
2	0	7	0	5.22	4.71	4.73
2	2	7	0	5.49	5.08	5.10
2	4	7	0	5.72	5.21	5.19
2	6	7	0	6.21	5.43	5.45
2	8	7	0	6.50	5.57	5.54
2	10	7	0	6.78	5.71	5.75
3	0	7	0			

For 50c extra per door we will apply one coat of filler.
DON'T STORE IN DAMP PLACE

The veneering process of our Flush Doors is so **unusual**, so different from other methods, that it produces a door **much stronger** than an ordinary solid paneled door—a door which cannot warp. The regular veneered doors are made 3 ply whereas the **Flush Doors** are made 5 ply, that is, besides the center core or base it contains a **double layer** of veneer on both sides of the core, the inner layer running crosswise, the core itself being thus protected in **double fashion**, making it impossible for the door to swell, shrink, crack or warp. This is the **only safe way** to make a **Flush Door**, so that we can without fear **guarantee** them to give absolute satisfaction, providing the usual care is taken when installing them. Doors should be given a coat of "filler" immediately upon receipt of same.

Mission Style Hardwood Doors

PERMANENT

Modern Doors at Moderate Prices

DISTINCTIVE



RUBENS



POE



DUMAS

Our "Mission" and other Veneered Hardwood Doors shown in this book—representing as they truly do—the highest type of Modern Door Making, are handled at our plant with greater care than seems necessary and they should receive equal care at your hands. If they are put into the building during cold, damp or rainy weather, there is a chance that the pores of the wood will absorb more or less moisture. A safe precaution is to give them a coat of filler upon arrival and paint top and bottom edges. While this will close the pores, they should not be placed into the building until the plastered side walls and ceilings are thoroughly dry. Artificial heat should be used to dry out the building whenever possible, no matter at what time of the year. You cannot be too particular in this respect with any Veneered Door, no matter from whom you buy. But we can give you positive assurance that if properly handled, i. e., if our instructions are followed, our doors will prove to give better satisfaction, both as to wearing qualities and appearance. You will neither be disappointed with the quality nor the price paid, and our prices are as low as this high standard can be purchased for.

PRICES OF "RUBENS."

1 3/4-inch thick.	Red Oak	Red Oak	Northern Birch	Northern Birch
SIZES.	10-E-240	10-E-241	10-E-242	10-E-243
Width. Height	Glazed	Glazed	Glazed	Glazed
Ft. In. Ft. In.	Plain D.S.A.	Bevel Plate.	Plain D.S.A.	Bevel Plate.
2- 8 x 6-8	\$8.72	\$11.51	\$8.29	\$11.08
2- 8 x 7-0	9.01	11.94	8.58	11.52
2-10 x 7-0	9.15	12.37	8.73	11.95
3- 0 x 7-0	9.44	12.58	9.02	12.15

PRICES OF "POE"

PRICES OF "DUMAS"

1 3/4 in. thickness	Red Oak	Northern Birch	Red Oak	Northern Birch
SIZES.	10-E-246	10-E-247	10-E-248	10-E-249
Width. Height.				
Ft. In. Ft. In.				
2- 0 x 6-0	\$4.36	\$3.93	\$4.50	\$4.07
2- 0 x 6-6	4.43	4.00	4.58	4.15
2- 4 x 6-6	4.72	4.29	4.86	4.43
2- 6 x 6-6	4.79	4.36	4.93	4.50
2- 0 x 6-8	4.43	4.00	4.58	4.15
2- 2 x 6-8	4.65	4.22	4.79	4.36
2- 4 x 6-8	4.79	4.36	4.93	4.50
2- 6 x 6-8	5.01	4.58	5.15	4.72
2- 8 x 6-8	5.22	4.79	5.36	4.93
2-10 x 6-8	5.51	5.08	5.65	5.22
2- 0 x 7-0	4.50	4.07	4.65	4.22
2- 4 x 7-0	5.01	4.58	5.15	4.72
2- 6 x 7-0	5.22	4.79	5.36	4.93
2- 8 x 7-0	5.51	5.08	5.65	5.22
2-10 x 7-0	5.72	5.29	5.86	5.43
3- 0 x 7-0	6.01	5.58	6.15	5.72

FOR 1 3/8 INCH THICKNESS DEDUCT
20c PER DOOR

Hardwood Front and Bungalow Doors

EXCLUSIVE

Uncommon Doors at Common Prices

PRE-EMINENT

Our **Hardwood Veneered Doors** are of better than standard construction. The **core** or inside is interlocked with "**Dove-tailed**" joints, impossible to come apart after they are once locked. The **3 ply panels** are so constructed that the grain of the wood in the inner section runs in opposite direction to the outer layers.

The "**Mozart**" and "**Gladstone**" Doors make very neat and substantial front doors and are especially desirable where one does not want the full length glass effect and at the same time retain the benefit of plenty of light.


The panel effect in both "**Mozart**" and "**Gladstone**" is somewhat unusual—different from the ordinary paneled front doors on account of the wide embossed moulding.

The "**Rembrandt**" Door is quoted with clear double strength "**A**" glass clear Beveled Plate and with **colored art**. The color scheme combines an **artist's selection** of variegated Cathedral, Iridescent and Opalescent blending. No one else has anything like it, regardless of price.


"Rembrandt" Makes a Very Appropriate Front Door in Bungalows.



MOZART



GLADSTONE



REMBRANDT

Veneered Red Oak and Northern Birch, 1 3/4 Inch Thick.

1 3/4 Inch Thick.		PRICES OF "MOZART"				PRICES OF "GLADSTONE"				PRICES OF "REMBRANDT"					
		Red Oak		Northern Birch		Red Oak		Northern Birch		Red Oak		Northern Birch			
		10-E-264		10-E-268		10-G-283		10-G-284		10-E-275		10-E-277		10-E-278	
		Glazed	Clear	Glazed	Clear	Glazed	Clear	Glazed	Clear	Glazed	Clear	Glazed	Clear	Glazed	Clear
Width.	Height.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.	D. S. A.	Bevel Plate.
Ft. In.	Ft. In.														
2-8	6-8	\$7.44	\$11.46	\$6.94	\$10.95	\$11.44	\$12.68	\$11.01	\$12.25	\$12.30	\$6.36	\$8.94	\$12.60	\$6.56	\$9.19
2-10	6-10	7.72	12.44	7.22	11.94	11.57	14.60	11.13	14.17
2-8	7-0	7.65	12.08	7.15	11.58	11.65	14.22	11.22	13.79
2-10	7-0	7.79	12.65	7.29	12.15	11.80	15.03	11.37	14.59
3-0	7-0	7.94	13.23	7.45	12.73	12.23	15.58	11.81	15.15	14.65	7.45	10.75	14.95	7.65	11.00

Only sizes listed carried in stock—Prices on other sizes on application.

12 When you Paint, remember our fine line of Paints, Oils, Stains and Varnishes.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Hardwood Front Doors


ENDURING

A Beautiful Front Door Reflects The Owners Good Taste

IMPRESSIVE

The designs of Hardwood Front Doors adorning this page are not overdrawn, that is, they are as near the original product as pictures can make them true to detail. Regular flat sawed veneers could not produce the flaky, curly grain. The improved rotary cut process employed by us makes the ordinary Birch resemble very closely the higher priced curly birch. In Oak Doors, most people would prefer this method of veneering to the finest quarter-sawed oak. But this is not the only modern improvement which distinguishes our doors from the common variety. They show an absence of that sameness in style and shape so much seen in other doors of a similar line. They are


different. **That's it.** Built different and built better. While this important feature makes our doors more valuable and worth at least 25 per cent more than the usual rotary veneered doors, our prices are actually on par and even lower than the cream of the others can be bought for. For this reason, we do not depend upon descriptive wording or pictures to sell our doors (the flower of the door makers craft), but our ability to undersell is only another illustration of this company's progressiveness, for no one would dare to offer doors of this character at such extremely low figures. **You have the opportunity to take advantage of a great bargain—grasp it.**



SHAKESPEARE



AMERICAN BEAUTY



MORNING GLORY

Veneered Red Oak and Northern Birch, 1 3/4 Inch Thick

1 3/4 Inch Thick	PRICES OF "SHAKESPEARE"				PRICES OF "AMERICAN BEAUTY"				PRICES OF "MORNING GLORY"			
	Red Oak.		Northern Birch.		Red Oak.		Northern Birch.		Red Oak.		Northern Birch.	
	No. 10-G-217 Glazed Clear D. S. A.	No. 10-G-218 Glazed Beveled Plate	No. 10-G-219 Glazed Clear D. S. A.	No. 10-G-220 Glazed Beveled Plate	No. 10-E-1 Glazed Clear D. S. A.	No. 10-G-3 Glazed Beveled Plate	No. 10-E-251 Glazed Clear D. S. A.	No. 10-E-253 Glazed Beveled Plate	No. 10-E-4 Glazed Clear D. S. A.	No. 10-E-6 Glazed Beveled Plate	No. 10-E-263 Glazed Clear D. S. A.	No. 10-E-265 Glazed Beveled Plate
SIZES Width, Ft. In. Height, Ft. In.												
2'-8" x 6'-8"	\$9.87	\$16.08	\$9.37	\$16.57	\$6.58	\$ 9.50	\$6.83	\$11.95	\$10.65	\$14.87	\$10.95	\$15.10
2'-10" x 6'-10"	10.15	17.61	9.65	17.10	7.08	10.75	7.33	12.90	11.25	16.09	12.00	16.50
2'-8" x 7'-0"	10.00	17.30	9.50	16.80	6.94	11.25	7.19	12.95	11.15	15.89	11.50	16.40
2'-10" x 7'-0"	10.22	17.66	9.72	17.16	7.15	11.65	7.40	13.30	11.30	16.23	11.60	16.53
3'-0" x 7'-0"	10.37	17.88	9.88	17.38	7.29	11.73	7.54	13.95	11.77	17.07	12.00	17.30

Only sizes listed are carried in stock. Prices on other sizes quoted upon application.

Hardwood Front and Vestibule Doors

EXPRESSIVE

SATISFYING

Incomparable in Quality

"Quality and Style" is expressive of all our Veneered Hardwood Doors, plus harmony. This truth is again exemplified in the designs shown here.


Read on previous pages how well all our Hardwood Veneer Doors are built. **None more lasting.**

To those preferring a medium size glass effect for a front door, our "Wagner" design satisfies this preference.

The Milton Door, used for the vestibule or side entrance, matches the "Wagner" front door to good effect.

The "Burns" Door is used mainly for vestibule and rear door purposes. May be utilized as a low priced front door glazed with bevel plate. It is also listed with plain D. S. glass. Makes a fine bathroom door if glazed "florentine."

Your attention is directed to the large built-up 3-ply panel in both the "Milton" and "Wagner" Doors, also the ornamental apron underneath the glass and heavy molded cap over the large glass "Wagner" Door displays a genuine wood carving. Thus we always supply more than full value.



MILTON



BURNS



WAGNER

Veneered Red Oak and Northern Birch, 1 3/4 Inch Thick

1 3/4-inch thick SIZES Width Height Ft. In. Ft. In.	PRICES OF "MILTON"				PRICES OF "BURNS"				PRICES OF "WAGNER"			
	Red Oak		Northern Birch		Red Oak		Northern Birch		Red Oak		Northern Birch	
	10-G-252 Glazed Clear D. S. A.	10-G-254 Glazed Bevel Plate	10-G-256 Glazed Clear D. S. A.	10-G-258 Glazed Bevel Plate	10-E-269 Glazed Clear D. S. A.	10-E-270 Glazed Bevel Plate	10-E-271 Glazed Clear D. S. A.	10-E-273 Glazed Bevel Plate	10-G-260 Glazed Clear D. S. A.	10-G-262 Glazed Bevel Plate	10-G-274 Glazed Clear D. S. A.	10-G-299 Glazed Bevel Plate
2-6 x 6-6					\$5.38	\$ 8.00	\$4.88	\$7.50				
2-8 x 6-8	\$7.00	\$8.79	\$6.57	\$8.36	5.43	8.15	4.93	7.66	\$8.44	\$11.44	\$8.01	\$11.01
2-10 x 6-10	7.29	9.30	6.86	8.87					8.72	12.16	8.29	11.73
2-8 x 7-0	7.58	9.44	7.15	9.00	6.08	8.65	5.58	8.16	9.01	12.58	8.58	12.15
2-10 x 7-0	7.87	9.65	7.44	9.22	6.29	9.15	5.79	6.66	9.30	12.87	8.87	12.44
3-0 x 7-0	8.15	10.01	7.72	9.58	6.51	10.08	6.01	9.58	9.72	13.16	9.29	12.73

Only sizes listed carried in stock. Other sizes—Prices upon application. "Burns" Doors furnished Glazed with Florentine glass at 10% extra over price of plain D. S. A. glass.

14 When you paint, remember our fine line of Paint, Oils, Stains and Varnishes.

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Hardwood Panel Doors

GENTEEL

Beautify and Harmonize the Interior

HIGH-CLASS

Modern Interior Doors are an important adjunct to the well appointed home and should harmonize with the exterior, especially with the front door. A perfect match can be made by the wide variety we offer. Have no fear that the large panels will warp out of shape **because there is no warp in their shape.** These panels are laminated, that is, built up from several layers of veneer and core, the grain of the cores running in opposite directions. Thus one layer counteracts the working of the other layer next to it and the result is a continuous, straight non-warping panel. This is true of the stiles and rails also, except they being heavier, the inner layer or core is very much thicker.

Only the highest grade of workmanship enters into the construction of a¹ our hardwood Doors, are as beautifully flaked and figured as the front doors therefore, not only will permit the finishing in the natural wood alone, but they can be stained to imitate practically any of the higher priced woods, such as Mahogany, Cherry, Rosewood and Walnut. Also to resemble very closely forest-green, mission or weathered oak. The Birch Doors being naturally very close grained, will take the finest egg-shell and white enamel finish.


Our prices are low. Crated securely, we guarantee them to reach you in the same perfect condition as they leave the factory. **Depend on it.**



"ELITE"



"ROSELAND"



"KENWOOD"

Veneered Red Oak and Northern Birch

Be Sure to State Thickness SIZES.		PRICE OF "ELITE DOORS"				PRICE OF "ROSELAND DOORS"				"KENWOOD"	
		Ven. Pl. Red Oak.		Ven. Nor. Birch.		Ven. Pl. Red Oak		Ven. Nor. Birch		Ven. Oak	Ven.N.B.
		No. 10-E-9		No. 10-E-10		No. 10-E-7		No. 10-E-8		No. 10-E-335	No. 10-E-336
		1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.	1 1/2-inch thick.
2'-0" x 6'-0"		\$4.00				\$3.42		\$2.76		\$4.82	\$3.93
2'-0" x 6'-6"		4.36				3.80				5.14	4.17
2'-4" x 6'-6"		4.39						\$3.09		5.15	4.21
2'-6" x 6'-6"		4.43		\$3.69		3.85		3.12		5.18	4.25
2'-0" x 6'-8"		4.44				3.88				5.16	4.18
2'-2" x 6'-8"		4.48								5.19	4.24
2'-4" x 6'-8"		4.49		3.71				3.14		5.22	4.26
2'-6" x 6'-8"		4.52		3.75		3.93		3.18		5.26	4.28
2'-8" x 6'-8"		4.55	\$5.07	3.79	\$4.37	3.97	4.54	3.20	\$3.77	5.28	4.32
2'-10" x 6'-10"		5.27	5.84	4.35	4.92	4.69	5.26	3.78	4.38	6.01	4.89
2'-0" x 7'-0"		5.05				4.44				5.68	4.60
2'-2" x 7'-0"		5.08		4.19							
2'-4" x 7'-0"		5.11		4.20		4.52		3.63		5.72	4.64
2'-6" x 7'-0"		5.12	\$5.67	4.23	4.81	4.53	5.10	3.65	4.22	5.75	4.68
2'-8" x 7'-0"		5.21	5.77	4.33	4.91	4.63	5.20	3.74	4.31	5.83	4.72
2'-10" x 7'-0"		5.25	5.81	4.41	4.98	4.67	5.24		4.40	5.95	4.80
3'-0" x 7'-0"			6.10		5.15	4.96	5.53		4.58	6.12	4.97

Only the sizes listed are carried in stock. Prices on other sizes upon application.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

A Heating Plant for Every Home.

Our Low Prices Grant This Boom to All.

15

Important

It is not necessary that birch trim be used with birch doors, if you intend to use a modern Mission stain, because our yellow pine trim can be harmonized perfectly with the birch, bringing out the natural grain and obtaining a uniform color combination.

A great many of our customers are changing their original plans, as far as the first floor is concerned, by using these low priced birch doors and yellow pine trim and none of our customers who have made this change, have regretted the expenditure of this small additional cost, nor will you.

Bevel or Plain Mirror Doors

Veneered Red Oak—Northern Birch—Soft Pine

See Yourself as Others See You

Full length Mirror Doors can no longer be considered a luxury since we are offering them at a price so reasonable that practically the humblest citizen can afford its conveniences. While primarily an article of feminine utility the men folks will recognize and appreciate its advantages over a short mirror and will not begrudge its low cost, since it combines the useful purpose of both door and wall mirror at a lower price and reduces danger of breakage.

You probably have never looked at the matter in this light, so if your means do not permit the purchase of a console by all means secure the same actual service in our Mirror Door. You have plenty of choice as to sizes, thicknesses of wood, two thicknesses and both plain and Beveled Plate Mirror. Naturally you will want your mirror door in your dressing room and as a closet door it will serve the double purpose admirably.

Our mirrors are of the regular standard American Beauty grade—noted for their high luster and lasting qualities. The mirror side of the door is finished as shown in the picture. The other side is regularly finished flush like "Emerson" door. Can also be furnished one or two panels. Our Mirror Doors are packed so well that they can be marred in transit under ordinary handling conditions.

1 3/8-inch Thick SIZES		PRICES OF "FULLVIEW" MIRROR DOOR							
		Red Oak		Northern Birch		Soft Pine		Size of Mirror	
		10-E-289 Plain Plate Mirror	10-E-290 Bevel Plate Mirror	10-E-291 Plain Plate Mirror	10-E-292 Bevel Plate Mirror	10-E-293 Plain Plate Mirror	10-E-294 Bevel Plate Mirror		
Width Ft. In.	Height Ft. In.								
2'-0" x 6'-6"	14" x 60"	\$10.08	\$11.73	\$ 9.83	\$11.48	\$ 9.78	\$11.48		
2'-2" x 6'-6"	16" x 60"	10.87	12.01	10.62	11.76	10.58	11.76		
2'-4" x 6'-6"	18" x 60"	12.00	13.23	11.75	12.98	11.70	12.98		
2'-6" x 6'-6"	20" x 60"	13.15	14.16	12.90	13.91	12.85	13.91		
2'-0" x 6'-8"	14" x 62"	10.30	12.02	10.05	11.77	10.00	11.77		
2'-2" x 6'-8"	16" x 62"	11.08	12.37	10.83	12.12	10.78	12.12		
2'-4" x 6'-8"	18" x 62"	12.38	13.59	12.13	13.34	12.08	13.34		
2'-6" x 6'-8"	20" x 62"	13.51	14.51	13.26	14.26	13.21	14.26		
2'-0" x 7'-0"	14" x 66"	10.94	12.44	10.69	12.19	10.64	12.19		
2'-2" x 7'-0"	16" x 66"	11.65	13.08	11.40	12.83	11.35	12.83		
2'-4" x 7'-0"	18" x 66"	13.16	14.30	12.91	14.05	12.86	14.05		
2'-6" x 7'-0"	20" x 66"	14.17	15.44	13.92	15.19	13.87	15.19		
2'-8" x 7'-0"	22" x 66"	15.45	17.02	15.20	16.77	15.15	16.77		

Any of the above sizes furnished 1 3/4-inch thick, 50 cents extra. Write for prices on other woods.

Make Your Own Mirror Door

Spare Time Made Profitable

Our Complete Outfit for a home made mirror door consists of heavy plate mirror; thin strips to form a bed between the face of the door and the glass; mouldings of special design to frame the mirror and hold it firmly in place; and a sufficient number of round-headed brass screws.

Prices Mirror Door Outfit No. 10-G-500

Size of Mirror	Plain Plate	Beveled 1 1/2-inch	Fits Common Panel Door
16" x 60"	\$ 6.20	\$ 7.40	2'-0" x 6'-0"
16" x 66"	6.70	8.25	2'-0" x 6'-6"
20" x 66"	8.45	9.90	2'-4" x 6'-6"
22" x 66"	9.85	11.30	2'-6" x 6'-6"
16" x 68"	6.90	8.50	2'-0" x 6'-8"
20" x 68"	8.65	10.10	2'-4" x 6'-8"
22" x 68"	10.00	11.80	2'-6" x 6'-8"
24" x 68"	10.95	12.65	2'-8" x 6'-8"
16" x 72"	7.25	9.10	2'-0" x 7'-0"
20" x 72"	8.90	10.85	2'-4" x 7'-0"
22" x 72"	10.70	12.50	2'-6" x 7'-0"
24" x 72"	11.55	13.45	2'-8" x 7'-0"

Order by No. 10-G-500

How to Order Take the measurement of your door just outside of the paneled part, allowing at least one-half inch all around for the mirror to rest upon. Then select your size from the accompanying table. In ordering, be sure and specify whether plain or beveled plate mirror is desired and state your preference in mouldings—Yellow Pine, Oak or Birch (if no preference is given, Yellow Pine will be furnished).

The Mirror, Mouldings, Strips and Screws will come in one box, carefully wrapped and packed to insure against damage in shipment.

Instructions Any door of the ordinary kind can be made into a mirror door in a jiffy and you can do the work yourself. **First:** Take the door off the hinges and lay it flat on the floor or on trestles. **Second:** Place the thin strips evenly on the face of the door and lay the mirror on top. **Third:** Screw the mouldings into place. (The mouldings are already fitted and mitred.) Presto: A real mirror door, just as good for all practical purposes as if you had bought a new one. (Note:—The outer edges of the moulding and strips used for backing should be exactly even to obtain the best results.)

Modern High Grade Front Doors

"The Soft Pine Front Door—The People's Choice"

NO HIGHER GRADE MADE

NONE MORE UP-TO-DATE

Our fine line of **Soft Pine Front Doors** cannot be equalled for durability and wearing qualities. Weather defying in the **greatest** possible measure, you cannot possibly get greater **money measure**. Of solid, substantial construction, they resist the element's powers of destruction.

You want a door that is **strictly first-class**, a door that not only will class first at the start in the **highest rank**, but a door that will be in the race to the last, a door on which you can **bank**.

If you are a judge of **door value** you know that our doors represent **more value** than the price we ask. Having studied the door question ourselves from all sides and angles, the question remains with **you**, not whether you should buy **this** door or whether you should buy **that** door, but rather whether you should buy a **good** door. You have the pictures of such doors before you, **actual photographs**.


A Higher Grade Door at a lower Grade Price.
You cannot make a mistake, whatever your choice—you will choose a **good door—at a low price.**



CHRYSANTHEMUM



ORANGE BLOSSOM



MAGNOLIA

Clear and Clean---First quality Soft Pine---Suitable for oil finish.


1½-inch Thick. SIZES.		CHRYSANTHEMUM.			ORANGE BLOSSOM.		MAGNOLIA.		
Width Ft. In.	Height Ft. In.	10-E-237. Glazed Lace as shown.	10-E-230. Glazed Clear D. S. A.	10-E-231. Glazed Beveled Plate.	10-E-13. Glazed Clear D. S. A.	10-E-14. Glazed Beveled Plate.	10-E-238 Glazed Lace as Shown	10-E-232. Glazed Clear D. S. A.	10-E-233. Glazed Beveled Plate.
2-8x	6-8	\$5.26	\$4.41	\$10.18	\$7.64	\$13.40	\$4.25	\$3.75	\$8.60
2-10x	6-10	5.86	5.04	11.54	8.27	14.77	4.80	4.30	10.00
2-8x	7-0	5.95	5.05	11.10	8.33	14.36	4.95	4.45	10.00
3-0x	7-0	6.22	5.42	12.69	8.60	15.98	5.25	4.75	10.90

Any door on this page furnished 1½ inches thick \$1.35 Extra.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Our Catalog contains nearly 1000 pages. Send for it.

Durable Front Doors—Wonderful Values




First Quality Clear Soft Pine

Always in the lead. We are showing some front doors on this page with **entirely new** glass effects not listed heretofore by us or anyone else. **Quality has been strictly maintained**, and comparison will reveal the fact that our prices must be considered extremely low, but if you will just bear in mind the fact we guarantee the **soft pine Front Door** to be equal or better in grade to any others that are offered on the market, you will know that for **one low price** you are buying quality, originality and durability.

"**RADIANCE**" is sold in leaded glass, as shown, of crystal clearness, also with one solid glass bevel plate and leaded bevel plate as shown in design. It is impossible here to show the colors in our "**SUNSET**" Door, but rest assured the design selected is most pleasing, a harmonious blending of various shades typical of a sunset scene.

1 1/4-inch door, \$1.35 extra.



SNOW FLAKE

10-G-315	10-G-316
Glazed	Glazed
Plain	Lace
Glass	Design
D. S. A.	as Shown
\$3.56	\$4.37
3.70	4.43
4.28	4.96
4.52	5.33
4.73	5.51

SUNSET

10-G-320	10-G-321	10-G-322
Glazed	Glazed	Glazed
Colored	Plain	Bevel
Art	Glass	Plate
	1 Light	1 Light
\$7.05	\$3.83	\$6.02
7.59	3.89	6.36
8.84	4.55	8.05
8.48	4.50	7.18
9.75	4.74	8.75

1 1/4 Inches Thick

SIZES


Width	Height
Ft. In.	Ft. In.
2 — 6 x	6 — 6
2 — 8 x	6 — 8
2 — 10 x	6 — 10
2 — 8 x	7 — 0
3 — 0 x	7 — 0

RADIANCE

10-G-317	10-G-318	10-G-319
Glazed	Glazed	Glazed
Leaded	Bevel	Leaded
Crystal	Plate	Beveled
D. S. A.	1 Light	Plate
\$5.65	\$6.26	\$9.61
6.13	7.41	11.33
7.20	8.68	12.66
7.29	8.72	12.76
7.98	9.72	14.05

DEWDROP

10-G-323	10-G-324
Glazed	Glazed
Plain	Lace
Glass	Design
D. S. A.	as Shown
\$4.08	\$5.03
4.13	5.26
4.80	5.71
4.75	5.66
5.25	6.26



First Quality Soft Clear Pine

Here is portrayed a quartet of door values not to be excelled in quality and impossible to match in price. "Goldenrod" with oval glass, glazed plain, as illustrated or beveled plate is a decorative addition to any residence. Our "Honeysuckle" door is a plain design, well built to support the full length glass. "Holly" has a long glass with artistic moulding all around and will be quite appropriate for some styles of houses. Look at the picture of our "Pond Lily" door and consider the remarkable bargain we offer. A very pretty little water scene is depicted in the glass design shown in illustration.

Taking quality and price into consideration, we are confident that this page of door values cannot be duplicated. Will take any kind of finish—oil, paint or enamel.

For any door on this page,
1 1/4 inch thick, add \$1.35



GOLDENROD

10-G-17	10-G-18	10-G-19
Glazed	Glazed	Glazed
Plain	as	Beveled
D. S. A.	Shown	Plate
\$4.95	\$5.45	\$7.36
5.16	5.66	7.87
5.73	6.25	8.44
5.87	6.40	9.15
6.15	6.70	10.69

HONEYSUCKLE

10-G-15	10-G-16
Glazed	Glazed
Plain	Beveled
D. S. A.	Plate
\$4.41	\$10.18
5.04	11.54
5.05	11.10
5.42	12.69

1 1/4 Inches Thick

SIZES

Width	Height
Ft. In.	Ft. In.
2 — 6 x	6 — 6
2 — 8 x	6 — 8
2 — 10 x	6 — 10
2 — 8 x	7 — 0
3 — 0 x	7 — 0

HOLLY LACE

10-G-23	10-G-24	10-G-27
Glazed	Glazed	Glazed
Plain	as	Beveled
D. S. A.	Shown	Plate
\$3.35	\$4.10	\$8.08
3.52	4.25	8.79
4.10	4.88	10.15
4.10	4.89	10.02
4.30	5.02	11.15

POND LILY

10-G-356	10-G-357
Glazed	Glazed
Plain	as
D. S. A.	Shown
\$2.89	\$3.29
3.06	3.50
3.58	4.00
3.59	4.01
3.76	4.22

Highest Quality—Artistic Front Doors—Lowest Prices



LAUREL

10-G-347 Glazed Lace Design As shown	10-G-348 Glazed Plain D. S. A.
\$6.26	\$5.66
6.58	5.79
7.09	6.45
7.14	6.43
7.83	6.95



POSY

10-E-358 Glazed Clear D. S. A.	10-E-359 Glazed as shown
\$3.50	\$3.95
3.65	4.08
4.08	4.55
4.20	4.62
4.36	4.80

First Quality Clear Soft Pine

We have made it a point to show a large variety of Front Door designs so that there may be freedom of choice in addition to relief from high prices and buyers will have so many styles from which to choose that no difficulty will be experienced in picking out one or more suitable designs.

Our "Mignonette" is a plain, cross-paneled door with an almost square light of glass. "Posy" design is ornamented by mouldings and carvings. Our "Laurel" door is an unusual value; glazed with long oval glass, combination scenic and lace effect. A heavy, raised panels surrounds it. This is strictly a door of merit and at our price a great bargain. Many will be attracted by the beautiful "Rosebud" design with its artistic Battenburg lace glass, very intricate and exclusive.

We are justly proud of our ability to offer these door values to the home builders of this country.

"A" grade doors can be finished in any manner desired.



MIGNONETTE

10-E-32 Glazed Clear D. S. A.	10-E-33 Glazed as shown
\$2.50	\$2.75
2.60	2.90
3.15	3.30
3.15	3.30
3.25	3.50



ROSEBUD

10-G-363 Glazed Lace Design As shown	10-G-364 Glazed Beveled Plate
\$6.31	\$8.18
6.63	9.48
7.15	10.32
7.19	10.00
7.88	11.65

Prices for 1 3/8-inch Thick

SIZES			
Width	Height	Width	Height
Ft.	In.	Ft.	In.
2'	6"	x	6' 6"
2'	8"	x	6' 8"
2'	10"	x	6' 10"
2'	8"	x	7' 0"
3'	0"	x	7' 0"



FORGET-ME-NOT

10-E-34 Glazed Clear D. S. A.	10-E-35 Glazed as shown
\$3.45	\$3.85
3.60	4.02
4.40	4.59
4.30	4.59
4.60	4.78



LARKSPUR

10-G-373 Glazed Lace Design As shown	10-G-374 Glazed Plain D. S. A.
\$4.27	\$3.46
4.33	3.60
4.86	4.18
5.23	4.42
5.41	4.63

Artistic Front Doors


First Quality Clear Soft Pine

Others may show these designs and some may be able to duplicate the price, but none can meet us in design, quality and price at the same time. These doors are strictly "A" quality by which term is meant the highest grade. They are well manufactured in every respect, made by skilled workmen with the aid of the latest improved machinery.

"Forget-me-not design has been sold by us for several years and has proved very popular. It is well adapted to plain, unpretentious little cottages. "Larkspur" door is more decorative, having a strand of carving under the glass and a neat, panel arrangement. Our "Tulip" and "Violet" designs are quite plain and free from ornamentation. This is where real character tells. Our plainest doors are so perfectly constructed and accurately proportioned that the high quality is readily apparent.

These doors will take any kind of finish—oil, paint or enamel.

For any door on this page
1 3/8-inch thick add \$1.35



TULIP

10-E-40 Glazed Clear D. S. A.	10-E-388 Glazed Chipped or Frosted glass
\$3.10	\$3.50
3.25	3.70
3.82	4.25
3.82	4.25
4.02	4.50



VIOLET

10-E-36 Glazed Clear D. S. A.	10-E-37 Glazed Flower design As shown
\$2.65	\$2.80
2.85	2.95
3.20	3.40
3.20	3.40
3.50	3.60

Prices for 1 3/8-inch Thick


SIZES			
Width	Height	Width	Height
Ft.	In.	Ft.	In.
2'	6"	x	6' 6"
2'	8"	x	6' 8"
2'	10"	x	6' 10"
2'	8"	x	7' 0"
3'	0"	x	7' 0"

Front Doors Made From The Mighty Fir

Monarch of All Western Woods

Before this Pacific Coast product was considered a desirable commodity for the finer grades of workmanship this firm strong Fir-wood had been successfully exploited for many other purposes, was for many years the mainstay of the bridge, ship and wharf builders. Giant timbers were used in immense quantities. Fir Porch Columns are so well known that further comment is a waste of space.


And during all this time only the rich and well-to-do could afford to pay the price of Eastern Hardwoods, leaving the modest home builder out in the cold. But "Progress" never slumbers long and so it is our pleasure to offer every one a share in our good fortune, since it is demonstrated that this choice soft grained wood is well suited to the finest kinds of interior work, principally Doors and interior Casings, Base, etc., and the supply is almost inexhaustible, vast acres of forests being as yet untouched to this day.



WASHINGTON



OREGON



PACIFIC

HARDWOOD VALUE AT SOFT WOOD INVESTMENT

Practically all known hard woods can be successfully imitated with Fir, through the use of our various shades of stain and oils. For further particulars in regard to staining effects read page showing slash grain Fir trim, page —. All made from firm first class Lumber, A-No. 1, strictly Clear stock.

1 3/8-inch thick SIZES Width Ft. In. Height Ft. In.	PRICE "WASHINGTON"			PRICE "OREGON"			PRICE "PACIFIC"		
	10-G-378 Glazed Plain Glass D. S. A.	10-G-379 Glazed Bevel Plate Glass	10-G-380 Lace Like Rosebud Door	10-G-381 Glazed Plain Glass D. S. A.	10-G-382 Glazed Bevel Plate Glass	10-G-383 Lace Like Larkspur Door	10-G-390 Glazed Plain Glass D. S. A.	10-G-391 Glazed Bevel Plate Glass	10-G-392 Lace Like Rosebud Door
2'-6" x 6'-6"	\$4.05	\$9.00	\$4.55	\$3.35	\$6.70	\$3.85	\$5.65	\$9.45	\$6.15
2'-8" x 6'-8"	4.30	10.05	4.85	3.65	7.45	4.40	5.90	10.30	6.45
2'-10" x 6'-10"	5.05	11.30	5.70	4.25	8.55	4.90	6.65	11.50	7.30
2'-8" x 7'-0"	5.00	11.20	5.60	4.15	8.25	4.75	6.55	11.05	7.15
2'-10" x 7'-0"	4.73	9.25	5.50	7.35	12.05	8.10
3'-0" x 7'-0"	5.35	12.30	6.05	4.70	9.40	5.40	7.00	12.60	7.70
2'-8" x 7'-6"	5.80	12.45	7.60	12.50	...

Sizes listed and not priced cannot be furnished. Can furnish "Washington" Door 3'6" x 7'0" 1 3/8" thick, glazed plain D. S. A. at \$7.90 and Glazed Bevel Plate at \$16.25. All doors priced can be furnished 1 3/4 inches thick at \$1.25 extra, over price of 1 3/8 inch.

Slash Grain Fir Interior Doors

Crowning Achievement of Doormaking. Straight Grain Stiles and Rails—Beautiful Slash Grain Panels

Nearly all sections of the **Fir** lumber region produce about the same variety of **Fir** and if any certain brand is more adaptable to the door maker's craft than another, the species known as **DOUGLAS FIR** captures the crown.


OUR FIR DOORS are made with straight grain stiles and rails (best for strength) and with slash grain panels (preferred for beauty) thus forming that rare combination of **Power and Style**. Straight grain resists all warping and twisting tendencies. Panels in the land 2 panel doors being laminated or "built-up" prevents them from shrinkage and curling out of shape, because the built-up process of three layers with the grain running in opposite directions which cannot help but keep them straight. Panels in the 5 Cross Panel Doors are thick **solid raised** panels, **not flat** as shown in picture.



OLYMPIA



SEATTLE



PORTLAND

Reproductions on this page were taken after the doors were treated with Mahogany stain, bringing out the tiniest curls of the slash grain in the panels, blending gracefully with the soft tones of the straight wood stiles. Fir Doors being finished in this manner, show up to much better advantage than if varnished natural. **All first quality, A-No. 1, Clear Stock.**

PRICE "OLYMPIA" DOORS					PRICE "SEATTLE"				PRICES "PORTLAND" DOORS—RAISED PANELS									
SIZES			No. 10-G-327		No. 10-G-326		SIZES		No. 10-G-325		SIZES			No. 10-G-325—Con't'd				
Width	Height		Thickness		Thickness		Width	Height	Thickness		Width	Height		Thickness		Width	Height	
Ft. In.	Ft. In.		1 3/8"	1 3/4"	1 3/8"	1 3/4"	Ft. In.	Ft. In.	1 3/8"	1 3/4"	Ft. In.	Ft. In.		1 3/8"	1 3/4"	Ft. In.	Ft. In.	
2'-0"	x 6'-0"		\$2.16	\$...	\$1.84	\$...	2'-0"	x 6'-0"	\$1.76	\$...	3'-0"	x 6'-8"		\$...	\$3.78			
2'-0"	x 6'-6"		2.41	2.05	2'-2"	x 6'-0"	1.99	2'-0"	x 6'-10"		2.32			
2'-4"	x 6'-6"		2.42	2.06	2'-4"	x 6'-0"	2.00	2'-6"	x 6'-10"		2.33			
2'-6"	x 6'-6"		2.45	2.08	2'-6"	x 6'-0"	2.06	2'-8"	x 6'-10"		2.37			
2'-0"	x 6'-8"		2.47	2.11	2'-4"	x 6'-4"	1.95	2'-10"	x 6'-10"		2.43	3.58			
2'-4"	x 6'-8"		2.48	2.12	2'-0"	x 6'-6"	1.95	2'-0"	x 7'-0"		2.34			
2'-6"	x 6'-8"		2.50	2.13	2'-2"	x 6'-6"	1.96	2'-2"	x 7'-0"		2.35			
2'-8"	x 6'-8"		2.52	3.67	2.15	3.13	2'-4"	x 6'-6"	1.97	2'-6"	x 7'-0"		2.36	3.43			
2'-0"	x 6'-10"		2.84	2.43	2'-6"	x 6'-6"	2.01	2'-8"	x 7'-0"		2.40	3.52			
2'-10"	x 6'-10"		2.99	4.37	2.55	3.72	2'-10"	x 6'-6"	3.56	2'-10"	x 7'-0"		2.48	3.64			
2'-0"	x 7'-0"		2.86	2.44	3'-0"	x 6'-6"	3.79	3'-0"	x 7'-0"		2.59	3.80			
2'-6"	x 7'-0"		2.88	4.21	2.46	3.59	2'-0"	x 6'-8"	2.02	2'-6"	x 7'-6"		2.87	4.21			
2'-8"	x 7'-0"		2.95	4.32	2.53	3.68	2'-4"	x 6'-8"	2.03	2'-8"	x 7'-6"		2.99	4.40			
3'-0"	x 7'-0"		3.17	4.64	2.69	3.96	2'-6"	x 6'-8"	2.04	3'-0"	x 7'-6"		4.83			
2'-6"	x 7'-6"		5.17	4.40	2'-8"	x 6'-8"	2.05	2.99	2'-6"	x 8'-0"		3.26	4.80			
3'-0"	x 7'-6"		5.92	5.04	2'-10"	x 6'-8"	2.44	3.57	3'-0"	x 8'-0"		5.45			

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Fancy figured Fir Interior trim to match the Doors. See following pages.

PAINTED

Sash Doors

GRAINED



"Poppy"

"Dandelion"

Painted a High Gloss Finish, or Grained Imitation Quarter- Sawed Oak

First class material is the only kind that should be used in a door to be finished in the usual way—that is to say, natural—oil, stain or varnish. Sound, second-grade lumber is all right for door manufacture if the defects are properly covered up as in our painted and grained doors shown here. The process we use in finishing these doors is the best known to the trade and the coating that is applied can be guaranteed to last as long as the door itself. Our painted doors are given a high gloss finish and our grained doors are a close imitation of quarter-sawed oak. Painted doors are recommended only in cheap houses. A grained sash door answers the purpose quite satisfactorily as a rear outside door in even a high class residence.

Note.—These doors are not second hand doors repainted, but made from bright new lumber, manufactured alongside our A quality doors, guaranteed to prove as strong and lasting as any other new painted and grained doors, no matter by whom made or sold.

The flowered glass is as carefully worked and shaded as the other sand-blast patterns shown in the A Quality doors. The glass is set in the doors with the same care. Nothing has been slighted to cheapen the cost and they are offered to you at almost cost.



"Buttercup"

"POPPY"				"DANDELION"				1½-inch thick. SIZES. Width. Height. Ft. In. Ft. In.	"BUTTERCUP"			
Painted.		Grained.		Painted.		Grained.			Painted.		Grained.	
No. 10-E-429 Glazed Clear Glass.	No. 10-E-430 Glazed Frosted Glass.	No. 10-E-431 Glazed Clear Glass.	No. 10-E-432 Glazed Frosted Glass.	No. 10-E-433 Glazed Clear Glass.	No. 10-E-434 Glazed as shown.	No. 10-E-435 Glazed Clear Glass.	No. 10-E-436 Glazed as shown.		No. 10-E-425 Glazed Clear Glass.	No. 10-E-426 Glazed as shown.	No. 10-E-427 Glazed clear Glass.	No. 10-E-428 Glazed as shown.
\$2.10	\$2.35	\$2.34	\$2.48	\$2.20	\$2.43	\$2.34	\$2.56		\$2.67	\$3.03	\$2.81	\$3.17
2.26	2.45	2.40	2.62	2.36	2.55	2.50	2.72	2- 6 x 6- 6	2.90	3.26	3.04	3.40
2.62	2.85	2.75	2.97	2.72	2.93	2.86	3.07	2- 8 x 6- 8				
2.62	2.85	2.75	2.97	2.72	2.93	2.86	3.07	2-10 x 6-10				
2.82	3.00	2.90	3.10	2.80	3.03	2.96	3.17	2- 8 x 7- 0				
								3- 0 x 7- 0	3.65	4.01	3.79	4.15



"Economy"

"Rockbottom"


Sash Doors

Real Bargains—Painted or Grained

Whatever the low prices named on these three doors may indicate to you, do not be persuaded or make yourself believe that they are not good values. As explained above, such surplus stock of lumber as will not work up to a higher grade is used for the manufacture of these new doors rather than cut it up into smaller pieces for boxes, etc., and the price has been kept down to whatever price the box lumber ordinarily would bring, plus the additional cost of manufacturing.

Remember now, please, that the off-grade is a drawback only because being painted, they cannot be used for oil finishing purposes, but if you intend to paint your woodwork anyway, you not only buy them so much cheaper here but save the price of paint and labor as well. This is a double saving. Do you see it that way? Then get in the money saving, economical and rock bottom class.

1½-inch thick. SIZES W'th. H'th Ft.In. Ft.In	"Money Saver"		"Economy"		"Rock Bottom"	
	Painted	Grained	Painted	Grained	Painted	Grained
	No. 10-E-53 Glazed Clear D.S.glass	No. 10-E-437 Glazed Clear D.S.glass	No. 10-E-54 Glazed Clear S.S.glass	No. 10-E-438 Glazed Clear S.S.glass	No. 10-E-55 Glazed Clear S.S.glass	No. 10-E-439 Glazed Clear S.S.glass
2-6 x 6-6	\$2.55	\$2.69	\$2.20	\$2.34	\$2.15	\$2.30
2-8 x 6-8	2.90	3.04	2.48	2.62	2.32	2.46
3-0 x 7-0	3.85	3.99	3.08	3.22	2.80	2.95



"Moneysaver"

Big Values in Painted and Grained Doors

We Make Only One Grade—The Best That Good Workman and Material Can Produce

By a remarkable process of finishing, material (which is not sufficiently high grade to put in a first-class door) is used, and by covering up the defects with a permanent coat of specially prepared paint or graining color, a good looking, solid and substantial door is the result. For practical purposes our painted and grained doors are plenty good enough as they are well-built, strong and durable. Our Painted Doors are given a smooth finish coat of solid color. Our 'Grained' Doors are finished in a very close imitation of beautifully figured oak.



10-G-287

Price List Painted Doors

Painted only—NOT GRAINED

Four Panel Painted—Order by No. 10-G-287.

Five Regular Panel Painted—Order by No. 10-G-295.

Five Cross Panel Painted—Order by No. 10-G-296.

SIZES		Thick- ness	10-G-287 Four Panels Painted	10-G-295 5 Regular Panels Painted	10-G-296 5 Cross Panels Painted
Width Ft. In.	Height Ft. In.				
2 0 x 6 0	6 0	1 1/8	\$0.98	These 3 sizes are not carried in stock in 5 Regular or Cross panel in 1 in. thickness.	
2 6 x 6 6	6 6	"	1.14		
2 8 x 6 8	6 8	"	1.18		
2 0 x 6 0	6 0	1 3/8	1.12	\$1.18	\$1.31
2 6 x 6 6	6 6	1 3/8	1.23	1.30	1.42
2 6 x 6 8	6 8	"	1.29	1.35	1.48
2 8 x 6 8	6 8	"	1.31	1.37	1.50
2 10 x 6 10	6 10	"	1.47	1.54	1.66
2 6 x 7 0	7 0	"	1.51	1.57	1.70
2 8 x 7 0	7 0	"	1.52	1.58	1.71
3 0 x 7 0	7 0	"	1.53	1.59	1.72



10-G-295



10-G-296

Doors Grained in Imitation of Quarter-Sawed Oak



10-G-288

Price List Grained Doors


First Painted, then Grained

Four Panel Grained—Order by No. 10-G-288.

Five Regular Panel Grained—Order by No. 10-G-297.

Five Cross Panel Grained—Order by No. 10-G-298.

SIZES		Thick- ness	10-G-288	10-G-297	10-G-298
Width Ft. In.	Height Ft. In.		Four Panels Grained	5 Regular Panels Grained	5 Cross Panels Grained
2 0 x 6 0	6 0	1½	\$1.17	These 3 sizes are not carried in stock in 5 Regular or Cross panel in 1½ in. thickness.	
2 6 x 6 6	6 6	"	1.27		
2 8 x 6 8	6 8	"	1.33		
2 0 x 6 0	6 0	1¾	1.27	\$1.31	\$1.44
2 6 x 6 6	6 6	"	1.36	1.44	1.55
2 6 x 6 8	6 8	"	1.43	1.49	1.61
2 8 x 6 8	6 8	"	1.46	1.52	1.64
2 10 x 6 10	6 10	"	1.62	1.69	1.81
2 6 x 7 0	7 0	"	1.66	1.72	1.85
2 8 x 7 0	7 0	"	1.67	1.73	1.86
3 0 x 7 0	7 0	"	1.68	1.74	1.87



10-G-297




10-G-298

**5 Regular
Panels**

Panel Doors

**5 Cross
Panels**



10-E-60.


Soft White Pine Stiles and Rails with Yellow Pine Panels

Superior Quality—Best Workmanship

Our superior doors made with **Yellow Pine panels** and white soft pine stiles and rails (which form the rim around the panels), have always been a **great favorite** wherever a particular job of oil finishing or natural finishing was wanted. **The reason** for this is plain, because it is customary to **select** all the lumber for this class of doors and are listed only, therefore, in one grade, strictly for **oil finishing** purposes. As shown in the two illustrations the somewhat darker shade on the panels form a very pleasing contrast with the whiteness of the surrounding rim, but the difference in the shade may **not be quite as prominent** in the actual doors, as shown in the design. It is very difficult to picture the **exact** contrast.

These are the doors that we usually furnish in connection with our other **high grade material** for our **regular and special house designs**, unless the specifications are changed to another kind of wood.

Being a thorough, **first class door** as to quality of material, the same thoroughness has been carried out **in their manufacture**; all cross pieces being blind-tenoned into the stiles or side pieces, and panels of good thickness.



10-E-61.

CLEAR YELLOW PINE PANELS

CLEAR SOFT W. PINE STILES AND RAILS

No. 10-E-60.

CLEAR YELLOW PINE PANELS

CLEAR SOFT W. PINE STILES AND RAILS

No. 10-E-61.

SIZES		5 Regular Panel Doors "A" Quality	
Width. Ft. In.	Height. Ft. In.	1½-inch thick.	1¾-inch thick.
2- 0 x 6- 0		\$1.83	\$. . .
2- 0 x 6- 6		2.05
2- 2 x 6- 6		2.05
2- 4 x 6- 6		2.05
2- 6 x 6- 6		2.08
2- 0 x 6- 8		2.10
2- 2 x 6- 8		2.10
2- 4 x 6- 8		2.10
2- 6 x 6- 8		2.12
2- 8 x 6- 8		2.15	3.17
2-10 x 6-10		2.56	3.79
2- 0 x 7- 0		2.45
2- 2 x 7- 0		2.45
2- 4 x 7- 0		2.45
2- 6 x 7- 0		2.46	3.65
2- 8 x 7- 0		2.55	3.74
2-10 x 7- 0		2.61	3.88
3- 0 x 7- 0		2.73	4.05

SIZES		5 Cross Panel Doors "A" Quality.	
Width. Ft. In.	Height. Ft. In.	1½-inch thick.	1¾-inch thick.
2- 0 x 6- 0		\$1.94	\$
2- 0 x 6- 6		2.15
2- 2 x 6- 6		2.15
2- 4 x 6- 6		2.15
2- 6 x 6- 6		2.18
2- 0 x 6- 8		2.19
2- 2 x 6- 8		2.19
2- 4 x 6- 8		2.19
2- 6 x 6- 8		2.23
2- 8 x 6- 8		2.24	3.26
2-10 x 6-10		2.65	3.89
2- 0 x 7- 0		2.56
2- 2 x 7- 0		2.55
2- 4 x 7- 0		2.55
2- 6 x 7- 0		2.56	3.74
2- 8 x 7- 0		2.62	3.84
2-10 x 7- 0		2.70	4.07
3- 0 x 7- 0		2.82	4.16

24 Have you posted up on our Bargains in Clothing, Dry Goods, Boots and Shoes.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Standard Soft White Pine Panel Doors

Quantity and Quality in Abundance

We aim to carry in stock all sizes, thicknesses and grades of doors on this page so you may expect prompt shipment.

By the term "A" Quality, we mean the best of clear, selected stock of the highest grade, suitable for any style of finish. We get our "B" Quality doors by a careful regrading of our "A" doors, as we occasionally sort out some which are not quite up to standard. Thus our "B" doors run much better than the ordinary "B" grade, which admits of certain defects. Of course we do not recommend our "B" doors for Oil Finish but they certainly are "Cracker Jack" doors to paint or enamel and are all right for stain finish.

We also list here "C" quality Four Panel Doors. This grade is intended for Paint finish. Recommended for cheap jobs only. Small, tight knots and other defects are permitted, but "C" doors are well made, all joints mortised and tenoned the same as our higher grades. Now, remember, in ordering doors, always specify "A" quality for a good oil finish job. The "B" grade is all right for nice work in Paint and stain. We know that our prices cannot possibly stand in the way of making the best selection, as we are offering High Grade Doors for less than they can be obtained elsewhere.

We feel satisfied that grade for grade our very low prices on these doors cannot be duplicated.

FOUR PANEL DOORS

SOFT WHITE PINE

No. 10-G-56

SIZES Ft. In. Ft. In.	Thick in.	"A" Quality	"B" Quality
2-0 x 6-0	1 1/8	\$1.50	\$1.43
2-6 x 6-0	"	1.83
2-4 x 6-4	"	1.71	1.54
2-0 x 6-6	"	1.67	1.56
2-4 x 6-6	"	1.82	1.63
6-6 x 6-6	"	1.81	1.64
2-6 x 6-8	"	1.85	1.67
2-8 x 6-8	"	1.86	1.68
2-10 x 6-10	"	2.39	2.14
3-0 x 7-0	"	2.55	2.26
2-0 x 6-0	1 3/8	1.75	1.58
2-6 x 6-0	"	2.01	1.80
2-8 x 6-0	"	2.57
2-4 x 6-4	"	1.88	1.72
2-0 x 6-6	"	1.89	1.71
2-2 x 6-6	"	1.94	1.74
2-4 x 6-6	"	1.95	1.75
2-6 x 6-6	"	2.00	1.79
2-8 x 6-6	"	2.09	1.87
2-0 x 6-8	"	1.92	1.73
2-2 x 6-8	"	1.97	1.82
2-4 x 6-8	"	1.98	1.81
2-6 x 6-8	"	2.06	1.84
2-8 x 6-8	"	2.07	1.85
2-6 x 6-10	"	2.37	2.16
2-10 x 6-10	"	2.38	2.14
2-0 x 7-0	"	2.35	2.15
2-2 x 7-0	"	2.36	2.17
2-4 x 7-0	"	2.39	2.12
2-6 x 7-0	"	2.40	2.13
2-8 x 7-0	"	2.45	2.23
2-10 x 7-0	"	2.54	2.30
3-0 x 7-0	"	2.64	2.39
2-6 x 7-6	"	3.67
2-8 x 7-6	"	3.84
2-6 x 8-0	"	4.20
2-8 x 8-8	1 3/4	3.12	2.82
2-10 x 6-10	"	3.73	3.36
2-6 x 7-0	"	3.60	3.23
2-8 x 7-0	"	3.70	3.22
2-10 x 7-0	"	3.81	3.45
3-0 x 7-0	"	3.98	3.60
2-6 x 7-6	"	5.50
2-8 x 7-6	"	5.76
2-10 x 7-6	"	6.07
3-0 x 7-6	"	6.35
2-6 x 8-0	"	6.20
2-8 x 8-0	"	6.58
3-0 x 8-0	"	7.20

Sizes on which prices are left blank are not carried in stock.

"C" QUALITY DOORS

FOUR PANEL ONLY

10-G-56


Width Ft. In.	Height Ft. In.	Thickness	
		1 1/8 In.	1 3/8 In.
2-0 x 6-0		\$1.16
2-6 x 6-6		1.29	\$1.45
2-8 x 6-8		1.39	1.54
2-10 x 6-10		1.64
3-0 x 7-0		1.75	1.92



4 Panel 10-G-56



5 Panel 10-G-57



5 Cross Panel 10-G-59

FIVE PANEL DOORS

SOFT WHITE PINE

No. 10-G-57

SIZES Ft. In. Ft. In.		Thickness Inches	Prices "A" Quality	Prices "B" Quality
2-0 x 6-0		1 3/8	\$1.90	\$1.70
2-0 x 6-6		"	2.11	1.89
2-2 x 6-6		"	2.12	1.90
2-4 x 6-6		"	2.13	1.91
2-6 x 6-6		"	2.17	1.95
2-0 x 6-8		"	2.18	1.96
2-2 x 6-8		"	2.19	1.97
2-4 x 6-8		"	2.20	1.98
2-6 x 6-8		"	2.24	1.99
2-8 x 6-8		"	2.25	2.00
2-10 x 6-10		"	2.69	2.38
2-0 x 7-0		"	2.54	2.27
2-2 x 7-0		"	2.55	2.28
2-4 x 7-0		"	2.57	2.28
2-6 x 7-0		"	2.56	2.30
2-8 x 7-0		"	2.62	2.35
2-10 x 7-0		"	2.71	2.42
3-0 x 7-0		"	2.83	2.53
2-6 x 7-6		"	3.80
2-8 x 7-6		"	3.96
2-0 x 8-0		"	4.35
2-6 x 8-0		"	4.30
2-8 x 8-0		"	4.92
2-0 x 6-8		1 3/4	3.27
2-10 x 6-10		"	3.95
2-6 x 7-0		"	3.81
2-8 x 7-0		"	3.88
2-10 x 7-0		"	4.01
3-0 x 7-0		"	4.16
2-6 x 7-0		"	4.58
3-0 x 7-6		"	6.48
2-6 x 8-0		"	6.30
3-0 x 8-0		"	7.32

FIVE CROSS PANEL DOORS

SOFT WHITE PINE

No. 10-G-59

SIZES Width Ft. In. Height Ft. In.		1 1/8 Inch Thick	
		"A" Quality	"B" Quality
2-0 x 6-0		\$1.98	\$1.65
2-0 x 6-6		2.00
2-6 x 6-6		2.01	1.89
2-0 x 6-8		2.25
2-6 x 6-8		2.30	1.92
2-8 x 6-8		2.32	1.93
2-10 x 6-10		2.75	2.32
2-0 x 7-0		2.65
2-6 x 7-0		2.66	2.23
2-8 x 7-0		2.73	2.29
3-0 x 7-0		2.93	2.41

SIZES Width Ft. In. Height Ft. In.		1 3/4 Inch Thick "A" Quality	
2-8 x 6-8		\$3.41
2-10 x 6-10		4.02
2-6 x 7-0		3.89
2-8 x 7-0		3.99
3-0 x 7-0		4.29

In ordering Doors be sure and specify Kind, Style, Thickness, Grade, how many panels and mention number of doors.

Sliding Doors and Inside Door Frames



Double Sliding or Folding Doors

SINGLE SLIDING DOOR shown to the right has **Yellow Pine Panels** and soft pine Stiles and Rails to match our Yellow Pine panel doors listed on **previous** page. Carried in stock in only **usual size, 5 ft. x 7 ft., 1 3/8 inch thick** and sold at the **unusual low price of each..... \$7.55**

Order by number **10-G-62.**

Illustration to the left shows a **pair of doors**, representing sliding or folding Doors. For prices refer to previous pages on single Doors and figure just double this price. For example, if you want a pair sliding doors for an opening **5ft. wide by 7 ft. high**, cross panels as shown, with **Y. P. Panels**, see price on single door, **No. 10-G-61—size 2 ft. 6 in. wide by 7 ft. high., (2 ft. 6 in. being half the width of a 5 foot opening) and figure twice the price.**

No. 10-G-62 1/2 same as above except **\$11.07**
1 3/4 in. thick. Price.....




Single Sliding Door, Order by No. 10-G-62

Door Jambs—Regular, Sliding, Folding, Transom

Clear Yellow Pine and Clear Red Oak

Lumber from which our interior jambs are manufactured is cut **smooth and true, clear face stock**. Side jambs dadoed for heads, heads cut **square and straight**. Prices do not include inside doorstops, which are extra. See price list below. Also listed elsewhere in this catalog. About 20 lineal feet of stops are required for each inside frame.



PRICES
ON
OTHER
SIZES
AND
WOODS
UPON
APPLICATION

Inside Door Jamb or Frame for
Regular Standard Doors

Prices for Regular Standard Door Jambs Without Stops

No. 10-G-101—Inside door jambs for 2x4 studding, for doors 3 ft. by 7 ft., or smaller sizes—Yellow Pine—Price each.....**.49c**

No. 10-G-602—Inside door jambs for 2x4 studding, for Doors 2 ft. 6 in., by 6 ft. 6 in., or smaller sizes—Red Oak—Price each.....**.86c**

No. 10-G-603—Same as above except for sizes up to 3 ft. by 7 ft.—Red Oak—Price each.....**.97c**

No. 10-G-604—Same as above except for sizes up to 3 ft. by 7 ft.—Red Oak—Price each.....**\$1.05**

SPECIAL—Add for Yellow Pine stops to price of Yellow Pine jambs per set.....**.10c**

SPECIAL—Add for Red Oak stops to price of Red Oak jambs per set.....**.20c**

Inside Folding Door Jambs

Folding Door jambs will be made the same as regular standard door jambs except for wider and higher openings. Price covers one complete frame made for 2x4 studding, without stops.

No. 10-G-625—Folding Door jambs (inside) for sizes up to 6 ft. wide by 8 ft. high, Yellow Pine, price each, 70c For stops add, per set.....**.15c**

No. 10-G-626—Same as above, except Red Oak, price each.....**\$1.50**
For Yellow Pine stops add, per set.....**.30c**

Sliding Door Jambs

Illustration shows a sectional view of double sliding door jambs for a pair of Sliding Doors. The same high quality material as our standard jambs for regular Doors shown to the left. Price covers one complete frame. Width of jamb from 2 3/4 in. to 4 3/4 in. for sides. Stops shown in illustration are priced extra. See below. If no width is specified in your order we furnish for studding set edgewise. Width of side jamb 4 3/4 in. and head jambs 5 1/2 in.

No. 10-G-615—Double Sliding Door jambs for openings up to 6 feet wide by 7 feet high—Yellow Pine—Price per set.....**\$1.48**

No. 10-G-616—Same as above except for openings up to 9 ft. wide by 8 ft. high—Yellow Pine—Price per set.....**1.97**

No. 10-G-617—Double Sliding Door jambs for opening up to 6 ft. wide by 7 ft. high—Red Oak—Price per set.....**2.98**

No. 10-G-618—Same as above except for openings up to 9 ft. wide by 8 ft. high, Price per set.....**3.57**

SPECIAL—Add for Yellow Pine Stops to price of Yellow Pine Sliding Door jambs, per set.....**.30**

SPECIAL—Add for Red Oak stops to price of Red Oak Sliding Door jambs, per set.....**.60**



Single Sliding Door Jambs

Illustration shows a sectional view of single sliding door. Prices below are for complete frame without stops, furnished for 2x4 studding, unless otherwise specified.

No. 10-G-619—Single Sliding Door jambs for openings up to 6 ft. by 7 ft. high—Yellow Pine—Price per set.....**\$0.98**


No. 10-G-620—Same as above except for openings up to 9 ft. wide by 8 ft. high—Yellow Pine—Price per set.....**1.25**

No. 10-G-621—Single Sliding Door jamb for sizes up to 6 ft. wide by 7 ft. high—Red Oak—Price per set.....**1.90**

No. 10-G-622—Same as above except for opening being 8 ft. wide by 9 ft. high—Red Oak—Price per set.....**2.38**

SPECIAL—Add for Yellow Pine stop to price of Yellow Pine Single Sliding jambs, pr set, 30c

SPECIAL—Add for Red Oak stop to price of Red Oak Single Sliding jambs, pr set.....**.60c**



INSIDE TRANSOM DOOR JAMBS


Illustration shows a sectional view of inside door jamb with transom head, made so that a transom can be used above the door. Price does not include transom, which are listed elsewhere in this catalog.

No. 10-G-623—Inside transom Door jambs for transom up to 2 ft. in height, for Doors up to 3 ft. by 7 ft.—Yellow Pine, Price per set.....**.85c**


If stops are wanted, add.....**.15c**
No. 10-G-624—Same as above, except Red Oak, Price per set.....**\$1.65**
If stops are wanted, add.....**.30c**

Sidelights and Transoms

For Front Entrances and Vestibules. Our Sidelights and Transoms are "A" quality Soft White Pine. The designs shown are in most popular use for front entrance and vestibule purposes and will be found thoroughly in harmony with our own Entrance designs illustrated on opposite page. Nos. 10-E-205 and 10-E-208 are glazed with clear double strength glass. Nos. 10-E-209, 10-E-212 and 10-E-214 are set with leaded Crystal glass. The lead bars are substantial and neat appearing. Sidelights and Transoms also furnished in Oak or Birch to match Hardwood Doors. Prices quoted on application.



No. 10-E-205




No. 10-E-208



No. 10-E-209




No. 10-E-212




No. 10-E-214


SIZES, 1½-inch Ft. In. Ft. In.	Sidelight Glazed Clear D. S. A.		Sidelight Glazed LEADED Crystal		
	10-E-205	10-E-208	10-E-209	10-E-212	10-E-214
1' 2"x 6' 8"	\$2.10	\$2.65	\$4.25	\$4.65	\$2.90
1' 2"x 6' 10"	2.35	2.85	4.45	4.85	3.30
1' 2"x 7' 0"	2.55	2.95	4.60	5.00	3.45




Transom No. 10-E-401



Transom No. 10-E-404



Transom No. 10-E-410



Transom No. 10-E-407

SIZES, 1½-inch thick Ft. In. Ft. In.	10-E-401—Glazed Clear Glass		10-E-410	10-E-407	10-E-404
	1 Lt. D. S.	2 Lts. S. S.	Glazed Clear D. S.	Glazed Leaded Crystal	Glazed Leaded Crystal
4' 6" wide, up to 1' 6" in height	\$2.40	\$1.67	\$4.98	\$5.75	\$3.00
4' 8" wide, up to 1' 6" in height	2.50	1.73	5.03	5.90	3.10
6' 0" wide, up to 1' 6" in height	3.06	2.22	5.63	6.68	3.92
6' 4" wide, up to 1' 6" in height	3.10	2.26	5.75	6.80	4.10

The 6 foot and 6 foot 4 inch sizes are for frame made for 3 foot door in width and for two Sidelights, 1 ft. 2 inches wide, while the 4 ft. 6 inch size is for frame, made for one Sidelight only. Transom prices remain the same if narrower doors than 3 feet are used.


CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago

Complete Equipment. We can Furnish any Mill Work—Regular or Special 27

STORE FRONTS

A store front of economical construction. Wood frame work, sash open and fitted with stops, clear, double-strength "A" quality glass for same shipped separately—carefully packed and boxed to insure against breakage in transit. Our "Premium" store doors, material for panels, door posts, jambs, casings and sills furnished in the knockdown, rabbeted to receive sash and doors. All new, first class material. We price only one size, 12 ft. high by 22 ft. wide. This is the most popular size but we can furnish store fronts of any size or style. Prices for other sizes and designs will be quoted on application. When writing for special quotations it will be necessary to give exact description accompanied by diagram or sketch.

We furnish Blue Print Plans and full instructions, free of charge, with each order so that builders will have no trouble in erecting our Store Fronts.



STORE FRONT No. 10-E-567.

Store Front No. 10-E-567 Width 22 feet. Height 12 feet.
Material as above described.....

\$79.00

Durable Store Doors

The three best designs in store doors are shown on this and the opposite page. We make our store doors extra heavy, one and three-quarter inches thick and use selected "A" grade stock in manufacturing them. Our "Premium" store door illustrated here, is glazed and divided in two lights as shown. This door is used in store fronts such as our design No. 10-E-567 (See above) and matches two-light or four-light store sash. Store doors are usually sold in pairs. However, we price them singly so that it may be understood that a single door can be purchased.

Prices of "Premium" Doors

1 3/4 Inch Thick	10-E-52 Glazed, Clear D. S. A.	Size of Glass
2'6"x7'0"	\$5.75	20x24
2'6"x7'6"	6.95	20x27
2'6"x8'0"	8.00	20x30
2'8"x7'0"	5.95	22x24
2'8"x7'6"	6.65	22x27
2'8"x8'0"	8.35	22x30
3'0"x7'0"	6.50	26x24
3'0"x7'6"	8.25	26x27
3'0"x8'0"	9.30	26x30

Glass

We handle glass of all kinds and make a specialty of best quality American Plate Glass for store fronts. Also ribbed and prism glass for transoms and basements. Our three-way prism glass is especially recommended for dark store-rooms, the light rays being multiplied and intensified, flooding the remotest corners. Write for prices. Glass will be packed and crated at factory and shipped direct to avoid all unnecessary handling and insure safe delivery.

"PREMIUM" DOOR 10-E-52.

28 Metal Roofing and Siding. We Surprise Ourselves—Our Prices Are So Low. CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

STORE FRONTS

Below We Show a Store Front With Recess, Using a Pair of our "Merchant" Store Doors.



STORE FRONT 10-E-568

Plate Glass Front

One of the most popular of modern store front designs. Wood frame construction. Our price covers material complete, as shown; "Merchant" doors, glazed plate glass; open sash 1½ inches thick, fitted with stops, plate glass for all sash (boxed and shipped separately); panels; frame, consisting of door posts, corner posts, jambs, sills and bars, knocked down and bundled. Furnished in the regular size, 12'x22'.

We will be glad to quote lowest prices on any style front. If you wish prices on a front of special design, be sure and give us exact description, stating dimensions, etc., and send diagram.

Store Front 10-E-568.

Width, 22 ft. Height, 12 ft. Material as above described. Price.. **\$185.00**

Blue Print Plans and full instructions accompanied by complete list of material furnished free with each order for our store fronts.

Store Doors—Built to Last

Our "Winner" Store Door has proved popular seller and is adapted to store fronts of almost any style. The "Merchant" Store Door has an extra long glass with no panel below. These doors are furnished in 1½ inches thickness only, as for the purpose a strong, heavy door should be used. Selected, thoroughly seasoned "A" grade lumber goes into our store doors. We would not recommend a lower quality for the purpose, as a door used for store entrance naturally is subjected to considerable hard usage and must be good stock to stand the wear and tear. We make our store doors in the same way that all of our high grade doors are made and offer the best that skilled workmen aided by modern machinery can produce.

Prices Here Given Are On Single Doors.

Winner 1½" thick	10-E-50 Glazed Clear D. S. A.	10-E-51 Glazed Polished Plate	Size of Glass
2'6" x 7'0"	\$ 6.25	\$10.85	20x50
2'6" x 7'6"	7.85	12.70	20x56
2'6" x 8'0"	8.70	14.25	20x62
2'8" x 7'0"	6.50	11.50	22x50
2'8" x 7'6"	8.05	13.60	22x56
2'8" x 8'0"	9.30	15.25	22x62
3'0" x 7'0"	7.10	13.05	26x50
3'0" x 7'6"	8.95	16.05	26x56
3'0" x 8'0"	10.48	17.95	26x62

Merchant 1½" thick	10-E-223 Glazed Plate D. S. A.	10-E-224 Glazed Polished B'l Plate	Size of Glass
2'6" x 7'0"	\$ 6.80	\$12.50	20x60
2'6" x 7'6"	8.08	14.14	20x66
2'6" x 8'0"	9.45	15.56	20x72
2'8" x 7'0"	7.23	14.30	22x60
2'8" x 7'6"	8.80	15.20	22x66
2'8" x 8'0"	9.78	16.64	22x72
3'0" x 7'0"	8.77	16.08	26x60
3'0" x 7'6"	9.98	17.58	26x66
3'0" x 8'0"	11.38	19.20	26x72

"WINNER" DOOR.

"MERCHANT" DOOR.

CHICAGO HOUSE WRECKING CO.
25th and Iron Streets, Chicago.

And Composition Roofings, Too.


We Always Get the Orders
on a Fair Comparison.

CORRECTLY BUILT



MAKE YOUR HOME COMPLETE

Consoles No Longer a Luxury

These Consoles are finished just like a fine piece of parlor furniture and ready to set up in your home. Filled, Shel-laced, Varnished, Rubbed and Finished to a high piano polish.



Oak Console No. 10-E-6401. Not including mirror... **\$20.90**
 Plain Plate Mirror, extra... **\$8.00**
 Beveled Plate Mirror, as illustrated, extra... **\$9.25**
 Birch, Mahogany finish, extra... **\$1.50**



Front Entrances

Our Superb Colonial Front Entrance

This imposing design is appropriate for almost any style of residence, but is particularly adapted to the Colonial type. The door, transom and sidelights shown in illustration are selected from our regular stock to convey an idea of the beauty of the complete entrance. Other suitable designs are described in this book. Prices here given cover FRAME only for wood buildings, with 5½ inch jamb and allows for door space up to 3 ft. x 7 ft.; sidelight space up to 1 ft. 2 inches by 7 feet; Transom space up to 18 inches high.

The Outside Casings are fluted, deep cut—not merely raised beading. The frame is capped with an extra wide Crown Moulding. The sill is 2x8, beveled. Made from bright Soft Pine and Poplar. Furnished in the knock-down, fitted ready to be put together. Securely bundled.


10-E-360. Price for frame as described above. **\$25.75**

10-E-365. Price for frame, same as above, **except made for one sidelight** **\$22.50**
only and panel above remaining sidelight omitted.

Prices on frame for brick wall, also in Oak and Birch, quoted on application.


CHICAGO FRONT ENTRANCE

See Style AA for Prices of Frames.



10-E-209 Sidelight. American Beauty Door. 10-E-208 Sidelight.

OUR SUPERB COLONIAL FRONT EN- TRANCE




Transom 10-E-407. Morning Glory Door. Sidelights 10-E-212.

WHITE CITY FRONT ENTRANCE

See Style BB for Prices of Frames.

In showing our "Chicago" and "White City" Front Entrance, herewith portrayed, our aim is to furnish examples of some of the most practical and desirable entrance designs. Prices here quoted are for frames only. (See styles in accompanying outline drawings). In these entrances, we illustrate 2 kinds of sidelights. Other designs will be found on the next page. The transom should be selected to match. The frames are made of Soft wood, Pine or Poplar and furnished in the knock-down, carefully bundled for shipment. Fitted, ready to put together. Furnished also in Oak or Birch. Prices on application.



10-E-214 Sidelight. Magnolia Door.

ENTRANCE FRAMES. With or without Transom Head.

For wood Buildings, we furnish with 1½-inch Outside Casings and Crown Mould Head. For brick wall frame, extra heavy Jambs are furnished and large Brick Moulding. Prices below cover frames with door opening up to 3 ft. x 7 ft.; sidelight opening up to 1 ft. 2 in. x 7 ft.; transom opening up to 18 in. high.




Style of Frame.	For Wood Building.	Price.	For 13-inch Brick Wall.	Price.
"A A"	10-E-450	\$7.00	10-E-452	\$7.50
"B B"	10-E-470	6.25	10-E-474	6.75
"C C"	10-E-460	6.00	10-E-464	6.50
"D D"	10-E-480	4.25	10-E-484	4.75

Oak Frames for 13-inch Brick wall, 25% extra.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Exclusive Designs. We do not wait for others to point the way. 31

COTTAGE WINDOWS



PLAIN VIEW No. 10-E-64




BRUSSELS ART No. 10-E-69

ART IN WINDOW DESIGNS

We show a number of the best designs in Cottage Windows and we are confident that a choice can be made to suit the taste of the most fastidious. The different styles range from the clear, plain glass of our "Plainview" Window to the stately beauty of leaded beveled plate as exemplified in our "Aristocrat" design on opposite page.

Here portrayed on either side we have some fine examples of lace designs, faithful reproductions of the famous Battenburg lace and rivaling in beauty by the closeness of imitation. It is plainly a matter of individual taste in making a proper selection of Cottage Windows. We make no recommendations of one design over another and only say that at our low prices, we are giving you the best values that money can buy.

This is not a complete list of sizes. We are able to furnish any standard size in Cottage windows up to and including 50x50 inches with 50x22 inch transom. Write for prices.



FAIRVIEW No. 10-E-63



YELLOWSTONE No. 10-E-272

Glass Size, Bottom Sash, Width, Height.	Glass Size, Top Sash, Width, Height.	Outside Measure, Width, Height.	"Plainview." 10-E-64. Price.	"Brussels." 10-E-69. Price.	"Fairview." 10-E-63. Price.	"Yellowstone." 10-E-272. Price.
40"x42"	40"x14"	3' 8"x5' 2"	\$3.75	\$3.93	\$3.95	\$4.28
40"x46"	40"x14"	3' 8"x5' 6"	3.92	4.08	4.10	4.45
44"x40"	44"x16"	4' 0"x5' 2"	4.20	4.22	4.25	4.60
44"x44"	44"x16"	4' 0"x5' 6"	4.56	4.36	4.40	4.75
44"x48"	44"x16"	4' 0"x5' 10"	4.96	4.80	4.85	5.15

COTTAGE WINDOWS



CRYSTAL No. 10-E-66




RAINBOW No. 10-E-282

SOME FINE EXAMPLES OF ART WINDOWS

Our "Crystal" design in clear glass is one of the best examples of a leaded glass pattern. It is exactly the same in design as our "Aristocrat", differing from it only in that the latter is beveled plate while the "Crystal" is clear double-strength glass.

We also show here two of the best designs in leaded colored art glass. Our "Herald" is made up after the same pattern as "Crystal" and "Aristocrat" and by a tasteful combination of colors, a real gem of a window results. Our "Rainbow" as its name implies, is a vari-colored design of leaded art glass. The colors are harmoniously blended and afford a shield from the sun's strong rays without making it necessary to draw the shades and exclude the light altogether.

The list given below is not complete as to sizes. We can furnish any standard size up to 50x50 inches with 50x22 inch transom and we will be glad to quote prices on request.



HERALD No. 10-E-281



ARISTOCRAT No. 10-E-70

Glass Size, Bottom Sash. Width, Height.	Glass Size, Top Sash Width, Height.	Outside Measure. Width, Height.	"Crystal" 10-E-66. Price.	"Herald." 10-E-281. Price.	"Rainbow." 10-E-282. Price.	"Aristocrat." 10-E-70. Price.
40"x42"	40"x14"	3' 8"x5' 2"	\$4.08	\$4.86	\$5.80	\$8.01
40"x46"	40"x14"	3' 8"x5' 6"	4.29	5.02	5.93	8.11
44"x40"	44"x16"	4' 0"x5' 2"	4.72	5.58	6.72	9.44
44"x44"	44"x16"	4' 0"x5' 6"	4.82	5.65	6.86	9.58
44"x48"	44"x16"	4' 0"x5' 10"	5.36	6.22	7.30	10.08

Check Rail

Windows

Plain Rail

All our windows are superior quality and well made in every way. Carefully selected, thoroughly seasoned "A" grade stock is used and each sash is primed in pure linseed oil before glazing. The glass is puttied in and is held firmly in place by extra strong glazier's

points and a liberal application of putty. The term window means two sash, upper lower. Check rail windows are grooved for the sash cord and intended to be hung by weights. The check is the beveled rail where the two sash come together, making a close



Two Light Check Rail Windows
1 1/2 inch thick


Size of Glass	Price per Window—Glazed.		Outside Measure With. Ht.
	Single Strength	Double Strength	
10-E-71.			
1x16	\$0.73	\$0.91	1- 8 1/2x3-2
1x18	.73	.91	3- 6
1x20	.73	.91	3-10
1x24	.77	1.00	4- 6
1x26	.87	1.15	4-10
1x28	.90	1.20	5- 2
1x30	.92	1.27	5- 6
1x32	.99	1.36	5-10
1x36	.99	.99	1-10 1/2x3-10
1x40	.84	1.10	4- 2
1x42	.86	1.14	4- 6
1x44	.91	1.19	4-10
1x46	.96	1.32	5- 2
1x48	.98	1.34	5- 6
1x50	1.04	1.42	5-10
2x20	.86	1.11	2- 0 1/2x3-10
2x22	.90	1.14	4- 2
2x24	.90	1.14	4- 6
2x26	.94	1.19	4-10
2x28	1.00	1.27	5- 2
2x30	1.05	1.34	5- 6
2x32	1.16	1.48	5-10
2x34	1.27	1.61	6- 2
2x36	1.34	1.72	6- 6
2x38	.95	1.20	2- 2 1/2x4- 2
2x40	.95	1.20	4- 6
2x42	.99	1.24	4-10
2x44	1.07	1.35	5- 2
2x46	1.15	1.47	5- 6
2x48	1.24	1.63	5-10
2x50	1.43	1.90	6- 6
2x52	.97	1.27	2- 4 1/2x3-10
2x54	1.02	1.32	4- 6
2x56	1.05	1.35	4-10
2x58	1.15	1.43	5- 2
2x60	1.22	1.50	5- 6
2x62	1.32	1.65	5-10
2x64	1.43	1.80	6- 2
2x66	1.45	1.81	6- 6
2x68	1.87	2.33	7- 2
2x70	1.12	1.50	2- 6 1/2x4- 2
2x72	1.12	1.50	4- 6
2x74	1.19	1.55	4-10
2x76	1.30	1.64	5- 2
2x78	1.37	1.76	5- 6
2x80	1.41	1.80	5-10
2x82	1.65	2.09	6- 2
2x84	1.66	2.10	6- 6
2x86	2.08	2.49	7- 2
2x88	1.37	1.76	2- 8 1/2x5- 2
2x90	1.38	1.77	5- 6
2x92	1.63	2.06	5-10
2x94	1.74	2.10	6- 2
2x96	1.80	2.31	6- 6
2x98	2.11	2.53	6-10
2x100	2.17	2.60	7- 2
3x24	1.35	1.81	2-10 1/2x4- 6
3x26	1.50	1.98	4-10
3x28	1.50	1.99	5- 2
3x30	1.70	2.17	5- 6
3x32	1.78	2.28	5-10
3x34	1.82	2.33	6- 2
3x36	1.83	2.34	6- 6
3x38	2.29	2.90	7- 2
3x40	1.54	1.90	3- 0 1/2x4- 6
3x42	1.64	2.04	4-10
3x44	1.87	2.34	5- 2
3x46	2.12	2.54	5- 6
3x48		2.58	5-10
3x50		2.64	6- 2
3x52		2.93	6- 6

Two Light Check Rail Windows (Continued)

34x24	1.75	2.08	3- 2 1/2x4- 6
34x28	2.01	2.37	5- 2
34x30	2.17	2.60	5- 6
34x32		2.70	5-10
34x36		3.13	6- 6
36x24	1.84	2.17	3- 4 1/2x4- 6
36x26	2.06	2.43	4-10
36x28	2.25	2.67	5- 2
36x30	2.26	2.68	5- 6
36x32		3.00	5-10
36x34		3.25	6- 2
36x36		3.28	6- 6
40x28		2.75	3- 8 1/2x5- 2
40x30		3.03	5- 6
40x32		3.30	5-10
40x34		3.31	6- 2
40x36		4.00	6- 6
40x40		4.07	7- 2

Pantry Windows Two Light Check Rail

Size of Glass	Price per Window—Glazed.		Outside Measure With. Ht.
	Single Strength	Double Strength	
10-E-85.			
12x20	\$0.72		1- 4 1/2x3-10
12x24	.75		4- 6
12x26	.86		4-10
12x28	.88		5- 2
12x30	.91		5- 6
12x32	.98		5-10
12x34	1.18		6- 2
12x36	1.18		6- 6
14x20	.74		1- 6 1/2x3-10
14x24	.76		4- 6
14x26	.87		4-10
14x28	.89		5- 2
14x30	.92		5- 6
14x32	.99		5-10
14x36	1.19		6- 6



Four Light Check Rail Windows

Size of Glass	Price per Window—Glazed.		Outside Measure With. Ht.
	Single Strength	Double Strength	
10-E-72.			
10x20	\$0.85		2- 1 x3-10
10x22	.83		4- 2
10x24	.89		4- 6
10x26	.95		4-10
10x28	1.03		5- 2
10x30	1.15		5- 6
10x32	1.28		5-10
12x20	.88		2- 5 x3-10
12x22	.99		4- 2
12x24	1.02		4- 6
12x26	1.07		4-10
12x28	1.14		5- 2
12x30	1.25		5- 6
12x32	1.33		5-10
12x34	1.57		6- 2
12x36	1.57		6- 6
12x38	1.80		6-10

Four Light Check Rail Windows (Continued)

12x40	1.98	7- 2
14x20	1.05	2- 9 x3-10
14x22	1.13	4- 2
14x24	1.14	4- 6
14x26	1.25	4-10
14x28	1.30	5- 2
14x30	1.40	5- 6
14x32	1.50	5-10
14x34	1.78	6- 2
14x36	1.78	6- 6
14x38	2.02	6-10
14x40	2.07	7- 2
15x30	1.57	2-11 x5- 6
15x32	1.66	5-10
15x36	2.12	6- 6



Eight Light Check Rail Windows

Size of Glass	Price per Window—Glazed.		Outside Measure With. Ht.
	Single Strength	Double Strength	
10-E-74.			
8x10	\$0.78		1- 9 x3-9 1/2
8x12	.85		4- 6
9x12	.87		1-11 x4- 6
9x14	.98		5- 2
10x12	.89		2- 1 x4- 6
10x14	.99		5- 2
10x16	1.16		5-10
10x18	1.43		6- 6
12x14	1.13		2- 5 x5- 2
12x16	1.25		5-10
12x18	1.43		6- 6
14x16	1.47		2- 9 x5-10
14x18	1.69		6- 6
14x20	1.86		7- 2



Twelve Light Check Rail Windows

Size of Glass	Price per Window—Glazed.		Outside Measure With. Ht.
	Single Strength	Double Strength	
10-E-76.			
8x10	\$0.91		2- 4 1/2x3-10
8x12	1.06		4- 6
8x14	1.25		5- 2
9x12	1.11		2- 7 1/2x4- 6
9x14	1.30		5- 2
9x16	1.47		5-10
10x12	1.22		2-10 1/2x4- 6
10x14	1.35		5- 2
10x16	1.55		5-10
10x18	1.85		6- 6
12x14	1.79		3- 4 1/2x5- 2
12x16	1.96		5-10
12x18	2.14		6- 6
12x20	2.47		7- 2

Plain Rail Window

Plain rail windows are made of stock 1/2 inches thick and are usually held in place by spring bolts on one or both sides of each sash. A window of this kind is rarely put in a class residence but for the cheaper house to be used in barns, shops and shops, the plain rail window is all right and can be recommended. The same high grade stock is as in our check rail windows and each is primed in oil and glass well puttied in.

Plain Rail Window Four Light

Size of Glass	Price per window		Outside Measure With. Ht.
	Thick- ness	Glazed	
10-F-73.			
12x20	1 1/2	\$.88	2- 5 x3-10
12x24	1 1/2	1.02	
12x26	1 1/2	1.07	
12x28	1 1/2	1.14	

Plain Rail Windows Eight Light

Size of Glass	Price per window		Outside Measure With. Ht.
	Thick- ness	Glazed	
10-F-75.			
8x10	1 1/2	\$0.69	1- 8 1/2x3-2
8x12	1 1/2	.80	
9x12	1 1/2	.80	1-10 1/2x4- 6
9x14	1 1/2	.94	
10x12	1 1/2	.84	2- 0 1/2x4- 6
10x14	1 1/2	.95	
10x16	1 1/2	1.12	
12x14	1 1/2	1.08	2- 4 1/2x5- 2
12x16	1 1/2	1.22	
12x18	1 1/2	1.40	

Plain Rail Windows 12 Light

Size of Glass	Price per Window		Outside Measure With. Ht.
	Thick- ness	Glazed	
10-E-77.			
7x9	1 1/2	\$0.86	2- 1 x3-2
8x10	1 1/2	.88	2- 4 x4- 6
8x12	1 1/2	1.01	2- 4 x4- 6
8x14	1 1/2	1.05	2- 4 x4- 6
9x12	1 1/2	1.27	2- 7 x4- 6
9x14	1 1/2	1.27	2- 7 x4- 6
9x15	1 1/2	1.43	2- 7 x4- 6
10x12	1 1/2	1.14	2-10 x4- 6
10x14	1 1/2	1.27	-10 x4- 6
10x15	1 1/2	1.39	-10 x4- 6
10x16	1 1/2	1.43	-10 x4- 6
10x18	1 1/2	1.86	-10 x4- 6
12x14	1 1/2	1.78	3- 4 x4- 6
12x16	1 1/2	1.95	4 x4- 6

Plain Rail Windows 15 Light

Size of Glass	Price per window		Outside Measure With. Ht.
	Thick- ness	Glazed	
10-G-76.			
8x10	1 1/2	\$1.64	2- 4 x4- 6
10x12	1 1/2	2.05	2-10 x4- 6

Plain Rail Windows 18 Light

Size of Glass	Price per window		Outside Measure With. Ht.
	Thick- ness	Glazed	
10-G-79.			
8x10	1 1/2	\$1.91	2- 4 x4- 6
10x12	1 1/2	2.53	2-10 x4- 6

Note:—Prices for all Windows on this page include top and bottom Sash, with glass puttied in.

Note: Prices for all Windows on this page include top and bottom Sash, with glass puttied in.

Special Windows

Fancy Cut Up Top Sash—Divided by Wood Bars

These are the best known and most popular designs in fancy cut up top sash. Wood bars are used to divide the lights and the work is done by hand, each piece being carefully mortised in and securely nailed. The sash are first primed in pure Linseed Oil and then glazed. Every light of glass is well puttied and will hold its place.


To arrive at the cost of one of these windows, add the amount given under illustration to the price of an ordinary two-light, check rail window of the desired size. For example, suppose you order Design 10-E-1337, size 24"x30", by referring to window table 10-E-71, you will find that the price of a 24"x30" check rail window, glazed, single strength, is \$1.22. Adding 86 cents, makes the price of this window \$2.08, glazed as shown in illustration.



10-E-1337.
Add 86c



10-E-1338.
Add 93c



10-E-1339.
Add \$1.14



10-E-1340.
Add \$1.36



10-E-1341.
Add 29c



10-E-1342.
Add 72c



10-E-1400.
Add \$2.22



10-E-1410.
Add \$1.72




10-E-1440.
Add \$1.29



10-E-1500.
Add \$2.00

TRANSOM SASH



Outside Measure, With H'th. Ft. In. In.	10-E-80. Thickness, Price 1 Lgt. Glazed.
6x10.....11	\$0.42
6x12.....11	.42
6x14.....11	.46
6x16.....11	.51
6x18.....11	.55
6x20.....11	.64
8x10.....11	.44
8x12.....11	.44
8x14.....11	.51
8x16.....11	.53
8x18.....11	.59
8x20.....11	.77
10x10.....11	.52
10x12.....11	.52
10x14.....11	.52
10x16.....11	.59
10x18.....11	.60
10x20.....11	.70
12x10.....11	.59
12x12.....11	.59
12x14.....11	.65
12x16.....11	.76
12x18.....11	.78
12x20.....11	.84
14x10.....11	.95
14x12.....11	1.12
14x14.....11	1.47
14x16.....11	1.80


ATTIC SASH

1-Light

3-Inch Bottom Rail, 1½-in. thick.

Size of Glass Inches.	10-E-84. Price Sash, Glazed.	Outside Measure, With H'th. Ft. In. Ft. In.
18x20.....	\$0.63.....	1-10 x2-1
20x20.....	.69.....	2-0 x2-1
20x24.....	.75.....	2-5
24x24.....	.86.....	2-4 x2-5
24x28.....	.92.....	2-9
24x30.....	1.06.....	2-11

CELLAR SASH




2 Light

Size of Glass Inches.	10-E-81. Thick-Price Glazed, nessSingle Double	Outside Measure, With H't. Ft. In. Ft. In.
10x12.....11	\$0.46.....	2-1x16
10x14.....11	.48.....	.77... 18
10x16.....11	.55.....	.88... 20
10x18.....11	.59.....	.94... 22
10x20.....11	.68.....	1.10... 24
12x12.....11	.50.....	.79... 2-5x16
12x14.....11	.56.....	.91... 18
12x16.....11	.59.....	.96... 20
12x18.....11	.62.....	1.03... 22
12x20.....11	.72.....	1.14... 24
14x16.....11	.68.....	1.12... 2-9x20
14x18.....11	.71.....	1.18... 22
14x20.....11	.81.....	1.30... 24

CELLAR SASH

3 Light



Size of Glass Inches.	10-E-82. Thick-Price Glazed, nessSingle Double	Outside Measure, With H't. Ft. In. Ft. In.
7x9.....11	\$0.43.....	2-1x1-1
8x10.....11	.45.....	.70... 2-4x1-2
8x12.....11	.50.....	.78... 1-4
8x14.....11	.55.....	.88... 1-6
9x12.....11	.52.....	.81... 2-7x1-4
9x14.....11	.55.....	.88... 1-6
9x16.....11	.64.....	.99... 1-8
10x12.....11	.57.....	.82... 2-10x1-4
10x14.....11	.64.....	.99... 1-6
10x16.....11	.69.....	1.11... 1-8
12x12.....11	.76.....	.95... 3-4x1-4
12x14.....11	.84.....	1.30... 1-6
12x16.....11	.88.....	1.35... 1-8
12x18.....11	.95.....	1.49... 1-10

STALL SASH



1 Light

1 Inch Thick.

Size of Glass Inches.	10-E-83. Price per Sash, Glazed.
10x12.....	\$0.40
10x14.....	.42
12x14.....	.46
12x16.....	.47

BARN SASH



1½ Inch Thick.

4 Lights.

10-E-86.

Size of Glass.	Price per Sash, Glazed.
8"x10".....	\$0.48
9"x12".....	.56
9"x14".....	.62
10"x12".....	.60
10"x14".....	.65
10"x16".....	.82
12"x14".....	.82
12"x16".....	.88

1½ Inch Thick.

6 Lights.

10-E-87.

Size of Glass.	Price per Sash, Glazed.
8"x10".....	\$0.68
9"x12".....	.80
10"x12".....	.88

All sash are primed in Linseed Oil or given a coat of white lead. Prices on sizes not listed here will be quoted on application.

For Blinds with Stationary Slats or half Stationary and half Rolling Slats, add 50 per cent to prices in accompanying table.

OUTSIDE BLINDS

ROLLING SLATS.

10-F-94. FOR TWO LIGHT WINDOWS. 1½ Inch Thick.

Size of Glass.	Price, per Pair.	Size of Glass.	Price, per Pair.
20x24.....	\$1.40	24x40.....	\$2.59
20x28.....	1.57	26x28.....	1.63
20x30.....	1.63	26x30.....	1.73
20x32.....	1.68	26x32.....	1.77
20x34.....	2.11	26x34.....	2.19
20x36.....	2.24	26x36.....	2.36
22x24.....	1.40	26x38.....	2.52
22x26.....	1.55	26x40.....	2.71
22x28.....	1.56	28x28.....	1.63
22x30.....	1.63	28x30.....	1.73
22x32.....	1.68	28x32.....	1.77
22x34.....	2.09	28x34.....	2.19
22x36.....	2.24	28x36.....	2.35
24x24.....	1.40	28x38.....	2.52
24x26.....	1.54	28x40.....	2.71
24x28.....	1.56	30x30.....	2.05
24x30.....	1.63	30x32.....	2.15
24x32.....	1.68	30x34.....	2.27
24x34.....	2.09	30x36.....	2.40
24x36.....	2.24	30x38.....	2.56
24x38.....	2.40	30x40.....	2.77

FOR TWO LIGHT PANTRY WINDOWS.

10-F-95. 1½ Inch Thick.	Price, per Pair.
12x24.....	\$0.96
12x28.....	1.01
12x30.....	1.09
12x32.....	1.12
12x34.....	1.34
14x24.....	\$1.11
14x26.....	1.15
14x28.....	1.21
14x30.....	1.27
14x32.....	1.31

FOR FOUR LIGHT WINDOWS, 1½ Inch Thick.

10-F-96. 1½ Inch Thick.	Price, per Pair.
12x20.....	\$1.26
12x24.....	1.40
12x26.....	1.54
12x28.....	1.56
12x30.....	1.63
12x32.....	1.68
12x34.....	1.77
12x36.....	2.19
12x38.....	2.35
12x40.....	2.52
14x24.....	\$1.54
14x26.....	1.56
14x28.....	1.63
14x30.....	1.73
14x32.....	1.77
14x34.....	2.19
14x36.....	2.35
14x38.....	2.52
14x40.....	2.71
15x32.....	2.15

FOR 8 LIGHT WINDOWS, 1½ Inch Thick.

10-F-97. 1½ Inch Thick.	Price, per Pair.
8x10.....	\$1.40
10x12.....	1.45
10x14.....	\$1.56
10x16.....	1.68

FOR 12 LIGHT WINDOWS, 1½ Inch Thick.

10-F-98. 1½ Inch Thick.	Price, per Pair.
8x10.....	\$1.28
9x12.....	1.54
9x14.....	1.64
9x16.....	1.77
10x12.....	1.80
10x14.....	\$2.01
10x16.....	2.14
10x18.....	2.40
10x20.....	2.77

Storm Sash = Storm Doors

DOUBLE YOUR DOORS AND WINDOWS :: :: SAVE ONE-HALF YOUR COAL BILL
HOLD THE HEAT IN. KEEP THE COLD OUT.

Winter's Chilling Blasts need tempering. Protect your home and cut your fuel bill in two. **ORDER NOW.** Don't wait until you are frozen. We list below the sizes we carry in stock which will take care of the usual requirements. Odd sizes can be made to order and prices will be quoted on application.

Our Storm Sash are made Stationary, glazed with clear, good quality glass, primed and puttied and strongly built in every way. Our Storm Doors are manufactured like the rest of our high grade doors and furnished either painted or grained. All Storm Sash and Doors are made 1½ inches thick to the rabbeted part of the jambs.

Special Hardware for our Storm Sash is described on page 50.



No. 10-E-89


Storm Sash Two Lights---Glazed and Primed Thickness 1 1-8 Inch

Special

All Storm Sash are glazed and primed in oil, are 1½ inch thick when finished.

Size of Glass.	Will Fill Opening.	Price Glazed Single Strength Glass.	Price Glazed Double Strength Glass.
16x24.	1' 8½"x4' 7"	\$.84	\$1.12
16x26.	" x4' 11"	.96	1.28
16x28.	" x5' 3"	.98	1.34
16x30.	" x5' 7"	1.02	1.42
16x32.	" x5' 11"	1.09	1.50
18x24.	1' 10½"x4' 7"	.95	1.27
18x26.	" x4' 11"	1.01	1.34
18x28.	" x5' 3"	1.06	1.47
18x30.	" x5' 7"	1.08	1.50
18x32.	" x5' 11"	1.15	1.59
20x20.	2' 0½"x3' 7"	.95	1.25
20x22.	" x4' 2"	.99	1.27
20x24.	" x4' 7"	1.00	1.27
20x26.	" x4' 11"	1.04	1.33
20x28.	" x5' 3"	1.12	1.41
20x30.	" x5' 7"	1.17	1.50
20x32.	" x5' 11"	1.28	1.66
20x34.	" x6' 3"	1.40	1.80
22x24.	2' 2½"x4' 7"	1.08	1.34
22x26.	" x4' 11"	1.10	1.39
22x28.	" x5' 3"	1.17	1.50
22x30.	" x5' 7"	1.27	1.63
22x32.	" x5' 11"	1.37	1.77
22x34.	" x6' 3"	1.54	1.96
22x36.	" x6' 7"	1.56	2.07
24x24.	2' 4½"x4' 7"	1.13	1.46
24x26.	" x4' 11"	1.17	1.50
24x28.	" x5' 3"	1.27	1.63
24x30.	" x5' 7"	1.34	1.74
24x32.	" x5' 11"	1.46	1.83
24x34.	" x6' 3"	1.59	1.90
24x36.	" x6' 7"	1.59	2.00
26x28.	2' 6½"x5' 3"	1.43	1.52
26x30.	" x5' 7"	1.52	1.99
26x32.	" x5' 11"	1.55	1.99
28x30.	2' 8½"x5' 7"	1.53	1.96
28x32.	" x5' 11"	1.80	2.20

Ventilators in Bottom, 15c Extra



No. 10-E-92

Storm Sash Twelve Lights---Glazed and Primed Thickness 1 1-8 Inch

Size of Glass	Will Fill Opening	Price, Glazed
8x10.	2' 4½"x3' 11"	\$1.02
9x12.	2' 7½"x4' 7"	1.23
9x14.	2' 7½"x5' 3"	1.44
10x12.	2' 10½"x4' 7"	1.34
10x14.	" x5' 3"	1.50

Ventilators in Bottom, 15c Extra



No. 10-E-91



No. 10-E-93



No. 10-E-90

Storm Sash Four Lights---Glazed and Primed Thickness 1 1-8 Inch

Size of Glass.	Will Fill Opening.	Price Glazed
10x20.	2' 1"x3' 11"	\$0.89
10x22.	" x4' 3"	.96
10x24.	" x4' 7"	.99
10x26.	" x4' 11"	1.08
10x28.	" x5' 3"	1.14
10x30.	" x5' 7"	1.25
10x32.	" x5' 11"	1.39
12x20.	2' 5"x3' 11"	.97
12x22.	" x4' 3"	1.08
12x24.	" x4' 7"	1.13
12x26.	" x4' 11"	1.19
12x28.	" x5' 3"	1.24
12x30.	" x5' 7"	1.39
12x32.	" x5' 11"	1.45
12x34.	" x6' 3"	1.75
12x36.	" x6' 7"	1.77
14x26.	2' 9"x4' 11"	1.39
14x28.	" x5' 3"	1.44
14x30.	" x5' 7"	1.56
14x32.	" x5' 11"	1.66

Ventilators in Bottom, 15c Extra.

Storm Sash Eight Lights Thickness 1 1-8 Inch

Size of Glass.	Will Fill Opening.	Price Glazed
8x10.	1' 9"x3' 11"	\$0.86
9x12.	1' 11"x4' 7"	.95
10x12.	2' 1"x4' 7"	.99
10x14.	" 1"x5' 3"	1.10
10x16.	" 1"x5' 11"	1.27
12x14.	" 5"x5' 3"	1.26
12x16.	" 5"x5' 11"	1.30

Ventilators in Bottom, 15c Extra.

Cottage Front Storm Sash---3 Lts. Thickness-1 1-8 Inch

Size of Bottom Glass.	Size of Top Glass.	Will Fill Opening.	Price Glazed.
40x40.	40x14.	3'8½"x5'2"	\$3.60
40x40.	40x16.	" x5'4"	3.73
40x44.	40x16.	" x5'8"	4.07
44x40.	44x16.	4'0½"x5'6"	4.21
44x44.	44x16.	" x5'8"	4.34
44x46.	44x18.	" x6'0"	4.56
44x50.	44x18.	" x6'4"	4.84

Ventilators, 15c Extra.

Storm Doors

Guaranteed the Best Manufactured
Hand Painted, Hand Grained,
Thickness 1 1-8 Inch

Regular Door Size	Size of Our Storm Doors	10-E-1720 Painted	10-E-1721 Glazed D.S. Painted
2' 6"x6' 6"	2' 6½"x6' 7"	\$1.56	\$2.04
2' 8"x6' 8"	2' 8½"x6' 9"	1.63	2.16
2' 10"x6' 10"	2' 10½"x6' 11"	1.75	2.23
2' 8"x7' 0"	2' 8½"x7' 1"	1.80	2.28
2' 10"x7' 0"	2' 10½"x7' 1"	1.87	2.40
3' 0"x7' 0"	3' 0½"x7' 1"	1.94	2.47

No. 10-E-1720.

For Grained Doors Add 25c Net.

No. 10-E-1721

China Closet and Cupboard Doors

For the Handy Man

Drawers and Bins for the Pantry

China Closet Doors


In these four designs, we offer a choice from which any one building his own china closet, can make a satisfactory selection. No. 10-E-201 is glazed clear glass, and Nos. 10-E-204 and 10-E-202 are glazed with Leaded Crystal Glass. No. 10-E-203 is exceptionally artistic and is only slightly higher in price. This is a leaded art glass pattern of very appropriate design.

Our China Closet Doors are made $\frac{3}{4}$ or $1\frac{1}{8}$ -inch thick and furnished at the following low prices, in either clear Yellow Pine or White Pine:

Prices on China Closet Doors.

Sizes,	10-F-201.	10-F-204.	10-F-202.	10-F-203.
1' 6"x3'	\$0.90	\$2.35	\$2.35	\$2.50
1' 8"x3' 4"97	2.79	2.79	3.57
1' 6"x4'	1.07	2.92	2.92	3.65
1' 8"x4'	1.14	3.30	3.30	3.93


Also furnished in Oak. Write for prices.



10-E-202



10-E-203




10-E-201



10-E-204

Drawer Case



Useful in many ways. Suitable for storing linen and can be placed in bedroom or hall closet. The drawers are deep and roomy, made with lip front which keeps out the dust. Clear Yellow Pine for oil finish is generally used for the face, but can also furnish in soft pine, and other soft woods for paint, if preferred. These cases are all made 2 feet 10 inches high; widths from 2 feet 6 inches to 4 feet 6 inches. Drawers are 12 to 16 inches deep from front to back, all at same price, and we usually furnish 18-inch, unless otherwise ordered.

Generally built between walls or made stationary in a corner, and we furnish with open or closed sides and back, as ordered, including the front, top and 3 drawers.

Prices below are for ceiling sides or ends. If wanted paneled as shown in picture add 50c each.

Prices—Order by No. 10-G-878.

Size.	Open Sides and Back.	Closed sides Open Back	Closed sides and Back
2 ft. 6 in. wide	\$4.50	\$5.75	\$6.50
3 ft. "	4.50	5.75	6.50
3 ft. 6 in. "	5.00	6.50	7.15
4 ft. "	5.75	7.15	8.10
4 ft. 6 in. "	6.50	7.90	8.75

Drive a Few Nails and Drive a Bargain

By just a little effort and utilizing spare time you can save some money by purchasing above Drawer Casing in the knock-down. The different sections are put together so no cutting or sawing will have to be done, just drive a few nails and that is all. Same will be crated securely with the three drawers. Impossible to be damaged in transit. Will be furnished as shown in cut, solid paneled if ordered with closed sides.


Order by No. 10-G-880.

Size.	Open sides and back	Closed sides Open back	Closed sides and Back
2 ft. 6 in. wide	\$3.50	\$3.85	\$4.80
3 ft. 6 in. "	4.90	6.35	7.30
4 ft. 6 in. "	5.55	7.00	7.90
4 ft. 6 in. "	6.10	7.50	8.45

Flour Bins

Made to set in wall pocket or Pantry Case. Hung by means of hinges at bottom face. Made of selected wood, clear yellow pine face and lined with Poplar or Whitewood.


It pays to be careful in the matter of wood used for lining flour bins. Some woods particularly Yellow Pine, are liable to impart a disagreeable flavor to the contents. The picture is a view of the bin taken at an angle from the back. It is constructed so that when the bin swings out, it is caught and held in place. These bins are made 2 feet 6 inches high, 1 foot 6 inches wide, 9 inches deep at bottom and 17 inches at top.



10-G-882 Price K.D. \$1.75
10-G-883 Price, set up. \$2.00

Separate Drawers


These drawers are made from seasoned, selected stock, with clear Yellow Pine lip face and soft wood body. They are well manufactured in every way. We furnish in the most desirable sizes, listed below, all drawers being made 18 inch deep.



Prices 10-F-879.

Sizes Width Up-to	H'ght in.	D'pth In.	Price, Each, K.D.	Price, Each, Set Up.
1'5"	4 1/2	18	\$0.50	\$0.65
3'	6 1/2	18	.55	.70
4'	8	18	.68	.84
4'6"	9	18	.87	1.00
4'8"	10	18	1.05	1.10
				1.38
				1.60

Two Panel Cupboard Doors



10-E-222

Our Cupboard Doors are made $\frac{3}{4}$ or $1\frac{1}{8}$ " thick and furnished in Clear Yellow Pine or Soft Pine. When ordering, select size from table below. Although illustrated and usually sold in pairs, our prices are on single doors only.


Size,	Price, Each	Size,	Price, Each.
1'6"x2' 0"	\$0.69	1'6"x4'0"	\$1.10
1'6"x2' 6"73	1'8"x4'0"	1.17
1'6"x2'10"76	1'8"x4'6"	1.27
1'8"x2' 7"75	1'8"x4'6"	1.81
1'8"x2'10"83	2'0"x5'0"	1.99
2'0"x3' 0"97		

Suitable hardware trimmings—Drawer Pulls, Hinges, Door Catches, etc.—will be found described elsewhere in this book.

Latest Creations in Art Glass. New Material and New Designs

SPECIAL NOTE:


Send for our Beautiful Colored Art Glass Pamphlet, showing some 60 of the most exquisite modern Art and Art Noveau Glass Designs at less than half of Art glass store prices.



10-E-1505X
Price sq. ft. \$0.60




10-E-1508X
Price sq. ft. \$0.44



10-E-1511X
Price sq. ft. \$0.45



10-E-1514X
Price sq. ft. \$0.46



10-E-1541X.
Price sq. ft. \$0.


**SEND FOR OUR FREE
COLORED PAMPHLET**

**FLORENTINE—MAZE AND
COLONIAL GLASS**

**CHIPPED OR FROSTED
GLASS**

This is a "rolled process" glass, particularly adapted for use in glass partitions, in offices and public buildings. Not as transparent as the chipped, but affording plenty of light for all particular purposes.

Our chipped glass is considered stronger than the ordinary run of chipped or frosted glass. Used mainly for bathroom doors and windows or for any other purpose where some privacy is desired, at the same time admitting an abundance of light.




10-E-1517X
Price sq. ft. \$0.50




10-E-1520X
Price sq. ft. \$0.50



10-E-1523X
Price sq. ft. \$0.50



10-E-1550X.
Price sq. ft. \$1.30



10-E-1553X.
Price sq. ft. \$1.30



10-E-1562X.
Price sq. ft. \$1.75




10-E-1598X
Price sq. ft. \$0.12



10-E-1595X
Price sq. ft. \$0.12

RIBBED GLASS.

Low in price. Used for any purpose where no particular fancy job is required, at the same time obscuring the view from the curious. Just the thing for basements of apartment buildings, factories, warehouses. As it diffuses more light than any other kind of glass (except Prism), it has proven a popular skylight glass.




Ribbed glass sold in 2 thicknesses. Would suggest the heavier grade for the larger sizes.

10-E-1583X Ribbed glass, 3-16-inch thick. Price per square foot..... **9c**

10-E-1586X Ribbed glass, 1-inch thick. Price per square foot **7c**

STRONG WIRE GLASS.

An extra heavy quality of wire glass, serves as a double protection against fire and storms and high insurance rates. Iron shutters are frequently dispensed with where wire glass windows are used. Our wire glass is heavy stock, being 1/4-inch thick, well made and will last a lifetime. All glass 1/4 inch thick.



10-E-1580X. Price 18c per square foot.....

**DON'T BUY
LUMBER
WITHOUT
GETTING
OUR
PRICES.**

SHEET PRISM GLASS. NEW, CLEAN STOCK ONLY.

The principle of Prism glass is to gather the light from the sky and send it into all parts of day interiors. A skylight of ordinary glass merely throws the light straight down, whereas Prism diffuses and spreads the light on all sides.



10-E-1589X Sheet Prism glass. Price for sizes up to 42-inch high, per square foot **20c**

10-E-1592X Sheet Prism glass. Price for sizes up to 6 inches high, per square ft **28c**

Art Glass

FOR

Church

Windows

Quality High

Prices Low

It would be almost impossible to do justice in colors to the designs we show on this page. We leave it to your own taste to select the colors. The illustrations are more to show the design and the prices. Whenever an order warrants we will submit colored designs showing how the finished window will look as desired.

Our factory's work in this line is of the very best and will compare favorably with the work turned out by the best window firms in the country. When ordering church windows it is best to order the sash and frames from us as well. Then you are sure a perfect fit.

We will not only save you big money on the art glass but on the frame and sash as well. You will get your shipment from one point and you will get it with the glass already set into the sash. The delivery to your station guaranteed.

If you order without the sash, or sometimes be sure to send exact measurements and full size paper pattern of all sash lights.

Art glass quoted on this page is based on using leaded bars. Zinc, Copper, brass bars furnished at an extra cost. Prices cheerfully furnished.

Workmanship, colors, glass first quality in every respect.

On design No. 1968 the price \$2.00 per foot is for the glass without the portrait. While the illustration shows the figure of our Saviour other figures can be furnished at approximately the same price, depending upon the amount of work required.

No orders for Leaded or Art Glass executed for less than the price of 3 square feet of glass.

Special Church
Windows Frames
Made to Order.
Our Prices Ex-
ceedingly Low.

A Few of Our Church Window Designs

We have thousands of others. If you are building a church, write us for water color sketches.



No. 10-E-1966.
95c sq. ft.



No. 10-E-1967.
\$2.25 sq. ft.




No. 10-E-1968.
\$2.00 sq. ft.




No. 10-E-1969.
\$3.75 sq. ft.



No. 10-E-1970.
85c sq. ft.



No. 10-E-1971.
90c sq. ft.



No. 10-E-1972.
98c sq. ft.



No. 10-E-1973.
\$1.00 sq. ft.

HIGH GRADE Colonial Columns

Scamozzi Cap 10-E-530.

Modern Ionic Cap




10-E-531.

Roman Corinthian Cap



10-E-532.

Plain Colonial Cap



10-E-533.

ROUND COLONIAL COLUMNS LOCK JOINT AND DOWEL CONSTRUCTION BUILT UP FROM CLEAR SELECTED STOCK OF THE MOST DURABLE LUMBER.

Our High Grade Colonial Columns are made of thoroughly seasoned lumber, selected with careful regard to weather-resisting quality, strictly clear stock being used. The staves are lockjointed and glued to make a perfect and tightly fitting joint.

In the matter of price, we have gone to the extreme limit to give the best quality for the least price, but in no way have we allowed price reduction to lower the high character of these goods.

We do not handle No. 2 Columns, as experience has proved that builders cannot be satisfied with an inferior grade.

PRICES COLONIAL COLUMNS.

Diam. of Shaft, Inches.	Length, Feet.	10-G-110. Plain, as Illustrated	10-E-210. Half Fluted as illustrated.	10-E-109. Full Fluted, as illustrated.
6x 6 ..	8	\$1.46	\$2.48	\$2.58
6x 6 ..	9	1.79	2.85	2.95
8x 8 ..	8	1.95	3.15	3.23
8x 8 ..	9	2.10	3.42	3.52
8x 8 ..	10	2.65	3.75	3.82
10x10 ..	8	2.55	4.20	4.30
10x10 ..	9	2.86	4.63	4.73
10x10 ..	10	3.61	5.06	5.16
12x12 ..	8	4.35	5.92	6.02
12x12 ..	9	4.50	6.93	7.03
12x12 ..	10	5.40	7.30	7.40

COMPOSITION CAPS.

All prices listed on this page are for columns complete with Plain Colonial Cap 10-E-533, and base as shown. Add extra for Composition Cap as follows:

COMPOSITION CAPS EXTRA.

For Size of Column, any Length.	Scamozzi Cap. 10-E-530.	Modern Ionic Cap. 10-E-531.	Roman Corinthian Cap. 10-E-532.
6" Column	\$.58	\$.72	\$1.14
8" "	.75	.95	1.58
10" "	.96	1.14	2.30
12" "	1.72	1.80	2.86


PRICES GIANT COLONIAL COLUMNS.

Diam. Shaft Inches	Length Feet	10-G-344 Fluted Shaft Scamozzi Cap as shown	10-G-345 Plain Shaft with 10-E-533. Plain Cap.	10-G-346 Plain Shaft with 10-E-530 Compo Cap.
14x14 ..	9 ..	\$ 11.45	\$ 8.68 ..	\$ 10.13 ..
14x14 ..	12 ..	14.17 ..	11.01 ..	12.45 ..
16x16 ..	14 ..	22.95 ..	17.36 ..	20.65 ..
16x16 ..	20 ..	30.57 ..	24.69 ..	27.90 ..
18x18 ..	20 ..	41.84 ..	30.35 ..	37.50 ..
20x20 ..	18 ..	45.27 ..	33.01 ..	41.60 ..
22x22 ..	18 ..	58.82 ..	41.69 ..	53.15 ..
24x24 ..	20 ..	63.13 ..	44.71 ..	56.15 ..
26x26 ..	24 ..	83.68 ..	60.68 ..	75.00 ..
28x28 ..	26 ..	105.60 ..	73.01 ..	94.45 ..
30x30 ..	28 ..	128.60 ..	89.76 ..	118.35 ..

"GIANT" COLONIAL COLUMNS

For the typical colonial home, nothing can surpass the majestic beauty and imposing grandeur of our "Giant" Colonial Columns. These columns are staved like the smaller columns and built of extra heavy stock, selected poplar. Even the smallest of these columns, 14 inches in diameter, are made of stock 2 inches thick and in the heaviest columns we use 3-inch lumber. This is an important fact and always should be considered when comparing values. To insure reaching you in perfect condition, the "Giants" are given a prime coat of paint and shipped direct from factory.

For Fluted "Giant" Columns with plain cap 10-E-533, deduct 5 per cent from prices as shown for 10-G-346. Delivered prices on application.



Giant Colonial Column. 10-G-344.
Fluted Shaft

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

COLUMNS, NEWELS.

PORCH MATERIAL

BALUSTERS, RAILS, ETC.

All outside material used in building should be adapted to the purpose. We have made a careful selection of the best weather resisting, paint holding woods for our Columns, Newels, Balusters, Cresting, Rafter Ends, etc., shown on this page.

SQUARE BUILT-UP COLUMNS AND NEWELS. There is considerable demand for square Colonial Columns, which usually have to be made to order—an expensive proposition. By having these Columns made in quantities, we are able to offer a solidly-built, high-grade Square Column at a price that is right. The Square Newel, 10-E-521, is made to match, but also can be used with round columns as well. The Box Porch Newel, 10-E-522, is neat and plain and will match with almost any style column. Remember, these are Built-up Columns, not solid or bored posts.




10-G-520


Size.	Length.	Price, Each.
8"x 8"	8	\$2.04
8"x 8"	9	2.22
8"x 8"	10	2.37
10"x10"	8	2.74
10"x10"	9	3.00
10"x10"	10	3.85
12"x12"	8	4.14
12"x12"	9	4.76
12"x12"	10	5.25

Newel 10-G-521.

Size.	Price, Each.
8"x 8"-4'-0"	\$1.22
10"x10"-4'-0"	1.61
12"x12"-4'-0"	2.19



10-G-521



10-E-522

Solid Wood Posts and Newels.

Fancy Turned Columns. 10-E-113. Prices.

Size.	8 ft.	9 ft.	10 ft.
4"x4"	\$0.68	\$0.73	\$0.97
5"x5"	1.02	1.15	1.32
6"x6"	1.52	1.68	1.94

Newels.

Size.	No. 10-G-112.	No. 10-E-114.	No. 10-E-115.
4"x4"-4 ft.	\$0.42	\$0.41	
5"x5"-4 ft.	.61	.59	
6"x6"-4 ft.	\$1.05	.78	.76
8"x8"-4 ft.	1.20		
10"x10"-4 ft.	1.80		

Newel No. 10-G-522.

Size.	Price, Each.
6"x6"-3'-0"	\$1.15
6"x6"-4'-0"	1.40



10-E-115.



10-G-112.




10-E-114.



10-G-113

Porch Rails



10-G-606.
Colonial Top
Rail,
Extra Heavy,
2 1/2"x3 1/2",
Per 100 Lin. ft.
\$6.50



10-G-145.
Special Top
Rail,
Extra Heavy,
2 1/2"x3 1/2",
Per 100 Lin. ft.
\$6.00



10-G-607.
Colonial Bottom
Rail, to match
above top rails.
Extra Heavy,
1 1/2"x3 1/2",
Per 100 Lin. ft.
\$5.25



10-G-146.
Top Rail,
1 1/2"x3",
Per 100 Lin. ft.
\$3.50



10-G-147.
Bottom Rail,
1 1/2"x3",
Per 100 Lin. ft.
\$3.50



10-E-149.
Frieze Rail,
1 1/2"x2 1/2",
Per 100 Lin. ft.
\$3.00



10-G-152.
Baluster Stock,
1 1/2"x1 1/2",
Per 100 Lin. ft.
\$1.25



10-G-151.
Baluster Stock,
1 1/2"x1 1/2",
Per 100 Lin. ft.
\$2.00


Porch Balusters and Spindles



Size.	Price, each.
1 1/2"x20"	\$0.05
1 1/2"x24"	.06

No. 10-E-200. Baluster Stock. Not beaded, 1 1/2"x1 1/2" inch square
Price per 100 lin. ft. **86c**


ROOF CRESTING. 10-E-573



Furnished in two sizes, 7-8x4 in., and 7-8x6 in.
End Bracket extra price, see below.

10-E-573.	1/4 in. Price per foot.	\$0.06
10-E-573 1/2.	1/2 in. Price per foot.	.07
10-E-575.	End Bracket. Price each.	.08

RAFTER ENDS.



10-E-590. 10-E-591. 10-E-592. 10-E-593.
Made from 2x4 stock, Select Common Norway and Cypress, surfaced four sides, cut as shown.
State pitch of roof on 10-E-590. Price each.

No.	4 ft.	5 ft.	6 ft.
10-E-590.....	14c	17c	21c
10-E-591.....	15c	18c	22c
10-E-592.....	22c	26c	31c
10-E-593.....	16c	19c	23c

Adjustable Gable Brackets



10-E-138. Adjustable to any pitch. Extends 4 feet down gable. Price, each. **\$1.00**

Sawed Balusters

Made of clear, soft pine
Good Workmanship.

10-E-601. Sawed Baluster, 1-inch thick, 5 1/2-inch wide, 2 ft. long.
Price, each


8c



Fancy Face Bracket

3-Member, 3 1/2-in. Thick.
10-E-137.

Size Inches	Price.
8x16.....	\$0.35
8x20.....	.40
8x24.....	.45
10x20.....	.55
10x24.....	.59
10x30.....	.72




Bay Bracket

10-E-612. 1 1/2-in. thick.

Size.	Price, each.
16x10.....	\$0.35
24x12.....	.45
28x14.....	.60
32x16.....	.70

Fancy Porch Brackets




10-E-134. 10-E-135

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

The Most Attractive Porches Will be Found in Our House Designs.

WINDOW AND SASH FRAMES



Window Frame No. 10-E-100

- No. 10-E-100A. Stationary Sash Frame, $1\frac{1}{2}$ inch casing, size up to 40x40 inch, 1 Lt. \$1.30
 No. 10-E-100C. Stationary Sash Frame, $\frac{3}{4}$ inch casing, size up to 40x40 inch, 1 Lt. \$1.25
 No. 10-F-100D. Casement Sash Frame, $1\frac{1}{2}$ inch casing, size up to 40x40 inch. Detail Sill. \$1.50

Drip Cap Window Frames

$1\frac{1}{2}$ inch Outside Casing


Window frame No. 10-E-100, includes everything complete, outside casing $1\frac{1}{2}$ x $4\frac{1}{4}$ inch, main sill $1\frac{1}{4}$ x $3\frac{3}{4}$ inch, sub sill $\frac{3}{4}$ x $5\frac{1}{2}$ inch, jambs, including stile and blind stops, $5\frac{1}{2}$ inch wide, parting strip, etc. Made from sound select clear face cypress or fir. Bright stock, guaranteed high-class in every particular.

No. 10-E-100. Window frames including everything as described, complete bundled for shipment in the knock-down, with pockets and pulleys. Price. **\$1.85**

All usual size window frames carried in stock and all take the one price. Any carpenter can put a knock-down frame together in ten minutes.

SPECIAL No. 10E100B.

Window Frames same as 10-E-100, with $\frac{3}{4}$ x 4 inch outside casing WITHOUT pulleys or pockets. Price. **\$1.49**



Window Frame No. 10-E-108

Cement, Block, Stone or Brick Wall Window Frames

A Full Box Frame made to fit your windows

This frame has a $1\frac{1}{2}$ x $1\frac{1}{2}$ inch clear brick mould, $\frac{3}{4}$ x 5 inch blind stop, $\frac{3}{4}$ x $4\frac{1}{2}$ inch pulley stile, $\frac{1}{2}$ x $1\frac{1}{2}$ inch parting stop, $\frac{3}{4}$ x $4\frac{1}{4}$ inch rabbet box lining and $\frac{3}{4}$ x $4\frac{1}{2}$ inch back box lining. The box linings are made from sound lumber. All stock used is the best manufactured for this purpose.

No. 10-E-108. Knocked down and carefully bundled for shipment, described above.

For windows 2 feet 6 inches wide by 5 feet 2 inches high or smaller opening.

Price, with pockets and pulleys. **\$2.1**

For windows 2 feet 10 inches wide by 6 feet 6 inches high or smaller opening.

Price, with pockets and pulleys. **\$2.2**

WINDOW FRAMES FOR BRICK VENEER BUILDINGS

We can also furnish you window frames for Brick Veneered Buildings with 2x4 studding, material surfaced to standard size for an additional cost of 25 cents extra over the price of a regular Drip Cap window frame.


Crown Mould Cap Window Frames

$1\frac{1}{2}$ inch Outside Casing

This frame has $1\frac{1}{2}$ x 3 inch Drip Cap, $2\frac{1}{4}$ inch Crown moulding, $1\frac{1}{2}$ x 7 inch head casing, $1\frac{1}{2}$ x $4\frac{1}{4}$ inch outside casing, $1\frac{1}{2}$ x $5\frac{1}{2}$ inch jamb, including blind stop, $1\frac{1}{2}$ x $1\frac{1}{2}$ inch blind stop, $\frac{1}{2}$ x $1\frac{1}{2}$ inch parting stop, $1\frac{1}{2}$ x $5\frac{1}{4}$ inch sub sill, $1\frac{1}{4}$ x $3\frac{3}{4}$ inch main sill, including pockets and pulleys.

No. 10-E-105. Plain Crown mould cap window frame for frame buildings with 2x4 studding, standard size. Knocked down and carefully bundled for shipment. Price, with pulleys. **\$2.05**

All material used in our Frames is best adapted to the purpose. Sound select, clear face cypress or FIR.



Window Frame No. 10-E-105

- No. 10-E-105A. Stationary Sash Frame, $1\frac{1}{2}$ inch casing, up to 40x40 inch, 1 Lt. \$1.40
 No. 10-E-105B. Stationary Sash Frame, $\frac{3}{4}$ inch casing, up to 40x40 inch, 1 Lt. 1.35
 No. 10-F-105C. Casement Sash Frame, $1\frac{1}{2}$ inch casing, size up to 40x40 inch. Detail Sill. 1.70

CELLAR FRAMES


ANY STYLE OR KIND OF FRAME THAT'S MADE. IF WE DON'T LIST JUST WHAT YOU WANT, SEND DESCRIPTION AND WE WILL NAME YOU A LOW PRICE

Cellar Sash Frame No. 10-E-107


Plank cellar sash frames are made with a $1\frac{1}{2}$ x 5 inch jamb, $1\frac{1}{2}$ x $1\frac{1}{4}$ inch clear brick moulding. Knocked down, bundled for shipment. Made of cypress or FIR sound select stock.

No. 10-E-107. Plank cellar sash frame, size 3 feet 4 inches by 2 feet or smaller openings. Price. **\$1.1**

All Mill Work and Lumber in this Catalogue is BRAND NEW. We Guarantee this, and Our GUARANTEE IS ABSOLUTELY GOOD AND BINDING.



OUTSIDE DOOR FRAMES



Plain Drip-Cap Door Frames


1½ inch Outside Casing

DOOR FRAME No. 10-E-99

Outside door frame, No. 10-E-99 includes everything complete as shown; outside casing, 1½x4¼; oak sill, 1½x7½; rabbeted jamb, 1½x5½. Made from Select, sound cypress or fir. Bright stock, guaranteed high-class in every particular.

No. 10-G-99. Outside door frames including everything complete, oak sill, bundled for shipment in the knock-down. **\$2.00**

No. 10-G-413. Plain Drip Cap Door frame with transom head, not exceeding 2 feet in height, see illustration below, (transom sash not included). Price. **\$2.30**



Crown Mould Cap Door Frames

1½ inch Outside Casing


This frame has 1½x3 inch Drip Cap, 1½x7 inch head casing, 1½x4¼ inch outside casing, 2¼ inch crown moulding, 1½x5½ inch jamb, rabbeted to suit thickness of door, oak sill.

No. 10-G-103. Crown mould cap outside door frame for frame buildings with 2x4 studding. Knocked down and carefully bundled. For door 3 ft. by 7 ft. or smaller opening. Price. **\$2.27**

No. 10-G-414. Crown mold cap door frame with transom head, not exceeding 2 ft. in height, see illustration to the right (transom sash not included.) Price. **\$2.59**

Door Frame No. 10-E-103

For Door Frame as above, without sill, deduct 25c.



Cement Block, Stone or Brick Wall Door Frames

This frame has a 1½x1½ inch clear brick moulding. The jamb is good, sound and practically clear. No sill furnished with this frame. Frames are used for stone, brick or cement buildings. Shipped, knocked down and carefully bundled.

No. 10-G-106-A. For 2x6 jamb
2 ft. 6 in. x 6 ft. 6 in. **\$1.65**
2 ft. 8 in. x 6 ft. 8 in. **1.70**
3 ft. x 7 ft. **1.80**


No. 10-G-106. For 2x8 jamb
2 ft. 6 in. x 6 ft. 6 in. **\$2.30**
2 ft. 8 in. x 6 ft. 8 in. **2.35**
3 ft. x 7 ft. **2.45**

No. 10-G-106½. For 2x10 jamb
2 ft. 6 in. x 6 ft. 6 in. **\$2.70**
2 ft. 8 in. x 6 ft. 8 in. **2.75**
3 ft. x 7 ft. **2.90**

In ordering be sure to state the thickness of the wall.

No. 10-G-415. Plank door frame with transom head, not exceeding 2 ft. in height, see illustration below, (transom sash not included.) Add to price above. **40c**

Transom Head Frames




No. 10-G-413
Plain Drip Cap Transom Head Door Frame.


For prices on transom head frames see No. 10-G-413, No. 10-G-414 and No. 10-G-415 under the respective door frames shown above and to the left.

Be careful to specify correct article number and height of transom you will use. Transom sash is never furnished with transom door frame. Same are listed elsewhere in this book. See Index.

When ordering frame for cement block, stone or brick wall, be sure to mention width of jamb wanted and allow correct price.




No. 10-G-414
Crown Mould Cap Transom Head Door Frame.




No. 10-G-415
Plank Transom Head Door Frame.


New, Bright, Clear Stock



O. G. CASING



ROUND EDGE CASING



OVALO CASING



BACK BAND CASING

MODERN INTERIOR FINISH

In Modern Interior Finish, we still maintain our position as foremost in quality variety and originality of design—at the same time giving our customers the benefit of lowest prices consistent with the high quality of our goods.

Careful regard is given to uniformity in manufacture, matching of design, blending grains, etc. Selected stock only is used and every piece must come up to our high standard or it is cast aside. The lumber used is put through a process of seasoning and drying which renders it in prime condition for any style of finish desired—oil, varnish, paint or stain.

On this page we show some of our most desirable designs in Casing and Base. Any standard pattern can be furnished or special designs made to order. Write for prices.

You will notice that we quote on Yellow Pine, Cypress, Oak and Birch—guaranteed strictly clear stock. Other kinds of wood can be furnished but the four listed here are all that we regularly carry in stock and with very few exceptions, meet the usual demands.


Prices of Casing per 100 Lineal Feet.

Style	Size	Lot No.	Yellow Pine	Cypress	Birch	Oak
O. G. Casing	1 1/2" x 4 1/2"	10-F-8384.	\$1.87			
	" x 5 1/2"	10-F-8385.	2.20			
Round Edge Casing	" x 3 1/2"	10-F-8308.	1.79	\$2.07	\$3.22	\$3.40
"	" x 4 1/2"	10-F-8309.	1.91	2.37	3.63	3.80
"	" x 5 1/2"	10-F-8310.	2.11	2.67	3.97	4.10
Ovalo Casing	" x 4 1/2"	10-F-8311.	2.71	2.95	4.85	5.00
"	" x 5 1/2"	10-F-8341.	2.02	2.47	3.63	3.80
"	" x 4 1/2"	10-F-8342.	2.27	2.69	4.01	4.80

TWO-MEMBER BACK BAND CASING. Each Member Priced Separately.

Casing	1 1/2" x 3 1/2"	10-F-1000.	1.76	2.03	3.34	3.80
	" x 4 1/2"	10-F-1001.	1.96	2.42	4.00	4.40
Back Band Mold	1" x 1 1/2"	10-F-1002.	1.28	1.50	2.46	2.80

No. 10-F-8386	Regular Size	per 100 Lineal Feet	No. 10-F-8385	per 100 Lineal Feet
O. G. Base			O. G. Closet Base	
Yellow Pine	1 1/2" x 7 1/4"	\$2.94	1 1/2" x 5 1/4"	\$2.20




O. G. BASE MOULDED BASE

Moulded Base.		
No. 10-F 8426	Size	Per 100 Lineal Feet
Yellow Pine	1 1/2" x 7 1/4"	3.91
Cypress	1 1/2" x 7 1/4"	6.05
Birch	1 1/2" x 7 1/4"	6.37
Oak	1 1/2" x 7 1/4"	

Round Edge Base		
No. 10-F-1003	Size	per 100 Lineal Feet
Yellow Pine	1 1/2" x 7 1/4"	\$3.19
Cypress	1 1/2" x 7 1/4"	4.07
Birch	1 1/2" x 7 1/4"	6.67
Oak	1 1/2" x 7 1/4"	6.95

3 Member Base.		
Each Member priced separately		
Base Mold.	Yellow Pine	\$1.08
No. 10-F-8420.	Cypress	1.38
1 1/2" x 2 1/4"	Birch	2.09
	Oak	2.26
Main Base.	Yellow Pine	2.94
No. 10-F-8421	Cypress	4.05
1 1/2" x 7 1/2"	Birch	6.23
	Oak	6.62
Base Shoe.	Yellow Pine	.33
No. 10-F-8422	Cypress	.46
1 1/2" x 3"	Birch	.77
	Oak	.81

Special Pattern Base.		
Base Mold.	Yellow Pine	\$1.28
No. 10-F-1004	Cypress	1.50
1 1/2" x 1 1/2"	Birch	2.46
	Oak	2.55
Main Base.	Yellow Pine	3.08
No. 10-F-1005	Cypress	4.18
1 1/2" x 7 1/2"	Birch	6.88
	Oak	7.17



ROUND EDGE BASE

3-MEMBER BASE

SPECIAL PATTERN BASE

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Base Shoe No. 10-E-8422, priced above.

For Satisfactory Results Use Our High Grade Paints, Stains, Oils and Varnishes.

Bright, Clear Stock

INTERIOR MOULDINGS

Fresh from the Machines

See description on preceding page which applies to all Interior Finish shown here. We handle only new, bright stock of the very best manufacture.

3-MEMBER HEAD TRIM.

Prices per 100 Lineal Feet.

Each member priced separately.	Size	Yellow Pine	Cypress	Birch	Oak
Cap Mold, 10-F-8396	1 1/8"x2 1/4"	\$1.65	\$2.13	\$3.49	\$3.65
Head Cas'g, 10-F-8394	1 1/8"x4 1/2"	1.87	2.41	3.83	3.99
Fillet, 10-F-8395.....	1 1/8"x1"	.36	.53	.87	1.01

4-MEMBER HEAD TRIM.

Prices per 100 Lineal Feet.

Each member priced separately.	Size	Yellow Pine	Cypress	Birch	Oak
Cap Mold, 10-F-8410.	1 1/8"x2 3/4"	\$2.11	\$2.46	\$4.05	\$4.22
Embossed Mold, 10-F-194	1 1/8"x1"	.96	1.10	1.18	1.27
Head Cas'g, 10-F-8394	1 1/8"x4 1/2"	1.87	2.41	3.83	3.99
Fillet, 10-F-8395.....	1 1/8"x1"	.36	.53	.87	1.01

3-Member Head Trim.

4-Member Head Trim.

PICTURE MOLD.

10-F-8264.

Prices per 100 Lineal Feet.

Size	Yellow Pine	Cypress	Birch	Oak
1 1/8"x1 1/4"	\$0.66	\$0.94	\$1.53	\$1.60

CHAIR RAIL.

Prices per 100 Lineal Feet.

Lot No.	Size	Yellow Pine	Cypress	Birch	Oak
10-F-1035	1 1/2"x3 1/2"	\$1.74	\$2.02	\$3.33	\$3.48

HOOK STRIPS.

Prices on Yellow Pine.

Lot Number	Size	Per 100 Lineal Feet
10-F-8234.....	1 1/8"x2 1/2"	\$1.30
10-F-8233.....	1 1/8"x3"	1.53

O. G. DOOR AND WINDOW STOPS.

Prices per 100 Lineal Feet.

Lot No.	Size	Yellow Pine	Cypress	Birch	Oak
10-F-8083	1 1/8"x1 1/2"	\$0.33
10-F-8084	1 1/8"x1 1/2"	.36	\$0.52	\$0.85	\$0.88
10-F-8085	1 1/8"x1 1/2"	.46
10-F-8095	1 1/8"x1 1/2"	.40	.56	.92	.96
10-F-8095	1 1/8"x1 1/2"	.53	.76	1.21	1.28
10-F-8093	1 1/8"x2 1/4"	.88	1.03	1.69	1.76

WAINSCOTING CAP.

10-F-8228.

Suitable for 1/2 inch and 3/4 inch Wainscoting.

Price per 100 Lineal Feet.

Size	Yellow Pine
1 1/8"x2"	\$1.14

COVE OR SCOTIA.

10-F-8060.

Size, 3/4 x 1 1/4.

Price per 100 Lineal Feet.

Yellow Pine	Cypress	Birch	Oak
\$0.33	\$0.52	\$0.77	\$0.81

10-F-8061.

Size, 1 1/8"x1 1/4".

Yellow Pine	Cypress	Birch	Oak
\$0.46	\$0.65	\$1.06	\$1.10

QUARTER ROUND.

Prices per 100 Lineal Ft.

No.	Size	Yellow Pine
10-F-8063	1 1/8"x1 1/2"	\$0.36
10-F-8064	1 1/8"x1 1/2"	.38
10-F-8065	1 1/8"x1 1/2"	.33
10-F-8066	1 1/8"x1 1/2"	.35
10-F-8067	1 1/8"x1 1/2"	.70

10-F-8065. Size 1 1/8"x1 1/4"

Cypress	Birch	Oak
\$0.46	\$0.79	\$0.80

Window Stool and Apron.

WINDOW STOOL.

10-F-8267.

Price per 100 Lineal Feet.

Size	Yellow Pine	Cypress	Birch	Oak
1 1/8"x3 1/4"	\$2.44	\$3.28	\$5.05	\$5.27

WINDOW APRON.

10-F-8379.

Price per 100 Lineal Feet.

Size	Yellow Pine	Cypress	Birch	Oak
1 1/8"x3 1/4"	\$1.74	\$2.02	\$3.22	\$3.35

All clear lumber described on this page. Special prices will be quoted on Quarter-Sawn Red or White Oak Finish.

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago



Special Mill Work—We Can Make Any Kind to Order

Correct Craftsman Interior Trim

Pretty Effects — Exclusive Designs

Every once in a while someone demands something different from the usual order of things, and to keep pace with the times we present our exclusive line of craftsman casings and other inside trimmings.

Original and neat in design. Architecturally correct. Our artistic arrangement will appeal to everyone interested in interior trimmings of refinement and good taste—embodying both simplicity of style and economy in price.


CRAFTSMAN CASING

Neat, nifty and new. Different from the common kind. Will also match other designs of trim.



We ship mixed lengths from 8 to 16 ft. Furnished in specified lengths, 5, 6, 7, and 8 ft., or longer lengths to cut them out of so there will be no waste. No separate lengths supplied in longer lengths.


Order by Number	Prices per 100 Lineal Feet	YELLOW PINE Width		RED OAK Width	
		4 1/4 in.	4 3/4 in.	4 1/4 in.	4 3/4 in.
10-G-1040	Craftsmans Casings	\$1.90	\$2.10	\$3.80	\$4.20



CRAFTSMAN WINDOW STOOL

Price per 100 Lineal Feet. Mixed Lengths.

Number	Size	Wood	Price
10-G-1041	1 1/2 x 3 3/4"	Yellow Pine	\$2.44
10-G-1042	1 1/2 x 3 3/4"	Red Oak	5.28



CRAFTSMAN 3-MEMBER BASE

All prices per 100 Lineal feet. Furnished mixed lengths only.

Size of top member or Base Moulding is 3/4 x 1 1/2 in.
Size of center member or Main Base is 1 1/2 x 5 1/2 in.
Size of lower member or Base Shoe is 3/4 x 3/4 in.

Order by number and name, state kind of wood and allow correct price.

Number	Name	Wood	Price
10-G-1043	Base Moulding	Yellow Pine	\$0.60
10-G-1044	Main Base	Yellow Pine	2.52
10-G-1055	Base Shoe	Yellow Pine	0.40
10-G-1056	Base Moulding	Red Oak	1.20
10-G-1057	Main Base	Red Oak	5.04
10-G-1058	Base Shoe	Red Oak	0.80



Craftsman Stops

Price per 100 Lineal feet. Mixed lengths only.
The 3/4 x 1 1/2 size are for Window frames and 1/2 x 1 1/2 size for door jambs. Other sizes extra price.


Number	Size	Wood	Price
10-G-1080	3/4 x 1 1/2 in.	Yellow Pine	\$0.44
10-G-1081	1/2 x 1 1/2 in.	Yellow Pine	.64
10-G-1082	3/4 x 1 1/2 in.	Red Oak	.88
10-G-1083	1/2 x 1 1/2 in.	Red Oak	1.28

Craftsman 3-Member Headtrim

All prices per 100 Lineal feet. Furnished mixed lengths only.

Size of top member or Cap Moulding is 1 1/2 x 1 1/2 in.
Size of center member or Head Casing is 1 1/2 x 4 1/2 in.
Size of lower member or Fillet is 1/2 x 1 1/2 in.
Order by number and name and allow correct price. Each member priced separately.

Number	Name	Name	Price
10-G-1059	Cap Moulding	Yellow Pine	\$1.32
10-G-1060	Head Casing	Yellow Pine	2.00
10-G-1061	Fillet	Yellow Pine	.56
10-G-1063	Cap Moulding	Red Oak	2.64
10-G-1064	Head Casing	Red Oak	4.00
10-G-1075	Fillet	Red Oak	1.12



Craftsman Window Apron

Price per 100 Lineal feet. Mixed lengths.

Number	Size	Wood	Price
10-G-1076	1 1/2 x 3 3/4 in.	Yellow Pine	\$1.68
10-G-1077	1 1/2 x 3 3/4 in.	Red Oak	3.33



Craftsman Picture Mold

Price per 100 Lineal Feet. Mixed lengths only.

Number	Size	Wood	Price
10-G-1078	1 1/2 x 1 1/4 in.	Yellow Pine	\$0.80
10-G-1079	1 1/2 x 1 1/4 in.	Red Oak	1.60

Craftsman Base Block

Thickness 1 1/2 in. Width to match 4 1/4 in. and 4 3/4 in. casing. Length 10 in. Order by number, give width and kind of wood.

Number	Wood	Price each	
		4 1/4 in. Wide	5 in. Wide
10-G-1084	Yellow Pine	4 c	4 1/2 c
10-G-1100	Red Oak	6 1/2 c	7 c



DASHING SLASH GRAIN FIR TRIM


The Conquering Fir is King—The Continent's Last Stand

When the Northern White Pine Forests became depleted and the East and South failed to produce a suitable substitute for certain purposes (both in price and quality) "Westward-Ho" became the watchword, till now the famous Oregon and Washington Douglas Fir Forests are truly the "Continent's Last Stand."

Very Susceptible to Imitative Treatment

By an ingenious method of combining inexpensive ingredients, the modern chemist produces Rubies and other precious jewels in perfect imitation of the genuine and so may anyone, by the use of our various oils and stains, transmute the economical and inimitable Douglas Fir finish into higher priced woods such as Rotary Cut Red Oak, Curly Red Birch, Mahogany, Cherry, Rosewood, Fumed and Mission Oak. In fact, any variety of shades almost without limit. And the softer the color, the truer it harmonizes. No other low priced wood lends itself so admirably for this purpose. Sizes and designs of trim shown are sufficient to cover any ordinary complete requirements, and we aim to carry same in stock, so by confining yourself to these limits, prompt shipment will be effected.

Different sections of the Pacific Coast produce different species, among which Douglas Fir takes first rank. And since it comes under the heading of Soft Wood it makes also a fine lumber for outside finishing boards.



PRICE LIST OF FIR TRIM

All prices per 100 lineal feet. Order by number and name

Number	Name	Size	Price
10-G-1101	Molded Base	1 1/2 x 7 1/2	\$2.84
10-G-1102	Main Base	1 1/2 x 7 1/2	2.93
10-G-1103	Base Mold	1 1/2 x 1 1/2	1.06
10-G-1104	Base Shoe	1 1/2 x 1 1/2	.36
10-G-1105	Window Stool	1 1/2 x 3 1/2	2.38
10-G-1106	Window Apron	1 1/2 x 3 1/2	1.51
10-G-1107	Cap Mold	1 1/2 x 2 1/2	1.50
10-G-1108	Head Casing	1 1/2 x 4 1/2	1.80
10-G-1109	Fillet Mold	1 1/2 x 1	.41
10-G-1110	Picture Mold	1 1/2 x 1 3/4	.72
10-G-1111	Cove Mold	1 1/2 x 1 1/4	.37
10-G-1112	Chair Rail	1 1/2 x 3 1/2	1.44
10-G-1113	Window Stop	1 1/2 x 1 3/4	.40
10-G-1114	Door Stop	1 1/2 x 1 3/4	.58

PRICE OF FIR CASINGS

Back band priced separately.



Number	Name	Size	Price
10-G-1125	Round Edge	1 1/2 x 4 1/2	\$1.70
10-G-1126	"	1 1/2 x 4 3/4	1.90
10-G-1127	Mission	1 1/2 x 3 1/2	1.45
10-G-1128	"	1 1/2 x 4 1/2	1.71
10-G-1129	Back Band	1 1/2 x 1 1/2	1.10

No Base Blocks are needed with Back Band Casing

PRICE OF FIR BASE BLOCKS

1 1/2 inch thick. Order by number.

Number	Width	Length	Price each
10-G-1130	4 1/2 inches	10 inches	\$0.04 1/2
10-G-1131	5 inches	10 inches	.05




SIDES OF WINDOW TRIM

Read what we have to say regarding Door Trims on preceding page. The same description applies to material used for our Window Trims as well as all interior finish furnished by us. The same careful selection is made and the same careful attention is given to matching grain.

In ordering your finish from these two pages of trim, it is of course advisable that you select door and window trim of the same style.

Please understand that we furnish **material only** for these trims. Better results are to be obtained by fitting on the job. We furnish in suitable lengths, the nearest sizes to required dimension.

The Casings, Head Blocks, etc., used in our Window and Door Trims are fully described and priced separately elsewhere in this book. If you wish to buy the material by the foot instead of by the side of trim, you may be able to effect some saving—the main object in offering these trims being that you run no risk in wasting the material.



3 Member Cap Window Trim.

THREE MEMBER CAP WINDOW TRIM

Complete with O. G. Stops.

Set consist of 4 1/2 inch casing, Cap Mould, Head Casing, fillet, Stool No. 8267, Apron No. 8379 and O. G. Stops. Your choice of any style casing we list in Clear Yellow Pine, except the two-member Blackband casing.


Prices per set for window sizes up to 30x30—2 lights.

No.	Per Set
10-F-988.	Clear Yellow Pine... 72c
10-F-989.	Yellow Pine to paint. 60c
10-F-990.	Clear Red Oak... \$1.45

Prices for Window sizes ranging 35x24 to 40x36—2 lights.

10-F-996.	Clear Yellow Pine... 84c
10-F-997.	Yellow Pine to paint. 70c
10-F-998.	Clear Red Oak... \$1.70

We furnish enough Cap Mould to make returns on ends, but do not mitre them, nor does anyone else.



Corner Block Window Trim.

CORNER BLOCK WINDOW TRIM

Complete with O. G. Stops.

Price of Corner Block Window Trim. Set consists of Corner Blocks, Stool No. 8267, Apron No. 8379, 3 1/2 in. casing and O. G. Stops.

Prices for Window sizes up to 28x32—2 lights.


No.	Per Set
10-F-964.	Clear Yellow Pine... 63c
10-F-965.	Yellow Pine to Paint. 55c

Same as above, except Casing 4 1/2 inch wide.

10-F-966.	Clear Yellow Pine... 65c
10-F-967.	Yellow Pine to Paint. 58c

Same as above, except Casing 4 1/2 inch wide.

10-F-968.	Clear Yellow Pine... 77c
10-F-969.	Yellow Pine to Paint. 68c



Mission Window Trim.

MISSION STYLE WINDOW TRIM

Complete with O. G. Stops.

Yellow Pine set consists of Corner Block 10-F-964, Casing No. 8309, Apron No. 8379, Stool No. 8267, and O. G. Stops.

Price for Window sizes up to 30x32—2 lights.

No.	Per Set
10-F-944.	Clear Yellow Pine... 71c
10-F-945.	Clear Red Oak... \$1.40

Our Two-member Back band Casing, described on a preceding page, harmonizes extremely well with Mission furnishings.



O. G. Casing Window Trim.

BARGAIN O. G. CASING WINDOW TRIM

Complete with O. G. Stops.

Set O. G. Casing Window Trim consists of 4 1/2 inch O. G. Casing as ordered, Apron, Stool and Stops.

We do not cope or mitre our O. G. trim. This should be done on the Job to insure close fitting joints.

No. 10-F-977 1/2.
55c per set for 4 1/2-inch O. G. Casing. Window Trim in Yellow Pine to paint, for sizes up to 26x32—2 lights.

Suitable for paint finish only. Good, sound, well finished stock. Just the same as clear, except that it may be slightly soiled or stained.

No. 10-F-978 1/2.

64c per set for Clear Yellow Pine.

This means the best of clear Yellow Pine. No defects permitted.

SPECIAL NOTE:—O. G. Stops furnished with Window Trim. Others figure this item as an extra.

48 Our Architectural Department Can Help You. Write for Book of Plans.

CHICAGO HOUSE WRECKING CO
25th & Iron Streets, Chicago.


SIDES OF DOOR TRIM

The best known and most largely used styles of Interior Trim are shown on this page and the page following. The stock from which our orders are filled is run fresh every day, the output sometimes running as high as 10 carloads. Thus you are assured of getting freshly machined goods that will come to you just as turned out by the factory, everything packed and bundled with great care to insure reaching you in the best condition.

Our stocks are carefully selected, too. We do not use lumber for this purpose unless it passes strict inspection. Every piece must be thoroughly seasoned and properly dried or it is not acceptable. Then, too, in making up these trims careful regard is given to the matching of the grain—a point too often overlooked by competitors.

Our Clear Yellow Pine is the best oil finish stock ever offered and it has the prettiest grain. Our Clear Red Oak is regular sawed stock, showing all the beautiful variations of the flowing grain. All of our Interior Finish is perfectly manufactured and smoothly run.

You will note that in addition to Clear Yellow Pine we list Yellow Pine for Paint finish. This is stock which is slightly sap-stained or in which the graining is not perfect; but, except for such minor defects, it is the same in manufacture and condition as the Clear grade. It is plenty good enough for paint jobs but not recommended for natural finish.



3 Member Cap Door Trim.

3 Member Cap Door Trim

Complete with O. G. Stops.

Set consists of 4½ inch Casing, two Base Blocks, Cap Mould, Head Casing, fillet and the necessary O. G. Stops.

Price for sizes up to 2 ft. 8 in. by 6 ft. 8 in.

No.	Per Set
10-F-914. Clear Yellow Pine.....	.63c

This means the best grade of clear Yellow (or Georgia) Pine to be had, no defects permitted, nice, bright, clean, smooth finished stock.

10-F-915. Yellow Pine to paint....	.58c
------------------------------------	------

Material suitable for paint finish and may be slightly soiled or stained.

10-F-916. Clear Red Oak.....	\$1.22
------------------------------	--------

Prices up to 3 ft. x 7 ft. 6 in.

10-F-920. Clear Yellow Pine.....	.70c
----------------------------------	------

10-F-921. Yellow Pine to paint....	.62c
------------------------------------	------

10-E-922. Clear Red Oak.....	\$1.35
------------------------------	--------



Corner Block Door Trim.

Corner Block Door Trim

Complete with O. G. Stops.

Set consists of 4½ inch Casing, two Base blocks, two Corner blocks, O. G. Stops.

Prices for sizes up to 2 ft. 8 in. by 6 ft. 8 in.

No.	Per Set
10-F-900. Clear Yellow Pine.....	.56c

This means the best grade of clear Yellow (or Georgia) Pine to be had. No defects permitted. Nice, bright, clean, smooth finished stock.


10-F-901. Yellow Pine to paint....	.49c
------------------------------------	------

Material is suitable for paint finish and may be slightly soiled or stained.

Up to 3 ft. by 7 ft. 6 in.

10-F-902. Clear Yellow Pine.....	.65c
----------------------------------	------

10-F-903. Yellow Pine to paint....	.57c
------------------------------------	------



Mission Style Door Trim.

Mission Style Door Trim

Complete with O. G. Stops.

Set consists of Corner Blocks, Base Blocks, No. 8309 Casing and O. G. Stops.

Price for sizes up to 3 ft. by 7 ft.

No.	Per Set
10-F-934. Clear Yellow Pine.....	.65c

This means the best grade of clear Yellow, (or Georgia) Pine to be had. No defects permitted. Nice, bright, clean, smooth finished stock.

10-F-935. Clear Red Oak.....	\$1.20
------------------------------	--------

The Mission Style Door Trim, is appropriate to use with our Flush Veneered Slab Doors or with one panel or two panel doors.



O. G. Casing Door Trim.

Bargain O. G. Casing Door Trim

Complete with O. G. Stops.

Set consists of 4½ inch O. G. Casing and Stops in Yellow Pine.

Sizes up to 2 ft. 8 in. by 6 ft. 8 in.

10-F-974½. Suitable for paint finish only. Good, sound, well finished stock. Just the same as clear, except that it may be slightly soiled or stained.

Price per set.....

10-F-975½. For Clear Yellow Pine..	.43c
------------------------------------	------

10-F-976½. For larger sizes up to 3 ft. by 7 ft. 6 in. add only.....	.10c
--	------

MISCELLANEOUS MOULDINGS

Trimmings For the Interior




Plate Rail
No.
10-F-340.

Furnished in clear Selected Yellow Pine or Oak. Three member. Projection from wall $4\frac{1}{2}$ inches. Height over all $4\frac{1}{2}$ inches. Price complete as shown.

Plate Rail 10-F-340.

Yellow Pine.....Per Lineal Foot.....\$0.07
Oak....."....."......11



Combination
Plate Rail
and Picture Mold.

Two members, fitted and glued together. Serves double purpose of Plate Rail and Picture Mold at price of one. Projection from wall 3 inches. Height over all 2 inches. Price complete as shown.

10-F-343. Per Lineal Foot.

Yellow Pine.....\$0.06
Oak......07



BASE
BLOCKS

$1\frac{1}{2}$ inch Thick

10 inches Long

Be Sure to State

No. 10-E-144. Width. No. 10-E-143


No.	Wood.	Price each	4 in. wide.	5 in. wide.	5 in. wide.
10-E-143	Yel. Pine	\$0.04	\$0.04	\$0.05	\$0.05
10-E-144	Yel. Pine	.04	.04	.04	.04
10-E-177	Cypress	.05	.05	.07	.07
10-E-159	Pl. R. Oak	.06	.07	.07	.07
10-E-178	Birch	.07	.07	.08	.08

HEAD BLOCK

No. 10-E-141.

CORNER BLOCKS

Nos. 10-E-142 and 10-E-164.



No. 10-E-141. No. 10-E-142. No. 10-E-164.
Prices of blocks, $1\frac{1}{2}$ inches thick.

No.	Wood.	4 in. wide.	5 in. wide.	5 in. wide.
10-E-141	Yel. Pine	\$0.04	\$0.05	\$0.05
10-E-142	Yel. Pine	.02	.02	.02
10-E-164	Yel. Pine	.02	.02	.03
10-E-164-C	Cypress	.03	.03	.04
10-E-164-O	Oak	.03	.04	.05
10-E-164-B	Birch	.03	.03	.04

Be sure to state width wanted.





Plate Rail
No.
10-F-341.

Embossed Moulding. Three member. Furnished in Clear Yellow Pine or Oak, carefully selected. Projection from wall $4\frac{1}{2}$ inches. Height over all $4\frac{1}{2}$ inches. Price complete as shown.

Plate Rail 10-F-341.

Yellow Pine.....Per Lineal Foot.....\$0.08
Oak....."....."......12

SLIDING AND FOLDING DOOR ASTRAGALS.



No. 10-E-8446.

10-E-8446. Sliding Door Astragal, Yellow Pine, for $1\frac{1}{2}$ Doors, 8 feet length. Price per pair...\$0.75

No. 10-E-8449.


10-E-8449. Folding Door Astragal, Yellow Pine, for $1\frac{1}{2}$ Door, 8 feet length. Price each...\$0.40
For Oak Astragal 10-E-8446, add 25 cts; 10-E-8449, add 15 cts

BASE ANGLES



No.	Size.	Wood.	Price, per 100.
10-E-131	$1\frac{1}{2}$ x12" or 14"	Yel. Pine	\$1.90
10-E-186	$1\frac{1}{2}$ x12"	Cypress	2.75
10-E-161	$1\frac{1}{2}$ x12"	Pl. R. Oak	2.75
10-E-187	$1\frac{1}{2}$ x12"	Birch	3.33

CORNER BEADS



No.	Size.	Wood.	Price, Ea.
10-E-130	$1\frac{1}{2}$ x4	Yel. Pine	\$0.09
10-E-130	$1\frac{1}{2}$ x4	Yel. Pine	.12
10-E-184	$1\frac{1}{2}$ x4	Cypress	.12
10-E-160	$1\frac{1}{2}$ x4	Pl. R. Oak	.13
10-E-185	$1\frac{1}{2}$ x4	Birch	.13

HARDWOOD THRESHOLDS



No. 10-E-154.

Clear Maple, length 3 feet. Price, each.....5 c
Clear Oak, length 3 feet. Price, each.....6 c





Plate Rail
No.
10-F-342.

Three member Rail with Brackets. The Brackets have $1\frac{1}{2}$ inch face and furnished to space regularly in proportion to the length of the rail. Clear Yellow Pine or Oak—selected stock. Projection from wall $4\frac{1}{2}$ inches. Height over all $4\frac{1}{2}$ inches. Price complete as shown.

Plate Rail 10-F-342.

Yellow Pine.....Per Lineal Foot.....\$0.10
Oak....."....."......15

EMBOSSED PICTURE MOLD



Price per 100 lineal feet.

No.	Size.	Wood	Price.
10-F-188	13-16x1 $\frac{1}{2}$	Yel. Pine	\$1.49
10-F-189	13-16x1 $\frac{1}{2}$	Pl. R. Oak	1.76


EMBOSSED EGG AND DART MOLD



Price per 100 lineal feet

No.	Wood	Size.	Price.
10-F-194	Yel. Pine	$\frac{3}{4}$ x1 $\frac{1}{2}$	\$0.88
10-F-195	Oak	$\frac{3}{4}$ x1 $\frac{1}{2}$.99
			1.27

SINK TRIMMINGS



Drip Board.

Sink Leg.

Sink Capping.

Apron.

Prices of Sink Trimmings.

Furnished in Plain Oak—Selected stock. Apron will be shipped plain, not beaded.

No.	Size.	Price.
10-E-179	Sink Board...24x24	Each, \$0.48
10-E-180	Sink Board...24x30	.50
10-E-181	Sink Legs...12x30	.12
10-E-182	Sink Apron...12x5 $\frac{1}{2}$	Per ft., .05
10-E-183	Sink Capping...12x3	.03

OUTSIDE MOULDINGS—SUPERIOR QUALITY

Clear Soft Woods for Paint

CROWN MOULDINGS.

Price per 100 lineal feet.

No.	Size.	Poplar or Soft Pine.
10E8000	3x1	\$1.55
10E8002	3x1	1.76
10E8003	3x2	1.32
10E8005	4x1	2.20
10E8006	4x2	1.99
10E8007	4x1	.88
10E8008	2x1	1.11

CROWN MOULDINGS.

No.	Size.	Poplar or Soft Pine.
10E8009	3x1	\$1.76
10E8010	3x2	1.32
10E8011	3x1	1.11
10E8012	4x1	1.99
10E8013	4x2	2.20
10E8014	3x1	1.55

BED MOULDINGS.

Price per 100 lineal feet.

No.	Size.	Poplar or Soft Pine.
10E8015	1x1	\$0.40
10E8016	1x1	.88

CROWN OR BED MOULD.

Price per 100 lineal feet.

No.	Size.	Poplar or Soft Pine.
10E8018	1x2	\$1.11
10E8019	1x2	1.32
10E8020	1x3	1.55

SPRUNG COVE.

Price per 100 lineal feet.

No.	Size.	Poplar or Soft Pine.
10E8024	1x1	\$0.80
10E8025	1x2	1.17
10E8026	1x2	1.40
10E8029	1x3	1.64

SPRUNG BED MOULDING.

Price per 100 lineal feet.

No.	Size.	Soft Pine or Poplar.
10E8030	1x2	\$1.11
10E8031	1x1	.88
10E8032	1x2	1.00

BAND MOULDING.

Price per 100 lineal feet.

No.	Size.	Soft Pine or Poplar.
10E8186	1x1	\$0.93
10E8187	1x1	.80
10E8188	1x2	1.05
10E8180	1x2	1.28
10E8182	1x3	1.52

Our outside mouldings are better than the ordinary run of mouldings, because we machine a fresh supply daily, insuring new, clean and bright stock.

SOLID BED MOLDS.

Price per 100 lineal feet.

No.	Size.	Poplar or Soft Pine.
10E8035	1x1	\$0.47
10E8036	1x1	.65
10E8037	1x1	1.17
10E8042	1x1	.47

BRICK OR STONE MOULDING.

Price per 100 lineal feet.

No.	Size.	Soft.	Yellow Pine.
10F8038	1x1	\$1.55	\$1.32
10F8039	1x1	2.57	2.42
10F8047	1x1	1.61	1.53

RETURN BEADS.

Price per 100 lineal feet.

No.	Size.	Yellow Pine.
10F8049	1x1	\$2.15
10F8050	1x1	1.22
10F8051	1x1	.74

COVES.

Price per 100 lineal feet.

No.	Size.	Yellow Pine.	Soft Pine.
10F8060	1x1	\$0.36	\$0.40
10F8061	1x1	.45	.51

QUARTER-ROUND.

Price per 100 feet.

No.	Size.	Yellow Pine.	Soft Pine.
10F8065	1x1	\$0.36	\$0.40
10F8066	1x1	.37	.41
10F8067	1x1	.66	.71

HALF ROUND.

Price per 100 lineal feet.

No.	Size.	Yellow Pine.	Soft Pine.
10F8077	1x1	\$0.44	
10F8078	1x1	.52	
10F8080	1x1	.78	
10F8081	1x1	.88	


O. G. STOPS.

Price per 100 lineal feet.

No.	Size.	Soft Pine.
10E8083	1x1	\$0.40
10E8084	1x1	.44
10E8085	1x1	.56
10E8094	1x2	.72
10E8095	1x1	.71
10E8096	1x1	.53
10E8097	1x1	.45

NOSINGS.

Prices per 100 Lineal feet.



No.	Size.	Soft Pine or Yellow Pine.
10F8123	1x1 for in. steps	\$0.74
10F8124	1x2	1.65
10F8125	1x2	2.18
10F8126	1x2	3.87
10F8131	1x1 floors	.62

ASTRAGAL OR SCREEN MOULDING OR CLOVERLEAF.

Price per 100 lineal feet.

No.	Size.	Yel. Pine	Soft Wood
10F8140	1x1	\$0.36	\$0.40
10F8141	1x1	.45	.50
10F8142	1x1	.57	.60
10F8143	1x1	.65	.71

PANEL OR BASE MOULD.

No.	Size.	Soft Pine
10E8169	1x1	\$0.65
10E8175	1x1	.93
10E8177	1x2	1.05

LATTICE

Prices per 100 lineal feet.

No.	Size.	Yel. Pine	Soft Wood
10F8280	1x1	\$0.31	\$0.35
10F8281	1x1	.36	.40
10F8282	1x1	.52	.59

WATERTABLE OR DRIPCAP.

Price per 100 lineal feet.

No.	Size.	Soft Pine or Poplar.
10E8283	1x1	\$1.29
10E8284	1x2	1.65
10E8285	1x2	2.00
10E8286	1x3	2.37

WINDOW FRAME STOCK.

8429 1/2
1 1/2 x 4 1/2 OUTSIDE CASING

8430
1 1/2 x 1 1/2
BLIND STOP

8432
1 1/2 x 1 1/2
PARTING STOP

8431 1/2
1 1/2 x 4 1/2 PULLEY STYLE

Many carpenters prefer to make their own window frames. Here is an opportunity to buy all the material required at minimum cost. This stock will make an elegant frame.

10F8429 1/2 OUTSIDE CASING.
Price per 100 lineal feet. Size 1 1/2 x 4 1/2.
Clear Yellow Pine.....\$3.45
Clear Poplar or Cypress... 3.67

No. 10F8430. BLINDSTOP.
Per 100 lin. ft. Y. P.....\$0.56
W. P......67

No. 10F8432 PARTINGSTOP.
Per 100 lin. ft. Y. P.....\$0.36
No. 10F8431 1/2 PULLEY STYLE.
Pulowed for parting stop.
Size 1 1/2 x 4 1/2. Price per 100 lineal feet. Yellow Pine practically clear.....\$2.20


No. 10E8440 1/2 SUBSILL.
Edges not Beveled. Size 1 1/2 x 5 1/2
Price per 100 lineal feet good sound stock.....\$2.80

No. 10E8439 1/2 MAINSILL.
Beveled edges and rabbeted for siding.
Size 1 1/2 x 3 1/2. Sound solid Cypress, Poplar and Fir stock. Price per 100 lineal feet.....\$5.13

**Highest Grade
Selected Stock**

STAIR MATERIAL

**Best
Workmanship**



The above illustration does not represent any particular one of our designs, merely showing a main landing view so that some idea may be gained of how the completed stairway will look.

Similar in design to our Stairways No. 10-E-631, No. 10-E-634 and 10-E-637.

GOODS OF SUPERIOR MERIT. PRICES THAT DEFY COMPETITION


Beginning with this page, we have for the attention of interested builders a fine line of first class materials for practically every kind of stair work. The very best selected stock is required for this kind of work and we have made it a special aim to give full measure of quality in addition to meeting and under-selling all competitors.

The stairway is the first thing to be noticed about the interior of a house, just as the stairway picture caught your eye when you opened the book at this page. Therefore, it is essential that you look well to the style and class of material used for this purpose.

We are positive that we are able to furnish better material at lower prices than any one else can offer. We adhere strictly to a high standard in the manufacture of these goods and we are much more desirous of maintaining a deserved reputation for quality than to be known for low prices only.

On the next two pages, we show diagrams of stairways—several different designs to suit any ordinary demand—and we put prices on the material so low that it seems unnecessary to invite comparison as any one at all familiar with such matters will easily recognize the big values we are offering.

Stair Rails




2 1/4 x 3 1/4
10-E-155.

2 1/4 x 3 1/4
10-E-156

Price per Lineal Foot.

	Yellow Pine.	Oak.
10-E-155.....	\$0.08	\$0.11
10-E-156.....	0.09	0.12

Rabbeted Bottom-Rail or Shoe



3/4 x 2 1/4
10-E-157.

Fillet



1/2 x 1 1/2
10-E-158.

	Price per Lineal Foot.	
	Yellow Pine.	Oak.
10-E-157.....	\$0.02 1/2	\$0.04
10-E-158.....	.01 1/2	.02

**Clear Selected Stock is used
in the Manufacture of all our
Stair Materials. Every piece is
New, Bright and Clean—Well
Machined and Ready for Finish-
ing in the Very Best Manner.**



10-E-123.



10-E-127.



10-E-206.



10-E-124.



10-E-126.



10-E-123.

MAIN NEWELS

8 inches at Base, 6 inches Shaft. 4 feet long, extra long Base.

	Price each, Yellow Pine.	Plain Oak.
10-E-123.....	\$2.70	\$3.00
10-E-124.....	2.85	3.05
10-E-126.....	2.55	2.95
10-E-206.....	2.25	2.55

ANGLE NEWELS

5 inch extra long Shaft can be cut down to use as landing or starting newels.

Prices of Angle Newels.

	Price each, Yellow Pine.	Plain Oak.
10-E-127.....	\$1.65	\$1.75
10-E-128.....	1.65	1.80

Prices of Stair Balusters

Cat. No.	28 inch.		32 inch.	
	Y. P.	Oak.	Y. P.	Oak.
10-E-116	\$0.10	\$0.12	\$0.11	\$0.13
10-E-117	0.10	0.12	0.11	0.13
10-E-118	0.09	0.10	0.10	0.11
10-E-652	0.07	0.09	0.08	0.10

10-E-652, Stair Baluster Stock

Price per 100 Lin. ft.	Y. P.	Oak
1 1/2 x 1 1/2	\$0.90	\$1.80



10-E-116



10-E-117



10-E-118



10-E-652

STAIR MATERIAL AND BILLS

STAIR TREADS AND RISERS




Illustration to the left shows a sectional view of our stair treads, risers, string, etc., showing how easy it is to put up a flight of stairs from the material we quote. Not only do our prices on stairwork effect a great saving for you, but you can build a larger range of sizes and a larger variety from the stock we list. You can put up a flight of stairs from our machined and cut-up stock in quicker time with less cutting, an important labor-saving feature.


Prices of Treads and Risers

Surfaced, cut smooth and nosed front. Clear Stock. Price each.

No.	Sizes	Y.-P.	Oak	Maple
10-E-666, Riser	1"x 8" 3 ft.	.14	.26	...
10-E-678, Riser	1"x 8" 3 ft. 6"	.20	.30	...
10-E-679, Riser	1"x 8" 4 ft.	.28	.41	...
10-E-667, Tread	1 1/2"x10" 3 ft.	.26	.50	.49
10-E-680, Tread	1 1/2"x10"x3 ft. 6"	.29	.70	.63
10-E-681, Tread	1 1/2"x10" 4 ft.	.40	.78	.75
10-E-682, Tread	1 1/2"x12" 3 ft.	.30	.56	.56
10-E-682, Tread	1 1/2"x12" 3 ft. 6"	.37	.70	.70
10-E-683, Tread	1 1/2"x12" 4 ft.	.46	.92	.92


Our Maple treads and Yellow Pine Risers make a fine combination
Remember, all our treads are nosed.

10-E-660. Circle tread and riser, forming a complete step, showing return on left end.



10-E-660

10-E-672. Circle step showing right hand return.



10-E-672

Prices of circle end steps for sizes up to 4 feet, that is, for stairways up to 4 feet wide.

Wood Prices

10-E-660.	Left hand return.....Y.-P.	\$4.15
10-E-661.	Right hand return.....Y.-P.	4.15
10-E-662.	Left hand return.....Oak	4.50
10-E-663.	Right hand return.....Oak	4.50
10-E-672.	Right hand return.....Y.-P.	3.40
10-E-673.	Left hand return.....Y.-P.	3.40
10-E-674.	Right hand return.....Oak	3.75
10-E-675.	Left hand return.....Oak	3.75

Give Width of your Stairs

Landing Nosing



10-E-8262. Landing Nosing.

Size, 1 1/2"x2 1/2".

Price for 100 Linal feet.

Yellow Pine..\$1.95

Plain R. Oak. 4.20

10-E-8262 1/2. Return Nosing.

Size 1 1/2"x1 1/2"


Y.-P.....\$1.00

Oak.....2.35

Return Nosing



Price



Stairway
10-E-630.

STAIR BILLS

Below we show diagrams of two stairways for which we propose to furnish material at very low cost. We have figured on the basis of the actual material only as specified in our bills listed here, based on average run not higher than 9 ft. 9 1/2 inches from floor to floor. Treads and risers will be cut to lengths specified. Carriages are not furnished—better results may be obtained by cutting them on the job as the variation of an inch or so in height from floor to ceiling is apt to cause trouble.

We furnish these stair bills in the knock-down, ready to put together. Carefully packed and bundled.

MATERIAL FOR STAIRWAY 10-E-630. \$13.78

Yellow Pine	Size	Catalog No.	Price Each	Totals
14 Treads....	3/0	10-E-668	\$0.30	\$4.20
2 Pcs. Nosing....	3/0	10-E-8262	.06	.12
16 Risers....	3/0	10-E-666	.14	2.24
2 Stringers....	10/8	10-E-678 1/2	.66	1.32
2 Stringers....	8/0	10-E-678 1/2	.48	.96
48 ft. Cove....		10-E-8060	.30	.14
1 Newel.....		10-E-206	2.25	2.25
1 Newel.....		10-E-128	1.65	1.65
6 ft. Rail.....		10-E-156	.09	.54
6 Balusters S4S	1 1/2"x1 1/2"-2/4	10-E-652	.03	.18
6 Balusters S4S	1 1/2"x1 1/2"-2/8	10-E-652	.03	.18

Stairway 10-E-630. Total price, K. D. and bundled.
Yellow Pine.....\$13.78
Stairway 10-E-630. If furnished in Red Oak 21.60

Wall Rosette

Size 4 1/2"x4 1/2".

10-E-669.

Price Each



Yellow Pine.....7c

Red Oak.....10c



10-E-671.

WALL-MOLD



Stairway 10-E-631.

MATERIAL FOR STAIRWAY 10-E-631. \$14.78.

Yellow Pine	Size	Catalog No.	Price Each	Totals
14 Treads.....	3/0	10-E-668	\$0.30	\$4.20
2 Pcs. Nosing....	3/0	10-E-8262	.06	.12
15 Risers.....	3/0	10-E-666	.14	2.10
2 Stringers.....	14/0	10-E-678 1/2	.84	1.68
1 Stringer.....	10/0	10-E-678 1/2	.60	.60
48 ft. Cove.....		10-E-8060	.30	.14
1 Newel.....		10-E-206	2.25	2.25
1 Newel.....		10-E-128	1.65	1.65
14 ft. Rail.....		10-E-156	.09	1.26
13 Balusters S4S	1 1/2"x1 1/2"-2/4	10-E-652	.03	.39
13 Balusters S4S	1 1/2"x1 1/2"-2/8	10-E-652	.03	.39

Stairway, 10-E-631. Total Price, K. D. and bundled, Yellow Pine...\$14.78
If furnished in Red Oak.....23.04

Round Rail

Acorn End for Round Rail

10-E-670.	Rail, 1 1/2 inches diameter, Y.-P., price per ft.....	6c
10-E-676.	Rail, 1 1/2 inches diameter, R. O., price per ft.....	6c
10-E-671.	Acorn End, Yellow Pine, price each.....	6c
10-E-677.	Acorn End, Red Oak, price each.....	9c

Stair Stringer

Prices per 100 Linal feet.

	Size	Wood	Price
10-E-654.	Wallmold.....	Y.-P.	\$0.75
10-E-655.	Wallmold.....	Oak	1.50
10-E-656.	String.....	Y.-P.	5.00
10-E-678 1/2.	String.....	Y.-P.	6.00
10-E-657.	String.....	Oak	7.50
10-E-679 1/2.	String.....	Oak	8.75

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Rugs, Carpets, Linoleums. Consult our offerings and give us an order. 53

STAIR BILLS

HOW TO SAVE MONEY ON STAIR WORK

The six stair bills shown here have been carefully designed to suit the average requirements. Material for the same designs reversed, furnished at prices quoted. We may not show the particular stair design you want, or you may wish to make changes in the material and use some other styles in Newels, Rail or Balusters. We are prepared to figure with you on any kind of Special Stair-work.


All bright, new stock, freshly machined. In our lists, we give our catalog number on each item so it will be an easy matter to identify just what each article is by referring to description of the goods.

Our price covers the material mentioned in our list, which is based on

average run of stairs not higher than 9 ft., 9 1/4 inches from floor to floor. Stair carriages are not furnished with these bills as this part of the work should be done on the job to insure an exact fit. Treads and risers are cut to lengths specified.

These bills of Stair Material are furnished in the knock-down only and we are very careful in preparing for shipment, everything being properly packed and bundled so as to reach you in the best of condition.

We quote on both Clear Yellow Pine and Clear Red Oak and taking quality into consideration, we know our prices are away below what ordinarily is asked for goods of this character.




\$8.26

Buys Material For This Stairway

STAIRWAY No. 10-E-632

Yellow Pine	Size	Catalog Number	Price Each	Totals
15 Treads....	3-0	10-E-667	\$0.26	\$3.90
1 Pcs. Nosing	3-0	10-E-8262	.06	.06
16 Risers.....	3-0	10-E-666	.14	2.24
2 Stringers....	16-0	10-E-678 1/2	.96	1.92
48 Ft. Cove....	12-0	10-E-8060	.30	.14

Stairway 10-E-632. Total Price, K. D. and Bundled, Yellow Pine..... **\$8.26**
Stairway 10-E-632. If furnished in RED OAK...\$14.94



\$8.62

Buys Material For This Stairway

STAIRWAY No. 10-E-635

Yellow Pine	Size	Catalog Number	Price Each	Totals
14 Treads....	3-0	10-E-668	\$0.30	\$4.20
2 Pcs. Nosing	3-0	10-E-8262	.06	.12
16 Risers.....	3-0	10-E-666	.14	2.24
4 Stringers....	8-0	10-E-678 1/2	.48	1.92
48 Ft. Cove....	12-0	10-E-8060	.30	.14

Stairway 10-E-635. Total Price, K. D. and Bundled, Yellow Pine..... **\$8.62**
Stairway 10-E-635. If furnished in RED OAK...\$15.41




\$15.09

Buys Material For This Stairway

STAIRWAY No. 10-E-633

Yellow Pine	Size	Catalog Number	Price Each	Totals
15 Treads....	3-0	10-E-668	\$0.30	\$4.50
1 Pcs. Nosing...	3-0	10-E-8262	.06	.06
16 Risers.....	3-0	10-E-666	.14	2.24
2 Stringers....	16-0	10-E-678 1/2	.96	1.92
44 Ft. Cove....	12-0	10-E-8060	.30	.13
1 Newell.....	10-E-206	2.25	2.25	
1 Newell.....	10-E-128	1.65	1.65	
16 Ft. Rail.....	10-E-156	.09	1.44	
15 Balusters S4S.	1 1/2 x 1 1/2 2-4	10-E-652	.03	.45
15 Balusters S4S.	1 1/2 x 1 1/2 2-8	10-E-652	.03	.45

Stairway 10-E-633. Total Price, K. D. and Bundled, Yellow Pine..... **\$15.09**
Stairway 10-E-633. If furnished in RED OAK...\$23.58




\$21.92

Buys Material For This Stairway

STAIRWAY No. 10-E-636

Yellow Pine	Size	Catalog Number	Price Each	Totals
13 Treads....	3-0	10-E-668	\$0.30	\$3.90
2 Pcs. Nosing	3-0	10-E-8262	.06	.12
1 Tread.....	10-0	10-E-673	3.40	3.40
15 Risers.....	3-0	10-E-666	.14	2.10
2 Stringers....	10-0	10-E-678 1/2	.60	1.20
2 Stringers....	8-0	10-E-678 1/2	.48	.96
48 Ft. Cove....	12-0	10-E-8060	.30	.14
1 Newel.....	10-E-123	2.70	2.70	
2 Newels.....	10-E-127	1.65	3.30	
14 Ft. Rail.....	10-E-156	.09	1.26	
13 Balusters....	1 1/2 x 1 1/2 11-28	10-E-116	.10	1.30
14 Balusters....	1 1/2 x 1 1/2 11-32	10-E-116	.11	1.54

Stairway 10-E-636. Total Price, K. D. and Bundled, Yellow Pine..... **\$21.92**
Stairway 10-E-636. If furnished in RED OAK...\$30.26




\$24.03

Buys Material For This Stairway

STAIRWAY No. 10-E-634

Yellow Pine	Size	Catalog Number	Price Each	Totals
13 Treads....	3-0	10-E-668	\$0.30	\$3.90
3 Pcs. Nosing	3-0	10-E-8262	.06	.18
16 Risers.....	3-0	10-E-666	.14	2.24
2 Stringers....	12-0	10-E-678 1/2	.72	1.44
2 Stringers....	8-0	10-E-678 1/2	.48	.96
48 Ft. Cove....	12-0	10-E-8060	.30	.14
2 Newels.....	10-E-124	2.85	5.70	
3 Newels.....	10-E-128	1.65	4.95	
16 Ft. Rail.....	10-E-156	.09	1.44	
12 Balusters....	1 1/2 x 28	10-E-118	.09	1.08
20 Balusters....	1 1/2 x 32	10-E-118	.10	2.00

Stairway 10-E-634. Total Price, K. D. and Bundled, Yellow Pine..... **\$24.03**
Stairway 10-E-634. If furnished in RED OAK...\$32.50



\$21.72

Buys Material For This Stairway

STAIRWAY No. 10-E-637

Yellow Pine	Size	Catalog Number	Price Each	Totals
12 Treads....	3-0	10-E-668	\$0.30	\$3.60
3 Pcs. Nosing..	3-0	10-E-8262	.06	.18
1 Tread.....	10-0	10-E-673	3.40	3.40
15 Risers.....	3-0	10-E-666	.14	2.10
2 Stringers....	8-0	10-E-678 1/2	.48	.96
2 Stringers....	14-0	10-E-678 1/2	.84	1.68
48 Ft. Cove....	12-0	10-E-8060	.30	.14
1 Newel.....	10-E-126	2.55	2.55	
3 Newels.....	10-E-128	1.65	4.95	
16 Ft. Rail.....	10-E-156	.09	1.44	
12 Balusters S4S	1 1/2 x 1 1/2 2x4	10-E-652	.03	.36
12 Balusters....	1 1/2 x 1 1/2 2x8	10-E-652	.03	.36

Stairway 10-E-637. Total Price, K. D. and Bundled, Yellow Pine..... **\$21.72**
Stairway 10-E-637. If furnished in RED OAK...\$30.44


PIONEER BOOKCASE COLONNADE

Combining utility and ornamentation in the most economical way.

Colonnades are primarily intended for decorative effect, and it is very seldom that an article of this merit can be made to serve a double purpose with such good results. This is economizing on an artistic note, nothing penurious about it.

The lower, or pedestal part of one side of the Colonnade may be used for books, magazines, or for a music cabinet; and the other half for bric-a-brac or curios.

One-half may be used with glass doors, the other half with panel doors, as shown in illustration. Reverse side is closed with stationary panels (not movable,) or can be supplied with glass doors or panel doors on both sides, just as ordered. Listed several different ways, so you can take your choice. Be sure, however, that you specify plainly correct combination wanted and order by number. State kind of wood wanted, and width and height of opening.



GENERAL DESCRIPTION

Suitable for openings from 6 ft. 6 in. to 8 ft. 6 in. in width, and up to 9 ft. in height. Columns or Posts are square, 6 in. at base tapering to about 5 in. at top. The Bookcase section is 4 ft. high, extend 2 ft. from wall and is made either 8 in., 10 in. or 12 in. on face, allowing for 6 in., 8 in. or 10 in. book or shelf space on the inside. When ordering, state what space is preferred.

The wide pedestal shelf on top of Bookcase affords a roomy space for a large vase or other ornamentation. Each section has three adjustable shelves, thus taking care of any variety of books or china. No hardware included; this should match your other hardware. The glass is a selected grade, set in strong, metal bars, design as shown. D. S. A. glass consists of one plain glass, double strength quality. Panel Doors are furnished with one long panel as shown. Interior door frames or jambs not included, nor side casing or head trimmings. Same are listed elsewhere in this catalog.

Shipped in the natural wood, not stained or varnished. Can supply that way for 20 per cent extra, for either a natural varnish or stained varnish finish. If ordered finished, be sure to say whether natural finish, showing the natural color of the wood and grain effect, or if wanted stained, state color and send sample if it is to match other woodwork.

Prices for Sizes up to 8 ft. 6 in. Wide by 9 ft. in Height.

All prices cover 2 posts and 2 pedestal bases		Yellow Pine	Red Oak	Birch
No. 10-G-1235	With leaded glass doors, reverse side closed.....	\$35.00	\$35.25	\$35.50
No. 10-G-1236	With panel doors, reverse side closed.....	28.60	28.80	29.00
No. 10-G-1237	With panel doors on both face and reverse side.....	31.50	31.75	32.00
No. 10-G-1238	With leaded glass on both face and reverse side.....	45.75	46.00	46.25
No. 10-G-1239	With leaded glass on one face side; reverse side panel doors	38.00	38.25	38.50
No. 10-G-1244	One-half of Colonnade leaded doors on face and reverse sides; and other half panel doors on face and reverse side	37.90	38.15	38.40
No. 10-G-1245	One-half of Colonnade leaded doors face side; (reverse side closed) other half panel doors and reverse side closed just as shown in illustration.....	31.00	31.25	31.50
No. 10-G-1246	One-half of Colonnade leaded doors face side, panel doors reverse side; other half panel doors face side, and reverse side closed.....	32.50	32.75	33.00
No. 10-G-1247	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1235, deduct..	\$5.50	
No. 10-G-1248	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1238, deduct..	11.40	
No. 10-G-1253	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1239, deduct..	5.50	
No. 10-G-1254	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1244, deduct..	5.50	
No. 10-G-1257	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1245, deduct..	2.75	
No. 10-G-1259	For changing leaded glass doors to one plain D. S. A. glass on	No. 10G1246, deduct..	2.75	

State if depth or thickness of pedestals are wanted 8, 10 or 12 inch, giving you either 6, 8 or 10 inch shelf space.

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

For Every Foot or Fraction of a Foot over 8 ft. 6 in. wide, add \$1.50

Superb Colonnades and Grilles

A pleasant surprise is awaiting those ordering any of our Colonnade or Grille Designs, because they are so well proportioned and so substantially built. Rich-looking, yet not gaudy. More ornamentation would spoil their effectiveness. They are impressive styles and will therefore mostly appeal to those of refined taste, but the price is not beyond the means of the modest purse, for would not anyone cheerfully expend a fair sum for a permanent piece of furniture?

Colonnades are as permanent or more so than most furniture, because the styles do not change at all. We dare say, that our designs will ornately express the style of any period, past, present and future, at least will not go out of date in the present generation.

Selected and sorted of choice grained material, the fore-most that the forests afford. Workmanship, such as only skilled workmen can produce. Results — a life time's service and enjoyment, so why should you hesitate to buy?



Monarch Colonnade
Challenge
Price . . **\$1640**

Combining Attractive-
ness in Design and
Lowness of Price.

Pedestal base of columns, neat, octagon shape, with convex shaped shaft. Very fetching. Octagon base $8\frac{1}{2}$ in., column 6 in., tapering to 5 in. Swell compo-carved cap, 6 in. high. Panel work 15 in. wide and 30 in. high. Price for any size up to 8 ft. 6 in. wide, 9 ft. high.

- 10-G-1261
Yellow Pine, \$16.40
10-G-1262
Red Oak . . \$16.50
10-G-1263
North'n Birch, \$16.60

All designs in this page shipped in the natural wood. Add 20 per cent to prices if a stained or natural varnished finish is wanted. Describe color if wanted stained to match other woodwork or send sample for us to match.

Jamb, side casings or head trimmings not included. Listed elsewhere in this book at low prices.



Queen Colonnade - \$19.95

A pretty Column Grille.
Done to a Queen's Taste.

As tempting in price as it is in design.


Artistically turned, fluted column, 6 in. diameter tapering to 5 in. at top. Panel work 18 in. and wider, according to width ordered, and 18 in. high.

Most appropriate for narrow openings, but price includes any width up to 9 ft., any height up to 9 ft.

- 10-G-1268
Yellow Pine . . \$19.95
10-G-1269
Red Oak . . \$20.10
10-G-1270
Northern Birch, \$20.25

PRINCESS COLONNADE

Matchless
Value . . **\$21.50**



There is a certain fascination about some Colonnades that is difficult to define or describe accurately, therefore must be left to a certain extent to the imagination. At the same time, whatever you see in our Princess Colonnades is real, and you get the Colonnade proper exactly as illustrated and priced. This consists of the two Columns, Panel Work below and composition carved Beam Brackets at the top. This is all that is usually required, as nearly always the side casings and head trimmings have already been installed, but if wanted, we list a variety in catalogue.

The post or column shaft is a combination of fluted, smooth turned and octagon handiwork, $7\frac{1}{2}$ ins. at the base, tapering to 5 ins. at the top. The oriental composition caps are 6 ins. high; Beam brackets over cap extend 33 ins. from wall, 9 ins. high and 5 ins. thick on face or under side. Panel work is 15 ins. wide and 30 ins. high. Prices cover any width up to 8 ft. 6 in. and any height up to 9 ft.

- 10-G-1274. Yellow Pine . . \$21.50
10-G-1275. Red Oak . . 21.75
10-G-1276. Northern Birch . . 21.85
40-G-1277. Southern Cypress . . 21.95

Order by number, state kind of wood wanted, specify width and height and allow correct price

LITTLE DIAMOND GRILLE



Typical Arch Design

Desirable for narrow openings, but can be furnished any width. Extends 24

inches at sides. Same price for yellow pine, oak, birch or cypress.

10-G-1207.

- Price up to 3 ft. wide . . \$2.55 Price up to 5 ft. wide . . \$3.75
Price up to 4 ft. wide . . 3.00 Price up to 6 ft. wide . . 4.50

56 Curtains, Draperies and other articles of ornamentation in our large General Catalog

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Showy—Stately Colonnades

Surprise

Design



\$28.50

Surprising
Value

To get some idea how this Arched Colonnade will appear when built in your home, hold the picture about two to three feet away from you. By concentrating your gaze on the fire-place for a moment, its gracefully defined outlines will gradually be unfolded to your view. Just sufficient curve and flexion to balance and harmonize with the interior as a whole. In a word, **symmetrically correct.**

If the Columns were turned to a larger mold, or inclined to a more pointed taper, if the carved and chiseled Beams and Caps and Brackets were handled by a more conservative shaper—if the paneled pedestals were not so evenly proportioned and arranged—there would still be a Colonnade—"on exhibition."

Height of Beam work at sides 18 inches, thickness $4\frac{1}{2}$ inches, Pedestal 18 inches from wall and 18 inches high, made to fit a $5\frac{1}{2}$ -inch or $7\frac{1}{2}$ -inch wall.

Price covers any size up to 8 ft., 6 in., by 9 ft.

No. 10-G-1282 Yellow Pine Price.....\$28.50


No. 10-G-1283 Red Oak Price.....28.75

No. 10-G-1284 Northern Birch Price.....29.00


Add \$2.00 for every foot, or fraction of a foot over 8 feet 6 inches in width.

Both designs on this page shipped in the natural wood. For natural varnish finish or stain and varnish add 15 per cent to prices quoted. Send sample if you want to match other woodwork.

No Jambes or Casing Included



Triumph Grille Colonnade



Triumphant

Price, \$22.88

Of late years, the Colonnade built along straight and simple lines, without arch, curve or angle, has held full sway, and while still favored by many and always will appeal to some home builders, there always exists a yearning for that something new and different, or just that which has long been admired, but never owned. Possession of that something variant is now within your easy grasp, in the shape of our TRIUMPH COLONNADE, a typical Arch Grille design. An old pattern modernized to a creation of genuine artistic merit.

Floor posts are 5 x 5 shaft and 34 inches high. Panel work from 15 to 18 inches from wall. Drop on grillework from 12 to 16 inches at center point. Built up in thorough first-class manner, packed with great care to reach you in perfect condition.

It is essential that correct size of your opening be given. Will look out of proportion if used for smaller openings than 6 ft. x 7 ft.

Price covers any size opening up to 9 ft. x 9 ft. Measure your opening correctly. Give width first. Order by Number

No. 10-G-1285 Yellow Pine Price.....\$22.88

No. 10-G-1286 Red Oak Price.....22.98

No. 10-G-1287 Northern Birch Price.....23.08

For every foot or fraction of a foot over 9 feet in width add \$1.50. For every extra foot in height add 75c.

It will delay your order if you fail to mention kind of wood, or forget to state width and height wanted.

Jambes, Casings and Head Trim not included.

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Many Other Colonnades in Our Special Book. Send for It.

57

INTERIOR COLUMNS AND COLONNADES

REGULAR BOX PEDESTALS ON THESE DESIGNS

Material and workmanship guaranteed to be equal to any similar line offered by others. Do not be misled by fictitious values. Merit and price count most—and ours are cheap in price only.

Never before did you have the opportunity to purchase high class interior columns and colonnades at such low prices. You can hardly imagine how much one of these colonnades enhances the beauty of any interior, especially if you desire to divide two rooms, for instance, the reception room and library, or dining room and parlor. In fact, no modern home should be without at least one of these openings. We offer plenty of choice so if you do not fancy one design, another will surely please you. The woods most commonly used for interior finishing are oak, yellow pine or birch, but should you desire our colonnade or columns made of some other wood to match other wood work in your house like cypress yr ash, we will furnish same at the same price as plain red oak.

Please do not confuse these colonnades with some that others list at higher prices which show a single paneled wainscoting, instead of regular box pedestal. The pedestals are about two feet projection from wall and about 11½ inches thick on face, made to fit around 5½ or 7½ inches wide jamb.

Our prices in every instance are for the wood named in the white, that is, just as it leaves the wood-workers' hands, not filled or varnished in any way. Should you want them finished in oil and varnished, we can do so at 15 per cent extra, or we can supply any design in white enameled at an increase of 30 per cent over prices named. In case you want a finished article and wish it to match other wood-work in the house, describe color as near as possible.



Interior Built Up Columns

Perfectly Manufactured
Sanded Finish.


No. 10-E-1250. With Wood Cap and Base.

		Price	
Dia.	Length	Y. P.	Oak
6 in.	x 6 ft.	3.25	3.85 \$3.95
6 "	x 7 "	3.45	4.02 4.16
6 "	x 8 "	3.75	4.30 4.45
7 "	x 6 "	3.60	4.16 4.30
7 "	x 7 "	3.95	4.52 4.66
7 "	x 8 "	4.30	4.88 5.02

No. 10-E-1251. With Composition Cap.

		Price	
Dia.	Length	Y. P.	Oak
6 in.	x 6 ft.	3.60	4.16 \$4.30
6 "	x 7 "	3.85	4.38 4.52
6 "	x 8 "	4.10	4.66 4.82
7 "	x 6 "	4.16	4.73 4.88
7 "	x 7 "	4.52	5.10 5.24
7 "	x 8 "	4.88	5.45 5.60

Be sure to state Size
and specify kind of
Wood.



\$12⁷⁵
for this
**Colonnade---Biggest
Value Ever Offered.**

The low prices quoted do not include interior trim, such as casing, baseboard, dentals, etc. The room base can be run around the pedestal as shown in illustration. Diameter of columns or pillars, 6 inches at base. Price for opening 9 ft. wide by 9 ft. high or smaller.

For each additional foot either in width or height add \$1.50.

10-C-1249, Yellow Pine.....	\$12.75
10-C-1252, Red Oak.....	\$15.35
10-C-1255, Birch....	\$15.35



**COLONNADE
\$14⁸⁰**

Great Bargain

This design follows the same description as above No. 10-E-1249 excepting that the cap of the columns is composition material, Scamozzi design; the lower part is a box pedestal and columns are 6 inches in diameter. Price for opening 9 ft. wide by 9 ft. high, or smaller.

For each additional foot either in width or height add \$1.50.

10-E-1256, Yellow Pine.....	\$14.80
10-E-1258, Red Oak....	\$16.95
10-E-1260, Birch.....	\$16.95



**This Fancy
Colonnade
\$17²⁵**

Very Fancy design with fluted columns and Scamozzi composition cap. Balance of description same as 10-E-1249.

Price for opening 9 ft. wide by 9 ft. high or smaller.

For each additional foot either in width or height add \$1.50.

10-E-1265, Yellow Pine....	\$17.25
10-E-1266, Red Oak....	\$19.50
10-E-1267, Birch..	\$19.50

**LATEST
DESIGNS**

Artistic Grillework

**BETTER
VALUES**

Just About One-Half Dealers' Regular Prices

When you want to liven up a certain arch or opening, you naturally want something that will not only look tasty and refined, but artistic and lively. That's just the effect our Grilles produce. An article of lasting adornment.


They are manufactured in a manner to suit the most fastidious. Worked from selected material to satisfy the most critical expert. A choice of woods so varied, to meet the wants of every locality and surroundings. The woods mainly used are Red Oak, Yellow Pine, Northern Birch, Southern Cypress and Brown Ash. For white enamel finish, nothing will equal Birchwood. Prices on other woods furnished on application.

All Grilles under four feet in width take the same price as though they measured four feet, with the exception of No. 10-G-1220, on which a minimum price up to three feet is listed.

Since all our Grilles are made to your order, they are shipped in the natural wood, just as they leave the wood-worker's hands, without varnish or stain. An extra charge of 20 per cent is made for finishing in oil and varnish, or in stain and varnish; for white enamel finish, add 40 per cent to catalogue prices. It often happens that grilles are wanted in a finish to match other woodwork, and by sending us a small sample of such finished woodwork, we can very easily duplicate the finish. However, if you know the kind of wood you want to match and it is finished natural, say Oak for instance, it will not be necessary to send us sample, just say if finish is to be light, dark or golden. Be particular to order correct size, state kind of wood, for if made according to your order and your size is wrong they will not be returnable.

Our Grilles are easy to set in place, because they are made up complete, in one piece, therefore requiring no expert labor.

If kind of wood wanted is not given in your order, we will ship Oak.




10-E-1211.

Up to 4 ft. wide, \$2.40
Up to 5 ft. wide, 3.00
Up to 6 ft. wide, 3.60




10-E-1208.

Up to 4 ft. wide, \$3.70
Up to 5 ft. wide, 4.55
Up to 6 ft. wide, 5.45




10-E-1219.

Up to 4 ft. wide, \$3.30
Up to 5 ft. wide, 4.15
Up to 6 ft. wide, 4.95




10-G-1213.

Up to 4 ft. wide, \$2.65
Up to 5 ft. wide, 3.30
Up to 6 ft. wide, 3.95




10-G-1215.

Up to 4 ft. wide, \$2.60
Up to 5 ft. wide, 3.25
Up to 6 ft. wide, 3.90



10-G-1216.

Up to 4 ft. wide, \$3.05
Up to 5 ft. wide, 3.85
Up to 6 ft. wide, 4.15



10-G-1218.

Up to 4 ft. wide, \$3.50
Up to 5 ft. wide, 4.30
Up to 6 ft. wide, 5.20



10-G-1220.

Up to 3 ft. wide, \$2.50
Up to 4 ft. wide, 3.20
Up to 5 ft. wide, 4.00
Up to 6 ft. wide, 4.80



10-E-1217.

Up to 4 ft. wide, \$4.30
Up to 5 ft. wide, 5.40
Up to 6 ft. wide, 6.45

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Portiers, Curtains and a Fine Selection of Draperies of all kinds in our up-to-date Furniture Dept.

Buffets and Sideboards

For Serviceable Enjoyment or Profitable Investment

More real solid comfort and modern convenience is derived from a well-designed, strongly-built roomy Buffet than from any other article of furniture, no matter whether such article be displayed for mere show, or expressly acquired for service.



"NORTH SHORE" SIDEBOARD

"North Shore" Buffet

The center section of our North Shore design Sideboard, consisting of the recess mirror and drawer part, is 16 inches deep; the two end sections, 12 inches deep. Note well the large size drawers and roomy shelf space. The doors are glazed with double strength glass, set in strong leaded bars. Can be placed in any part of the room where most convenient, the same as any other piece of movable furniture. Be careful to give exact correct size, if you want to build it into an offset in wall, which should not be over 12 inches deep. Note that the mirror sets back against the wall, the same as on a regular sideboard. Shipped complete as shown, except hardware. Ready to set in place.

Prices with leaded crystal glass, design as shown in Doors and Bevel Plate Glass Mirror.

"North Shore" Buffet Number	Sizes	Wood	Price
No. 10-G-712	4 ft. x 5 ft. 6 in.	Yellow Pine	\$39.60
No. 10-G-713	5 ft. x 5 ft. 6 in.	Yellow Pine	40.00
No. 10-G-714	6 ft. x 5 ft. 6 in.	Yellow Pine	40.40
No. 10-G-715	4 ft. x 5 ft. 6 in.	Red Oak	39.75
No. 10-G-718	5 ft. x 5 ft. 6 in.	Red Oak	40.25
No. 10-G-719	6 ft. x 5 ft. 6 in.	Red Oak	40.50
No. 10-G-720	4 ft. x 5 ft. 6 in.	Northern Birch	39.95
No. 10-G-721	5 ft. x 5 ft. 6 in.	Northern Birch	40.35
No. 10-G-722	6 ft. x 5 ft. 6 in.	Northern Birch	40.65

Prices with Plain Glass in Doors (one pane only) and Plain Plate Mirror, instead bevel.

"North Shore" Buffet Number	Size	Wood	Price
No. 10-G-723	4 ft. x 5 ft. 6 in.	Yellow Pine	\$37.50
No. 10-G-724	5 ft. x 5 ft. 6 in.	Yellow Pine	37.75
No. 10-G-725	6 ft. x 5 ft. 6 in.	Yellow Pine	38.00
No. 10-G-726	4 ft. x 5 ft. 6 in.	Red Oak	37.75
No. 10-G-727	5 ft. x 5 ft. 6 in.	Red Oak	37.95
No. 10-G-728	6 ft. x 5 ft. 6 in.	Red Oak	38.25
No. 10-G-729	4 ft. x 5 ft. 6 in.	Northern Birch	37.90
No. 10-G-738	5 ft. x 5 ft. 6 in.	Northern Birch	38.30
No. 10-G-739	6 ft. x 5 ft. 6 in.	Northern Birch	38.50

For every foot, or fraction of a foot over six feet in width, add \$3.00. Intermediate sizes same prices as next larger listed size.

"Belmont" Buffet Pre-eminent

Have you longed for a Sideboard of conspicuous proportion, built and designed on a plan to compare agreeably with your other fixtures? Then your desires can be gratified by the ownership of our "Belmont Buffet." Your expectations will be more than realized, because it is bound to impart that final polished-finishing touch (call it character, elegance, dignity or what you will), that so often is lacking in such homes where a spirit of reserved refinement rules and modest taste predominates.

Purposely designed so it can be installed in any new or old time residence, and while it affects the mission style it will appear to advantage amongst any surroundings. Can be placed in a recess or offset in wall, or any place flat against the wall. Glass shown in the four doors above the mirror and the two side doors below is crystal quality, set in neat, narrow metal bars.


The highly polished beveled mirror is set back, providing for a large display space. Unique are the peaked openings between the upper and lower doors. Center part below mirror is 16 inches deep, balance and sides, 12 inches. Workmanship beyond criticism. Made any size, but looks best when the width exceeds the height by about one foot.

Price covers any size up to seven feet wide by seven feet high. Hardware not included; otherwise furnished exactly as shown.

No. 10-G-745 Yellow Pine	\$63.95
Price.....	
No. 10-G-747 Red Oak	64.75
Price.....	
No. 10-G-749 Northern Birch	65.15
Price.....	

By using clear, plain glass in the doors, one pane only, and plain plate mirror instead of beveled, deduct \$6.50

For every foot or fraction of a foot over 7 ft. in width add \$3.00



"BELMONT" BUFFET

Built in China Closets and Sideboards!



Avondale

THRIFTY HOUSEWIVES! HERE'S YOUR CHANCE!

\$18¹⁹ for a combination china closet and side-board, 4 ft. wide. Why are we selling more china closets and side boards than other concerns? Because our designs are the most practical; because they afford the most glass space to display china and glass ware to the best advantage and because our prices are so extremely close.

Where else can you buy a roomy combination china closet and side-board like our Avondale design for \$18.19?

It has three very large drawers, two smaller drawers for silver-ware, a panel door and shelf below and two glass doors above with large wide glass and shelves. Ornamented with two scroll brackets. An open space for special display. Furnished with or without mirror.

PRICES OF AVONDALE WITHOUT MIRROR.

No.	Wth.	Ht.	Yellow Pine	Birch	Oak
10-E-700.	4'	x6'8"	\$18.19	\$20.75	\$20.75
10-E-701.	4'	x7'	20.25	21.75	21.75
10-E-702.	5'	x6'8"	21.75	22.50	22.50
10-E-703.	5'	x7'	22.00	22.75	22.75
10-E-704.	5'6"	x6'8"	22.50	24.75	24.75
10-E-705.	5'6"	x7'	22.75	25.00	25.00
10-E-706.	6'	x7'	26.25	27.75	27.75

If wanted to extend into the room with sides exposed add \$1.50 for Yellow Pine and \$2.25 for Oak or Birch.

If wanted with plain plate glass Mirror, add 20 per cent to above prices.

➡ All our china closets and side-boards are durably constructed with heavy ceiling back and the sides of smooth lumber. They are made 14 inches deep to set into recess in wall or can be made to extend out into the room with the sides as well as the front part exposed just as ordered.

All furnished complete as shown and quoted, including the trim, such as the moulded side casing, fancy base blocks and the 3 members of Cap trim, but no hardware.



Elmhurst

Prices of Elmhurst with plain glass doors.

This design affords large drawer and shelf display and is especially desirable for a Kitchen Case.

\$17²⁵

for this handy Cupboard.

If wanted to extend into the room with the sides exposed, instead of setting in recess in wall, add \$1.50 for Yellow Pine and \$2.25 for Oak or Birch.

For sizes larger than here listed, send us dimensions for our quotations. All intermediate sizes take the price for the next largest size here quoted.



Ravenswood

Price of Ravenswood with 4 leaded Crystal glass Doors and wide plain polished plate Mirror.

	Wth.	Ht.	Yel. Pine	Birch	Oak
10-E-800.	5' x 7'		\$39.00	\$42.00	\$42.00
10-E-803.	6' x 7'		41.25	43.50	43.50
10-E-806.	7' x 7'		43.50	46.50	46.50
10-E-809.	8' x 7'		45.00	48.75	48.75

If plain glass is wanted in the Doors instead of leaded Crystal deduct 10 per cent.

If wanted to extend into room with the sides exposed the same as the front, add \$1.50 for Yellow Pine and \$2.00 for Oak or Birch.

Price of Wakeford with 2 Mirrors of plain polished plate glass and plain glass Doors.

Note—The small top mirror sets back into the case same as the large lower Mirror.


	Wth.	Ht.	Yel. Pine	Birch	Oak
10-E-780.	5' x 7'		\$39.75	\$42.75	\$42.75
10-E-781.	5' 6" x 7'		42.00	44.25	44.25
10-E-782.	6' x 7'		45.00	48.75	48.75
10-E-785.	7' x 7'		48.75	51.75	51.75
10-E-788.	8' x 7'		52.50	56.25	56.25

If wanted to extend into the room with exposed sides, add \$1.50 for Yellow Pine and \$2.25 for Oak or Birch.

Remember that prices here quoted of Aurora include leaded Crystal Glass in Doors and Polished Plate French Mirror.

If wanted to extend into the room with sides exposed, add \$1.50 for Yellow Pine and \$2.25 for Oak or Birch.


If plain glass is wanted in doors instead of leaded crystal glass, deduct 10 per cent.



Aurora

	Wth.	Ht.	Yel. Pine	Birch	Oak
10-E-756.	3' x 7'		\$24.75	\$26.25	\$26.25
10-E-757.	3' 6" x 7'		26.25	27.75	27.75
10-E-758.	4' x 7'		27.75	29.25	29.25
10-E-759.	4' 6" x 7'		29.25	30.75	30.75
10-E-760.	5' x 7'		30.00	33.75	33.75
10-E-761.	6' x 7'		33.75	36.75	36.75

Our Medicine Cabinets are furnished in 2 sizes. The smaller one has 2 adjustable shelves, the large one has 3. We furnish everything as shown with Cap, Casing, Stool and Apron. Furnished with plain D. S. or Plate Mirror as ordered. Price of Cabinets with double strength mirror.



	10-E-851	10-E-855
Size of Mirror	14" x 18"	16" x 24"
Door	18" x 22"	20" x 28"
Opening to be Left in Wall	20" x 24"	22" x 30"
Kind of Mirror	Plain D. S.	Plain D. S.
Prices: Yel. Pine	\$4.65	\$5.36
Oak	5.36	6.08
Birch ...	5.36	6.08

(For Polished Plate Mirror Add \$1.00.)



Wakeford

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Don't Fail to get acquainted with our wonderful Rug & Carpet Bargains 61

MANTELS FOR THE HOME BEAUTIFUL

Fireplace Fixtures On the pages following mantels—we illustrate and describe a complete line of dependable fireplace fixtures. We believe in giving you an article that is absolutely dependable, at the lowest direct-to-you, one-small profit price. The goods themselves will prove this, as well as the saving.



STONE or brick mantel cannot find its proper place in a room in which it is the only material of its kind used, and it is out of harmony with the rest of the decorations. The mantel should really harmonize with its surroundings, its lines as well as its structural material, should be made as nearly as possible in accordance with the general style of the room. The importance of the wood mantel in furnishing the home cannot be over-estimated. A badly designed piece of furniture can easily be removed, but the mantel cannot be; hence the importance of your selection.

A few years ago, in some sections of the country, a sentiment gained ground that fireplaces were not needed, as most houses contained different kinds of furnaces, which supplied the want, and some people being quick to adopt new suggestions, commenced to eliminate fire-places and chimneys from their homes. However, if anyone doubts that this was a mistake, ask any one of your neighbors who have built a house without a fire-place, and they will tell you it was the saddest mistake in the building of their home.

The fireplace is the heart of the home—the center of every interesting thing that happens—where sentiment reigns supreme. The father, mother, and children all gather around it evenings, and it is made a centre for the family,—but the furnace! Who ever invited the faithful few of his friends about him and bade them make merry over a register? Did you ever hear of a laughing, loving family gathered around a radiator?

Gather your family around an open fire-place and life begins to look reasonable;—a sweet serenity fills your soul, and an unwonted comfort pervades the marrow of your bones.

Our designs include the different period styles. We can furnish them in the natural wood, without stain or varnish. Our stock woods are *Birch, Mahogany, Quartered Oak, Plain Oak*. Mantels are carried in stock, and ordinarily can be furnished promptly. Mission Mantels are finished in all the popular Mission colors, such as Early English, Weathered, and Fumed, and the designs harmonize with the best Mission furniture made. Mantels quoted in Oak and Mahogany are carried in stock finished in Golden Oak and regular Mahogany, Rubbed Piano Polish and so shipped unless otherwise ordered.

Mantels can also be furnished **painted three coats white**, without extra charge, so that you may have same white enameled after setting it up in your house, as it is impossible to ship white enameled mantels without damage. Extra charge and special quotation will be made for mantels wanted in other woods than those specified under each mantel, and also for different sizes.

Our Guarantee Remember!—there is as much difference in Guarantees as there is in Mantels. Our line is sold under a Guarantee that covers every point,—material, construction, newness of design, finish and safe delivery. If same is found not as represented, notify us and it will be your privilege to return the goods at our expense, so you are safe. We feel equally safe, as nothing but the most unfortunate combination of circumstances could result in defective goods leaving our factory.

PRICES quoted herein are net for the goods—free on board cars at factory. These are our lowest factory prices.

\$895

Refinement and Style in This Mantel Predominate


Quartered Oak.
Birch Mahogany.
5 ft. high.
5 ft. wide.
Tile opening, 42x42 in.
Profile, 3 1/4 in.
Polished Piano Finish.

We believe you will agree that we have succeeded in getting an elegant refinement and style into a mantel of this character.

You will notice the plain elegant lines along which this mantel was built. Absolutely selected figure throughout. This mantel is one that you will never be ashamed of, no matter where you use it, and if you are going to use a Base in any of your rooms you will do well to consider this one.

Remember,—we can furnish this in Mahogany as well as Quartered Oak. No. 10G821 MANTEL—woodwork only. Price -----\$8.95

Specify Oak or Birch Mahogany



Art Glazed Tile Glazed tile are also illustrated in the following pages with full information as to how to order. All first-quality—no seconds—absolutely guaranteed. For the convenience of those who install their own mantels, you will find **Marbelized Slate Tile** also illustrated and priced. If at all interested in mantels and fixtures, do not pass over these pages lightly.

The wood mantel is built along entirely different lines from that formerly used. It is not cumbersome, or commonplace, but our best architects and furniture manufacturers now advocate designs such as we are showing this year.

Beware of cheap imitations and meaningless ornaments spread all over your mantel. The plain effects and designs are correct and show good taste, and it should be so, because the mantel is conspicuous on account of its connection with the fire-place, around which everyone gathers, and it is generally the first thing seen when first entering a room. Our mantels are approved of and specified by the best architects.

\$2498

The Most Popular Design Ever Made

Quartered Oak.
Birch Mahogany.
Large 18 x 36 in.
French bevel plate mirror.
7 ft. long.
5 ft. wide.
Tile opening, 42 in. wide by 39 in. high.
Profile, 3 1/4 in.
Polished Piano Finish.

This is a design that has been unsuccessfully copied by practically every mantel manufacturer, and today it still stands supreme as our pattern. Appropriate for most any house, and equally adaptable to any room.

While of no particular class of architecture, the genuine simplicity immediately catches the eye.


The rising pedestals on either side joined at the breast by the deep swelled shelf has an effect that is incomparable. The mirror running to the shelf reflects all ornaments placed thereon.

Can furnish in either wood,—Quartered Oak or Mahogany No. 10G820 MANTEL—woodwork and mantel only-----\$24.98

Specify Oak or Birch Mahogany



MANTELS—Highest Grade at Lowest Prices



\$27 75


Handsome Buffet Dining Room Mantel

Quartered Oak only.
Three large leaded glass doors.
6 ft. high, 5 ft. wide.
Tile opening, 42 x 42 in.
Profile, 3 3/4 in.
Polished Piano finish.

A most desirable Mantel that can possibly be used in the Dining Room. The leaded glass doors opening into a deep closet gives an excellent opportunity for display of a few pieces of fancy china and cut glass, which one does not always want to leave

on the tops of Mantels to be broken. This design should certainly appeal to those able to discriminate, and the price is very low.

No. 10G822 MANTEL—with leaded glass only, ----- \$27.75
Cannot Furnish this Mantel in Mahogany



\$21 50

Do Not Leave This Mantel Out of Your Selection

Quartered Oak. Birch Mahogany. Large 18x36 in. French bevel plate mirror.
7 ft. high, 5 ft. wide.
Tile opening, 42 in. wide by 39 in. high.
Profile, 2 1/2 in.
Polished Piano finish.

There never has been a Mantel offered to compare in design and price as with this one. Take particular notice of the size and also that the general proportions are correct. This Mantel can also be furnished with the *square posts instead of the round*, without any additional charge.

No. 10G824 MANTEL—woodwork and mirror only ----- \$21.50
Specify Oak or Birch Mahogany

\$22 00

One of Our Best Sellers

Quartered Oak or Birch Mahogany. Large 18x36 in. French bevel plate mirror.
7 ft. high, 5 ft. wide.
Tile Opening, 42 in. wide by 39 in. high.
Profile, 2 1/2 in.
Polished Piano finish.


This is a wonderful value, considering the price.

The Quartered Oak is of the choicest selection, and the simple design of the Mantel brings out the rich grain effect of the wood.

While possibly more appropriate for the Parlor or Living Room, it is desirable for any room.

Can also be furnished with the *round columns, instead of the square*, at no additional charge. Do not pass this Mantel by hurriedly. It improves upon acquaintance.

No. 10G823 MANTEL—woodwork and mirror only, ----- \$22.00
Specify Oak or Birch Mahogany



\$21 00

An Ideal Hall or Library Mantel


Quartered Oak. Birch Mahogany. Large 18x36 in. French bevel plate mirror.
6 ft. high, 5 ft. wide.
Tile opening, 42 in. wide by 45 in. high.
Profile, 3 3/4 in.
Polished Piano finish.

The acme of perfection in the way of a Hall or Library Mantel.

There is more and more demand for Mantels of this character, we do not believe there is one anywhere to compare with.

Our special shelf construction and the beautiful grain effect obtained both in the Quartered Oak and Mahogany, is most attractive, the low price at which it is quoted, you make no mistake in choosing this one.


No. 10G825 MANTEL—woodwork only ----- \$21.00
Specify Oak or Birch Mahogany



For Lowest Prices on Grates, Tile and Fixtures, see following pages

CHICAGO HOUSEWRECKING CO.
35th and Iron Sts., Chicago

Mantles—Built Right—Finished Right



\$2200

**An Absolutely
High Class
Mantel**

Quarterd Oak or
Birch Mahogany.

Large 18x36 inch
French bevel plate
mirror.

7 ft. high, 5 ft. wide.

Tile opening, 42 in.
wide x 39 in. high.


Profile, 2½ in.

Polished Piano
Finish.

No effort spared to
give our customers
a selection of man-
tels unequaled by
any other manufac-
turer.

Workmanship,
construction and fin-
ish are absolutely
necessary and some
other manufacturers
avoid these points.

Satisfaction in full measure is sure to follow the purchase of this pattern
No. 10G826 Mantel—woodwork and mirror, only ----- \$22.00
Specify Oak or Birch Mahogany



\$1850

**Wonderful
Mantel for
the Price**

Selected Oak or
Birch Mahogany.

Large 18x36 inch
French bevel plate
mirror.

7 ft. high, 5 ft. wide.

Tile opening,
36x36 in. or 42x39
in.


Profile, 3¾ in.

Polished Piano
Finish.

A truly wonderful
bargain. Nothing as
good has ever been
offered anywhere
near the price. We
make them in large
quantities so we are
able to sell cheaply.

This is a mantel
we often finish in
one of the Mission
shades, and can also
be furnished with the round posts instead of the square, at the same price.

No. 10G828 Mantel—woodwork and mirror, only ----- \$18.50
Specify Oak or Birch Mahogany



\$1790

**Large, Massive
and
Inexpensive**

Selected Oak or
Birch Mahogany.

Large 18x36 inch
French bevel plate
mirror.

7 ft. high, 5 ft. wide.

Tile opening, 36x
36 in. or 42x39 in.

Profile, 2½ in.


Polished Piano
Finish.

Inexpensive but
massive appearing.
A large mirror. Ex-
ceptional value.

The fronts of the
shelves and columns
are quarter-sawn
oak, showing ele-
gant figure. The bal-
ance of the mantel is
selected oak.

This is one of the
Best Bargains we
have. Will be fur-
nished with the round posts instead of the square, at the same price.

No. 10G827 Mantel—woodwork and mirror, only ----- \$17.90
Specify Oak or Birch Mahogany



\$1675

**Best for
Dining Room
or Den**

Oak Only.

Fretted work glass
doors.

6 ft. 4 in. high, 5
ft. wide.

Tile opening, 42
in. wide x 39 in. high.

Profile, 3¾ in.


Finished Royal
Gloss or Mission
such as Early Eng-
lish, Weathered or
Fumed.

A very inexpensive
Dining Room Man-
tel in perfect good
taste and design.
Will match other fur-
niture of Mission or
Arts and Crafts. The
above style is sure to
please.

The two doors open
into a deep cabinet
to hold small bric-a-
brac, and while an ideal Dining Room mantel, also appropriate for a
Den, and has been used with telling effect in a Bed Room.

No. 10G829 Mantel—with glazed doors, only ----- \$16.75
OAK ONLY—Specify kind of finish

Mantels—From Factory to You—No Middlemen



\$17⁰⁰

Quoted at
Lowest of Low
Prices

Selected Oak or
Birch Mahogany.
6 ft. 10 in. high.
5 ft. wide.
Large 18 x 36 in.
Bevel plate mirror.
Tile opening, 36x36
in. or 42 in. wide
x 39 in. high.
Profile, 2½ in.
Royal Gloss finish.

In this Mantel is
embodied more
style and better
quality than we
have ever been
able to offer before
at such a remark-
ably low price. At
our price this is the
handsomest man-
tel of its class.

The columns and
shelf fronts are of
the very choicest
Quartered Oak.

The mirror is
beveled. Very ap-
propriate mantel
for Parlor, Living
or Bed Room.

No. 10G830 MANTEL—woodwork and mirror only\$17.00
Specify Oak or Birch Mahogany.


\$16²⁵

Look No
Further if Price
Suits.


Selected Oak only.
6 ft. 10 in. high.
5 ft. wide.
16x28 in. French
bevel plate mir-
ror.
Tile opening, 36x36
in. or 42x39 in.
Profile, 3¼ in.
Royal Gloss finish.

No such value
has ever been of-
fered—a splendid
mantel, and we
stand by it as we
do all of our goods,
with a strong guar-
antee.

Since the photo-
graph of this man-
tel was made we
have improved it
very much, and are
now making it
with Quartered
Oak shelf fronts,
you have no idea
how much this
change improves it.



No. 10G831 MANTEL—woodwork and mirror only\$16.25
OAK ONLY.



\$14⁰⁰

A Real
Money Saver
for You

Selected Oak.
6 ft. 4 in. high.
Three size mirrors.
4 ft. 6 in. to 5 ft.
wide.
Tile opening, 36x
36 in.
Projection, 3¼ in.
Royal Gloss finish.

Some people like
the two long posts
rather than the
four broken ones,
and in order that
you may see the
difference right
before you, we are
showing this de-
sign.

Very similar to
our No. 10G831 and
we feel as though
your choice of one
of these mantels is
almost certain.—
the two long posts
costing a little less
money.

No. 10G833 Mantel—woodwork and 14x24 mirror only ...\$14.00
No. 10G834 Mantel—woodwork and 16x28 mirror only ...\$14.50
No. 10G835 Mantel—woodwork and 18x36 mirror only ...\$15.50
OAK ONLY


\$11⁰⁰

An Elegant
Little
Parlor Mantel

Selected Oak only.
80 in. high.
54 to 60 in. wide.
Tile opening, 36x
36 in. or 42 in. wide.
Projection, 3¼ in.
14x24 in. French
bevel plate mir-
ror.
Royal Gloss finish.

The design of
this mantel has
never before been
adopted by any
manufacturers in a
low-priced mantel.
Has always been
worked out in ex-
pensive mantels.
Note the shaped
crown-board,
moulding around
the four sides of
the French bevel-
ed mirror.

The columns are
strictly Quartered
Oak, an attractive
mantel for any
room in the house,
but particularly for
a pretty parlor.



No. 10G836 MANTEL—woodwork and mirror only\$11.00
OAK ONLY

MANTELS—Make the Home More Attractive



\$14⁷⁵

**A Lot
For The
Money**

Selected Oak or Birch Mahogany.
Two different size mirrors.
7 ft. high, 57 to 60 in. wide.
Tile opening, 36 x36 or 42x39 in.
Projection, 3 3/4 in.
Royal Gloss Finish.

One of the largest low priced mantels we make.

Designed especially for those who want a large mantel at a small price.

Workmanship, finish, and general character, are the same as our best Mantels.


The box fronts, columns and brackets under lower shelf are all genuine quartered oak. Will fit into any room nicely.

SIZE OF MIRROR

No. 10G837 MANTEL—woodwork and mirror only, 16x28 \$14.75

No. 10G838 MANTEL—woodwork and mirror only, 18x36 \$16.00

Specify Oak or Birch Mahogany



\$13⁵⁰

**An Unusually
Attractive
Design**

Selected Oak only.

Three different size mirrors.

6 ft. 4 in. high, 54 to 60 in. wide.

Tile opening, 36 x36 in.

Profile, 3 3/4 in. Royal Gloss Finish.

We do not believe this attractive mantel can be duplicated anywhere in the country.

The construction and finish are the best and the proportions are perfect.

You will note the full Quartered Oak Columns and shelf fronts.

For a cottage it is a mantel that should certainly not be passed by.


SIZE OF MIRROR

No. 10G839 Mantel—woodwork and mirror only, 14x24—\$13.50

No. 10G840 Mantel—woodwork and mirror only, 16x28—\$14.50

No. 10G841 Mantel—woodwork and mirror only, 18x36—\$16.00

OAK ONLY



\$10⁰⁰

**Low-Priced—
Splendid
Proportions**

Selected Oak only.

14x24 in. French bevel plate mirror.

6 ft. 2 in. high, 54 to 60 in. wide.

Tile opening, 36 x36 in.


Projection, 3 3/4 in. Royal Gloss Finish.

Of unusually good proportions, one of the lowest priced cabinet mantels made.

The same cabinet makers who make our very highest priced mantels make this one, and the same care and skill is used as in our best designs. It is a mantel that can be used anywhere. You will make no mistake in buying it.

No. 10G842 MANTEL—woodwork and mirror only—\$10.00

OAK ONLY



\$9⁰⁰

**Lowest Priced
Cabinet Mantel
Made**

Selected Oak only.

14x24 in. French bevel plate mirror.

6 ft. 2 in. high, 48 to 54 in. wide.

Tile opening, 36 x36 in.

Projection, 3 3/4 in. Royal Gloss Finish.

First class in every respect.

This mantel is sold on a closer margin than any other cabinet mantel made which contains a mirror.

The columns are Quartered Oak. The shelves are nice and wide.

The rough lumber in this mantel is worth the price we are asking for it made and finished.

Also furnished with flat jamba—no profile—without extra cost.

No. 10G843 MANTEL—woodwork and mirror only—\$9.00

OAK ONLY

MANTELS—NO EXCUSE FOR NOT Having at These Low Prices



\$7⁷⁵

**An Elegant
Medium-Priced
Base**

Selected Oak or
Birch Mahogany.
57 in. high.
57 to 60 in. wide.
36x36 in. or 42x
39 in tile opening.
Projection, 3 3/4 in.
Royal Gloss finish.

One of the
best of its kind
made.

It is large—
made in both
selected Oak,
with Quartered
Oak columns

and shelf front, and in Birch Mahogany, and finished in best Royal Gloss finish.

It is one that you will be proud of, wherever it is put. Consider it very carefully.

G844 MANTEL—woodwork only, price, Oak -----**\$7.75**

G845 MANTEL—woodwork only, price, Mahogany -----**\$8.25**

Specify Oak or Mahogany



\$4⁰⁰

**Artistic and
Neat**

Selected Oak or
Birch Mahogany.
56 in. high.
56 to 60 in. wide.
Tile opening, 36x
36 in. or 42x36 in.
Projection, 3 3/4 in.
Royal Gloss finish.

This pattern
is somewhat
similar to others
shown, except
the broad stiles
in front, rather
than the use of
the column or
pilaster.

Neat, attractive looking, and the price is very low. It should certainly not be missed from one of your bed rooms.

This Mantel can also be furnished with flat jambs—no profile—without additional cost.

G848 MANTEL—woodwork only, price, Oak -----**\$4.00**

G849 MANTEL—woodwork only, price, Mahogany -----**\$4.50**

Specify Oak or Mahogany

REMEMBER: All our mantels including the above can be furnished in the white just as they come from the final sand-papering—no varnish or stain—so you can finish them to match your interior finished woodwork.

\$6⁹²

**Same Design as
No. 844—
Lower Price**

Solid Oak or Birch
Mahogany.
56 in. high.
56 to 60 in. wide.
Tile opening, 36x
36 in.
Projection, 3 3/4 in.
Royal Gloss finish.


Feeling that
some of our
trade will want
a lower priced
mantel than our
No. 844, we have
gotten up the
above design
with an idea of construction so that we can sell a lot of them, and make them up in large quantities—hence the low price.

The columns are strictly Quartered Oak—the Mantel well proportioned, and one of the Mantels we sell practically at cost.

10G846 MANTEL—woodwork only, price, Oak -----**\$6.92**

10G847 MANTEL—woodwork only, price, Mahogany -----**\$7.50**

Specify Oak or Mahogany



\$2⁹⁸

**A Less-Than-
Cost
Mantel**

Selected Oak only.
48 in. high.
48 to 54 in. wide.
Projection, 3 3/4 in.
Royal Gloss finish.

On account of
the severe com-
petition we have
had on a small
base of this
character, our
factory has
adopted the
principle of cut-
ting these out

in numerous quantities, reducing our cost of them to a minimum, and then, without charging up any selling expenses, we are offering them to our trade at factory cost.

The price is so ridiculously low that no argument as to the value is necessary. This Mantel can be furnished with flat jambs—no profile—without additional cost.

10G850 MANTEL—woodwork only, price -----**\$2.98**

OAK ONLY

CAUTION: We do not believe in the **cheapest** fire place fixture—but in a dependable article that will satisfy you and prove a bargain long after the original cost has been forgotten.

MANTEL SHELVES AND MANTELS


Very Neat, Appropriate and Timely

MANTEL SHELVES

These well designed mantel shelves are used primarily in connection with "all-brick" or stone fireplaces, and while we recommend the use of our regular modern wood mantels as fully illustrated on this and other pages, we must cater to all demands and satisfy all tastes.

The designs shown are **very appropriate** and will cover all general requirements. Furnished in the natural wood, **not stained or varnished**, so your decorator can finish them to match other woodwork.

HOW TO ORDER—State **exact width**, measured across the front of tile or mantel brick, also state depth or projection from wall so the ends can be returned the proper length. **Send rough sketch if possible, with measurements.**




End View

Mantel Shelf No. 10-G-884, Mission style, 6 member, built up 3" thick on face. Heavy effect, 12" wide shelf. Face brackets are 4x6x6". 2 member top 4 1/4" in cover. Fillet between brackets, 1 1/4 x 1 1/4".

Be sure to give correct exact measure	Yellow Pine	Oak	Birch
Price up to 4 ft. on face of tile or brick.....	\$6.65	\$7.05	\$7.10
Price up to 5 ft. on face of tile or brick.....	6.85	7.25	7.30

For every foot or fraction of a foot over 5 feet, add \$1.00.

Mantel shelves, if made as ordered, cannot be returned.




End View

Mantel shelf No. 10-G-885, 3 member, shelf 2" thick, 12" wide shelf. Top member and apron 4 1/4".

Be sure to give correct exact measure	Yellow Pine	Oak	Birch
Price up to 4 ft. on face of tile or brick.....	\$4.05	\$5.15	\$5.20
Price up to 5 ft. on face of tile or brick.....	4.25	5.35	5.40

For every foot or fraction of a foot over 5 feet, add \$1.00.

Remember your order is not complete unless you mention kind of wood and projection from wall.



End View

Mantel shelf No. 10-G-886, 8 members, built up 5" thick on face, 12" wide shelf. Massive effect. 2 member top, 4 1/4" and 1/4" round. Two Molded Face Brackets or supports 6"x8"x10". Wide crown mold apron and fillet.

Be sure to give correct exact measure	Yellow Pine	Oak	Birch
Price up to 4 ft. on face of tile or brick.....	\$8.50	\$8.75	\$8.90
Price up to 5 ft. on face of tile or brick.....	8.75	9.25	9.10

For every foot or fraction of a foot over 5 feet, add \$1.00.

Before mailing your order, see that you have specified correct number of design wanted, correct width and depth.

Mantel shelves, if made as ordered, cannot be returned.

These two mantel designs are the only ones we list at price in the natural Oak, and Yellow Pine wood, unfinished that is, **without varnish or stain**, just as they leave the wood worker's hands, so that your decorator can finish them to match the other woodwork in your home.

Price includes woodwork only, just as shown in illustration. Shipped from factory on short notice.

These two designs **cannot** be supplied in any other wood. If you desire something more elaborate in the natural wood please make your selection from foregoing finished mantel pages and write us for lowest prices.

Well Poised Mantel Base

Yellow Pine and Selected Oak.

56 in. wide.

48 in. high.

Tile opening, 36x36 in.

Projection, 4 1/4 in.

Wide shelf, 9 1/2 in.

Prices have been cut down in anticipation of a large demand, so we must sell many of them to realize on our small profit.

\$333

and worth more

Wall plates can be extended to 60" wide, if so ordered, at 25c additional.

- No. 10-G-892 Mantel, woodwork only, Yellow Pine in the natural wood.....\$3.30
- No. 10-G-893 Mantel, woodwork only, Red Oak in the natural wood.....3.60
- No. 10-G-894 Mantel, woodwork only, Filled and Varnished, gloss finish, Yellow Pine.....4.00
- No. 10-G-895 Mantel, woodwork only, Filled and Varnished, gloss finish, Selected Oak.....4.40

A Pretty Mission Style Mantel

Yellow Pine and Selected Oak.

56 in. wide.

40 in. high.

Tile opening, 36x36 in.

Projection, 4 1/4 in.

Heavy shelf supported by brackets to match.

New design, very nifty, and well built, cut on somewhat different lines than the ordinary. For this reason, we expect it to sell extremely well.

\$388

and worth double

Wall plates can be extended to 60" wide, if so ordered, at 25c additional.

- No. 10-G-896 Mantel, woodwork only, Yellow Pine.....\$3.88
- No. 10-G-897 Mantel, woodwork only, Red Oak.....4.65
- No. 10-G-898 Mantel, woodwork only, Filled and Varnished, gloss finish, Yellow Pine.....4.63
- No. 10-G-899 Mantel, woodwork only, Filled and Varnished, gloss finish, Selected Oak.....5.40

TILE-ANDIRONS

Glazed Art Mantel and Hearth Tile

Glazed Tile is positively the only kind that can be kept perfectly clean.
No trouble at all to keep spotless and bright.

Every piece of our Enameled Art Mantel Tile is guaranteed flawless in quality and perfectly manufactured. These are the essentials that ensure permanency and when you have your mantel faced and your hearth laid with our strong, durable vitreous Art Tile, you have not only added beauty to your home, but you have also built for all time to come.

All of the most desirable colors—Ivory, Cream, Green, Brown, Delft Blue and Mottled Onyx in various shades. The glazing of our tile is an exceptionally brilliant hard enamel. The colors are literally burned in and it is impossible for the tints or shades to fade, discolor or tarnish.

Our Enameled Art Tile makes the best sanitary hearth and mantel facings and our low prices put this high grade material within the reach of the smallest purse. Low in price but not "cheap." We have not sacrificed quality for price. Quality first and the price as low as is consistent—that's our motto. There are some inferior tilings on the market of the "cheap" variety, manufactured from poor quality of clay and with a finish which cannot be guaranteed. Such a tile will not stand the test of wear and hard usage.

The size of each piece is 6x1½ inches. In barrel lots, special prices will be made.


Explanation How to Order

"A" to "A" shown on the opposite illustration is the "Grate Opening" measurement.

"B" to "B" is the Mantel "Tile Opening" measurement.

The first thing to do is to select the Mantel, then select the Grate, then see the size of the tile opening of the mantel as well as the size of the grate opening of the grate, and in ordering your tile, be sure that you allow sufficient to cover the proper opening. If Summer Front is not included in the grate and you desire it, allow the amount charged extra.

For instance, we will assume that you select Mantel No. 10-E-5061, tile opening 42x39" and that you select the smallest size Mephisto Grate Outfit No. 10-E-1354, the size which will fit into a grate opening 24½x30½. You will thus require the largest amount of tile, as the mantel tile opening is the largest that is made and the grate opening is the smallest, leaving a large space to be filled with tile. You would, therefore, require our No. 10-E-1608 for tile opening 42x39, grate opening 24½x30½, amounting to \$7.49.



Number.	Size of tile opening of Mantel.	Size of Grate opening.	Size of Hearth	Price.	Weight.
10-G-1603	36"x36"	30½"x30½"	60"x18"	\$3.68	58 Lbs.
10-G-1604	36"x36"	24½"x30½"	60"x18"	4.20	60 Lbs.
10-G-1605	36"x39"	30½"x30½"	60"x18"	3.97	61 Lbs.
10-G-1606	36"x39"	24½"x30½"	60"x18"	4.38	63 Lbs.
10-G-1607	42"x39"	30½"x30½"	60"x18"	4.55	66 Lbs.
10-G-1608	42"x39"	24½"x30½"	60"x18"	5.98	73 Lbs.

BERLIN BLACK ANDIRONS



10-E-215. Per pair..... \$2.00 Shipping wt. 25 lbs.	10-E-1241. Per pair..... \$2.25 Shipping wt. 30 lbs.	10-E-216. Per pair..... \$1.90 Shipping wt. 25 lbs.	10-E-1242. Per pair..... \$3.95 Shipping wt. 40 lbs.	10-E-1240. Per pair..... \$4.55 Shipping wt. 50 lbs.	10-E-1243. Per pair..... \$5.75 Shipping wt. 65 lbs.
--	---	--	---	---	---

These Andirons represent the very highest type of the designer's art and the workman's skill. A specially prepared metal composition is used in manufacture, capable of withstanding the intense heat to which andirons are liable to be exposed. Finished in a very superior manner. Color, deep Berlin black. The designs we show have been carefully selected with particular reference to their adaptability to our fine line of Mantels and they will be found in keeping with any arrangement of modern furniture and furnishings.

MARBLEIZED SLATE TILE

Takes the Place of Regular Glazed Tile

Save 50 per cent in Price and 75 per cent in Labor

Here is something **Attractive**. Slate marbleized to imitate the various shades of tile. It comes in slabs, requiring three pieces for the facings for a mantel and one piece for the hearth. These slabs come to you all ready to set up, no tile setting required and consequently a great saving to you not only in the first cost of the material but in the cost of setting up.

The material is **regular slate** about 7-16 inch thick for facings and double that thickness for hearths. It is scored to represent tile and covered with a chemical composition on face, having a **polished finish** and **marbleized** to represent the various colors of different tiles. The following are stock mottled colors: Order by number.

- (1) Brown and white.
- (2) Green, yellow and white.
- (3) Light green and white.
- (4) Dark green and white.
- (5) Green, Rose, Pink and White.
- (6) Green, brown and white.


The cut shows these slabs ready to place in the tile opening of the mantel. "B" is the top piece and "A" and "C" the side pieces.

Just think of it! A set of 3 pieces of these facings for a mantel with 36 inch by 36 inch tile opening, and hearth piece, size 5 feet x 2 feet will cost only \$4.90 for the 4 pieces. They are ready to set up. You can do the work yourself. Compare this price against the bare cost of glazed tile, to say nothing of the cost to set up regular glazed tile. By using Marbleized Slate you have no unsightly cracks.

10-E-1601. Complete set, of 4 pieces, Marbleized Slate Facings for mantel tile opening 36 inches x 36 inches (for grate 24½ inches x 30½ ins. and hearth 5 feet x 2 feet. **\$4.90**

10-E-1602. Complete set, of 4 pieces, Marbleized Slate Facings for mantel tile opening, 42½ inches x 39 inches (for grate 30½ inches x 30½ inches), and hearth 5 feet x 2 feet. **\$5.40**

Shipping weight approximately 140 lbs.



Dependable Fireplace Outfits

QUALITY THE VERY BEST THROUGHOUT


Do not make a mistake and buy a grate without seeing how it is built, the damper, the ash dump and above all the **Fire Clay Linings**. A careful comparison of our full line of **Grates** and fireplace fixtures is invited. You can absolutely depend upon the **price** as being the **lowest**, material of the **best** according to its kind. All of our **grate outfits** are new designs, modern in style, matching perfectly with our line of modern mantels, containing the latest improved ventilating and regulating devices. They are outfits very much desired, and, therefore are in great demand. We

will furnish any of our outfits plated in either oxidized copper, oxidized brass or brush brass and all take the same price.

Neither the **fire brick** or **cement** are included in any of our quotations nor do we furnish same, for they can generally be purchased to a better advantage locally on account of heavy freight charges.

Please read our descriptions and specifications carefully, to prevent error in ordering. We **guarantee** that all of our **fixtures and grates** are manufactured in the very best manner, and also guarantee **safe delivery**.

\$2.56 Buys Our Combination
"MEPHISTO" GRATE
Burns Wood or Coal



Our "Mephisto" COMBINATION GRATE is excellent for burning wood and soft coal. The basket or fire pot is made of heavy cast iron and very serviceable. The **Frame** has projecting canopy at top. This grate is intended to be used where the back and sides are built of brick.

The **Summer Front** is of ornamental steel, cannot break; very much superior to the old fashion cast iron kind.

MEPHISTO GRATE OUTFIT

10-E-1354. Mephisto Grate 24½ in. wide x 30½ in. high, with fire pot 20 in. wide x 9 in. deep; Berlin black finish. Price.....**\$2.56**

Plated, 50c extra.
Shipping weight, 70 lbs.


EXTRA: Summer Front add**\$0.75**

LARGER SIZE MEPHISTO GRATE

10-E-1354½. Mephisto Grate outfit with a frame 30½ in. x 30½ in. with a fire pot 24 in. wide and 9 in. deep. Price...**\$2.95**

Extras, same as above.
Shipping weight, 80 lbs.

\$7.95 Buys this Beautiful
"AJAX" GRATE
Burns Wood or Coal



Our "Ajax" DOUBLE DAMPER Set Grate invariably gives perfect satisfaction. It is a beautiful ornament and the material is the very best. This Grate has a heavy fire clay lining on back and sides, in one piece, ready to put in place and does not require the services of a skilled workman to set. Grates with Fire Clay linings on back only soon burn out at the sides and become worthless.

To those desiring an inexpensive serviceable and attractive grate or fire place, fitted and mounted ready for use, we highly recommend our **Ajax** as here described and illustrated. This grate is also equipped with a **Shaker** to shake down ashes and **Dumping Bottom** to dump them.

The arrangement of the double dampers give perfect control to the draft and fire.


"Ajax" grates require little labor or expense to set. Just push it into the fire place and it is ready to start the fire.

AJAX GRATE OUTFIT

10-E-1405. Ajax Grate, frame, 24½ in. wide x 30½ in. high and with a basket 20 in. wide x 9 in. deep. Berlin Black Finish. Summer Front included. Price.....**\$7.95**

Plated, 75c extra.

Furnished in the above size only. Shipping weight, 160 lbs.




SECTIONAL VIEW OF AJAX OUTFIT

Illustration shows the side view of the damper attachment and the full fire clay brick lining of fire pot.

Please note the arrangement of the two dampers and the heavy fire clay sack lining. These are important features.

\$10.50 The Very Best Made
OUR "METEOR"
Burns Wood or Coal.



In presenting our "Meteor" DOUBLE DAMPER set grate we show a grate that has damper slide in ash screen. Both can be closed completely to throw the fire and prevent dust when shaking.

The **Double dampers** give complete control of the fire and perfect ventilation at all times. Very simple in its construction—all in one piece and ready for putting in place. Does not require the service of a skilled workman.

This Grate has large fire pot with full set of **Clamping Liners** which may be removed and replaced from the front without disturbing the grate or setting.

METEOR GRATE OUTFIT

10-E-1420. Meteor Grate, 24½ in. wide x 30½ in. high, with a 20-in. plated basket, with double damper attachment and fire clay brick lining, and including **Summer Front** in heavy cast iron Berlin black finish. Price...**\$10.50**

Plated, 75c extra.
Shipping weight, 160 lbs.


LARGER SIZE METEOR GRATE

We can furnish the Meteor Grate with frame 30½ x 30½ with 24 in. wide fire pot 9 in. deep. 10-E-1420½. Berlin black finish. Price...**\$11.25**

Plated 75c extra. Shipping weight, 200 lbs.

SECTIONAL VIEW

Illustration shows arrangement of damper, fire tile and general construction of our Meteor outfit. Attention is called to the rear view showing the arrangement of the two dampers and the heavy fire clay linings. Shaking and dumping attachment is furnished with each grate without extra cost.



For Prices and Illustrations
of
MANTELS
See Preceding Pages
ENAMELED
or
MARBLEIZED
SLATE TILE
See Following Pages

Gas Grates and Fireplace Fixtures

Vesuvius Mounted Gas Grate.

\$5.50

Outfit consists of:

Complete mounted Gas Grate and Summer Front, copper plated; 24½ inches wide by 30½ inches high. It is fitted with our latest improved 5-row steel burners, spreading one continuous sheet of fire over the asbestos back, and radiating at least one-third more heat than can be produced by any other gas grate with same amount of gas. It has projecting canopy top, and damper for regulating the ventilation; also gas valve, air mixer and copper reflectors. Grate is all put together complete, ready for use. Shipping weight, 75 lbs.

10-E-1314. Vesuvius Mounted Gas Grate Outfit, 24½ x 30½ inches, as described above. Berlin Black Finish.

Price complete..... **\$5.50**


Plated 75c extra.

10-E-1316. Same Outfit as above, except it is 30½ inches wide by 30½ inches high. Berlin Black Finish.

Price complete..... **6.58**

Plated 75c extra.


Note: The Vesuvius Gas Grate is the cheapest, cleanest and quickest fire ever produced. Leaves no dust or ashes. Try one and be convinced.



"Vesuvius" Mounted Gas Grate.

Superior Terra Cotta Triple Gas Log.

\$4.95



This Triple Gas Log shows a beautiful reproduction of natural wood. It is made of the best heavy terra cotta, highly burned, and with reasonable care will last a life time.

10-E-1501. 18 inch, including adjustable spud and mixer. Price each..... **\$4.95**

Portable Basket Grates.


Made with dumping bottom, triple plated, of exceptionally good quality Berlin black finish. Shipping weight of all Basket Grates, about 70 lbs.



10-E-1311. 20 inches wide. Price..... **\$3.80**
10-E-1312. 22 inches wide. Price..... **3.95**
10-E-1313. 24 inches wide. Price..... **4.40**




10-E-1305. 18 inches wide. Price..... **\$3.65**
10-E-1306. 20 inches wide. Price..... **3.90**
10-E-1307. 22 inches wide. Price..... **4.00**
10-E-1308. 24 inches wide. Price..... **4.40**
10-E-1309. 27½ inches wide. Price..... **4.55**



10-E-1317. 18 inches wide. Price..... **\$3.75**
10-E-1318. 20 inches wide. Price..... **4.00**
10-E-1315. 22 inches wide. Price..... **4.50**
10-E-1319. 24 inches wide. Price..... **4.75**
10-E-1320. 27½ inches wide. Price..... **4.95**

Ash Pit Doors.




Special Size Hinges. Extra Strong Catch.

No.	SIZES	Price
10-E-1325.	12 x 16 In.	\$1.65
10-E-1326.	16 x 16 In.	1.98

Chimney Flue Dampers.

With or without Ratchet Control.

Ratchet Control is a device consisting of a simple bent flat piece of iron with saw teeth and ring in end, so that damper opening may be regulated with end of poker.




No.	Outside.	Size of Opening.	Price.
10-E-1327.	24 x 7 in.	18 x 5 in.	\$1.00
10-E-1328.	30 x 9 in.	24 x 6 in.	1.50
10-E-1329.	36 x 9 in.	30 x 6 in.	2.10
10-E-1330.	42 x 9 in.	34 x 6 in.	2.66
10-E-1331.	48 x 13 in.	38 x 9 in.	3.50

Wire Spark Guards.

10-E-1502. Coppered fine wire lining, 24-inches wide, 30-ins. long. Price..... **\$1.65**

10-E-1503. Coppered fine wire lining, 30-inches wide, 30-ins. long. Price..... **1.75**



Ash Pit Trap.



Strong Automatic Will Last a Life Time.

10-E-1333. 7 x 9 inches. Price..... **44c**
10-E-1334. 9 x 11 inches. Price..... **66c**

Highest Quality

Screens

Lowest Prices

Keep The Flies Out--
Save Doctor Bills.

The lumber used in the manufacture of our Door and Window Screens is carefully selected for the purpose, thoroughly seasoned and kiln dried.

BEST CONSTRUCTION


In the manufacture of Screens, our factory uses great care not only in the selection of material but in putting it together. All our Doors are made with dowel joints and we use heavy hardwood corrugated dowels well glued. They are much stronger than the ordinary screen doors, sold by retailers. The cross rails are blind-tenoned into the stiles and not mortised through, giving the water no chance to soak in, therefore prevents rotting.

While screens are primarily an article of necessity and not intended for ornamentation, nevertheless, we believe in making our designs as neat and attractive as possible. The wire cloth is put on by special machinery, stretched drum-head tight and securely tacked. Covered with bead mould, except the "Mission" and "Supreme" doors which have raised mouldings. The black enamel cloth that we use is made from hard steel wire, coated with a durable enamel, baked on. If repainted occasionally, it will last for years.

The Aluminoid Rustless wire cloth furnished for our "Supreme" Doors is made of very hard steel wire, electroplated with a rust proof composition of zinc and aluminum. It is finished with a high grade transparent weather-resisting varnish and far excels ordinary galvanized cloth in wearing qualities.


The Antique Bronze wire cloth is made from 90 per cent pure copper finished in rich antique color which requires no painting. It will not rust and we recommend its use in preference to bright copper cloth on account of its subdued color.

All Doors shown here are made with stiles and rails, 1 1/4 inches thick and manufactured from choice selected Soft Arkansas Pine lumber, with the exception of No. 10-F-526, which is made of kiln-dried Oak.




"POPULAR"

No. 10-F-501.—1 1/4-inch thick.
Made of Selected Soft Arkansas Pine—Stained Walnut. Covered with Black Wire Cloth.
Width. Height. Price, Each.
2' 6"x6' 6".....\$0.85
2' 8"x6' 8"......90
2' 10"x6' 10"......95
2' 8"x7' 0"......93
2' 10"x7' 0"......96
3' 0"x7' 0"......98



"COTTAGE"

No. 10-F-502.—1 1/4-inch thick.
Made of Selected Soft Arkansas Pine—Finished Natural, two coats Varnish. Covered with Black Wire Cloth.
Width. Height. Price, Each.
2' 6"x6' 6".....\$1.03
2' 8"x6' 8"......1.10
2' 10"x6' 10"......1.16
2' 8"x7' 0"......1.15
2' 10"x7' 0"......1.17
3' 0"x7' 0"......1.19



"FAVORITE"

"FAVORITE"


No. 10-F-518.
1 1/4-inch thick.
Made of Selected Soft Arkansas Pine—Finished Natural. Two Coats Varnish. Covered with Black Wire Cloth.
Width. Height. Each.
2' 6"x6' 6".....\$1.19
2' 8"x6' 8"......1.26
2' 10"x6' 10"......1.32
2' 8"x7' 0"......1.31
2' 10"x7' 0"......1.33
3' 0"x7' 0"......1.36

"MISSION"

Made of Selected Soft Arkansas Pine. 1 1/4-inch thick. Very Substantial. Finished Natural. Two Coats Extra Quality Varnish.

No. 10-F-505. Covered with Black Wire Cloth.
Width. Height. Each.
2' 6"x6' 6".....\$1.62
2' 8"x6' 8"......1.69
2' 10"x6' 10"......1.76
2' 8"x7' 0"......1.73
2' 10"x7' 0"......1.78
3' 0"x7' 0"......1.79

No. 10-F-505 1/2. Covered with Galvanized Wire Cloth.
Width. Height. Each.
2' 8"x6' 8".....\$1.93
2' 10"x6' 10"......2.00
2' 8"x7' 0"......1.98
2' 10"x7' 0"......2.02
3' 0"x7' 0"......2.05



"MISSION"

"SUPREME"

(With solid raised panel)

No. 10-F-525. Selected Soft Arkansas Pine, 1 1/4 inch thick. Finished Natural. Two Coats Extra Quality Varnish. Aluminoid Rustless Wire Cloth.

Width Height Each.
2' 8"x6' 8".....\$1.89
2' 10"x6' 10"......1.97
2' 8"x7' 0"......1.94
2' 10"x7' 0"......1.98
3' 0"x7' 0"......2.02


"SUPREME"

SOLID OAK

THE SCREEN DOOR OF QUALITY

No. 10-F-526. Made of Kiln-dried Oak. Golden glass finish. 1 1/4 inch thick. Very strong and substantial. Antique Bronze Wire Cloth. Extremely distinctive in appearance.

Width. Height Each.
2' 8"x6' 8".....\$4.25
3' 0"x7' 0"......4.50



"SUPREME"

Made To Order

Window Screens

Stay in Order

How to Order Window Screens.

Prices given here are per square foot of surface figured on basis of multiplying width and height extreme outside measure over wood and wire both. For Sliding Screens, measure the width between the blind stops and the height from the sill to the point where the glass in the upper sash joins the lower rail. In ordering always give width first. For the Full Length Screens, measure the width between the outside casings and the height from the sill to the top or head casing. It is well always to allow one inch extra for length on account of sub-sill. It is better always to give the glass size of the window.

Now, take for example an ordinary 2-light window, glass measurement 20"x28" in each sash. The outside measure for a full length screen will be 2' wide by 5'2" high; allowing one inch extra, the size to be figured is 2' by 5'3", a total of 10½ square feet.

"STANDARD" Window Screens

Our "STANDARD" Window Screens are well made from carefully selected materials. Close-fitting joints. Strongly built in every way.

Small outlay of money invested in screen doors and windows may not only save you doctor bills but may save the lives of yourself and children. Danger lurks in the hairy, clinging feet of the common house fly. Millions of disease breeding germs are carried into your home, contaminating your food, and the entire list of ravaging fevers are liable to follow, to which children are especially susceptible. And not only that, but what a nuisance they are.

Shut out these pests, and keep them out by using our custom-made screens.

"STANDARD" Screens are made to order either full size or half size. The half size screens are grooved at the sides for slides. Slides are included in the prices quoted. Furnished in three grades of wire as listed.

Our custom made Window Screens are furnished painted black or Unpainted.

PRICES PER SQUARE FOOT FOR WINDOW SCREENS MEASURING FROM OUTSIDE TO OUTSIDE.

No.	Full size, Black Wire Cloth.....	Thickness.	
10-F-506.	Half " " " " " " " " " " " "	1/16"	8½c
10-F-507.	Full " " " " " " " " " " " "	1/16"	9c
10-F-508.	Half " " " " " " " " " " " "	1/16"	10c
10-F-509.	Full " " " " " " " " " " " "	1/16"	10½c
10-F-510.	Half " Galvanized Wire " " " " " "	1/16"	10c
10-F-511.	Full " " " " " " " " " " " "	1/16"	10½c
10-F-512.	Half " " " " " " " " " " " "	1/16"	11½c
10-F-513.	Full " " " " " " " " " " " "	1/16"	12c
10-F-514.	Half " Coppered Bronze Wire.. " " " " " "	1/16"	16c
10-F-515.	Full " " " " " " " " " " " "	1/16"	17c
10-F-516.	Half " " " " " " " " " " " "	1/16"	17c
10-F-517.	Full " " " " " " " " " " " "	1/16"	18c

No screen covered with Black wire, furnished for less than 75c.
No screen covered with Galvanized or Aluminoid Wire, furnished for less than 90c.
No screen covered with Bronze or Copper Wire furnished for less than \$1.00.

HALF SIZE SCREENS WINDOW WITH GROOVED STILES AND LOOSE SLIDES



FULL SIZE

SOMETHING BETTER

"RELIABLE" Window Screens

BUILT TO LAST

Our "RELIABLE" Window Screens have full mortise and tenoned joints, the tenons being securely wedged in the mortise after being dipped in boiling hot glue. This is unquestionably the strongest joint that can be made.



Window Screens of Unusual Merit.

A special feature is the small duplicate brass numbers furnished free with our "RELIABLE" Screens. You know at a glance where each screen belongs.


This is a strictly high grade screen in every way, made from the best materials carefully selected for the purpose, extra fine finish. Made to your order.

The Side Stiles and Top Rails are 13-16"x1½". Bottom Rails, 13-16"x2½". The Wire Cloth is stretched tight, tacked securely on edges add covered with half round mitred mouldings.

Illustrations shown represent half the size of a full window, to cover the bottom sash. The cut at left shows the hand holes and the cut at right shows imaginary sections cut out so that you can see the brass plated steel springs which are set in the grooves. These springs are fastened at one end only, allowing a certain amount of play so that the screens can be easily raised and lowered. Easily removed and in-falled by pushing against springs that clear the grooves from opposite sliding strip. Oiled hardwood sliding strips are furnished.

The "RELIABLE" Full Length Window Screen is made the same as the Sliding Screen, with the exception that there are no grooves or springs at sides and no hand hole lifts. Full length screens have narrow bar across the center.

Finished with preventative primer and painted one coat pure lead, Olive, Green or Black Paint.



PRICES per square foot, outside measure. For 1½ inch thick add 10 per cent to these prices.

Covered with **BLACK ENAMELED** wire 14 mesh Cloth. No Screen furnished under 85c.
No. 10-F-534. Full length Screens, 10c
per square foot.....
No. 10-F-535. Half length Sliding Screens, per square foot..... 10½c

Covered with **ALUMINOID RUSTLESS** wire 14 mesh Cloth. No Screen furnished under \$1.00.
No. 10-F-536. Full length Screens, 12c
per square foot.....
No. 10-F-537. Half length Sliding Screens, per square foot..... 12½c

Covered with **ANTIQUE BRONZE** wire 14 mesh Cloth. No Screen furnished under \$1.25.
No. 10-E-538. Full length Screens, 19c
per square foot.....
No. 10-F-539. Half length Sliding Screens, per square foot..... 20c

"FLI-PROOF" Adjustable Window Screens

No. 10-F-512.

This is the most satisfactory Adjustable Window Screen made. Material and workmanship are the best and the new method of center metal bars makes this screen absolutely fly-proof. Made of Selected Hard Wood, finished in Oak. Beaded both sides. Covered with Black Wire Cloth. Can be adjusted to fit any width window between open and closed sizes given.

Our Adjustable Screens are shipped direct from our Ohio factory, packed and crated in dozen lots of the same size and sold only by the doz. at the prices named

Size, Closed Inches	Size, Open Inches	Height Inches	Price per Dozen
21	33	14	\$1.95
21	33	18	2.20
16	26	24	2.68
21	33	24	2.68
23	37	24	3.05
23	37	28	3.40
16	26	30	3.52
21	33	30	3.52
23	37	30	3.93
27	45	30	4.62
23	37	36	4.62
27	45	36	5.35

No. 10-E-519.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

EXTRA FOR LESS THAN DOZEN LOTS.

We are offering Wonderful Bargains in Groceries.



Screen Door Sets

4-E-3673. Consists of one pair heavy hold back spring hinges, Japanese finish, one steel door pull, one hook and screw eye. Per set..... 10c



Screen Door Catches
4-E-3675. Vienna bronze finish, suitable for doors 1 to 1½ inch thick, complete with screws. Price each..... 12c
Price, per dozen..... \$1.29

Malleable Iron Hangers

For full size Window Screens
4-E-2006. Price per pair, with screws..... 10c
4-E-2009. Price per doz pair, with screws... \$1.08
For description see Hardware Section of Catalog.

It Won't Burn

COMPOSITION
Top and Bottom Layers—Strong, heavy Fibre Board.
Center Layer—Rock Plaster Composition.

NOTE—EUREKA Plaster Board is full 5-16 of an inch thick, much heavier and stronger than any similar plaster board on the market. With its two heavy layers of fibre paper and between these a thick layer of Rock Plaster Composition, it is equal to eight-ply of the old style sheathing. Made by special process. Enormous pressure is applied and when the composition has set, it is practically a solid mass.

FIVE-IN-ONE

EUREKA Plaster Board combines in one operation, five distinct advantages

1. WALL COVERING

The perfect substitute, better than lath and plaster.

WHY?

BECAUSE it is safer and cheaper and it does away with 99% of the muss and dirt which is unavoidable with the old style lath and plaster. There is no dampness to contend with, nor waiting for the walls to dry out. The work of interior finish can proceed at once.

2. FIREPROOFING

EUREKA Plaster Board is non-inflammable. That is one of its most important features. It simply cannot burn.

WHY?

BECAUSE it is a well known fact that fibre paper itself, when closely packed together, will not burn through even when exposed to a direct flame. The edges and corners may become charred, but it would take the heat of the hottest furnace a long time to thoroughly consume it. By actual test it will stand 1700 degrees of heat. The outside layers of fibre are thoroughly saturated with the Rock Plaster Composition and this material absolutely CANNOT burn.

3. SOUNDPROOFING

As a sound deadener, it has no equal.

WHY?

BECAUSE if ordinary plaster is considered reasonably sound-proof, we make it 99% more so in manufacturing our EUREKA Plaster Board by putting on each side of plaster, a heavy layer of fibrous paper which everybody knows is used in all kinds of mechanical work as a sound-deadener.

4. HEATPROOFING

With EUREKA walls you can keep cool in the hottest weather.

WHY?

BECAUSE we all know that paper is one of the best non-conductors of both heat and cold. EUREKA Plaster Board gives 99% more protection than ordinary Plastered walls. Even the hottest rays of the sun cannot get through this Rock Plaster Composition and the two heavy coats of fibrous paper.

5. COLDPROOFING

Saves Fuel. The sharp winds of winter cannot penetrate.

WHY?

BECAUSE as a non-conductor of cold, any kind of paper is superior to other materials. Anyone familiar with building construction knows that sheathing paper is used between sheathing and siding on the outside walls for protection against the wind and cold. Every-

one knows that a single sheet of newspaper wrapped around your body under your coat, will keep you warm on a cold day, and it stands to reason that EUREKA Plaster Board, with its two thicknesses of good quality heavy fibrous paper, is impervious to the severest weather. As a fuel saver alone, if it had no other merits, EUREKA Plaster Board would pay for itself in a season or two.

THE MOST ECONOMICAL

Besides being a fire-resistant, a sound-deadener and a non-conductor of heat and cold, EUREKA Plaster Board actually is much cheaper than the old-fashioned method of construction, and combines many advantages which are not obtained with lath and plaster. It can be put on in just one-third the time required for lath and plaster, and it takes the place of the first and most expensive coating of plaster which is absolutely essential with the old method. And further than this, EUREKA Plaster Board makes by far the most enduring walls and will last as long as your building stands.

MAKES A PERFECT BOND WITH PLASTER

There is a firm grip to EUREKA Plaster Board, even firmer than the clinch on metal or wooden lath. The adhesion is perfect. For this operation it is not necessary to moisten the wall, therefore, a big saving in labor is effected; also, you do not have to wait a long time for your walls to dry out, which is always an additional expense and disagreeable feature attached to the lath and plaster process.

NO WASTE

Every inch of EUREKA Plaster Board can be used. It cuts with a smooth, even edge and positively will not crack in sawing or nailing.

Eureka

FIVE-IN-ONE

FIRE PROOF

Plaster Board

MANY USES

Without Plaster

You can put wall paper or burlap right on EUREKA Plaster Board and have the most comfortable kind of rooms. When paper over, best results are obtained by filling the joints smooth with plaster or pasting strips of muslin over the joints. For Summer Cottages EUREKA Plaster Board is just the thing. The expense of applying plaster is completely done away with.

Ordinary Kalsomine or Paint can be applied directly to the surface of EUREKA Plaster Board making a good finished wall without the use of plaster, at almost one-half the cost of lath-and-plaster wall.

With Plaster

When the highest grade of work is required first apply a one-fourth to three-eighths inch brown coat of a good brand of hard wall or wood-fibre plaster on EUREKA Plaster Board, and then, after this has thoroughly set, top it with a thin coat of finishing plaster. On account of the added weight of plaster it is advisable sometimes to put in cross pieces between the ceiling joists for extra nailing strips. This is not necessary on the side walls except to give support where most needed, say about the first joint from the floor.

For Repair Work

After the cracked and broken plaster has been removed EUREKA Plaster Board can be nailed directly on to the old lath, in a building where you wish to repair, then finished with a thin, white coat.

For Poultry Houses, Etc.

EUREKA Plaster Board is positively VERMIN PROOF and makes excellent walls for poultry houses, barns, etc. It is very effective in preventing the encroachments of vermin of all kinds.



Easily Applied

The picture shows how simple is the process of putting EUREKA Plaster Board on the walls and ceiling. It is nailed directly to the studding and ceiling joists. It cuts as readily as a board and leaves an even edge without cracking. Can be put on by anyone who knows how to swing a hammer.

Sheets are 32 x 36 inches and are nailed directly to studding, set 16 inches centers. Spacing—Space boards 1/4-inch apart, breaking joints. For Nailing use 1 1/2-inch wire nails with small shank and large heads, spacing nails to 6 inches apart. For Cutting, use ordinary cross-cut saw.

EUREKA Plaster Board is regularly put up in crates containing two squares (200 sq. ft.) 25 sheets to the crate, size of each sheet 32 x 36 inches.

No. 22-F-1730. Price, F. O. B. Cars Chicago, per square (100 sq. ft.).....**\$2.50**
Per crate (200 square feet).....**\$5.00**

Shipping weight, per square, 140 pounds.
We also manufacture larger sizes to meet special requirements and furnish sheets 32 x 72 inches (crate 224 sq. ft.), 36 x 72 inches (crate 216 sq. ft.), 48 x 72 inches (crate 216 sq. ft.).
Price, per square.....**\$2.75**

"CEIL-TITE" WALL BOARD

IT IS
DAMP PROOF
COLD PROOF
SOUND PROOF
VERMIN PROOF
FIRE RETARD-
ING
WEAR PROOF

**ABSOLUTELY
THE BEST
BOARD OF ITS
KIND ON THE
MARKET TODAY**


**STRONGEST
and
MOST
DURABLE**



An artistic interior—using "CEIL-TITE" Wall Board

FOR
CEILINGS
WALLS
LINING
BASEMENT
ATTICS
BARN
GARAGES
DAIRY
BUILDINGS
POULTRY
HOUSES
ETC., ETC.

**NO DIRT
PUT ON IN ONE-
TENTH THE
TIME OF PLAS-
TER—WITHOUT
ONE
HUNDREDTH
PART OF THE
DIRT AND FUSS—
ALL FOR MUCH
LESS COST**



"CEIL-TITE" CONSTRUCTION
VERMIN PROOF Vermin and germs will not nest and breed in CEIL-TITE Board, due to the presence of asphalt which is a disinfective. Plaster harbors vermin and therefore is unsanitary.
MANY USES CEIL-TITE Board is the most durable and artistic material on the market for finishing new or remodeling dwellings throughout—also for sheathing purposes and floors and roofs where perfect insulation is desired and never needs replacing.
PERMANENCE CEIL-TITE Board, on account of the tough fibre used is guaranteed to have less contraction and expansion than any similar board on the market. Because it is made of the best quality of fibreboard, much better than that used on imitations, our fibreboard being of long, woody stock. It is unaffected by cold or heat by actual tests.


VALUABLE INFORMATION
CONSTRUCTION CEIL-TITE Board is composed of three heavy sheets of fibre board, united by walls of asphalt waterproofing compound, the total forming a firm and rigid sheet. 3-16 inch total thickness.
SIZES CEIL-TITE Board does not require unsightly strips close together, as we are offering you the greatest selection of sizes that have ever been offered on the market; sheets as long as 16 feet, which is longer than most rooms ordinarily are in length and certainly longer than the width of almost any room. Beautiful effects for beam ceilings and side walls can be had. For instance—if your room is 16x16, you can buy the 16 foot length sheets, place a beam at every joint and thus have a perfect ceiling.
WATERPROOFING CEIL-TITE Board is impervious to water, moisture and dampness as it is impossible for moisture to penetrate the two inner sheets of asphalt thereby insuring dry, healthy rooms regardless of outdoor conditions.
NON-CONDUCTIVE CEIL-TITE Board is a non-conductor of sound, heat or cold and possesses greater tensile strength than plaster and will not disintegrate.
FIRE RETARDING CEIL-TITE Board retards the progress of fire and resists heat to a degree of high intensity. It will remain rigid and firm in place up to the time that the fire is beyond control and does not pull away or crack, thereby offering leeway to the flames as does plaster.
DECORATION CEIL-TITE Board offers unlimited opportunities for artistic decoration. It can be papered, tinted, panelled, stenciled, enameled, frescoed or painted with oil or water colors. Many artistic panel designs may be obtained by its use; or the joints between the sheets of board may be filled with a crack filler, as well as the depressions over the nail heads, leaving a smooth surface over which to apply the decoration. It requires approximately 1 pound of crack filler to every 150 lineal foot of CEIL-TITE Board. After the filler has set three or four days, scrape it off smooth, then give it a coat of shellac.
SHIPMENTS CEIL-TITE Board is packed for shipment in special crates; we guarantee safe delivery in good condition. The shipping weight is approximately 80 pounds per 100 square feet. We also show shipping weight per sheet.



Showing the studding arrangement, also how clean and easily CEIL-TITE Board is applied. Nailed directly to the studding which are set 16" to centers.

APPLICATION CEIL-TITE Board is applied directly to the studding and joists. Headers should be placed not over five feet apart and also that all four edges of the board may be nailed securely. The ceiling boards should be applied first and reach clear to the wall studs, permitting the wall sheets to fit up snugly under them. Flat Head or Box Nails and Bung Head or Casing Nails should be used. Size for direct application, 1 1/2 inch. For applying over old plaster, 2 inch nails should be used, nails to be placed not more than 2 inches apart in both cases.
NOTE Owing to the great variety of sizes we offer, and the fact that we are extremely crowded for warehouse room here in Chicago, until our new buildings are finished, compels us to offer same for shipment direct from our factory only, same being located at Cincinnati, Ohio, and from which point freight rates, of course are considerable less to all central and eastern territory. Below find a table of sizes and prices of CEIL-TITE Board.

SAMPLE FREE



The same room showing one of the many artistic decorative effects possible with CEIL-TITE Wall Board.

Width, Inches.	Length, Feet.	Sq. Feet per Sheet.	Price per Sheet in Less than Crate Lots.	No. of Sq. Feet in a 20 Sheet Crate.	Price per Sheet in Crate Lots.	Price per Sheet in Lots of over 5,000 Sq. Feet.	Weight per Sheet.	Width, Inches.	Length, Feet.	Sq. Feet per Sheet.	Price per Sheet in Less than Crate Lots.	No. of Sq. Feet in a 20 Sheet Crate.	Price per Sheet in Crate Lots.	Price per Sheet in Lots of over 5,000 Sq. Feet.	Weight per Sheet.
32	6	16	\$0.40	320	\$0.36	\$0.34	13	48	6	24	\$0.58	480	\$0.54	\$0.51	19
32	7	18 1/2	.44	373 1/2	.42	.40	15	48	7	28	.67	560	.63	.60	22
32	8	21 1/4	.50	426 1/4	.46	.46	17	48	8	32	.77	640	.72	.68	26
32	9	24	.55	480	.52	.51	19	48	9	36	.86	720	.81	.77	29
32	10	26 1/2	.65	533 1/2	.60	.57	21	48	10	40	.96	800	.90	.85	32
32	11	29 1/4	.70	586 1/4	.65	.63	23	48	11	44	1.08	880	.99	.95	35
32	12	32	.75	640	.71	.68	26	48	12	48	1.15	960	1.08	1.02	38
32	14	37 1/4	.90	746 1/4	.84	.80	30	48	14	56	1.34	1120	1.25	1.20	45
32	16	42 1/2	1.10	854 1/2	.96	.91	34	48	16	64	1.54	1280	1.43	1.37	51

CRACK-FILLER CEMENT—The Best—5 lb. can, 23c per lb.; 10 lb. cans, 21c per lb.; 25 lb. cans, 19c per lb. One pound will cover from 125 to 150 lineal feet of joint including nail depression.


**OUR
IMPROVED**

"MAGIC" WALL BOARD

Takes the Place of Lath and Plaster. Makes Warm Houses.


"Magic" Wall Board as now manufactured by the improved process is a perfect substitute for old style lath and plaster. An important change has been made in the form of construction which we have found to give more satisfactory results. The same composition is used as formerly and all the good features of the original wall board are preserved and some bad features, such as shrinkage and blistering, eliminated. We have found a better process.

"Magic" Wall Board takes the place of lath and plaster. It is manufactured for us exclusively under licensed patent. It is a combination of lath, asphaltic mastic and heavily sized cardboard paper all in one. It is manufactured in sheets 4 feet square; it is ready to nail up. Anyone who can drive nail can do the work.



How It is Made

The top or flat surface is heavy sized card board—strong, durable, fibrous paper. Next comes a thick layer of asphalt mastic and then regular building lath, planed smooth, spaced about 3/4 inch apart. The mastic is applied while hot and the lath are imbedded in the solution under an enormous pressure of 500 lbs. to the square inch, thus assuring positive adhesion. When it has cooled and set, the composition is as strong and rigid as if one solid piece. Impervious to changing weather conditions. Not affected by dampness nor heat.



This illustration shows just one of the many possibilities—an attic finished off with "Magic" Wall Board. No dirt, no muss and very little expense.

The Old and New Way

Advantages of Asphalt Mastic

AS USED IN THE MANUFACTURE OF OUR MAGIC WALL BOARD.

Asphalt Mastic is proof against (1) Moisture—(2) Heat—(3) Cold—(4) Wind or Air—(5) Sound—(6) Vermin—(7) Acid.

Asphalt Mastic is unaffected by climatic conditions or changes in the weather. Its advantages, therefore, over lime plaster for wall and ceiling purposes at once becomes apparent.

Dry Walls and Ceilings

"Magic" Wall Board makes a sanitary, firm, substantial wall, which insures apartments anywhere at any time as dry as a chip.

"Magic" Wall Board is delivered to users dry, is applied dry, and stays dry for all time.

"Magic" Wall Board does not absorb moisture. That's why the unsightly ragged, ever lengthening and widening cracks common in plaster walls and ceilings are not to be found in houses finished with "Magic" Wall Board.

Some of the Many Uses

(1) **SUBSTITUTE FOR LATH AND PLASTER.** "Magic" Wall Board takes the place of lath and plaster when nailed directly to the inside studding with the finished surface exposed on inside of building. Sheathing boards in many cases will not be necessary, unless climate is severe when "Magic" Wall Board is used on inside instead of lath and plaster.

(2) **SUBSTITUTE FOR SHEATHING.** "Magic" Wall Board is used as a substitute for sheathing. That is, it is nailed to the studding on the outside of building with lath side exposed, then the weather boarding nailed over same. This offers double protection, gives insulation and dead air space between "Magic" Wall Board and the siding and makes a thoroughly warm house. When "Magic" Wall Board is used as a sheathing on the outside of a building, and if "Magic" Wall Board is used as a substitute for lath and plaster on the inside of building, it offers great protection, giving an ideal building regardless of climatic conditions. It keeps out wind in the winter and heat and moisture in the summer.

(3) **FOR CEMENT COATING.** "Magic" Wall Board nailed on the outside studding with the lath side exposed is suitable for cement coating. It has been tested and found that cement will adhere to the asphalt mastic with the combination of lath and asphalt, backed by a heavy cardboard paper, and then when the cement coating is applied, a better wall will be had than can be secured from any other combination. It will be moisture proof and will mean a saving of 50 per cent in cement, as the cement does not have to drop down behind to make a "key", as is the case with ordinary lath either of wood or wire.

(4) **POULTRY HOUSE OR BARN LINING.** Mice and vermin will not nest in "Magic" Wall Board, as it contains no hair, and asphalt mastic is very objectionable to them and they will not attack it as they do ordinary lath and plaster. It will make a warm poultry house or barn.

If you have an attic to finish off, "Magic" Wall Board is just the thing. You can do the work yourself in less time than it would take you to hunt up a plasterer and talk it over.

Magic Wall Board is made in sheets of the most convenient size, 4 feet square, and put up in crates containing 16 sheets—256 square feet.

How it is Applied

"Magic" Wall Board is made in four foot squares to meet the demand of standard sized studding, set to 16-inch centers. (Equally adapted to 12 or 24 inch centers.)

"Magic" Wall Board is easy to handle. It is nailed with the lath side directly to the studding, leaving a smooth paper to be the face; or if a brick, stone or cement block wall is to be covered, directly to the furring strips, requiring no special or intricate tools and any one who can drive a nail can apply it. Use an ordinary 4-penny wire box nail or a 4-penny lath nail, driving nails in every lath at every studding. It can be cut into any shape to fit any corner. It can be bent to fit any curve. It cannot possibly drop off. It is well to leave a space of 1-8 inch between the joists to allow for settling of the building if the building is new. Fill the joints carefully with plaster of paris or wood fibre plaster. After this is nearly set smooth down with an ordinary wetted brush and trowel before applying the kalsomine, paint or wall paper over the surface for the final decoration. There is no product upon which wall paper will stick better than on "Magic" Wall Board.

Begin at the Top

In applying Wall Board, begin at the top, as it is easier to fit at the bottom on the floor than at the top on a scaffold.

Drive one nail in every lath, and every studding.

This method is sufficient to hold tight and it means a saving of labor as well as nails.

When wall paper is applied it is best to use muslin or cheese cloth strips over joints. To obviate any possibility of paper cracking, use shrunken cloth.

No Waste

Every foot of wall board can be utilized. You do not have to pay for window and door spaces in its application. "Magic" Wall Board is readily cut with a hand saw and knife to fit all spaces without any waste at all. Therefore, 1,000 square feet of Wall Board will cover 1,000 square feet of space. Coal oil will remove asphalt mastic from saw or knife.

Here's a remarkable item on saving. You can apply Magic Wall Board in half the time required in the use of any other material. That means an additional saving of 50 per cent in labor. One man is all that is required in applying "Magic" Wall Board to the studding. An ordinary lather can finish a wall with "Magic" Wall Board in less time than he can put on lath or plastering.

Decoration

"Magic" Wall Board will take any kind of decoration—wall paper, paint or kalsomine. A very good combination is to paper the side walls, paneling the ceilings in 4-foot squares, the exact size of "Magic" Wall Board sheets. The most artistic effect may be obtained by the use of ceiling beams.

After the joints have been properly filed, you can paint or kalsomine your walls and no cracks will show. If wall paper or burlap is used, all that is necessary is to strip the joints with shrunken muslin, as explained in the instructions.

PRICE

Per square of 100 square feet... **\$2.50**

Per crate of 256 square feet..... **6.40**

F. O. B. Chicago

Freight prepaid. Prices will be quoted upon application.

Note: Send for Special Prices on Car Load Lots of Not Less Than 250 Squares.

No Orders Accepted for Less Than 256 Square Feet at Above Prices.



Greenhouse Material

Hotbed Sash, Glass, Sash Bars, "Pecky" Cypress Lumber

13 Points of Superiority

1. Four rows of glass.
2. Clear Stock.
3. Standard size glass.
4. Large triangle points.
5. Strong center bars.
6. Extra size tacks.
7. Glass set by hand.
8. Chicago shipments.
9. Pure Linseed oil putty.
10. Extra deep rabbet.
11. Oregon Fir.
12. Maximum of strength giving qualities.
13. Minimum of useless and shadow-casting bracing devices.

ALL PRICES FOR MATERIAL named on this page are F. O. B. our Yards or delivered to any DEPOT or DOCK in CHICAGO.

Prices of Glazed Hotbed Sash

Size, 3 ft. by 6 ft.
1 3-8 inch thick.

Clear Oregon Fir

No. 10-G-1701. Single lots.	\$1.94
Price each.....	
No. 10-G-1702. Dozen lots or more. Price each...	1.88
No. 10-G-1703. Lots of 50 or more. Price each...	1.80

Prices of Open Hotbed Sash

Clear Oregon Fir

No. 10-G-1704. Price, single lots, each.....	\$1.00
No. 10-G-1705. Price in lots of 1 doz. or more, each	.98
No. 10-G-1706. Lots of 50 or more. Price.....	.92

GREENHOUSE LUMBER

We have in stock ready for shipment, "PECKY CYPRESS" BOARDS one inch thick in the rough. Furnished in mixed widths and lengths only. Every greenhouse man knows that "Pecky Cypress" while not much for looks is the longest lasting wood known for hotbed and greenhouse purposes.

Price, per 1,000 feet surface or board measure.....**\$17.50**

Gardeners, Florists, Celery Growers and Greenhouse Men In General! Look at These Low Prices! Then Read How Well Our Sash Are Made!

Here are the 13 points of superiority analyzed. Read them over carefully and be convinced. But greater than these 13 points of superiority are our low prices.

Practical greenhouse men applying common sense to their business will readily concede that the standard size Sash 3 ft. x 6 ft., made with four rows of glass makes the ideal Hotbed or Greenhouse. If the stiles, rails and bars were made narrow like the ones in sash made with five rows of glass, you would have a little more glass space to begin with but less glass to end with because such sash lack the strength and rigidity necessary to support the weight of 20 lbs. of glass. That is the very reason such sash require bracing. And such bracing bars cast an extra amount of shade and cost an extra amount of money. Our four-row sash don't need bracing of any kind and you don't want any other kind.

LISTEN. The five-row sash is inferior in more ways than one, they are made that way for the distinct purpose by the manufacturer so he can use his odds and ends of broken glass cut down to 6 inch in width. Such lights as a rule are not uniform in length, because the broken pieces from which they are cut are not uniform. This means an extra expense for you when repair time comes around, because 6 inch glass is not a standard size glass in the first place and you would have to buy larger sizes and cut them down, and in the second place because the length of the glass in the sash varies which will entail an extra amount of waste. This is especially true when buying open sash.

In the third place because of many lights being shorts require more laps and laps harbor dirt and dirt casts shade. There you are. You will take the four-row sash with standard glass every time.

In the fourth place if the narrow bars are not braced there is danger of spreading in one row and danger of contraction in another. Result? Breakage of glass and loosening of putty. No—you can't use the five-row sash at any price and our standard four-row sash are lowest in price.

About sash made with three rows of 10 in. glass. There is a decided disadvantage, because the price is higher to start with and they only have 2 center bars and cost twice as much to repair broken glass. The bars cannot be made heavier than the ones in our four-row sash because this will weaken the stiles or side pieces which are narrow enough already. You are safer with the superior kind and why shouldn't you buy them when you can get them for less money?

You get a Sash made of Clear Stock and in addition the Western Pine Sash are painted in Lead and Oil. An extra deep rabbet means an extra amount of putty protection. Glass is set and pointed by hand, using large triangle tins and extra size tacks.

And last but not least, our Hotbed Sash are Shipped from our Chicago Yards, assuring better service than you could possibly obtain from any other point. Eastern customers especially should take this into consideration.

How to Make a Hotbed and How to Make It Pay.




great demand everywhere.

Illustration shows how simple it is to make a hotbed. You should dig your pit 2 ft. deep and as long as you wish to make the hotbed. Board up the sides with 1 in. or 1 1/2 in. lumber. The frame should be made in two sections. The lower section about 18 in. high all around, and the top section should be made 16 in. at the back and 8 in. in the front. This will give a slope of 8 in. to shed the rain. Place fresh manure in the pit to a depth of about 18 or 20 inches, then put the hotbed sash on and let them remain for 3 or 4 days, then cover with soil as rich as you can get. Let it stand for 5 or 6 days longer depending upon the temperature. Soil should be about 6 in. from the glass at the lowest point. Hotbeds should be made about two weeks before seeding. Be sure to raise your sash a little every morning for ventilation but not far enough so that the cold air can flow directly on the plants, and as soon as the sun sets close the sash over night to retain the heat.

To obtain best results the Bed should be given a Southern exposure and be protected from the North Wind.

COMMUTERS AND OTHER country folk who are fond of Chinese Gardens. Make your garden pay by making a Hotbed.

You can have radishes, vegetables, and strawberries long before the man who does not use Hotbed sash, and whatever you do not need for your own use, you can without trouble, dispose of to others at fancy prices because home grown garden truck is in



Hot Bed Glass.



Standard quality. Large stock on hand. Packed strong. Safe delivery guaranteed.

Lot Number	Size inches.	Price per Box.	No. of Lights in Box.
10-G-1707.	7x9	\$2.60	114
10-G-1708.	8x10	2.32	90
10-G-1709.	9x12	2.65	67
10-G-1710.	10x14	2.70	51
10-G-1719.	16x18	2.80	25


INSIDE SASH BAR

No. 10-G-8435.
Used between Sash, Size 1 1/2x2 1/2. Price per 100 running feet.....**\$3.05**




END SASH BAR

No. 10-G-8436.
Used at ends of Hotbeds. Has but one square shoulder for Sash to rest upon. Size 1 1/2x2 1/2. Price 100 running feet.....**\$2.95**



FINISH LUMBER

CEILING AND PARTITION



King of the Forest— The Stately Fir

Fairminded, farsighted folk, who are familiar with Fir **k-n-o-w** that this fine, choice lumber, grown in the **Pacific Coast States**, has taken great forward strides in the last few years, being used more and more for all kinds of building purposes. Suitable for all around interior and exterior work. A great favorite for finishing boards.

Why "F-I-R" Fears No Competition

Many woods are being used and pushed for outside finish, but **none come nearer than Fir** to the Northern Soft Pine when both economy and utility are considered. There may be other woods equalling Fir's durability, but none **can equal Fir's low price.**

When one can buy a **Selected** grade of lumber practically **clear and free from knots** at a **lower price** than common knotty White Pine—will not any **common sense** builder promptly take advantage of it? If he uses his brain he surely will.

All finishing furnished in regular lengths, dressed on two sides to standard widths and thicknesses.

Prices of FIR FINISHING LUMBER

Mixed lengths 8 to 20 ft. not sorted out as to any particular length. Price covers 100 ft. (lumber feet or board measure). Weighs 250 lbs. per 100 ft.

Number	Grade	Thick-ness	4 inch wide	6 inch wide	8 inch wide	10 inch wide	12 inch wide
22-G-5500	Select Fir	1"	\$3.80	\$3.90	\$4.00	\$4.20	\$4.50
22-G-5503	Clear Fir	1"	4.30	4.40	4.50	4.70	5.00
22-G-5505	Clear Fir	1½"	4.90	5.20	5.40	5.60	5.80
22-G-5508	Clear Fir	2"	5.10	5.40	5.60	5.80	6.00

For specified lengths (all one certain length) add 30c per 100 ft.

Minnesota and Western Soft White Pine

Price per 100 ft. Board measure. Weight per 100 ft. 200 lbs. Mixed lengths.

Number	Grade	Thick-ness	4 inch wide	6 inch wide	8 inch wide	10 inch wide	12 inch wide
22-G-5510	Select common	1"	\$4.00	\$4.20	\$4.40	\$4.60	\$4.80
22-G-5513	Select common	1½"	4.80	5.00	5.20	5.40	6.00
22-G-5515	Select common	2"	5.30	5.50	5.70	6.00	6.60
22-G-5518	"C" Select	1"	4.50	4.70	4.90	5.40	5.60
22-G-5520	"C" Select	1½"	4.70	4.90	5.70	5.60	6.00
22-G-5522	"C" Select	2"	5.50	5.60	5.90	6.10	6.50

Short Leaf Southern Yellow Pine Finish

Price per 100 ft. Board measure. Weight per 100 ft. 260 lbs. Furnished in specified or separate lengths from 8 to 20 ft.

Number	Grade	Thick-ness	4 inch wide	6 inch wide	8 inch wide	10 inch wide	12 inch wide
22-G-5524	Select common	1"	\$2.90	\$3.00	\$3.10	\$3.20	\$3.50
22-G-5527	Clear	1"	3.60	3.80	3.90	4.00	4.20
22-G-5529	Clear	1½"	4.00	4.20	4.40	4.60	4.80
22-G-5532	Clear	2"	4.20	4.60	4.80	5.00	5.50

Clear Grade Cypress, Poplar, Western Spruce, Red and White Oak Finish

Price per 100 ft. Weight 300 lbs. per 100 ft. Furnished mixed lengths up to 16 ft. For specified lengths add 30c per 100 ft.

Thick-ness	Width	22-G-5535 Cypress Clear	22-G-5540 Poplar Clear	22-G-5545 Spruce Clear	22-G-5550 Red Oak Clear	22-G-5555 White Oak Clear
1 inch	4"-6"-8"	\$4.90	\$5.30	\$5.00	\$6.80	\$7.00
1 inch	10" and 12"	5.50	6.50	5.50	7.00	7.00
1½ inch	4" to 12"	5.60	7.00	6.00	8.00	8.50
2 inch	4" to 12"	6.00	7.50	6.50	9.00	9.80

Yellow Pine Ceiling and Wainscoting

For porches and under eaves. Dressed, matched and beaded. Machine in first-class shape. Sold in mixed lengths only from 8 to 20 ft. 80 per cent of our sales are for the No. 1 grade. Specified lengths 30c per 100 ft. extra.

Number	Rough size	Finished size	Grade	Price 100 ft.	Weight 100 ft.	Add 25 per cent or one fourth on account of loss in working tongue groove.
22-G-5560	1x4	¾"x3 ¼"	No. 2	\$1.75	160 lbs.	
22-G-5562	1x4	¾"x3 ¼"	No. 1	2.30	160 lbs.	
22-G-5565	1x4	¾"x3 ¼"	Clear	2.60	160 lbs.	
22-G-5567	1x6	¾"x5 ¼"	Clear	3.00	170 lbs.	

White and Yellow Pine Partition

Dressed and matched-beaded on 2 sides. Specified lengths, 30c per 100 ft. extra.

Number	Rough size	Finished size	Grade	Wood	Price	Weight 100 ft.
22-G-5572	1x4	¾"x3 ¼"	No. 1	Y. Pine	\$2.70	220 lbs.
22-G-5575	1x6	¾"x5 ¼"	No. 1	Y. Pine	3.20	240 lbs.
22-G-5578	1x4	¾"x3 ¼"	No. 1	W. Pine	3.90	180 lbs.
22-G-5580	1x6	¾"x5 ¼"	No. 1	W. Pine	4.10	200 lbs.

On 4 inch partition add 25 per cent on account of loss in working.
On 6 inch partition add 15 per cent on account of loss in working.

GRADES:—Finishing Lumber grades cover a great many technical points, depending upon the character of the wood. Briefly described—one face or side of **clear grade** must be suitable for natural or hard oil finish, free from knots. **Select grade** of Fir is especially recommended for outside work, but not for interior finish. Use the clear for that.

Select Common White Pine contains a certain number of knots, fewer and smaller in proportion in the 4" and 6" than in the wider boards.

"C" Select White Pine is two grades below clear grade. Contains some few sound knots, smaller than appear in select Common White Pine, also sap stain.

No. 1 White Pine Partition is practically the same quality as Select Common with some imperfections in manufacture.

No. 1 Yellow Pine Ceiling and Partition, same grade as "C" Select White Pine and some slight imperfections in manufacture.

No. 2 Ceiling—Lowest grade made in ceiling. Contains more knots than No. 1 but as a rule are sound and not large. Suitable for cheap partition and especially for cheap sheathing on which wall paper is to be applied.

**ALL STYLES
ALL GRADES**

SIDING

**ALL WOODS
ALL WIDTHS**

SIDING! SIDING! In quantities running into millions of feet handled every year. Carload lots coming in all the time. All best and well known woods, noted for their paint-adhering and weather-defying qualities.

You will find some variation in price, partly because some woods are more durable, but this difference is governed mainly by the general supply. If the market is overstocked on a certain item, the price goes down and we are always on the spot to take advantage of market conditions, securing a large share and more of such surplus.

Remember when comparing prices, that we ship direct from our main plant in Chicago, with the lowest freight rates and quickest services assured and if others equal our price or their price seems lower, it is due to the fact that you would have to pay freight from some long distance mill point or unimportant distributing center. Therefore you would not only be exposed to financial loss on account of freight charges but you might also lose valuable time, let alone your peaceful state of mind.

For explanation of grades, see below.

Beveled Siding


Also known as weather-boarding, Split siding, Clapboards or Lap siding. Yellow Pine, White Pine, Poplar, Fir, Red Wood, Red Cedar and Spruce. Machined to standard width and thickness. Prices are for mixed lengths varying from 4 to 16 feet and on some kinds up to 20 feet.

Since 10 feet is now called a standard length, the percentage of short lengths is considered small and the shorter lengths always can be used to better advantage between doors and windows, so no waste will result.

Drop Siding

Also known as Novelty siding, Rustic siding, German or Dutch siding, Patent siding. This page also contains plain Tongued and Grooved Barn Siding. Plain shiplap siding, plain Boards, dressed on two sides and battens.

Yellow Pine or Soft Arkansas Pine—Northern Soft Pine and Western Fir. Machined to standard width and thickness. Prices are for mixed lengths running from 10 to 20 feet in Yellow Pine and Fir. White Pine lengths from 8 to 16 feet only.



No. 117

No. 113

No. 106

BEVEL SIDING

All prices per 100 ft. Weight per 100 ft. Mixed lengths only.

Number	Wood	Size	Grade	Price	Weight
22-G-5000	Yellow Pine	1 1/2"x4"	Clear	\$2.40	90 lbs.
22-G-5003	Yellow Pine	1 1/2"x5"	Clear	2.40	90 lbs.
22-G-5005	Yellow Pine	1 1/2"x6"	Clear	2.45	90 lbs.
22-G-5008	Western Fir	1 1/2"x4"	Clear	2.70	85 lbs.
22-G-5010	Western Fir	1 1/2"x6"	Clear	2.75	85 lbs.
22-G-5013	Western Spruce	1 1/2"x4"	Clear	2.65	80 lbs.
22-G-5015	Western Spruce	1 1/2"x6"	Clear	2.75	80 lbs.
22-G-5018	Red Cedar	1 1/2"x4"	Clear	2.90	80 lbs.
22-G-5020	Red Cedar	1 1/2"x6"	Clear	2.95	80 lbs.
22-G-5023	Red Cedar	1 1/2"x4"	"B" or seconds	2.40	80 lbs.
22-G-5025	Red Cedar	1 1/2"x6"	"B" or seconds	2.45	80 lbs.
22-G-5033	Poplar	1 1/2"x4"	Clear	2.90	85 lbs.
22-G-5035	Poplar	1 1/2"x5"	Clear	3.00	85 lbs.
22-G-5038	Poplar	1 1/2"x6"	Clear	3.00	85 lbs.
22-G-5040	Redwood	1 1/2"x4"	Clear	2.75	80 lbs.
22-G-5043	Redwood	1 1/2"x6"	Clear	2.85	80 lbs.
22-G-5045	White Pine	1 1/2"x4"	Clear	3.30	80 lbs.
22-G-5048	White Pine	1 1/2"x6"	Clear	3.40	80 lbs.
22-G-5055	White Pine	1 1/2"x4"	"C" grade	2.55	80 lbs.
22-G-5058	White Pine	1 1/2"x6"	"C" grade	2.65	80 lbs.

EXPLANATION OF GRADES

Clear grade means free from knots without any reservation.

Select grade—Pitchstreak is the principle defect in Select Fir Flooring and Siding. Some appear on the surface only, some go down deeper. But for this drawback the grade would be practically clear, so the Fir is very nice stock. By just a little cutting you will lose very little time and gain a clear clean-cut job.

B grade—Next grade to clear. On siding the main defect is in manufacture. Some few small knots are admissible, not many. Some of our "B" Red Cedar runs practically free from knots.

C grade—This grade in White Pine Siding contains too many knots and other defects to go for clear or "B" grade. Makes a good siding for jobs not requiring an entire clear surface and with a little cutting here and there even this objection can be largely overcome.

No. 1 grade—Allows for some knots, but they must be sound, not loose, usually the wider the boards the larger the knots. Sometimes some pieces contain splits or cracks but if painted, this defect will do no harm. Our No. 1 Soft Arkansas Pine Drop Siding runs much better for the grade, knots are fewer and smaller than in White Pine, some nearly coming up to a Select grade.

No. 2 grade—Cheapest grade we make in siding. Allows for more knots than No. 1, both large and small, as well as imperfections in manufacture and an occasional small knot hole, so if you want to make a pretty good job, there will be some waste.



Remember that all our stock is brand new, not a piece of second-hand lumber listed in this book

Plain and O. G. Battens

Price per 100 lin. ft. Lengths 8 to 20 feet.

Number	Finished size	How Worked	Kind of wood		Weight 100 lin. ft.
			Fir	Yellow Pine	
22-G-5155	1 1/2"x1 3/4"	O. G.	\$0.75	\$0.73	30 lbs.
22-G-5157	1 1/2"x2 1/4"	O. G.	.83	.80	35 lbs.
22-G-5160	1 1/2"x2 1/2"	Flat	.65	.50	25 lbs.

DROP SIDING

Price per 100 ft. Weight per 100 ft. Mixed lengths 8 to 20 ft. See below for prices on specified lengths.

Number	Wood	Size	Grade	Price	Weight	Pat-
22-G-5101	Soft Arkansas Pine	1"x6"	Clear	\$3.00	190 lbs.	No. 106
22-G-5104	Soft Arkansas Pine	1"x6"	No. 1	2.60	190 lbs.	No. 106
22-G-5106	Soft Arkansas Pine	1"x6"	No. 2	2.25	190 lbs.	No. 106
22-G-5109	Soft Arkansas Pine	1"x6"	Clear	2.90	190 lbs.	No. 113
22-G-5111	Soft Arkansas Pine	1"x6"	No. 1	2.75	190 lbs.	No. 113
22-G-5114	Soft Arkansas Pine	1"x6"	No. 2	2.50	190 lbs.	No. 113
22-G-5116	Soft Arkansas Pine	1"x6"	Clear	2.90	190 lbs.	No. 117
22-G-5119	Soft Arkansas Pine	1"x6"	No. 1	2.75	190 lbs.	No. 117
22-G-5121	Soft Arkansas Pine	1"x6"	No. 2	2.50	190 lbs.	No. 117
22-G-5124	Western Fir	1"x6"	Clear	3.20	190 lbs.	No. 106
22-G-5125	Western Fir	1"x6"	Select	2.95	190 lbs.	No. 106
22-G-5126	White Pine	1"x6"	No. 1	3.50	180 lbs.	No. 106

If any certain length is wanted it is necessary to order Clear or No. 1 Soft Arkansas Pine, and price will be 20c more per 100 ft. No. 2 Arkansas Pine, Fir and White Pine, cannot be furnished in specified lengths.

If you would rather use White Pine in preference to Soft Arkansas Pine for siding (which however, is all shortleaf) but should hesitate to place your order for White Pine because of the doubtful grade at a commensurate higher price for such grade, why not reverse this condition by ordering a higher grade commodity at a lower price.

That commodity is Fir—Pacific Coast Fir. Not a new wood by any means. Read what we say about Fir for porch floors on other page. So don't remain under the impression please, that White Pine is the only wood to use.

Upright Barn Siding

Plain tongued and grooved. Plain Boards dressed on two sides and Battens, Shiplap Siding.

Separate lengths furnished from 8 to 20 feet. No. 1 Yellow Pine Only.

Number	Size	How Worked	Price per 100 ft.		Weight 100 ft.
			8 to 16 ft.	18 and 20 ft.	
22-G-5140	1"x 8"	Tongued and grooved	\$3.00	\$3.25	240 lbs.
22-G-5142	1"x10"	Tongued and grooved	3.00	3.25	250 lbs.
22-G-5145	1"x 8"	Shiplapped	2.85	3.00	240 lbs.
22-G-5147	1"x10"	Shiplapped	2.80	3.10	250 lbs.
22-G-5150	1"x 8"	Dressed 2 sides only	3.00	3.15	260 lbs.
22-G-5152	1"x10"	Dressed 2 sides only	3.00	3.15	270 lbs.

Siding is figured on the basis of the ripping width of the lumber from which it is machined. For instance, 1x6 Drop Siding is made from a 6 inch strip but when machined finishes up 5 1/4 inches only, so this loss of 1/4 inch in working must be added to the quantity of space you want to cover. On bevel or lap siding allowance must also be made for the lap. If you will order according to the following table you should have enough. Table shows how much 100 ft. will cover, also what percentage to add to your wall space.

Ripping Size	Finished Size	100 feet will cover	Add for loss
1 1/2"x4"	1 1/2"x3 1/2"	75 ft. of space	33 1/3% or one-third.
1 1/2"x6"	1 1/2"x5 1/2"	80 ft. of space	25% or one-fourth.
1"x6"	3/4"x5 1/4"	87 ft. of space	15% or one-seventh.
1"x8"	3/4"x7 1/2"	90 ft. of space	10% or one-tenth.



While above table shows actual net amount to be added for loss in working, on account of lap or tongue or groove, it shows no allowance for any emergency, so it is always safe to order a little more, especially on the No. 1 and No. 2 grades.


In explaining the grading rules, we have purposely omitted all mention of technical details, describing in short, concise language, just what you may expect to get. Thus we avoid all misunderstanding. If in this manner we are expressing ourselves more clearly than others, we are glad to give you the benefit of it.

House Flooring
Barn Flooring
Factory Flooring

FLOORING

Southern Pine
White Pine
Oregon Fir

Our line of Flooring is unusually large because we handle so many varieties. No use to look elsewhere for something different, or a lower price, or a better grade. Shipped from CHICAGO within the low freight rate zone, and not from some distant mill point from whence freight charges are high.



Yellow Pine Flooring

Price per 100 ft. Weight per 100 ft.
Mixed length 8 to 20 ft. Lengths not sorted.

Number	Grain	Rough size	Finished size	Grade	Price	Weight
22-G-5202	Flat Grain	1x3"	1 1/2 x 2 1/4"	Clear	\$3.30	200 lbs.
22-G-5207	Flat Grain	1x4"	1 1/2 x 3 1/4"	Clear	3.60	220 lbs.
22-G-5212	Flat Grain	1x3"	1 1/2 x 2 1/4"	No. 1	3.10	200 lbs.
22-G-5219	Flat Grain	1x4"	1 1/2 x 3 1/4"	No. 1	3.00	200 lbs.
22-G-5222	Flat Grain	1x6"	1 1/2 x 5 1/4"	No. 1	2.90	240 lbs.
22-G-5227	Flat Grain	1x3"	1 1/2 x 2 1/4"	No. 2	2.20	200 lbs.
22-G-5233	Flat Grain	1x4"	1 1/2 x 3 1/4"	No. 2	2.20	220 lbs.
22-G-5239	Flat Grain	1x6"	1 1/2 x 5 1/4"	No. 2	2.30	240 lbs.
22-G-5242	Flat Grain	1x3"	1 1/2 x 2 1/4"	No. 3	1.80	200 lbs.
22-G-5247	Flat Grain	1x4"	1 1/2 x 3 1/4"	No. 3	1.90	220 lbs.
22-G-5253	Flat Grain	1x6"	1 1/2 x 5 1/4"	No. 3	2.10	240 lbs.
22-G-5259	Edge Grain	1x3"	1 1/2 x 2 1/4"	Clear	4.20	200 lbs.
22-G-5260	Edge Grain	1x4"	1 1/2 x 3 1/4"	Clear	4.10	220 lbs.
22-G-5261	Flat Grain	Thin	3/8 x 1 1/2"	Clear	2.50	100 lbs.
22-G-5262	Flat Grain	Thin	3/8 x 2"	Clear	2.65	100 lbs.

White Pine Flooring

Price per 100 ft. Weight per 100 ft. Mixed lengths only 8 to 16 ft.

Number	Rough Size	Finished Size	Grade	Price	Weight
22-G-5263	1x4"	1 1/2 x 3 1/4"	No. 1	\$3.50	180 lbs.
22-G-5265	1x6"	1 1/2 x 5 1/4"	No. 1	3.65	190 lbs.

Yellow Pine Barn Flooring and Factory Flooring

Price per 100 ft. Weight per 100 ft. Standard mixed lengths.

Number	Rough size	Finished size	Grade	Price	Weight
22-G-5267	2x6"	1 5/8 x 5 1/4"	No. 1	\$2.55	250 lbs.
22-G-5269	2x8"	1 5/8 x 7 1/8"	No. 1	2.80	250 lbs.
22-G-5270	2x10"	1 5/8 x 9 1/8"	No. 1	2.90	250 lbs.
22-G-5271	1x8"	1 1/2 x 7 1/8"	No. 1	3.20	250 lbs.
22-G-5272	1x10"	1 1/2 x 9 1/8"	No. 1	3.50	250 lbs.

EXPLANATION OF GRADES

Clear grade:—Means free from knots, without any reservation.

Select grade:—The only defect worth considering in Select Fir is pitch streaks, most of which can be cut out with little waste.


No. 1 grade:—Allows for a few knots, but they must be sound, not loose, usually the wider the boards the larger the knot. Sometimes some pieces contain slight checks but this defect will do no harm. Our No. 1 Soft Arkansas Pine Flooring runs much better for the grade, knots are fewer and smaller than in the White Pine.

No. 2 grade:—Allows for a larger percentage of knots, as well as imperfections in manufacture and an occasional small knot hole, when balance of piece is good, and will make a pretty fair job, there will however be some waste.

No. 3 grade:—No. 3 Flooring is suitable for sheathing and lining and is recommended for no other purpose than a cheap kind of floor.

We have refrained on purpose to mention technical description of grades, explaining same briefly yet concisely so that those the least posted may fully understand. Thus we say what others omit, because we want to avoid all confusion at the start.

Save money on freight charges by ordering a carload of 12,000 feet or more, or if you order 4,000 or 5,000 pounds of millwork we can give you the benefit of "special" freight rates, if you can make a combined weight of 24,000 pounds lumber and millwork.



Oregon Fir Porch Flooring

We cannot recommend too strongly this Western wood for the purpose of porch floors. When clear Soft White Pine Porch lumber became scarce and high priced, it became necessary to find something else to take its place, something that not only would measure up nearest to Soft Pine in durability but in wearing qualities. That's Fir, and it wears. It wears better because it is not as soft as Soft Pine and some other woods now being endorsed for Porch floors. As to its durability, don't you worry that this close knit fibrous Fir of the Western Slope will decay in a hurry. Do you suppose we would go to the trouble of hauling lumber all the way across the Cascades and Rocky Mountain Ranges if it was not a durable wood? Would we be foolish enough to pay freight over a distance of 2500 miles or more if it was an inferior article? Don't you worry. Therefore we say again—Fir has all other woods backed off the boards for the purpose of porch floor—bar none, especially if you take the edge grain. It can't sliver and that's what you want to avoid on a porch floor.

Fir edge grain is the only edge grained wood now on the market suitable for porch floors, and even flat sawed Fir is less liable to sliver than other flat sawed woods.

Please bear that in mind too.

Price List Oregon Fir Porch Flooring

Price per 100 ft. Weight 220 lbs. per 100 ft. Some specified lengths.

Number	Size	Grade and Kind	Lengths	Price
22-G-5350	1x3"	Clear Edge Grain	Mixed lengths 8 to 20'	\$4.80
22-G-5352	1x3"	Select Edge Grain	Mixed lengths 8 to 20'	4.50
22-G-5354	1 1/4 x 4"	Select Edge Grain	Mixed lengths 10 to 20'	5.00
22-G-5355	1 1/4 x 4"	Clear Edge Grain	Mixed lengths 10 to 20'	5.30
22-G-5357	1x4"	Clear Flat Grain	Mixed lengths 10 to 20'	4.00
22-G-5358	1x4"	Clear Edge Grain	Mixed lengths 10 to 20'	4.50
22-G-5360	1x4"	Clear Edge Grain	6', 7', 8', or 9'	3.90
22-G-5363	1x4"	Clear Flat Grain	6', 7', 8', or 9'	3.50
22-G-5366	1x4"	Select Flat Grain	6', 7', 8', or 9'	3.30
22-G-5368	1x4"	Select Edge Grain	6', 7', 8', or 9'	3.50
22-G-5369	1x4"	Select Edge Grain	Mixed lengths 10 to 20'	4.00
22-G-5371	1x4"	Select Flat Grain	Mixed lengths 10 to 20'	3.80

Order by number, State Size, grade and length, and if Flat or Edge Grain. No other lengths sorted out except short lengths from 6 to 9 ft.

HOW TO ORDER


Flooring is figured on the basis of the ripping width of the lumber from which it is machined. For instance, 4 inch flooring is made from a 4 inch strip and sold as such, but when machined finishes up 3 3/4 inches face only, so this waste of 1/4 inch in working must be added to the quantity of space you want to cover. If you will carefully order according to the following table, you will have enough.

Table shows how much 100 feet will cover, also what percentage to add to space you want to cover, and how much is lost in machining.

Ripping Size	Finished Size	100 ft. will Cover	Add for waste in working tongue and groove
1x2"	1 1/2 x 1 1/2"	75 ft. of space	33 1/3 per cent, or one-third.
1x3"	1 1/2 x 2"	72 ft. of space	37 1/2 per cent, or three-eighths.
1x4"	1 1/2 x 2 1/4"	75 ft. of space	33 1/3 per cent, or one-third.
1x6"	1 1/2 x 3 1/4"	80 ft. of space	25 per cent, or one-fourth.
Thin	3/8 x 5 1/4"	84 ft. of space	20 per cent, or one-fifth.
Thin	3/8 x 1 1/2"	75 ft. of space	33 1/3 per cent, or one-third.
Thin	3/8 x 2"	80 ft. of space	25 per cent, or one-fourth.

Hardwood Flooring, Lath and Shingles

Smooth Hardwood Flooring



Cut shows our high grade, 3/4-inch flooring. End matched and bored for blind nailing.

Store your flooring in a dry place, if you don't expect to use it right away

Hardwood Floors are Healthful and Economical. A Permanent Sanitary Improvement.

Hardwood floors are more economical than the average home builder realizes, are easily kept smooth and clean. When used in connection with rugs a very handsome effect is obtained.

As all our flooring is run with matched ends, the question of laying a hardwood floor is a very simple matter and any lengths, however short, can be utilized, making a floor as substantial as though it was laid in one piece. The 3/4 inch flooring takes the place of the old fashioned pine and other soft wood floors, practically everlasting.

The greatest feature of the 3/4 inch flooring is its adaptability and usefulness for covering old floors, doing away with the worn and yielding soft wood floors and musty carpets. The result is a strictly "hygienic" floor, much more attractive because finished in the natural wood.

It is a permanent sanitary improvement, besides adding greatly to your renting value.

Hardwood Flooring—Its Varied Use.

The Clear grades are suitable for any residence, for there are no higher grades of flooring made. For residences the Clear grades of Maple flooring are usually ordered for kitchen, hall and bathroom. Oak will be more suitable for the dining room, living room, parlor, reception, room, etc., and Yellow Pine could be used for the bedrooms, making a very economical floor combination.

Select Maple flooring is mainly used for public halls, stores, hotel chambers, and wherever a good but not absolutely perfectly clear floor is wanted.

Factory flooring is recommended only where a good low priced floor is wanted. Used extensively for ware-houses, factory buildings and other large buildings where strength is of more importance than beauty.

SUPERIOR MANUFACTURE

Hardwood Flooring is manufactured from superior kiln dried stock, scientifically treated and is as near perfect as modern machinery can make it, smoothly run, tongued and grooved on end edges as well as side edges and steel polished which gives it the smoothest finish possible. 3/4 inch flooring is hollow backed and bored for secret nailing. All grades furnished in standard lengths and securely bundled.

Thick Hardwood Flooring, End Matched and Bored

Price per 100 feet. Weight per 100 feet Standard lengths. Lengths not sorted.

Number	Wood	Rough Size	Finished Size	Grade	Price	Weight
22-G-5274	Maple	1x2"	1 1/2 x 1 1/2"	Clear	\$5.50	210 lbs.
22-G-5276	Maple	1x2 3/4"	2 x 2"	Clear	5.65	210 lbs.
22-G-5278	Maple	1x3"	2 1/4 x 2 1/4"	Clear	5.65	210 lbs.
22-G-5280	Maple	1x4"	3 1/4 x 3 1/4"	Clear	5.30	230 lbs.
22-G-5281	Maple	1x2"	1 1/2 x 1 1/2"	Select	3.90	210 lbs.
22-G-5282	Maple	1x2 3/4"	2 x 2"	Select	4.50	250 lbs.
22-G-5284	Maple	1x3"	2 1/4 x 2 1/4"	Select	4.75	210 lbs.
22-G-5286	Maple	1x4"	3 1/4 x 3 1/4"	Select	4.75	230 lbs.
22-G-5288	Maple	1x3"	2 1/4 x 2 1/4"	Factory	3.15	210 lbs.
22-G-5290	Maple	1x4"	3 1/4 x 3 1/4"	Factory	3.65	230 lbs.
22-G-5291	Red Oak	1x2"	1 1/2 x 1 1/2"	Clear	7.10	240 lbs.
22-G-5292	Red Oak	1x3"	2 x 2"	Clear	6.70	250 lbs.
22-G-5294	Red Oak	1x3"	2 1/4 x 2 1/4"	Select	5.90	250 lbs.
22-G-5296	White Oak	1x3"	2 x 2"	Clear	7.20	250 lbs.
22-G-5297	White Oak	1x2"	1 1/2 x 1 1/2"	Select	5.70	250 lbs.
22-G-5298	White Oak	1x3"	2 1/4 x 2 1/4"	Select	5.90	250 lbs.
22-G-5300	Red Oak	1x3"	2 1/4 x 2 1/4"	Clear	10.80	250 lbs.
22-G-5306	White Oak	1x3"	2 1/4 x 2 1/4"	Clear	11.17	250 lbs.

End Matched Thin Hardwood Flooring

Price per 100 lineal feet. Standard mixed length.

Net Finished Size Ins.	Select Maple	Clear Maple	Select Red Oak	Select White Oak	Clear Red Oak	Clear White Oak	Weight per 100 Lin. ft. lbs.
3/4 x 1 1/2	\$0.33	\$0.46	\$0.48	\$0.48	\$0.70	\$0.70	17
3/4 x 2	.61	.73	.65	.65	.93	.93	20

How to Order Thin Flooring: Get the square feet space of your floor, which if your room is 10x12 figures 120 square feet. If covered with 3/4x1 1/2", multiply by 8, result 960 lineal feet and if you want to cover same with 3/4x2", multiply by 6, result 720 lineal feet.

Question:—What is price of 10 ft. x 12 ft. room covered with 3/4x1 1/2" Select Maple Flooring?

Answer:—960 lineal feet at 33c per 100 lineal feet is \$3.17.


How to Order Thick Flooring: See previous flooring page

EXPLANATION OF GRADES

CLEAR grade means free from knots and other defects. **Select Grade**—The defects in this grade flooring are mainly of a technical character with an occasional very small knot in the 1/2 inch stock. There are no knots in 3/4 inch thickness, principle imperfection is in manufacture, sap stain and off color.

Factory grade:—This grade appears in Maple Flooring only. Is mainly used for factory purposes. Contains larger and more defects than Select grade, also some knots, but with a little cutting here and there will make a good serviceable floor.

SHINGLES



Choice Red Cedar Shingles	Price per 1000	Weight per 1000	Special Information
22-G-5400—Common 6 to 8 inch Clears, 5 to 2, 16 inch, not less than 6" Clear from butt end. (Special Brand).	\$2.75	180 lbs.	This brand may contain some shorts. Knots main defect.
22-G-5405—Common 10 inch Clears, 5 to 2, 10 inch Clear from butt end. (Special Brand).	3.25	180 lbs.	Very few shorts in 10 inch Clears. Some knots.
22-G-5410—Extra Star A Star Clear 16 inch, 6 to 2 butts. (Regular Brand).	3.48	160 lbs.	The best quality 6 to 2 shingle made more solid than any other brand on the market.
22-G-5415—Extra 16 inch Clears, 5 to 2 butts, Highest grade made. (Regular Brand).	3.97	180 lbs.	All strictly Clear. All strictly 16 inches long. No defects whatever.
22-G-5420—Square Butt Dimension Shingles. Clear 16 inches long.	5.50	175 lbs.	Sold same as other shingles, 4 bunches per 1,000 measure. Usually carried in 4, 5 and 6 inch widths, and run 1/4" to 1/2" scant.
22-G-5425—Fancy Butt Dimension Shingles. Clear 16 inches long.	6.00	175 lbs.	

Prices on Shingles subject to change on account of market fluctuations. Write for delivered prices.

These shingles are manufactured and graded strictly according to official standard as specified by the manufacturers. Our guarantee is back of every bundle. Do not ask us to send sample pieces of shingles, as the grades cannot be correctly judged from a few pieces. If the grades are not clear to you, we will ship you One Thousand Shingles (4 bunches) upon receipt of price. These four bunches may be all one kind or different kinds but if more than one kind are ordered in a sample lot of one thousand, we will charge on the basis of the highest priced kind in the lot on account of the extra handling.

5-2 or 5 to 2 means that the combined thickness of 5 shingles measured across the butt shall measure practically 2 inches.
6-2 or 6 to 2 means that the combined thickness of 6 shingles measured across the butt shall measure 2 inches. 4 Bunches per 1000.

Bright LATH



Always in stock in 32 inch lengths. Full thickness and width. Correct length. Our 32 inch Soft Pine Lath are usually far above the grade of No. 1, strictly first class.

LOW PRICES per 1,000 pieces.

22-G-5450, 32 inch Lath, Soft Pine, \$2.45, 325 lbs.

22-G-5455, 32 inch Lath, Northern Hemlock, \$2.40, 325 lbs.

22-G-5460, 48 inch Lath, Soft Pine, \$4.80, 500 lbs.

22-G-5465, 48 inch Lath, Kiln Dried, Short Leaf Southern Pine, \$4.65. 550 lbs.

Byrkit's Patent Sheathing Lath



Sold in random lengths only—4 to 16 ft. No specified quantity of any certain lengths supplied. Tongued and grooved or square edged as ordered.

22-G-5475, Run from 1x3" strips, per 1,000 ft., \$19.00

22-G-5480, Run from 1x6" strips, per 1,000 ft., 20.00

The "Adjustable" Floor Scraper \$19.75

HARD WORK MADE EASY!

This adjustment shows handle low. Weight on blade 40 lbs., vertical angle of blade 75 degrees. Blade Head left hand "Shear" cut.

Note the overhead weight is adjustable and may be removed.



OUR GUARANTEE Five days are allowed for a thorough test. If the "Adjustable" does not do all we claim, send it back and we will return your money, paying freight both ways.

Introductory Offer \$40 SCRAPER FOR \$19.75

Our object in making this special offer is to introduce the best Scraper that brains and modern ingenuity can devise, and place them where they will show the best results, at a price that is within the reach of all. Remember, this offer is for a limited time only.

This machine is regularly sold on the market for \$40. Through an exceptionally fortunate buying arrangement we are able to offer it to the public at a discount of over 50% from the usual market price. You reap the benefit of this saving.

10-G-1620. "Adjustable" Floor Scraper \$19.75

Complete as above, securely crated, F. O. B. factory near Chicago.

The "Adjustable" Scraper can be used by anyone. It is a Quality Machine. It is strong, durable, simple in construction, easy of operation and adaptable to any kind of practical floor scraping. It can be adjusted to suit the convenience of the operator. The blade can be adjusted to any vertical or lateral angle to the floor. The overhead weight can be adjusted so that anywhere from 30 to 40 pounds of pressure rests directly on the blade, will scrape right up in the corners, close to the moulding along the wall, and do perfect and rapid work on hard or soft wood floors, old or new. Simply push and pull the machine forward and backward in an easy, natural way.

For finishing work the weight can be moved entirely, leaving but a slight weight upon the blade. Under a uniform pressure, an absolutely true and even cut is insured, leaving a perfectly smooth surface.

The iron wheels have rubber tires; are mounted on a split axle, so that each wheel operates and any corners or angles can be turned without marking the finished surface. The weight of the machine is 125 lbs. The blades are 8 inches wide and are made of Disston's Saw Steel—the best blade material manufactured. With each machine we send complete instructions for operating same. In addition, we also furnish six Blades, Burnisher and Wrench, all guaranteed against defective workmanship. Extra blades furnished at 22c each.

PAYS FOR ITSELF!

The time you save in wages pays for the machine in a very short while, you can make some easy money on the side by taking odd jobs. You don't take any chances. All that we ask is that you give it a fair trial and if it does not do all we claim for it, send it back and we will return your money, paying freight charges both ways. The machine must be returned not later than five days after you have received it. This will give you sufficient time to give it a thorough test.

Don't confuse the "ADJUSTABLE" with any other Scraper on the market. The "ADJUSTABLE" is in a class by itself. We are using a number of them right here in our own plant, so if they did not do all we claim we would not be using them ourselves.

THE "ADJUSTABLE" WAY



FROM TESTIMONIAL "I did more work in two hours with the "Adjustable" than an entire gang of six could do in one day by hand."

\$3.75 For a \$10 "Adjustable" Sander Attachment

This Sander is to be Used in Connection with the Above Scraper,

and by simply removing the blade can be attached ready to use. It is adjustable to any angle and a straight or diagonal stroke may be used. The weight adjustment also can be used for light or heavy pressure as desired. By running this over the floor a few times it gives it a perfectly smooth surface, and in one-quarter the time it usually takes it is ready for finishing. We suggest that you include one of these with your order for Scraper, so that you can complete your job ready for finishing. Our binding guarantee also protects you on this if you are not satisfied.

No. 10-G-1621.
"Adjustable"
Sander
Attachment.



\$3.75

Illustration shows Sander attached ready for use.

THE "HARRIS JUNIOR" FLOOR SCRAPER

The Harris Junior is Positively the Best Scraper on the Market for the money, and you can save enough on one

job to pay for it. It is a model of efficiency and does perfect work. The body slides on the floor like a plane, insuring a uniform cut. Works equally well on all kinds of hardwood flooring, including Georgia pine. Old floors may be made to look like new. A rubber cushion over the knife prevents chattering (jumping and chopping up the surface.) Complete outfit includes: **Five curved blades, size 3x4, one straight blade, oil stone, burnishing steel and wrench.** This scraper has an adjustable handle easily raised or lowered. The wheels are rubber tired. Weight of machine, 70 lbs.

No. 10-G-1650. Harris Junior Floor Scraper, complete outfit as above described, F. O. B. cars, factory near Chicago. Price \$9.98

The method of operation is simple. The machine is pulled toward the operator, allowing the entire weight to fall upon the blade, thus assuring a steady, even cut. The blades are made of hard tempered steel.

A Regular Little Giant—Does the Work of 3 Men.

\$9.98



Great Paint Announcement

IS NOW OUR
PAINT SUPERINTENDENT


MICHAELSEN

KNOWN FROM
OCEAN TO OCEAN

**Write Michaelsen
For
Paint Information**

Quality. The Michaelsen quality is best represented in our Premier Brand Ready Mixed Paint. It is of the highest quality. You cannot possibly do better than to favor us with your order for your requirements in the paint line. Our PREMIER PAINT is made only of the best materials it is possible to procure and is manufactured under the direct supervision of the foremost paint maker in the business today. Every shipment comes from freshly made stock, thus insuring uniformity of color, greater covering capacity and absolute ease of application. The careful work and study of our paint experts and the personal supervision of each order, makes our PREMIER PAINTS the most durable, unfading and satisfactory that can be produced. That is why we guarantee it so freely.

**His Picture Has
Appeared on More
Than 6,000,000
Cans of Paint**



**Michaelsen Has Had
30 Years of Honest
Paint Experience**

A Saving of at least 50 cents per gallon. PREMIER READY MIXED PAINTS are equal and even superior to most of the paint sold at \$1.65 to \$2.00 per gallon. Why take chances in buying your paint from a stock that has been on hand for an indefinite period? Any experienced painter will tell you that paint freshly made up is much superior to a paint that has been mixed for some time. It often occurs that dealers will carry paint over from year to year and you have no assurance of getting your paint of uniform color and consistency. In buying PREMIER READY MIXED PAINTS you are absolutely sure of fresh stock of the highest grade of ready mixed paint on the market.

*Yours for good Paint
V. Michaelsen*

**He Is the Best
Posted Man On
Good Ready Mixed
Paint Today**

Mr. V. Michaelsen, superintendent of our Paint Department, has for 30 years produced paint according to the most modern methods. His picture has appeared on over 6,000,000 cans of paint. Wherever paint is used his name has become a standard of quality. He is a pioneer in the manufacture of high grade paints at popular prices. He is known from ocean to ocean. He has

made only paint of quality. Hereafter every can of paint bought from this company will have **Michaelsen's** guarantee of quality. In his position as head and superintendent of our Paint Department he stands ready to co-operate with paint buyers. Ask him questions—write to him personally—and he will advise you how to obtain best results in your purchase of paint for any purpose.

It is Economy to Paint. The cost of painting a house, barn or fence is so little as compared to the value of protection against rot and decay, caused by the elements, and to the length of time it prolongs your buildings, that you cannot afford to let your house, barn or fence stand unpainted.

Easy to Paint. YOU CAN DO PAINTING BY USING PREMIER READY MIXED PAINTS. It no longer requires an expert to make up paints for each job. The mixing of paints is done properly at our factory and the paint is ready to apply. All it requires is to be stirred up and possibly thinned a little. This you can easily do and make a first class job.

**HIS NAME
A STANDARD OF
QUALITY**

CHICAGO HOUSE WRECKING CO.
CAPITAL STOCK AND SURPLUS \$1,000,000.

"MICHAELSEN'S INSURANCE POLICY"

We guarantee each and every can or package of Premier Paint, Varnish or Paint Product, bearing the name "Premier," as follows:

If, after applying according to directions (and using pure thinners, if any are used), the result is not entirely workmanlike in every way as regards gloss, finish, durability, color or any other particular whatsoever, return to us the figures on top of packages, giving date of purchase, and if the fault is ours we will cheerfully replace each and every gallon free of charge.

Remember most paint makers guarantee house paint only. Our Paint Insurance covers every can or package of Varnish or Paint bearing the name "Premier."

CHICAGO HOUSE WRECKING CO.
V. MICHAELSEN, Supt. of Paint Dept.

Do Not Let Anyone convince you that it is necessary to pay a higher price for paint. It is possible for us to furnish you with our line of PREMIER PAINTS at the low prices quoted, owing to the simple fact that our paint trade has developed to the point where we are able to dispose of the entire output of a large factory, and in view of our immense paint sales we are able to make our contracts on the most favorable basis, and are, therefore, in a position to save our customers the large profits that a regular dealer in paints is obliged to make.

Shipments are made from our paint factory and are fresh, properly ground and mixed in exact proportions. This insures the strongest colors, durability and ease of application.

**PIONEER
OF PAINT
MANUFACTURE**

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.



Lace, Leather, Packing and Belting at Wrecking Prices.

PREMIER BARN PAINT 59¢ to 80¢ PER GALLON

GUARANTEED SUPERIOR TO ALL OTHERS

SUITABLE FOR BARN, ROOFS, FENCES, OUTHOUSES AND STRUCTURAL IRON WORK

AN IDEAL PROTECTION

A COMBINATION OF THE FINEST MINERAL PIGMENTS, PURE LINSEED AND PRESERVATIVE OILS

PREMIER BARN, ROOF AND FENCE MINERAL PAINT Is a high-class preservative for barns, roofs, fences and out-buildings. It is the only paint to use for structural iron and bridge work. A lasting preparation compounded by our expert chemist, **Mr. Michaelson**, who is also superintendent of our new paint plant, he is acknowledged to be the best known paint authority today—has 30 long years of experience producing paint according to the most modern methods, regardless of cost, and he guarantees that as a preservative for exposed surfaces, it is the best wearing, resisting mineral paint manufactured. It is absolutely waterproof and will not peel, blister, crack or rub off and will withstand the most severe weather which outside paints have to undergo.

It is a study to meet the extreme conditions in the warping, expansion and contraction of the open grained wood generally used in barn construction and exposed to the severest sun and weather action.

Premier Barn Roof and Fence

Paint is of the highest quality composed of the very best materials, absolutely free from injurious ingredients that is possible to procure; and is manufactured and tested under the most trying conditions. The mineral pigments are thoroughly ground and re-ground with the finest linseed and preservative oils obtainable with the most modern up-to-date grinding machinery at our own plant. This places us in a position to save our customers the large profits that your local dealer is obliged to make; he can't understand how it is possible for us to furnish you with our line of Premier Paints at the low prices quoted.

Why take chances in buying your paint from a stock that has been on hand for an indefinite period. Any experienced painter will tell you that paint freshly made up (such as ours) is much superior to a paint that has been mixed for some time.

Premier Barn Paint

Represents a brand so radically different from anything ever offered as "Barn Paint," it is in a class by itself, it not only forms a protective coating (not a penetrating stain like most barn paints which leave only the stained original wood surface), but with its rich, non-fading color contains also a powerful wood preservative which kills wood germs and destructive rot producing agents.

The Oil in Premier Barn Paint

Is practically the same as we use in our **Premier Ready Mixed House Paint**. Our red shade is the result of our absolute control of a natural product of pure iron oxide, the most durable pigment known. The chemical composition and its absolute non-fading properties make it impossible to duplicate with any other coloring agent.

Your Barn, Roof, Fences, in fact any house on your premises in need of paint will be very much improved by using **Premier Barn Paint**.

A great many manufacturers nowadays take and mix a cheap Venetian Red with nothing but gloss oil as a thinner. This we know is nothing but a cheap imitation of varnish, we will admit this combination will look as good and in some cases better than ours, but its life is short, it will not wear, it will fade and crumble in a very short time.

OUR PAINT INSURANCE POLICY
COVERS THIS LINE FULLY



\$13.38

Buy the Paint for Two Coat Work on the Outside of this Barn, Size 36 Feet by 48 Feet by 38 Feet 6 Inches high.

BODY PAINT, 3-5 gal. Kits—total 15 gallons, No. 804 Premier Barn Paint. Price, 75c Gal. \$11.25
TRIM PAINT, 2 Gal. of No. 801 Premier Barn Paint. Price 80c GAL. Price. 1.60
1 Quart of Shellac to cover any knots. Price.58

Total..... **\$13.38**

OUR PAINT CATALOG CONTAINS COLOR CARD SHOWING ACTUAL COLORS

9-G-701. "Premier" Barn, Roof and Fence Mineral Paint in one gallon cans. **80c**
Per can.....

9-G-703. "Premier" Barn, Roof and Fence Mineral Paint, in five gallon kits. **75c**
Per gallon.....

9-G-705. "Premier" Barn, Roof and Fence Mineral Paint, in 25 gallon, half barrel. **67c**
Per gallon.....

9-G-707. "Premier" Barn, Roof and Fence Mineral Paint, in 50 gallon barrel. **59c**
Per gallon.....

BE SURE TO STATE NUMBER AND NAME OF COLOR WHEN ORDERING

84

90c Will Make Your Buggy Look Like New



CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

How to Figure Amount of Paint Needed!

THE COST, or how to figure the amount of paint needed to paint a house, barn or fence is one of the most important and essential things you should know. The familiarizing ones self with the information explained below will go a great way in tending to prevent a short or an excessive order of paints, although it is better to be over than short, as you can always find something or other around the house that requires painting, thereby improving the appearance of the part painted at practically no cost whatever.

On new work that has not been painted, one gallon of **Premier Ready Mixed Paint** will cover about 250 square feet, two coats. On wood that is to be repainted, that is, if it is in fair condition, one gallon will cover 300 square feet, two coats.

EXAMPLE: Should your building measure 40 feet long, 20 feet wide and have an average height of 25 feet, you figure as follows:

Front and Rear,	20 feet each.....	40 feet.
Two Sides,	40 feet each.....	80 feet.
Total.....		120 feet.
Multiply by average height.....		25
	250	3000 (12 gallons required.)
	500	
	500	

PLEASE NOTE that you add together the width and the length of the building, multiply by the average height, then divide by 250, which is the covering of one gallon for two coats; and the result, as in the example above, is 12 gallons, which is the amount of paint required to coat a house of the above size, two coats.

COST. We sell **PREMIER READY MIXED PAINTS** in various sized cans, and for the building below you would require two 5 gallon cans and two 1 gallon cans, viz.:

The two 5-gallon cans we furnish at \$1.08 per gallon..... 10.80
The two 1 gallon cans we furnish at 1.10 per gallon..... 2.20

Total cost to paint building below would be.....\$13.60

FOR PAINTING BARNs or FENCES, use our **PREMIER BARN AND ROOF PAINT** and figure the same way.

Over Fifty
Different
Shades of
"Premier"
Paint
to Select from

Write for Our
Paint Catalog
Containing
Color Card

\$13⁰⁰

Buys the paint for two coat work on this house

SIZE 23 FEET BY 33 FEET BY 28 FEET HIGH.
BODY: 10 gallons, **PREMIER READY MIXED PAINT**
No. 9-G-150, at \$1.08 per gallon..... \$10.80
TRIM: 2 gallons, **PREMIER READY MIXED PAINT**
No. 9-G-149, at \$1.08 per gallon..... 2.20
Total..... \$13.00

Free, with this Paint 2 good Brushes.

Extras

PORECH: 1 gallon of floor paint, sufficient for porch floor only, price..... \$1.07

SASH: 1/2 gallon of black paint for outside of all sash, price..... 65c

INTERIOR FINISH:

5 gallons of Liquid Wood Filler for first coat interior wood work, price, \$5.15

6 gallons of Extra Coach Varnish for second coat interior wood work, price..... \$7.30

2 quarts of Shellac to cover any knots, price, \$1.05

5 lbs. of Putty for filling nail holes, etc..... 20c

Note—Please observe in the above list we furnish sufficient paint, etc., for two coat outside and inside complete except interior floor and roof paint.

ROOF PAINT: If you wish roof paint it will require 5 gallons of our No. 703 Red Roof Paint, price..... \$3.75



Remember We
Protect You
By Our
Binding
Guarantee

Buy Your
Paints
From Us and
Take No
Chances

DIRECTIONS FOR USING PREMIER READY MIXED PAINTS

FIRST: The surface must be thoroughly dry. Paint is very often applied to surfaces before it is dry, this causes the paint to blister and peel within a few weeks; don't blame the paint, this can happen to any paint. Prepare the surface by giving all knotty or sappy parts a coat of orange shellac. Remove all loose or old paint with a scraper and be sure to dust the surface if you want a nice, clean job.

SECOND: Open the can, then carefully pour off the liquid in an empty can provided for that purpose. Stir thoroughly, gradually adding the liquid you poured off; the paint is ready for use after this is done.

THIRD: For the first coat, reduce the paint to the proportion of one quart of linseed oil to one gallon of paint. Brush out well and let it dry thoroughly before applying the second coat. Allow 5 to 10 days for drying.

FOURTH: Putty all nail holes, cracks, etc. Watch carefully for these imperfections before applying the second coat.

FIFTH: For the second coat apply the paint in its actual thickness, brushing out well. If necessary, thin with linseed oil.

Remember the condition of the surface to be Painted has much to do with the results.

Never apply Paint in cold or wet weather, be sure to allow plenty of time between coats.

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Premier Paint Covers One-Third More Surface Than Others

85

PREMIER ^{READY MIXED} HOUSE PAINT

GUARANTEED SUPERIOR TO ALL OTHER

98c to \$1.10 PER GALLON



THIS PAINT BRIEFLY DESCRIBED

as to manufacture in first part of this catalog is an original departure in beautifying protective coating, the word coating is especially adaptable to this material as it is so radically different from other paints in composition. The secret of durability, one of the features of **PREMIER READY MIXED HOUSE PAINTS**, is in the fact that it is almost all oil and a percentage of pigments (pigments are what tend to make paints brittle). No paint will last longer than the life of the oil which it must contain. This paint works smoothly under the brush as oil itself, hence it can be brushed out to a greater covering capacity than any other paint known. Combine this feature with the absolute non-fading properties of the colors used and you will have the secret of supremacy of our paints over any other paint on the market and the only paint you should consider if you want the best results in outside exposed painting.

IT IS POSSIBLE

for us to furnish you with our line of **Paints** at the low prices quoted below, owing to the simple fact that our paint trade has developed to the point where we are able to dispose of the entire output of our large factory, and in view of our immense paint sales we are able to make our contracts on the most favorable basis, and are, therefore, in a position to save our customers the large profits that a regular dealer in paints is obliged to make. You can save 30 to 50 per cent per gallon. **PREMIER READY MIXED PAINTS** are equal and even superior to most of the paint sold at \$1.75 to \$2.00 per gallon. It often occurs that dealers will carry paint over from year to year and you have no assurance of getting your paint of uniform color and consistency. In buying of ready mixed paint on the market. Bear in mind our **INSURANCE POLICY** is your protection and that we will replace gallon for gallon without cost to you, any **PREMIER READY MIXED PAINT** that fails to give the utmost satisfaction.



PREMIER READY MIXED PAINTS you are absolutely sure of fresh stock of the highest grade protection and that we will replace gallon for gallon without cost to you, any **PREMIER READY MIXED PAINT** that fails to give the utmost satisfaction.

THE COST OF PAINTING

a house, barn or fence is so little, as compared to the value of protection against rot and decay, caused by the elements and to the length of time it prolongs your buildings, that you cannot afford to let your house, barn or fence stand unpainted. **PREMIER READY MIXED HOUSE PAINT** not only beautifies but protects your house against weather and other causes such as rot or decay. **MR. MICHAELSEN'S** 30 long years of experience enabled him to find material to produce these protective qualities of this paint. His thorough knowledge of what they will do has made **Premier Ready Mixed House Paint** the most durable paint manufactured. It is made in 36 colors as listed on the preceding page and put up in 50 gallon barrels, 25 gallon barrels, 5 gallon kits, 1 gallon cans, $\frac{1}{2}$ and $\frac{1}{4}$ gallon cans. We will also make to order promptly any shade that you may submit at the same price as our shade which it comes nearest to matching.

PRICE FOR ANY COLOR—EXCEPT THOSE MARKED WITH * (Write for Paint Book)

★ 9-F-601. Premier Ready Mixed Paint. 1 quart can, each 34c	9-G-605. Premier Ready Mixed Paint. 1 gallon can, each \$1.10	9-G-609. Premier Ready Mixed Paint. 25 gallon half barrel, per gallon \$1.03
★ 9-F-603. Premier Ready Mixed Paint. $\frac{1}{2}$ gallon can, each 65c	9-G-607. Premier Ready Mixed Paint. 5 gallon kit, per gallon. \$1.03	9-G-611. Premier Ready Mixed Paint. 50 gallon barrel, per gallon 98c

Outside White, Inside White, and Black, furnished in addition to colors shown, at the above prices. Be sure and mention name and number of color when ordering.

PRICES FOR SPECIAL COLORS MARKED WITH * (Write for Paint Book)

CHERRY No. 2152-H and VERMILLION No. 5154-H.		BLIND GREEN No. 5140H—DEEP GREEN No. 4140H—MOSS GREEN No. 5160H, DARK GREEN No. 6139H.	
9-G-615A. 5 Gallon can, per gallon.....	\$1.25	9-G-615E. 5 gallon can, per gallon	\$1.25
9-G-615B. 1 gallon can, each	1.30	9-G-615F. 1 gallon can, each.....	1.30
★ 9-G-615C. $\frac{1}{2}$ gallon can.....	.76	★ 9-F-615G. $\frac{1}{2}$ gallon can	76c
★ 9-G-615D. 1 quart can42	★ 9-F-615H. 1 quart42c

CHALLENGE BARN PAINT 39^C to 48^C Per Gallon

We do not guarantee the lasting qualities of **Challenge Barn Paint**, neither do we recommend its use: If you feel prompted to buy the **Challenge Barn Paint** for economical reasons, we assure you that you will find it far more economical to buy the **Premier Barn Paint**, which is sold under our binding guarantee and would give you the utmost satisfaction. The **Challenge Barn Paint** is intended only for rough or temporary work.

LIST OF COLORS OF CHALLENGE BARN PAINT, Red, Brown, Maroon or Yellow.

9-F-709. Challenge Barn Paint, put up in 1-gallon cans. Your choice of any color mentioned above	48c	9-F-719. Challenge Barn Paint, 25-gallon barrel. Your choice of any color as mentioned above, per gallon.....	43c
9-F-711. Challenge Barn Paint, put up in 5-gallon kit. Your choice of any color as mentioned above, per gallon.....	45c	9-F-721. Challenge Barn Paint, in 50-gallon barrels. Your choice of any color as mentioned above, per gallon.....	39c

86

We Save You 30 to 50 % on Brushes, Varnishes, Paints and Oils

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

PREMIER DURABLE FLOOR PAINT

MIXED READY FOR USE

30^c PER QUART TO \$1⁰⁴ PER GALLON

P**REMIER READY MIXED FLOOR PAINT** is a specially prepared paint made to resist the wear and tear of shuffling feet, heel marks or scratches, the severe tests of alkali soap, hot water, washing and scrubbing; it will not only resist this severe action, but must retain the bright, shining surface demanded by the most scrupulous housekeeper. It is the only floor paint to buy if you want the most durable and best all around floor paint ever put on the market.

Mr. Michaelsen, superintendent of our NEW PAINT and VARNISH PLANT has studied the requirements demanded on this particular oil and varnish color, and has continually improved upon it by using special high grade ingredients that are known to have the best resisting qualities manufactured, regardless of the price.

This paint dries over night with a high gloss, and will remain dust free, and will be hard enough to walk on in 24 hours. No amount of washing will injure the surface, and will never spot white or discolor. It is equally desirable for old or new floors. We guarantee that should you use our PREMIER READY MIXED FLOOR PAINT you will be highly pleased with the results.

NEW FLOORS WHICH HAVE NOT BEEN PREVIOUSLY PAINTED REQUIRE THREE COATS. Old floors which have been previously painted, require two coats. ONE GALLON WILL COVER FROM 300 TO 350 SQUARE FEET, TWO COATS, AND FROM 200 TO 250 SQUARE FEET, THREE COATS, AND WILL DRY IN 12 HOURS. It is easily applied. Anyone who is capable of handling a brush can make a first-class job. On old floors it is merely necessary to wash the floors thoroughly, removing the dirt, dust and grease and apply the paint 24 hours after washing. The application of our Floor Paint will wonderfully improve the appearance of the room and relieve the housewife from constantly scrubbing the floor. A painted floor is sanitary and is more easily washed up.



MADE IN THE FOLLOWING COLORS (Order by Color)

Grey, Russet	Yellow, Red,	Lead, Green,	Tan, Maroon.
9-F-809. 5 gallon cans, each	\$1.04	½ gallon cans, each	50c
1 gallon cans, each	\$1.07	½ gallon cans, each	30c

Our Paint Insurance Policy covers this line fully. Read it again.

Premier Durable Porch Floor Paint

P**REMIER PORCH FLOOR PAINT** is especially prepared paint for outdoor porches and stairways, to resist the rain, sun, and, in fact, the most severe weather of any climate. It is the most durable porch floor paint made, and its wearing qualities are superior to all others. This paint has been put to the most trying tests known, merely to satisfy ourselves as to its action. We all know that no other surface receives the wear and tear that porch and stairs do. It is guaranteed to stand more foot wear and general usage than all other porch paints on the market. It is practically made of the same special high grade ingredients used in our PREMIER DURABLE FLOOR PAINT. It is known to have the greatest preserving and resisting qualities for all exposed surfaces. It dries over-night and retains a high luster. Our PREMIER PORCH FLOOR PAINT will wonderfully improve the appearance of your porch and steps. It is easily applied. Don't fail to wash the surface to be painted thoroughly. Remove the dirt, dust and grease. Apply paint about 24 hours after washing. It is made in the same shades as our regular floor paint. **Our Paint Insurance Policy covers this line fully.**



Read it again.

MADE IN THE FOLLOWING COLORS (Order by Color)

Grey, Russet,	Yellow, Red,	Lead, Green,	Tan, Maroon.
9-F-810. 5 gallon cans, each	\$1.04	½ gallon cans, each	50c
1 gallon cans, each	\$1.07	½ gallon cans, each	30c

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.



Our Guaranteed Pure Paint is PURE

PREMIER CREOSOTE SHINGLE STAIN

56¢ TO 71¢ PER GALLON

SPECIAL FEATURES

Creosote is acknowledged to be the best wood preserver known at the present time. This Premier Creosote Shingle Stain is scientifically prepared, the colors are extremely durable and penetrating and will positively not fade. We offer the shingle stain as a particularly high grade article. We do not pretend to compete with the cheap mixtures offered by many dealers. We well know that this stain will give our customers the best of satisfaction, hence make more trade from friends and neighbors. We send sample shades on real cedar shingles, upon request.

HOW APPLIED

Premier Creosote Shingle Stain can be applied with a brush after the shingles are laid or the shingles can be dipped before laying. When applied with a brush one gallon will cover about 150 square feet of surface, one coat, or 100 square feet, two coats. For dipping it requires from 2½ to 3 gallons to dip 1,000 shingles. The shingle need be dipped only two-thirds of its length. This stain can be used on wood tanks and troughs. It preserves them.

A GOOD INVESTMENT

A shingle roof is expensive and you no doubt realize the importance of using a preservative which will make them water proof and will thereby prevent them from rotting out.

PRICE FOR ANY OF THE SIX COLORS SHOWN ON COLOR CARD.

Write for Paint Book

9-F-901. "Premier" Creosote Shingle Stain. 1 gallon can. **71¢**

9-F-902. "Premier" Creosote Shingle Stain, 5 gallon can. Per gallon. **65¢**

9-F-904. "Premier" Creosote Shingle Stain, 25 gal. can; 1 barrel. Per gallon. **61¢**

9-F-906. "Premier" Creosote Shingle Stain, 50 Gallon Barrel. Per gallon. **56¢**

PREMIER WEATHER PROOF CEMENT FLOOR COATING

On ordinary floors it is almost impossible to make them look clean, but with our Premier Cement Floor Coating, they not only make an attractive appearance, but are durable, and it is almost impossible for any dust to lie on the surface. The concrete absorbs moisture so rapidly that it is impractical to clean them by ordinary methods.

Premier Cement Floor Coating makes the surface water-proof and at the same time so binding the particles that the dust making feature is eliminated.

Just what you want for coating on cement, stone, brick, concrete and stucco.

Lot No. 9-F-1211.	1 quart.	Per can.	\$0.42
Lot No. 9-F-1213.	½ gallon.	Per can.70
Lot No. 9-F-1215.	1 gallon.	Per can.	1.25
Lot No. 9-F-1217.	5 gallons.	Per kit	6.00

For sanitary purposes this coating cannot be excelled. Superior to all others.

We Can Furnish Same In the Following Colors: Cement, Pearl Gray, Slate, Terra Cotta

Premier Flat Wall Paint

This material must not be confused with kalsomine or water paints, as it is strictly an oil paint, drying down to a beautiful soft, non-gloss tone and possessing that tough, elastic finish which prevents plaster or cement from cracking or crumbling, whereas water paints would not. **Cheaper than wall paper, more easily applied and more sanitary.** Lasts forever, and only needs washing with soap and water to make it like new. Will not rub off on the clothes as kalsomine does. It is prepared in liquid form ready for use, and put on with a brush; dries to a hard surface, which may be washed and is unaffected by steam or heat. Will not spot, turn color or fade. Made in the following nine shades (see house paint color card): Tan, Light Yellow, Pea Green, Grey, Yellow, Pink, Azure Blue, Deep Green, Maroon. Remember that these shades appear on our regular color card, and this Flat Wall Paint shows the same color in every way as the house paint color card shows, **except that it will not be glossy**, but will be flat and without luster. Applied with a brush, same as house paint. Figure 1-gal. can will do 200 square feet, two coats.

9-F-905-A. ½-Gallon can, each.	1-Gallon cans.	1-Gallon cans.
1.05	1.56	1.53

PREMIER WEATHER PROOF CEMENT COATING

When placing before the public our "Premier" Weather-Proof Cement Coatings, we give them our best efforts of years of experimenting with this peculiar style of paint and have resorted to all means to carefully compound a formula that will withstand all elements. Premier Cement Coating is strictly formulated after exhaustive tests to meet the exact physical and chemical requirements of a masonry surface, providing the most efficient and damp-proofing treatment for exterior masonry surfaces. It penetrates into the pores of the surface and on hardening thoroughly seals them, preventing any possibility of the absorption of water into the treated area. It is thoroughly uniform and equalizes the color and imparts a finish of the most attractive nature. This finish dries to a flat, uniform, stonelike texture without any tendency to impart a painted appearance to the surface. The damp-proofing efficiency of the Premier Cement Coating is not only evident in eliminating the saturated appearance of the treated area after a rain and the tendency of the surface to become stained and unsightly, but by excluding the dampness from the wall, maintains a perfectly dry and sanitary condition on the inside.

We can furnish same in the following colors: Dark Cement, Moss Green, Tan, Brown, Copper Color, Slate.

Will not wash off, it stands all kinds of weather and clings to the material it is applied on.

Lot No. 9-F-1201.	One gallon cans.	\$1.25
Lot No. 9-F-1203.	Five gallon kits	1.20
Lot No. 9-F-1205.	Twenty-five gallons or ½ Bbl.	1.18
Lot No. 9-F-1207.	Fifty gallons. 1 Barrel	1.13
Lot No. 9-F-1197.	1 quart can42
Lot No. 9-F-1199.	½ Gallon can70

The ideal paint for Hotels, Hospitals, School Houses, and every place where cement is used.

88 Have You a Copy of Our New Wire and Fencing Catalog? If not Send for One;

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.



PREMIER VARNISHES

Realizing the importance of furnishing varnishes that will give perfect satisfaction for the purpose for which they are intended, we offer our line of Premier Varnishes which are manufactured from the finest selected imported gum at the newest, largest and best equipped plant in the United States.

We guarantee our Premier Varnishes to give perfect satisfaction in every particular where directions are followed, or money refunded.

In presenting our line of premier varnishes we do so with the utmost confidence that they will prove entirely satisfactory. Under the favorable arrangements which we have made in the manufacture of these varnishes, our prices will represent a considerable saving to you. You will please bear in mind that each of the various grades offered are the best of their respective kinds on the market.

Premier Extra Light Hard Oil Finish.

9-G-1001. This is a good, durable varnish. Has a fine gloss and will rub nicely. It is light in color and will dry dust proof in 8 hours. Can be rubbed in 48 hours.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
22c	38c	73c	\$1.19	\$5.45

Premier No. 1 Hard Oil Finish.

9-G-1003. This Hard Oil is well adapted for any inside work. Dries hard over night with a gloss and is elastic and durable. It is slightly darker in color than our Extra Light Hard Oil.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
19c	32c	55c	94c	\$3.95

Premier Coach Varnish.

9-G-1005. A fine grade of Interior Finish for use on all kinds of woodwork, furniture or over graining. Works freely and dries hard over night with a high gloss.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
20c	37c	65c	\$1.10	\$5.00

Premier Extra Coach Varnish.

9-G-1007. Suitable for the best interior work. A varnish of medium color and good body and very durable. Can be rubbed or left in the gloss. Dries dust free in 3 to 4 hours and sufficiently hard for rubbing in about 48 hours.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
23c	43c	75c	\$1.30	\$6.00

Premier Extra Furniture Varnish.

9-G-1009. A strictly high grade varnish, used largely by manufacturers of high grade furniture. Is very durable and gives a hard and brilliant luster which can be rubbed and polished. Guaranteed suitable for first class furniture finishing.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
23c	42c	73c	\$1.28	\$5.50

Premier Furniture Varnish.

9-G-1011. This is a very reliable varnish for ordinary finish. Dries rapidly and gives a high luster. Suitable for use in brightening up worn or lusterless furniture. Recommended for general repair work.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
18c	31c	52c	85c	\$3.67

Premier Wearing Floor Varnish.

9-G-1013. A high grade floor varnish, suitable for use on floors of all kinds. Natural wood or painted. This is an elastic varnish and will not scratch, turn white or show heel marks. It is manufactured specially for floors and contains the best material. It is perfectly transparent and will preserve the natural wood for years. The most economical and durable floor finish made.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
29c	53c	95c	\$1.70	\$8.00

Premier White Damar Varnish.

9-G-1015. Made from imported Batavia Gum. For finishing over any enameled surfaces, White or Ivory, without producing discoloration. Can also be used with excellent satisfaction on fine wall paper hangings or on delicately tinted painted walls. Is of good body and dries well.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
28c	51c	91c	\$1.63	\$7.65

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Premier Interior Spar Varnish.

9-G-1017. Adapted for interior finishing of residences. Light in color and made from pure hard gum. Can be left in the gloss or rubbed if desired. Dries hard for rubbing in about 3 days.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
28c	52c	95c	\$1.70	\$8.00

Premier Outside Spar Varnish.

9-G-1019. For finishing all kinds of exposed surfaces. For exterior use, such as outside doors, windows, gates and in fact any work that is exposed to the weather. It is also suitable for finishing woodwork in bath rooms or any woodwork that may have hard usage or come in contact with water.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
33c	58c	\$1.07	\$1.93	\$9.15

Premier Church and School Seat Varnish.

9-G-1021. Hard Drying Pale Varnish, specially suitable for use on church and school seats and other surfaces subjected to pressure and moderate heat. It is pale, brilliant, a hard dryer and very durable. Dries dust free in 5 or 6 hours. Hardens in 48 hours.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
30c	54c	98c	\$1.75	\$8.25

Premier Oil Shellac.

9-G-1023. Used as a first coat or filler for new woods that have not been previously finished. It is clear, has a good body and produces a substantial and safe surface or base coat. It dries to sandpaper from 6 to 8 hours.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
20c	35c	65c	\$1.15	\$5.25

Premier Turpentine Japan Dryer.

9-G-1025. A first-class house painter's Japan, dependable in all kinds of weather. A good binder and a sure and quick dryer. It contains no acids and will not cause the paint with which it is mixed to burn, blister, crack, chalk or peel. It mixes readily with oil and does not detract from the elasticity of the paint.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
18c	30c	50c	80c	\$3.45

Premier Gloss Oil.

9-G-1027. A gloss oil for sizing plastered walls before calcimining.

Quart	1/2 Gal.	1 Gal.	5 Gal.
17c	25c	40c	\$1.50

Premier Wearing Body Varnish.

9-G-1029. A pale varnish of great brilliancy and durability, for finishing carriage and buggy bodies. Works with great freedom, dries without dust in 12 hours and hardens in 2 to 3 days.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
45c	85c	\$1.60	\$3.00	

Premier One-Coat Coach Varnish.

9-G-1031. An excellent varnish for general repair work on carriages where the surface is dull or lusterless, otherwise in good condition. One coat of this varnish on the entire vehicle will produce a finish practically equal to a new job. It is light in color, elastic, brilliant, and durable. Dries free from dust in about 12 hours and hardens to permit the use of the vehicle in about 3 days.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
38c	72c	\$1.35	\$2.50	

Premier Elastic Gear Varnish.

9-G-1033. Used for finishing gear parts and wheels. A pale and elastic varnish. Works freely. Dries free from dust in 6 to 8 hours and gives a brilliant and durable finish. This varnish may also be used for body finishing when drying, dispatch being an important consideration. This is a superior all around varnish for carriage finishing.

Pint	Quart	1/2 Gal.	1 Gal.
42c	79c	\$1.53	\$2.80

Premier Wagon and Implement Varnish.

9-G-1035. For agricultural implements, wagons, etc. A good varnish for general outside work. Has an excellent body, a fine luster and light in color. Wears well and dries in about 10 to 14 hours.

Pint	Quart	1/2 Gal.	1 Gal.
25c	45c	83c	\$1.45

Premier Coach Japan.

9-G-1037. A light color dryer, possessing superior binding and drying qualities. For colors and rough stuff.

Pint	Quart	1/2 Gal.	1 Gal.
25c	44c	78c	\$1.35

Denatured Alcohol Orange Shellac.

9-G-1039.				
Pint	Quart	1/2 Gal.	1 Gal.	
27c	47c	83c	\$1.45	

Denatured Alcohol White Shellac.

9-G-1041.				
Pint	Quart	1/2 Gal.	1 Gal.	
28c	50c	90c	\$1.60	

Premier Floor Oil.

9-G-1043. Premier floor oil. Prepared especially for floors of residences and stores, small quantity applied with a cloth will bring out the natural color, and make scrubbing unnecessary. Floors oiled with Premier Floor Oil are easily cleaned by washing them with soap and water.

Pint	Quart	1/2 Gal.	1 Gal.	5 Gal.
20c	30c	52c	90c	\$4.00

Paint and Varnish Remover.

9-G-1045. Softens the paint or varnish so that it can be removed easily with a piece of cloth or putty knife. Removes every vestige of paint from the surface so that it looks like new. 1 pint will remove the varnish from 1 to 2 table tops. 1/2 gallon will remove the paint from a floor 12x12 ft.

Pint	Quart	1/2 Gal.	1 Gal.
28c	48c	90c	\$1.60

Premier Black Covering.

9-G-1047. For Nigrite kinds of castings, smokestacks, fenders, coal hods, iron work of agricultural implements, etc. It produces a jet black brilliant finish and absolutely prevents rust or corrosion. It is heavy in body, and quick drying.

1/2 Gal.	1 Gal.	5 Gal.
30c	45c	\$1.95

Premier Liquid Wood Filler.

9-G-1049. For filling or first-coating all kinds of close grained natural woods, such as pine, poplar, etc., that have not been previously finished. It thoroughly seals up the wood pores and effectually prevents suction or the absorption of moisture. This material is transparent and does not need to be rubbed off or sandpapered before applying varnish coats. It does not sink away like varnish, but dries on the surface, thus making it equal for work of this nature to 2 coats of varnish. A coat or two of varnish applied on this work produces a really remarkable finish.

Quart	1/2 Gal.	1 Gal.	5 Gal.
40c	78c	\$1.45	\$6.95

Premier Paste Wood Filler.

9-G-1051. All open grained woods such as oak, ash, etc., should be filled, in order to obtain a perfect varnish. Our Paste Filler is better than any other, as it completely fills the pores, making an impervious surface over which to varnish.

Made in three shades.		
Natural	Light Oak	Dark Oak
1 pound can	5 pound can	25 pound can
7c	30c	\$1.40

Crack and Crevice Filler.

9-G-1053. A superior elastic preparation for filling cracks in floors or woodwork before painting. Will not shrink.

1 pound can.	5 pound can
12c	55c

All Material on this page excepting one and five gallon cans, can be sent by Parcel Post.

THE ONLY COLORED PAINT MANUFACTURED WITH AN ASPHALT BODY

71c

Premier Mineral Asphalt Paint is entirely different from any other brand that is manufactured. It is made of the best grade of Trinidad Asphalt melted and specially treated and combined with pure kettle boiled Linseed Oil. Can be used to advantage on any kind of surface. It is not affected by contraction, expansion, acids, gases or alkali. When dry it forms a tough, elastic and impervious surface. It has a high gloss and is the most durable and best preservative paint on the market.

Covering capacity: On an old Surface 1 gallon will cover from 200 to 250 square feet. On a Wood Surface 1 gallon will cover 200 square feet 1 coat work or 100 square feet 2 coat work. On Prepared roofings 1 gallon will cover 100 square feet. Guaranteed not to contain a trace of coal tar.

		50 gal. Bbl. Per Gal.	25 gal. Bbl. Per Gal.	5 gal. Can Per Gal.	1 Gal. Can
9-F-913.	Maroon.....	\$0.71	\$0.73	\$0.77	\$0.86
9-F-915.	Green.....	.71	.73	.77	.86
9-F-917.	Brown.....	.71	.73	.77	.86



When applied to a metal surface one gallon will cover 300 square feet, giving a glossy black finish which is not affected by the weather and which will not crack or peel. For use around factories, it is unequalled on smoke stacks, boilers, pipes and machinery. It will not taint the water and can be used for painting the inside and outside of cisterns to prevent seepage.

9-F-919.

FURNISHED IN BLACK ONLY.

Per 1 Gallon Can.....	\$0.53	Per 5 Gallon Can.....	\$1.90	Per $\frac{1}{2}$ Barrel (25 Gallons).....	\$ 6.59
Per 2 Gallon Can.....	.89	Per 10 Gallon Can.....	3.50	Per 1 Barrel (50 Gallons).....	12.25

Price per pound.....	18c
Price, 100-pound drums, per pound.....	17c



Price, per pound.....	28c
Price, 100-pound drums, per pound.....	27c
Price, 200-pound drums, per pound.....	26c



with this cement. Comes in semi-paste form.
Price, 2 pound cans, 25c; 5 pound cans.....40c

quart capacity. Weight 6
pounds. 50c

GLUE BRUSHES.

ferrules and selected
white bristles. **WAR-
RANTED TO STAND HOT GLUE.**

5 and 10 gallon cans	70c per gal.
1 gallon cans 15-F-348	79c " "
$\frac{1}{2}$ " "	45c per can.



100 lb.	Kegs.....	per lb.	5 c
50 lb.	".....	"	5½ c
25 lb.	".....	"	6 c

100	lb. Kegs.	Per lb.	7 c
50	"	"	7 1/2 c
25	"	"	7 1/2 c
12 1/2	"	"	8 c

90

Our Special Painter's Outfit Can't be Beat.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Premier High Gloss Enamel

FOR FINE INTERIOR ENAMEL WORK



A HIGH GRADE INTERIOR FINISH on woodwork or plaster walls. Especially for use on walls where you wish to have a real enamel finish. This result has been secured in the Premier High Gloss Enamels so well that the largest and most modern hospitals have placed their stamp of approval on them and specifically state they will consider no others.

These Enamels are especially prepared to meet the "easy to apply" requirements of the novice or housewife. They work easily under the brush and will produce the same results as though you secured the services of an expert. It is particularly adapted for walls and ceilings in bedrooms, bathrooms and kitchens, making an impervious enamel finish. It is also used extensively for work on bedsteads, exposed pipes and

other metal surfaces. Made in twelve beautiful, delicate shades, representing the highest attainment in the study of compounding paint materials to produce a marble tile-like surface:

White	Vermillion	Orange	Green
Pale Blue	Sea Green	Royal Blue	Carmin
Bright Green	Rose Pink	Silver Grey	Black
9-F-921. Prices for above colors:	1/2 Pint can... 14c	1/2 Gallon... 77c	1 Gallon... \$1.47
1-Pint can... 31c	1-Quart can... 45c		

Premier High Gloss Lacquer

FOR REFINISHING FURNITURE AND OTHER WOODWORK



PREMIER GLOSS LACQUER should be in every household. Scratched and marred pieces of furniture and floors can be made into new and beautiful objects; can be applied by the most inexperienced person, and at an expense of a few cents you can convert a piece of furniture on which the finish has become marred so that it will look like new. Best of all, this beautiful finish can be applied by any housewife and the work will be as satisfactory as if an experienced wood finisher had done it.

If you have in your house, from basement to garret, a chair, table, chiffonier, bedstead, book case or desk or any floors or woodwork, baseboards or doors which you would like to renew in the natural wood colors, all you need is a small amount of Premier Gloss Lacquer. A few minutes' time and a small can of Premier Gloss Lacquer will change any article in the house to a bright, new-looking object. Directions for use of Premier

Gloss Lacquer are printed on all cans. Made in the following shades:

Light Oak	Flat Black	Dark Oak	Mahogany	Flat White
Cherry	Rosewood	Moss Green	Royal Red	Ground Color
Gloss White	Walnut	Gloss Black	Ceal	

Prices for any of the above colors:			
9-F-1101. 3-Pint can...	20c		
1-Pint can...	32c	1-Gallon can...	\$1.90
1-Quart can...	57c	5 Gallons...	9.00
Apply Premier High Gloss Lacquer with a flat varnish brush. For brushes see pages 20 and 21.			
Be sure to mention name and number of colors when ordering.			

Bath Tub Enamel



AN ORDINARY IRON TUB can be made to look like the finest porcelain tub by the use of our Bath Tub Enamel. Produces a hard, smooth, highly polished and non-absorbent surface. Effectually resists the action of hot and cold water, soaps and other preparations used in baths. In fact, it will resist the wear and tear which bath tubs usually undergo. With one pint you can do over and give it that new effect of an iron, tin or paper tub, or you can use it with the same remarkable results on sinks, and wood and iron work about the house. No skill is required. It can be easily applied with a 1 1/2-inch varnish brush and will dry over night.

9-F-903. Half pint...	25c
1-Pint...	45c
1-Quart...	75c

Premier Floor Wax

PREMIER FLOOR WAX is a specially prepared compound for polishing hardwood floors. It produces a lasting, brilliant polish. Floors can easily be kept clean by using Premier Floor Wax, as dirt and dust will not stick to it; it will not change the color of the wood, as it is transparent. It can easily be applied, dries quickly and can be rubbed to a brilliant polish, producing a lasting finish. One pound is sufficient for about 800 square feet. Directions are simple and easily understood and are printed on every can. It is put up in 1-pound cans only.

9-F-900-A. Per can...	27c
-----------------------	-----

Premier Flat Wall Paint

THIS MATERIAL must not be confused with kalsomine or water paints, as it is strictly an oil paint, drying down to a beautiful, soft, non-gloss tone and possessing that tough, elastic finish which prevents plaster or cement from cracking or crumbling, whereas water paints would not. Cheaper than wall paper, more easily applied and more sanitary. Lasts forever, and only needs washing with soap and water to make it like new. Will not rub off on the clothes as kalsomine does. It is prepared in liquid form ready for use, and put on with a brush; dries to a hard surface, which may be washed and is unaffected by steam or heat. Will not spot, turn color or fade. Made in the following nine shades (see house paint color card): Tan, Light Yellow, Pea Green, Grey, Yellow, Pink, Azure Blue, Deep Green, Maroon. Remember that these shades appear on our regular color card, and this Flat Wall Paint shows the same color in every way as the house paint color card shows, except that it will not be glossy, but will be flat and without luster. Applied with a brush, same as house paint. Figure 1-gal. can will do 200 square feet two coats.

9-F-905-A. 1/2-Gallon can, each...	69c
1/2-Gallon cans...	\$1.05
1-Gallon cans...	\$1.55
5 and 10-Gallon cans...	1.53

Premier Rubbing Oil

Expert wood finishers pronounce our Rubbing Oil the best for rubbing and polishing the finest work; used with pumice or rotten stone for rubbing down varnish with felt or burlap.

9-F-910-A. 1 Quart...	12c
1 Gallon...	34c
5 Gallons...	\$1.50

Premier Auto Metal Polish

As a burnisher of metals this liquid is without an equal. Contains no injurious materials, and brilliant results are quickly obtained with the slightest expenditure of labor.

9-F-915-A. 1-Gallon can, each...	89c
1-Gal. cans, 45c.	1-Gal. can, 25c.
1-16 Gal., 15c	

Premier Varnish Stain

Stains and Varnishes in One Operation



Recommended for use over a surface already varnished or painted, such as old furniture, varnished or painted woodwork. It is necessary, in order to obtain the best results, to use a stain of a similar shade as the old finish. You cannot finish a Mahogany chair Light Oak by applying Light Oak Varnish Stain. If a change of color is desired, we would recommend the use of our Premier Gloss Lacquer. By using the Ground Color as a first coat and the Premier Gloss Lacquer as a change of color can be made. Premier Varnish Stain dries hard with a high luster and is easily applied with a varnish brush. It is made in the following colors: Cherry, Mahogany, Rosewood, Dark Oak, Light Oak, Walnut, Antique Oak.

9-F-171. Per half pint can...	15c
Per 1-pint can...	21c
Per 1-quart can...	38c
Per 1-gal. can...	\$0.72
Per gallon can...	1.30

Oil Stains

A Perfect Imitation of Natural Wood

Used for staining interior woodwork and other work not finished. Dries with a flat finish. One or two coats of varnish will produce a fine glossy surface. It is easily applied with a varnish brush. Made in the following shades: Cherry, Dark Oak, Mahogany, Light Oak, Rosewood, Walnut, Antique Oak.

9-F-173. Per 1/2-pint can...	13c
Per 1-pint can...	19c
Per 1-quart can...	34c
Per 1-gal. can...	\$0.66
Per gallon can...	1.24

Wire Screen Enamel



9-F-931. A small can of our Premier Screen Enamel and a few minutes of easy work with the brush will make your screens look like new. It will not clog the mesh and will double the life of any screen; it dries hard and quickly, with a rich, brilliant gloss. To apply, brush one side only, and use just enough paint so it will not run. Easily applied with a small varnish brush. Put up in two colors—black and green.

Price, half pint...	14c
1-Pint...	24c
Quart...	48c

Premier Stove Pipe Enamel



9-F-935. Premier Stove Pipe Enamel is the best coating for stove pipes, stoves, furnaces, grates, smokestacks, iron fences. Will give any iron surface an enamel finish. Wears longer and has a smoother, more elastic finish than any other stove pipe enamel on the market. We have reduced to a liquid state a mineral of volcanic deposit of intense blackness. This liquid enamel will consequently withstand heat and retain its beautiful, brilliant, black luster. It will not peel or burn off. It must be applied when the surface to be painted is cold; it is ready for the brush and dries quickly. A pint can is sufficient for six lengths. It is put up in black only. Price, 1 pint...

12c	
Pint...	20c.
Half gallon...	70c.
Gallon...	\$1.25

Premier Linoleum and Floor Oil Cloth Finish



9-F-933. Do not let your floor, oil cloth or linoleum wear out when you can, for a few cents, preserve it and give a most lasting and finer finish than it had when new. Put this material over your linoleum. It gives it a hard, smooth, elastic finish that will bend as the linoleum does and will not crack. It overcomes the uneven wearing quality of linoleum, which has always before been objectionable. It keeps your floor bright and beautiful and largely increases the life of the linoleum or oil cloth. Not affected by hot or cold water. One coat put on at night will be all that is needed—dries to walk on the next morning. One quart will cover about 175 square feet.

1-Pint can...	30c
1-Quart can...	55c
1-Gallon can...	\$1.05
	1.98

OUR INSURANCE POLICY COVERS THIS LINE FULLY. READ IT AGAIN—

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Our new Wire Catalog contains Ornamental Fencing. Ask for it.

PREMIER READY MIXED PURE PAINT

ABSOLUTLY PURE—ITS WEARING QUALITIES ARE NOT GUARANTEED

\$1⁴³ to \$1⁵⁶

THE DEMAND among those who absolutely must and will have a strictly **PURE PAINT** was so great that we now make a strictly pure paint in every way, as expensive as it can possibly be made, using nothing but strictly pure white lead, the best grade of zinc and linseed oil and the highest grade pure colors for tinting wherever they can possibly be used. In fact, the paint as far as purity and standing is concerned and according to the accepted opinion of strictly pure paint authority there is absolutely nothing better on the market.

Our formula: Carbonate of Lead; Oxide of Zinc; Linseed Oil; Pure Turpentine Japan; Pure paint and according to the Pure Paint Law.

YOU CANNOT OBTAIN any better paint of this kind anywhere, and whenever you pay more than we ask for this paint, you are absolutely getting no return value whatever, for the cost of manufacturing this paint by others cannot be more than what we pay. Don't let anyone tell you that more expensive materials than we use in manufacturing these goods are obtainable. There is not. Should anyone discover more expensive materials, we will use them. We use the best, and there are none better than the best.

WE MAKE THESE GOODS in order to meet competition with those people who think that a lack of knowledge of manufacture after the modern standard can be overcome by falling back on the old-fashioned way of making, and if they are right we are right, and we will give the same class of goods at the proper price. Our goods are exactly as we claim—absolutely pure. We use the finest material obtainable. Remember we do not guarantee its wearing qualities.

PURITY, QUALITY AND STANDARDIZATION are the important factors of **PREMIER** guaranteed **PURE PAINT**. They can only be developed in long tried out equipment of the best machines and active interest in every customer as though he was the only one we do business with.


WE CAN MAKE BETTER PAINT for the same money and cheaper for the same quality than any other paint manufacturer. We know some paints are made as cheap as they can be and much better than they ought to be; our aim to combine what is effective in one instance with what is good in the other. This is why our **PREMIER** guaranteed **PURE PAINTS** are made as cheap as they can possibly be made. Do not take any chance in buying your paints from a local dealer.

MR. MICHAELSEN, SUPERINTENDENT of our **PAINT AND VARNISH PLANT**, is recognized all over the country as one of the few men in whom are combined the rarely associated qualities of the successful business man and the practical chemist, and to this combination is due, undoubtedly, a complete and uniformity of product throughout our plant, which perhaps cannot be duplicated and certainly is not excelled in any other paint and varnish plant in the country.

PRICE FOR ANY COLOR EXCEPT THOSE MARKED WITH * WRITE FOR PAINT BOOK

★4-D-301. Premier Ready Mixed Pure Paint. 1 quart can, each.....	\$0.69	4-D-305. Premier Ready Mixed Pure Paint. 1 gallon can, each.....	\$1.56	4-D-309. Premier Ready Mixed Pure Paint. 25 gallon barrel, per gal....	\$1.46
★4-D-303. Premier Ready Mixed Pure Paint. Half gallon can, each....	1.05	4-D-307. Premier Ready Mixed Pure Paint. 5 gallon kit, per gallon....	1.53	4-D-311. Premier Ready Mixed Pure Paint. 50 gallon barrel, per gal....	1.43

ASK FOR OUR PRICES ON SPECIAL COLORS—CHERRY, VERMILION, BLIND GREEN



PREMIER COLD WATER PAINT

PREMIER WHITE COLD WATER PAINT is a dry powder specially prepared, the addition of cold water is all that is required to make it ready for use. There is nothing better on the market than Premier White Cold Water Paint for painting or to increase the light of interiors of warehouses, factories, shops, barns, basements, sheds, chicken houses, summer cottages, elevators, etc. It is universally recognized for its fire resisting qualities. It is strictly sanitary and can be used in place of whitewash. It is exceedingly durable and will not rub, scale or crack: can be applied with a whitewash, kalsomine or wide paint brush, or spraying machine.

10-Pound package, per pound. 9-F-312.....6c 25, 50, 100 pound drum, per pound... 9-F-313.....5½c
9-F-314. 400 Pound drums, per pound.....4½c

TEN POUNDS WILL COVER FROM 600 TO 800 SQUARE FEET. FURNISHED IN WHITE ONLY

SATIN KOTE KALSOMINE

OUR SATIN KOTE KALSOMINE REQUIRES NO EXPERIENCE WHATEVER TO APPLY

WE CAN FURNISH IN ALL TINTS.

THIS IS A SPECIALLY PREPARED POWDER made to fill a long standing need for the decoration of walls and ceilings. It produces a smooth, velvety flat finish which is absolutely fire-resisting and sanitary. It will not rub off and costs much less than wall paper or paint.

SATIN KOTE KALSOMINE is the most hygienic wall coating ever offered. It is especially adapted for private residences, public schools, hospitals, hotels, etc., can be easily removed from the walls or ceiling with sponge and water, that is, if you wish to recast your walls with new kalsomine.

ALL THAT IS NECESSARY to make it ready for use is to simply mix with boiling water. Can be applied by an inexperienced person, and covers all the way from 35 to 70 per cent more surface than other so-called kalsomines.

IN THIS KALSOMINE we offer an ideal finish for walls and ceilings; will wear better, last longer and give greater satisfaction than any other preparation used for this purpose. Again, it will not rub off.

DIRECTIONS are plainly printed on every can, and if you follow our instructions and do not get the results that we claim, we will cheerfully return your money, as our Insurance Policy covers this line also. Read it again.

A NEW ROOM FOR 24^c

9-F-315. Be sure to mention name and number of color when ordering



49c

4-C-1401. Extra Select Long Bristle Wall Brush. Superfine black Chinese bristles, brass bound. An excellent brush for house and barn painting.

Width, inches..	3	3½	4	4½
Length, inches..	3½	3½	4½	4½

Price each.....49c 64c 80c \$1.07

73c

4-C-1403. All White Russian Bristle Wall Brush. Extra long and full. Brass bound. A strictly high grade brush and is guaranteed to give entire satisfaction. A brush that is very popular with the painters.

Size.....	6	7	8	9	10
Width, in.	3	3½	4	4½	5
Length, in.	3½	4	4½	4½	4½

Each 73c \$1.06 \$1.31 \$1.68 \$1.91

LEATHER BOUND PAINT BRUSHES

93c

4-F-1405. Extra Long White Russian Bristles. A strictly high grade brush. Fully warranted. Will hold more paint and spreads smoother than a short bristle brush. It is also used by frescoists and is generally known as a "stucco" brush.

Width, inch.	3	3½	4	4½
Length, inch.	4	4½	4½	4½

Price each...\$0.93 \$1.08 \$1.40 \$1.55

72c

4-F-1407. Chinese Bristle Leather Bound Paint or Stucco Brush. The highest grade genuine black Chinese bristles, extra stiff and elastic. A general favorite with painters. Warranted to give entire satisfaction.

Size.....	25	30	35	40
Width, inch.	3	3½	4	4½
Length, inch.	4	4½	4½	4½

Price each...\$0.72 \$0.92 \$1.14 \$1.30

4-F-1409. Rubberset Flat or Wall Paint Brush. Selected Chinese bristles. Nickel bound. The best moderate price brush ever offered.

Width, inches..	2	3	4	4½
Length, bristles,	2½	3	3½	3½

Price each.....31c 36c 50c 60c

62c

4-C-1411. Rubberset Flat or Wall Brush. Superior quality. All white pure Russian bristles, long and full, and will do first-class work. Bristles will not come out.

Width, inches..	3	3½	4
Length, inches,	3½	4	4½

Price each.....\$0.62 \$0.85 \$1.05

4-C-1413. BRICK LINER

6c

White bristles, well made.

Size, inches	2	2½	3
Price, each	6c	7c	9c

WALL STIPPLING BRUSH



4-C-1415. Used for Obscuring Brush Marks and to Produce Rough Effect on Painted Walls. Made of the highest grade Russian bristles. Length of bristles, 3 inches. Size brush 3½ x 8 inches.

Price.....\$1.53

KALSOMINE BRUSHES

68c

We guarantee our Kalsomine Brushes to be absolutely free from fiber. We use nothing but the finest selected bristles.

4-C-1417. Kalsomine Brush. Guaranteed all white bristles, metal bound. An excellent brush for ordinary work.

Width, inches	6	7	8
Length, bristles	3½	3½	3½

Price, each.....68c 80c 99c

98c

4-C-1419. All White Russian Bristle Kalsomine Brush.

Width, inches..	6	7	8
Length, bristles, in.	3½	4½	4½

Price, each.....98c \$1.38 \$1.68

\$1.98

4-C-1421. The best quality Okatka Bristle Kalsomine Brush. Brass bound. A strictly high grade brush which will give excellent satisfaction. Fully warranted.

Width, inches.....	7	8
Length bristles, inches	4½	5

Price, each.....\$1.98 \$2.83

\$2.97

4-C-1423. New York Standard Kalsomine Brush. Selected Russian Bristles, galvanized iron band. The best working and most satisfactory kalsomine brush of its kind on the market. Fully warranted.

Width, inches	7	8
Length bristles, inches	5½	5½

Price each.....\$2.97 \$3.65

\$2.85

4-C-1425. Rubberset Kalsomine Brush. White Russian bristles. Brass bound. Bristles firmly imbedded in hard vulcanized rubber and will not come out. Setting not affected by lime or water.

Width, inches	7	8
Length bristles, inches	5½	5½

Price each.....\$2.85 \$3.58

4-C-1427. An excellent brush and can be used for cold water paint. This style of brush is used by the largest painting contractors in the country. It will hold more kalsomine and do better work than other styles of kalsomine brushes. Especially desirable for rough walls. Made of extra quality Russian bristles, set with special brushmakers' pitch and is fully warranted.

Size of block, inches	2½ x 7½
Length bristles, inches	4½

Price.....\$2.85

WHITEWASH BRUSHES

4-C-1429. White Hair outside Mixed Fiber Center. A very satisfactory brush for rough whitewashing. Leather bound, width, 7 inches. Length of bristles, 2½ inches.

Price.....\$0.25

4-C-1431. White wash brush. Metal bound; all white bristles. A good medium quality mechanics' brush.

Width, inches	7½	8
Length, inches	3½	4

Price each.....\$0.87 \$1.15

4-F-1433. Whitewash Brush. All white Russian bristles, very heavy. Metal bound. A fine brush for the professional kalsominer and whitewasher. Width, 8½ inches. Length 4½ inches.

Price each.....\$1.45

4-C-1435. Extra Quality Leather Bound Whitewash Brush. Highest quality white Okatka bristles, very stocky. Strictly high grade brush. Fully warranted.

Width, inches	9	9
Length, inches	4½	5

Price each.....\$2.49 \$3.37

4-C-1437. Rubberset Whitewash Brush. All white Russian bristles, leather bound. Bristles firmly embedded in hard vulcanized rubber.

The setting is not affected by lime or water. Width, inches 8; length, inches, 3½

Price each.....\$1.10

4-C-1439. Rubberset Whitewash Brush. Gray Russian bristles, white outside, leather bound. Strictly high grade brush that will give excellent satisfaction. The bristles firmly imbedded in hard vulcanized rubber and will not come out.

Width, inches	8	9
Length bristles, inches	4	5

Price each.....\$1.73 \$3.23

53c

4-C-1441. Painter's Round Duster. Strictly pure, black and gray mixed bristles. Width 2½ inches; length 4½ inches. Price.....53c

PAINTERS' FLAT DUSTER



4-C-1443

Flat dusters are preferred by many painters, inasmuch as they will not roll off on to the ground. Made with black bristles, set deep into the block. Width 5 inches.

Price.....46c

FLOOE WAXING AND POLISHING BRUSH




4-F-1445 Iron Weighted with Protected corners and sides.

Used for waxing and polishing hard wood floors.

Price, 15 lb. brush	\$1.30
Price, 25 lb. brush	1.75

PLASTERERS' FINISHING BRUSH



4-C-1447. All Gray Selected Bristles, flat handle, leather bound. A brush that is popular with the plasterers.

Width, inches	7	8
Length, inches	4	4½

Price, each.....\$1.63 \$2.45

PAPER-HANGERS' PASTE BRUSH



4-F-1449. All Gray Russian bristles, free from fibre, galvanized iron bound. Width 7 inches, length of bristles, 4½ inches. Price..\$1.40

4-C-1451. Smoothing Brush. Two rows of selected black hair.

Suitable for those who wish to do their own wall-papering. This is a first-class, low priced brush, and will give good satisfaction. It is not to be compared with the cheaper brushes that are being generally offered.

Width 10 inches	Price....	36c
-----------------	-----------	-----



4-C-1453. Paper hangers' Smoothing Brush. Two rows stiff, selected Chinese bristles. 2½ inches long.

Width, inches	10	12
Price, each.....	55c	70c



4-F-1455. Steel Wire Brush for removing old paint, rust and dirt from stone, brick, iron and woodwork. Made of special tempered high grade steel wire, hardwood block, six rows. Length 7 inches, width 2½ inches.

Price, each.....25c

We Sell Bargains Nothing Else

Order Complete Outfits Shown Above and Save Time

93



CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

PAINTERS' SUPPLIES AT BARGAIN PRICES

For the convenience of our customers

These outfits are carefully selected and

we have made up a proper selection of paint brushes for barn or house painting, and have made up two outfits consisting of the necessary brushes and material required.



"Popular" Outfit, No. 1.

Brushes included with these outfits are extra good quality and the selection answers all practical requirements for house or barn painting.

4-F-1300. A Complete outfit consisting of one 3½ inch rubber set paint brush.

One 3 inch Black Bristle Paint Brush.

Two Black China Bristle Sash Brushes.

One extra quality steel blade putty knife with four pounds of pure putty.

Price complete **\$1.19**



"Complete" Outfit, No. 2.

This assortment includes all brushes required for larger jobs. Each article extra quality and guarantee to give satisfaction.

4-F-1300-B. Outfit Complete consisting of one 3-inch rubber set Black China Bristle Paint Brush.

One 4-inch rubber set extra quality Black China Bristle Paint Brush.

One Painters' duster.

Two Black China Bristle Sash Brushes.

One 10 pound can pure putty.

One Extra quality steel blade putty knife.

Price of outfit complete. **\$2.35**

RUBBERSET HOME BRUSH

For Varnishing, Enameling, Staining and Painting.

4-F-1301. The most durable brush made for home use. Metal bound, selected Chinese bristles, solidly imbedded in hard vulcanized rubber and will not come out. Guaranteed to stand any amount of rough usage. Width 2 inches. Price..... **27c**



Size, inches. 1 1½ 2 2½ 3
Price, each 16c 23c 32c 40c 48c

4-C-1305. Double Thick Fitch Flowing Varnish Brushes. Superfine, chiseled, tin ferrules. For carriage and other fine varnishing.

Size, inches. 1 1½ 2 2½ 3
Price, each 18c 28c 36c 45c 51c

4-F-1307. Badger Hair Flowing Varnish Brush. Suitable for fine furniture, picture frames and all kinds of high grade work. Single thick, chiseled point, tin ferrule



Size inches..... 1 1½ 2 2½ 3
Price each..... 19c 30c 40c 55c 60c



4-F-1309. Rubberset Varnish Brush. Bristles firmly imbedded in hard

vulcanized rubber, bound with nickel plated metal ferrule, selected Chinese bristles, long and full. Adapted for first class work. Bristles will not come out.

Width, inches..... 2 2½ 3 3½
Length, bristles..... 2½ 2½ 2½ 3
Price, each..... 27c 38c 48c 75c



4-C-1311. Flat Flowing Varnish Brush. Selected black Chinese bristles. Chiseled tin ferrules.

Size, inches..... 1 1½ 2 2½ 3
Price, each..... 7c 9c 12c 16c 20c



4-C-1313. Extra Quality Flat Flowing Varnish Brush. Thick, soft, high

grade Chinese bristles. An excellent brush for mechanics' use.

Size, inches..... 1 1½ 2 2½ 3
Price, each..... 11c 19c 25c 34c 42c

Oval Varnish Brushes. For varnishing floors, woodwork and other surfaces of considerable area. Flat brushes are generally used for buggies, carriages, furniture and other fine work.

4-F-1315. Oval Varnish Brushes. All pure Chinese bristles, chisel

pointed, full and elastic, nickel plated ferrule and a first class brush which will give excellent satisfaction.

Size..... 1-0 2-0 3-0 4-0 5-0 6-0
Length, inches.... 2½ 2½ 3 5½ 3½ 3½
Price, each..... 27c 35c 40c 45c 54c 65c



4-F-1317. Oval Varnish Brush for Family Use. A good, durable brush suitable for varnishing floors and woodwork. Genuine Chinese bristles, nickel plated ferrule.

Size..... 2-0 3-0 4-0
Length, inches..... 2½ 3 3½
Price, each..... 27c 32c 35c

4-C-1319. Rubberset Oval Varnish Brush. Extra long selected Chinese bristles firmly imbedded in hard vulcanized rubber. Will not come out. Bound with seamless nickel plated ferrule. Can be used for painting as well as varnishing. Especially adapted for mechanics' use.

Size..... 7-0 8-0 10-0
Diameter, ferrule inches..... 2½ 2½ 2½
Length, bristles inches..... 4½ 4½ 4½
Price each..... \$1.03 \$1.19 \$1.35

MOTTLING BRUSHES. Made of Camel's Hair. Used for carriage work, in putting on color. Also for applying gold, silver, aluminum and other thin paint. Not suitable for varnishes.

4-F-1321. Short Cedar Handles, tin ferrules, superior quality.

Size, inches..... 1 1½ 2 2½ 3
Price each..... 14c 17c 23c 32c 39c

4-F-1323. Extra Thick Camel's Hair Mottling or Color Brush. Brass bound.

Size, inches..... 1 1½ 2 2½ 3
Price each..... 20c 30c 43c 59c 80c

SASH TOOLS. Used for Painting Sash, Mouldings, and for work in corners or close places where a small brush is required.

4-F-1325. Selected Black Chinese Bristles, oval chiseled point. Very elastic and a good

working tool.

Size, inches..... 1 2 4 6 8 10
Width, inches..... ½ ½ ½ ½ ½ ½
Length, inches..... 1½ 1½ 1½ 1½ 1½ 1½
Price each..... 6c 7c 9c 12c 16c 22c

4-F-1337. Wall Brush. Extra quality Chinese bristles, metal bound. An excellent brush for painting

floors, walls and for general family use.

Width, inches..... 3 3½ 4 4½ 5
Length, inches..... 2½ 3 3½ 3½ 3½
Price each..... 25c 35c 45c 60c 71c

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**



CHINESE BRISTLES

4-C-1327. Extra French Sash Tools.

All fine white bristles, wire bound. An excellent family brush.

Size, inch .. 1 2 3 4 5 6 7 8 9 10
Width..... 1 1½ 2 2½ 3 3½ 4 4½ 5 5½
Length, inch..... 1½ 1½ 1½ 1½ 1½ 1½ 1½ 1½ 1½ 1½
Price each..... 3c 5c 6c 7c 8c 9c 10c 12c 13c

4-C-1329. Rubberset Sash Tool. Chinese bristles chiseled, solidly imbedded in hard vulcanized rubber, bound with metal ferrule. A brush that will give excellent service. Bristles will not come out.

Size..... 4 6 8 10
Width, inches..... 1 1½ 1½ 1½
Length, bristles..... 1½ 1½ 2 2½
Price each..... 12c 15c 18c 21c

ROUND PAINT BRUSHES

4-C-1331. Round Paint Brush. White bristles outside, mixed center, wire bound. Made especially for painting rough surfaces. Bristles are too coarse for house painting and other work requiring smooth finish.

Size..... 3 4 5 6 7 8 9 10
Length, inches..... 3 3½ 3½ 3½ 3½ 3½ 3½ 3½
Price each..... 17c 19c 23c 25c 30c 38c

4-C-1333. Round Paint Brush. Finest selected white

Russian Bristles, wire bound. For house painting and good work.

Size..... 1-0 2-0 3-0 4-0 5-0 6-0
Length, inches 3½ 4 4½ 4½ 4½ 5
Price each..... 60c 72c 97c \$1.19 \$1.42

FLAT PAINT OR WALL BRUSHES

For painting walls, floors, roofs and other large surfaces. Length is length of bristles clear of ferrule.

4-F-1335. All Pure Chinese Bristles, Metal Bound. The best brush ever offered at the price.

Width, inches..... 2½ 3 3½ 4 4½
Length, inches..... 2½ 2½ 2½ 2½ 2½
Price each..... 11c 14c 17c 22c 31c

4-F-1337. Wall Brush. Extra quality Chinese bristles, metal bound. An excellent brush for painting

floors, walls and for general family use.

Width, inches..... 3 3½ 4 4½ 5
Length, inches..... 2½ 3 3½ 3½ 3½
Price each..... 25c 35c 45c 60c 71c

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

4-F-1339. A Brush that is always sold for One Dollar, and is considered good value at that price. All pure black Chinese bristles, nickel plated ferrule, yellow varnished handle. Full, firm and elastic. Strong enough to carry lead color. Suitable for the painter and others who have need of a high grade brush. Each brush is packed in an individual box. Width 4 inches. Length of bristles 4½ inches. Price..... **80c**

Strictly Pure Linseed Oil at the Market Price.

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

IMPROVED RUBBER GRAINING ROLLS.




9-G-1501. Improved wood grainers. Are composed of three rubber rolls, 5 inches in length. With the corrugated roll any known growth of wood can be imitated. Quarter-sawed oak grain is produced with roll No. 2 with the irregular grooves. No. 3 is used in place of combs. Any one with a set of improved graining rolls, with a little practice can do a perfect job of graining and imitate the natural wood so that it will be almost impossible to distinguish the natural grain from the grain made by improved wood grainers. Complete instructions packed with each set. Weight, 14 ounces. Price per set of 3 rolls. **94c**

HOUSEHOLD GRAINING ROLLERS.



9-G-1503. For graining doors, wainscoting, floors and wood-work of all kinds. A first class job can be done without previous experience. We refer you to our Colors in Oil for graining colors. All that is necessary is a can of Graining Colors and a small quantity of turpentine or benzine and a household graining roller to do first-class work. Price per roller, only **28c**

RUBBER GRAINING COMBS.



9-G-1505. Used in place of steel combs for a certain class of work. The rubber securely set in wood handles. The highest grade rubber comb made. Packed in cardboard boxes in sets of 12 combs assorted, six, nine and twelve teeth per inch. Price per set of twelve combs. **48c**

STEEL GRAINING COMBS.

9-G-1507. High grade English graining combs. Best quality of steel, in sets of 12 combs assorted, 1 to 4 inches, in tin compartment case. Price per set. **70c**



GRAINING CHECK ROLLERS.

9-G-1509. Double line graining check roller for producing the oak overgrain. A better imitation is obtained with double line check roller than with single line rollers. **50c**

GLASS CUTTERS GUARANTEED TO CUT.



9-G-1511. Royal Glass Cutters. Hard, bright steel frame, cutters revolve on steel pin in steel cap. Japanese Handle. Cutter made from the highest speed steel. **6c**



9-G-1513. Solid Steel Head. Revolving cutter made of special high carbon steel, hand honed. Black ebonized handle, finely finished. Guaranteed to make a smooth cut and to give entire satisfaction. **12c**

GOODELL'S GLASS CUTTER.



9-G-1515. Turret Head with six cutter wheels, which can be instantly revolved into position for use. The cutters are carefully hardened and ground by special process. Polished nickel plated frame, nickel ferrule, rosewood finish handle. Price. **18c**



9-G-1517. Magazine Glass Cutter. With six extra wheels stored in handle. Wheels are made of high carbon steel hand honed. Each wheel guaranteed to cut 500 feet of glass. Price. **20c**

UNIVERSAL DIAMOND GLASS CUTTERS.

A strictly high-grade cutter with which anyone can cut glass perfectly. A genuine diamond on one end and steel guide wheel on the other. Metal parts finished in a superior manner and nickel plated. **9-G-1519. No. 9. Will cut single strength glass. \$2.80**

9-G-1521. No. 10. With fine diamond. Will cut double strength glass. \$3.75

9-G-1523. No. 12. Extra quality diamond. Will cut anything except plate glass. \$4.85

Paper Hangers' Tools.

SEAM ROLLERS.



Guaranteed to be strictly high class tools and necessary for good work in hanging wall paper. **9-G-1525. Seam Roller, 1 inch, oval face, polished, hardwood roller. 8c**

9-G-1527. Seam Roller 1 1/2 inch, Oval Face, polished, hardwood Roller. 12c



SIDE ARM ROLLERS.



For ceilings and around door and window frames. **9-G-1529. 1 inch bevel face. Composition Roller. 27c**

9-G-1531. 1 inch bevel face. Polished hardwood Roller. 14c

9-G-1533.

Smoothing Rollers. 8 inches wide, felt covered. Guaranteed to be strictly high grade. **39c**



WALL PAPER TRIMMING KNIVES.

Blades are of the highest quality tool steel, properly tempered and fully warranted.

9-G-1535. Wheel knife for trimming wall paper. Plain blade, 2 inches in diameter. Nickel plated frame. **20c**

9-G-1537. Base trimmer. Serrated edge, blade 1 1/2 inches in diameter. Nickel plated frame. **22c**

9-G-1539. Wheel Knife. Offset handle, 1 1/2 inch blade. Nickel plated frame. **35c**

9-G-1541. Paper hangers' shears. The highest quality, nickel plated. Steel laid blades and enameled handles. Fully guaranteed. Size, inches 10 12 14 16 Length cut, inches 5 7 8 10 Price. \$.60 .70 .98 1.35

PAPERHANGERS' KNIVES ROUND AND SQUARE POINT. High grade tempered steel blade. Wood handles. **9-G-1545. Square Point. 12c**

9-G-1547. Round Point. 12c

WALL SCRAPING KNIVES.

9-G-1549. Three inches, square point. Beechwood handle. Price. **8c**

9-G-1543. Scraping Knife. Finest tempered steel blade with cocobolo handle. Heavy metal bolster. Width blade, inches 2 3 3 1/2 4 Price. 30c 35c 43c 50c

PUTTY KNIVES.

9-G-1551. Putty Knife. With stiff blade. Square point. Price. **4c**

9-G-1553. Putty Knife. With stiff blade. Square Point. Cocobolo handle. Lap bolster. Price. **12c**

9-G-1555. Putty Knife. Spring blade. Square point. Cocobolo handle. Lap bolster. **12c**

GLAZIERS' PUTTY KNIFE

9-G-1557. Finest Spring Tempered Steel. Cocobolo handle. Brass ferrule. Width of blade, 1 1/2 inches. Length, 3 1/2 inches. Strictly high grade tool. Price, each **18c**

PASTE BOARDS.



Made of the best quality of clear air-dried whitewood. Built up several boards, 1/2 inch thick, tongued and grooved and glued to prevent warping. Four battens to prevent warping. Made with three hinges. Strictly first quality board. 23 inches wide, open; 11 1/2 inches wide, closed. **9-G-1559. 7 feet long, plain. Weight, about 14 pounds. \$1.33**

9-G-1561. 7 feet long, with 4-inch strip. Weight, about 16 pounds. Price. \$1.62


PAPER HANGERS' FOLDING TRESTLES.



9-G-1563. Made of the finest, selected hard wood, strongly constructed. Guaranteed to be equal to any trestle made. 75c

Price, per pair


FOLDING PASTE TABLES.



Strictly high grade folding paste tables. Strongly constructed and light in weight. With space and hooks for carrying straight edge and tools. 22 inches wide, open; 11 inches wide, closed. Weight, 20 to 23 pounds. **9-G-1565. 7 feet long. \$2.80**

9-G-1567. 8 feet long. \$2.90

ECONOMY TRIMMERS



Why pay double for trimmers no better than these. Guaranteed easiest working trimmer made.

9-G-1569. Six foot complete with wood straight edge. \$2.05

9-G-1570. Seven foot complete with straight edge. \$2.20

9-G-1572. Six foot with metal straight edge. \$2.70

9-G-1572 1/2. Seven foot with metal straight edge. \$2.90

RIDGLEY'S STRAIGHT EDGE RULED TRIMMER.



The best straight edge manufactured. Made of air dried hardwood. Built up in five sections alternately, with grain reversed in each section. Brass bound on both sides and cannot twist or warp. This is the regular Model "D" Trimmer Straight Edge that can be used for knife work.

9-G-1573. Length 6 feet. \$1.75

9-G-1575. Length 7 feet. \$1.85

9-G-1576. Length 8 feet. \$2.00

HIGH GRADE WINDOW SHADES

Each Shade is Wrapped Separately ready for Hanging, Complete with Brackets, Nails and Slats

ALWAYS ALLOW about 6 inches from lengths of all shades quoted. For instance a 3x6 foot shade is cut 6 feet long before being mounted, hemming and mounting take up about 6 inches, therefore, a 6 foot shade will measure a trifle over 5½ feet. All shades are quoted ready to hang.

REGULAR SIZES of window shades are 36 inches wide by six feet long and seven feet long before mounting. All other sizes are **special** and must be made to order and will take from 3 to 5 days. All window shades made to order are not returnable if made as ordered.

PLAIN OPAQUE WINDOW SHADES.



24-G-100. Plain Water Color Opaque Window Shades. Mounted on patent spring rollers. Made plain without fringe or lace. Colors, light olive, pea green, terra cotta, dark green, light buff, dark olive, slate or white. **Always state color desired.** Size, 3x6 feet (manufacturer's measurement). **24c**

Price, each.....**\$2.75**
Per doz.....**\$32.50**

24-G-102. Plain Water Color Opaque Window Shades, same as above, but cut down less than 3 feet wide. **27c**

Price, each.....**\$3.15**
Per doz.....**\$37.80**

24-G-104. Plain Opaque Shades, same quality and colors as above. Size, 3x7 feet (manufacturer's measurement). **28c**

Price, each.....**\$3.25**
Per doz.....**\$39.00**

24-G-106. Same as 24-G-104, cut down to less than 3 feet wide **30c**

Price, each.....**\$3.60**
Per doz.....**\$43.20**

24-G-108. Plain Water Color Opaque Window Shades. Exactly same quality as above. Size, 3x8 feet. **37c**

Price, each.....**\$3.95**
Per doz.....**\$47.40**

FRINGED WINDOW SHADES.

24-G-138. Fringed Water Color Opaque Window Shades with very handsome 3½ inch fringe at bottom. Mounted on patent spring rollers. Colors, same as 24-G-100. **Always state color wanted.** Size, 3x6 feet (manufacturer's measurement). **33c**

Price, each.....**\$3.80**
Per doz.....**\$45.60**

24-G-140. Fringe Water Color Opaque Window Shades. Same quality as above, but cut down to less than 3 feet wide. **35c**

Price, each.....**\$4.00**
Per doz.....**\$48.00**

24-G-142. Fringed Water Color Opaque Window Shades. Same quality as 24-G-138 but 7 feet long. Price, each **38c**


Price, per dozen.....**\$4.25**
Per doz.....**\$51.00**

24-G-144. Fringed Water Color Opaque Window Shades. Same as 24-G-142 but cut down to less than 3 feet wide. **40c**

Price, each.....**\$4.50**
Per doz.....**\$54.00**

24-G-146. Fringed Opaque Window Shades. Same as 24-G-142 but size 3x8 feet. Price, each **42c**

Price, per dozen.....**\$4.75**
Per doz.....**\$57.00**



OIL OPAQUE WINDOW SHADES.

24-G-110. Plain Opaque Shades. Made from very best grade oil opaque, and mounted on patent spring rollers. Plain, without fringe or lace. Colors, same as 24-G-100. **Always state color wanted.** Size, 3x6 feet. **35c**

Price, each.....**\$4.00**
Per doz.....**\$48.00**

24-G-112. Plain Opaque Shades. Same as above, cut down to less than 3 feet wide. **40c**

Price, each.....**\$4.50**
Per doz.....**\$54.00**

24-G-114. Plain Opaque Shades. Same quality as 24-G-110, but 3x7 feet. **39c**

Price, each.....**\$4.40**
Per doz.....**\$52.80**

24-G-116. Same as 24-G-114, but cut down to less than 3 feet wide. **44c**

Price, each.....**\$5.00**
Per doz.....**\$60.00**

24-G-118. Plain Opaque Shades. Same quality as 24-G-110, but 3x8 feet. Price, each **46c**

Price, per dozen.....**\$5.40**
Per doz.....**\$64.80**

Following are prices on the above shades made to order in the following widths and 7 feet long. Hand made. Highest Grade Spring Rollers.

24-G-120. Over 38 inches wide up to 42 inches wide. Price, each **80c**

Price, per dozen.....**\$9.50**
Over 42 inches wide up to 45 inches wide. Price, each **95c**

Price, per dozen.....**\$11.40**
Over 45 inches wide up to 48 inches wide. Price, each **1.05**

Price, per dozen.....**\$12.60**
Over 48 inches wide up to 54 inches wide. Price, each **1.35**

Price, per dozen.....**\$15.00**
Above sizes 8 feet long at 10 cents, each, extra.

BEST QUALITY PLAIN

DUPLEX (DOUBLE FACED) OPAQUE SHADES

Genuine Hand Made. Mounted on Highest Grade Spring Rollers.

24-G-200. 38 in. by 7 ft. One side dark green, reverse side white. **75c**

Price, each.....**\$8.50**
Per doz.....**\$102.00**

24-G-202. 38 in. by 7 ft. One side dark green, reverse side cream. **75c**

Price, each.....**\$8.50**
Per doz.....**\$102.00**

24-G-204. 38 in. by 7 ft. One side olive green, reverse side white. **75c**

Price, each.....**\$8.50**
Per doz.....**\$102.00**

24-G-206. 38 in. by 7 ft. One side olive green, reverse side cream. **75c**

Price, each.....**\$8.50**
Per doz.....**\$102.00**

For sizes other than above, see 24-G-208.


24-G-208. Special Size Duplex Shades, made to order. If the exact size you wish is not given in the following schedule, the next larger size will be charged, but the shade will be cut the exact size you order. Colors are: Dark Green and White, Olive Green and Cream, Olive Green and White, Dark Green and Cream.

WIDTH IN INCHES

Length in ft	38	42	45	48	54	63
5	\$0.75	\$0.95	\$1.15	\$1.25	\$1.50	\$2.15
6	.85	1.05	1.35	1.45	1.70	2.45
7	1.00	1.20	1.45	1.55	1.85	2.65
8	1.05	1.30	1.55	1.75	2.05	2.95

BE SURE TO STATE SIZE AND COLOR WANTED.

ARTISTIC EFFECT WINDOW SHADES



This is the very newest and most artistic effect in window shades and is only carried by high grade concerns. They are made of extra fine shade material and has hand painted panel exactly as illustrated in illustration. Patent Spring Rollers.

The panel is absolutely fast color and very beautiful, which runs the full width of the shade. Nothing finer or handsomer on the market. Complete with roller ready to hang. We can furnish this shade in Dark Green, Light Green, Terra Cotta, Buff or White. **24-G-186. Size, 36 inches by 6 feet. Each.....53c**
Per dozen.....**\$6.25**

24-G-188. Size, 36 inches by 7 feet. (Made in one width only).....59c

Per dozen.....**\$6.75**

SPECIAL SIZE SHADES MADE TO ORDER

HIGHEST GRADE SPRING ROLLERS

FOR STORES, OFFICES AND RESIDENCES. The following shades we make to order from the very best quality hand made oil painted opaque shade cloth. It usually requires about four days to have special size shades made to order. We require the full amount of cash with the order in every instance.

SHADES MADE TO SPECIAL ORDER CANNOT BE RETURNED IF SENT AS ORDERED.

COLORS.—Special size shades are made only in the following colors: Dark green, olive, terra cotta, slate, pea green and light buff.

State whether width you desire is width of cloth or roller measure. Roller measure means from end to end of tips. We quote the width of cloth complete.

24-G-210. Order by number, size and price, and be sure to state color wanted.

Length in feet	WIDTH IN INCHES.										
	38	42	45	48	54	63	72	81	90	102	120
4	\$0.57	\$0.67	\$0.85	\$0.93	\$1.10	\$1.55	\$2.00	\$2.50	\$3.00	\$3.40	\$6.50
5	.66	.77	.96	1.02	1.25	1.80	2.25	2.75	3.30	3.80	7.35
6	.72	.87	1.05	1.17	1.35	1.98	2.50	3.00	3.60	4.25	7.95
7	.78	.96	1.14	1.25	1.50	2.20	2.75	3.30	3.95	4.60	8.56
8	.87	1.05	1.25	1.35	1.65	2.40	2.95	3.55	4.20	5.00	9.20
9	1.02	1.23	1.35	1.50	1.75	2.60	3.20	3.85	4.50	5.35	9.95
10	1.11	1.32	1.45	1.65	1.90	2.80	3.40	4.20	4.75	5.75	10.50
11	1.16	1.43	1.55	1.75	2.05	3.15	3.60	4.35	5.10	7.75	11.00
12	1.23	1.50	1.60	1.85	2.20	3.35	3.85	4.60	5.40	7.75	11.75

DON'T FAIL TO GIVE SIZE AND COLOR WANTED.

\$37.50 MAJESTIC BATH ROOM OUTFIT

**STRICTLY "A" GRADE
BEST QUALITY MADE.**

Compare This Outfit as here illustrated and described with the outfits offered by Plumbing Goods Concerns as advertised in magazines and elsewhere. Then you will readily appreciate the great value we offer in this outfit and the large saving in price we make to you.

We appreciate the fact that there are Outfits sold at even a lower price than "Our Majestic" Outfit, however, we assure you there is **no outfit of its equal quality or of such fine appearance that is offered at anywhere near our low price of \$37.50.** Our special low price is based on the actual factory cost, with but one small profit added.

When you take into consideration that every item on this Outfit is strictly "A grade" and perfect, this means you receive the highest grade of material and the best of workmanship, then you will agree with us that this is the lowest priced Outfit on the market today.

We positively guarantee this Outfit to satisfy you in every way, or we will cheerfully refund your money with any freight charges paid out by you.

Bath Tub furnished with this Outfit is a strictly "A" Grade, 5 ft. heavy cast iron Tub with wide roll rim. The Tub is 30 inches wide and is heavily coated with white porcelain enamel, which is thoroughly baked on.

The very best grade of gray cast iron is used in the manufacture, and the Tub is furnished complete with ornamental legs. The Tub is very graceful in appearance and one of the best designs on the market.

The Tub is furnished complete with No. 41 Fuller pattern nickel-plated combination bath faucet, marked "Hot" and "Cold" with a nickel-plated jewel cup. Has highly nickel-plated connected waste and overflow and two heavy nickel-plated supply pipes with nickel-plated floor flanges. Has nickel-plated chain and rubber stopper.

Closet sent with this Outfit is strictly "A" grade, low-down pattern, improved type, and one that will pass the most rigid inspection. The Closet Tank is made of Golden Oak, thoroughly seasoned and highly polished. Has a heavy lining of copper. All fittings and trimmings are made of heavy brass, and it is furnished with the Douglas pattern valve, which is positive in action and made of such high grade material, by skilled mechanics that it never gets out of order. The water is shut off by a rubber ball set into the seat of the flush valve, and if the occasion arises to repair the valve, all that is necessary is to simply unscrew the rubber ball from the rod and screw in a new ball at a very slight expense; an exceedingly easy operation, that requires no previous experience. This Tank has a china push button in front, which adds to the appearance of the Tank. The tank is attached to the wall by our improved concealed wall hanger.

The Closet Bowl is an "A" grade Syphon wash-down pattern of very fine quality, strictly modern and well proportioned.

The Closet Seat is oak finish and well made. The trimmings consist of a heavy nickel-plated supply pipe and nickel-plated 2 inch flush elbow connection and nickel-plated screws for fastening closet bowl to floor, making the Outfit complete above the floor line.

Lavatory furnished with this Outfit is strictly "A" grade and made of the very best grade of cast iron. Is heavily coated with high grade white porcelain enamel, which is thoroughly baked on.

The Slab of Lavatory measures 18 inch x 21 inch with 8 inch back and a "D" pattern bowl 10 inch x 14 inch. Has a neat roll rim with no sharp edges of corners, which is an improvement over the old style Marble Slab Lavatory. This Lavatory has an elegant and massive appearance and is an ornament to any Bath Room.

Furnished complete with depressed Soap Cup and 1 1/2 inch nickel-plated "S" trap with waste to floor and floor flanges. Has two nickel-plated low-down compression basin cocks with china tops marked "Hot" and "Cold" and with nickel-plated chain and rubber stopper. Has two nickel-plated 1/2 inch supply pipes from basin to floor with nickel-plated floor flanges. Lavatory has concealed wall hanger easily put up and doing away with the unsightly brackets.

Pipe Connections We can furnish "Our Majestic" Bath Room Outfit fitted for lead pipe connections or fitted for iron pipe connections. We fully describe on the previous pages our special iron pipe connections, and if you intend to install this Outfit



yourself or with the aid of a handy workman, by all means order this Outfit fitted for iron pipe connections.

Prompt Shipment We carry an enormous stock of Plumbing material, so as to ship all orders promptly. The Closet and Lavatory are shipped from our Chicago warehouse. Combined shipping weight is about 200 lbs. The Tub and Lavatory are shipped from our factory in Southern Wisconsin, and weighs about 250 lbs.

Our Prices We offer "Our Majestic" Bath Room Outfit, complete as described, and fitted for either lead pipe or iron pipe connections. We also quote the extra bath room accessories as shown in the illustrations.

Please observe that we make a special offer in price on the above Bath Room Outfit complete, with extra bath room accessories as illustrated

5-C-33. "Our Majestic" Bath Room Outfit complete, as illustrated as described above, with lead pipe connections, price..... **\$37.50**

5-C-35. "Our Majestic" Bath Room Outfit complete, as described above with iron pipe connections..... **\$39.00**

Extra Bath Room Accessories as shown in the illustration, furnished at the following prices

5-C-3051. Nickel-plated Toilet Paper Holder..... **50c**

5-C-3061. Bath Seat with rubber covered nickel-plated supports to protect Bath Tub..... **45c**

5-C-3081. Nickel-plated Bath Soap Cup for Bath Tub..... **57c**

5-C-3091. Nickel-plated Brass Towel Rack, 1/2 x 24"..... **45c**

5-C-3093. Nickel-plated Brass Towel Rack, 1/2 x 30"..... **55c**

5-C-3112. Oval Bath Room Mirror, 12"x18", ivory white enameled frame with French bevel plate mirror..... **\$2.80**

Special Offer Please observe in the following proposition we include entire Bath Room Outfit with all accessories as listed above, giving you a complete up-to-date outfit in every detail; and we suggest that you select either one of these special offers as these accessories are very useful and necessary to complete a Bath Room.

5-C-37. "Our Majestic" Bath Room Outfit as described above, complete with all bath accessories offered above, and Outfit fitted for lead pipe connections, price..... **\$42.50**

5-C-39. "Our Majestic" Bath Room Outfit as described above, complete with all bath accessories offered above, and Outfit fitted for iron pipe connections, price..... **\$44.00**

Note If 4 ft. Tub is wanted, deduct..... **\$1.50**

If 5 1/2 ft. Tub is wanted, add..... **1.50**

If 6 ft. Tub is wanted, add..... **2.00**

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.


We have the latest styles in Hair Ornaments at lowest prices.

BATH TUBS

"Best Quality" Every cast iron tub offered on this and the following page is brand new, absolutely "A" grade, which means perfect in every detail. They are all heavily coated with the finest white porcelain enamel, thoroughly baked on by a secret process. They are guaranteed against flaws, chips or defects of any nature. If you would pay the ordinary retail price, which is double ours, you will get no better quality than what we offer you here.

"Latest Design" We particularly call your attention to the graceful, yet massive design of our entire line of cast iron, white porcelain enameled tubs shown on this and the next page. These tubs are our exclusive pattern, designed especially for us, and the tubs are furnished complete with handsome ornamental cast iron feet.

\$11⁴⁰ Buys this "A" Grade Roll Rim Porcelain Enameled Bath Tub



"Material" The above tub is strictly "A" grade, and perfect. It is made of the very best grade of gray cast iron, has a heavy coating of white porcelain enamel, which is thoroughly baked on.

"Guarantee" This tub is guaranteed strictly "A" grade, which means it is perfect in every detail, absolutely free from flaws and defects of any kind or character. If you do not find the tub entirely satisfactory, and exactly as represented you have the privilege of returning it, and we will refund the purchase price and freight charges both ways.

"Dimensions" The tub is 30 inches wide, with a heavy 3-inch roll rim, height on legs 23 inches; depth inside 17 inches. Tubs come in lengths from 4 to 6 feet, as quoted below.

"Price Is for Tub Only" The price is for the tub only, without any fittings or connections, exactly as shown in the illustration. However, we include with each tub a complete set of ornamental feet. This tub is shipped from our factory in Southern Wisconsin.


Order No.	5-C-101	5-C-103	5-C-105	5-C-107	5-C-109
Lengths	4 ft.	4½ ft.	5 ft.	5½ ft.	6 ft.
Weight, lbs.	200	250	300	350	400
Price	\$11.40	\$12.75	\$13.50	\$15.30	\$18.00

Extra for 4½ Fuller Double Bath Cock, \$1.75. Connecting waste and overflow, \$1.35.

"Reduced Prices!" We offer you lower prices than ever quoted before on strictly "A" grade tubs. Our enormous trade enables us to take almost the entire output of one of the leading tub manufacturers. Hence we can save you from 30 to 50 per cent over the prices asked by your local dealer. Furthermore, you can depend that every tub is perfect, and exactly as represented.

"Fittings" All our fittings are the most modern, "up-to-date" type; and no better or higher grade can be purchased elsewhere. Please note that our prices on the various tubs include both the tub and the fittings, as shown in the illustrations. This will assist you in ordering, and avoid any mistakes, for you will get the tub and the fittings exactly as illustrated. It makes it easy for you to order direct from this catalog.

\$15⁴⁰ FOR THIS HIGH GRADE PORCELAIN BATH TUB Complete With All Fittings Above Floor



Quality. These tubs are brand new and strictly "A" grade. Every tub guaranteed free from all blemishes or defects of any character. At our prices they are positively bargains.

Dimensions. Height on legs, 23 inches; depth inside, 17 inches; width over all, 30 inches, with a graceful 3-inch roll rim. They come in lengths from 4 to 6 feet inclusive. These Tubs are shipped direct to you from our factory in South Wisconsin.

Fittings. Tub is complete with all fittings as shown in illustration, consisting of one nickel-plated No. 4½ Fuller pattern combination Bath Faucet, with jewel cup, indexed for "Hot" and "Cold" water and a special shampoo connection. Has a high grade nickel-plated connected waste and overflow with nickel-plated chain and rubber stopper. Has nickel-plated off-set ½ inch supply pipes with nickel-plated floor flanges. Please bear in mind that this Tub comes with all necessary nickel-plated trimmings above the floor.

PRICE OF BATH TUB COMPLETE WITH CONNECTIONS FOR LEAD PIPE.					
Order No.	5-C-201	5-C-203	5-C-205	5-C-207	5-C-209
Length	4 ft.	4½ ft.	5 ft.	5½ ft.	6 ft.
Appr. Wt.	200 lbs.	250 lbs.	300 lbs.	350 lbs.	400 lbs.
Price	\$15.40	\$17.25	\$18.00	\$19.80	\$22.50

Note:—Be sure to add \$1.00 to above prices, if iron pipe thread connections are desired.


EXTRA HIGH GRADE WHITE PORCELAIN BATH TUB \$23⁰⁰
WITH **NICKEL-PLATED BATH TRAP** OVERFLOW AND WASTE **COMBINATION**

You will note from illustration the special feature of this Tub is the heavily nickel plated bath trap connected above floor directly to nickel plated waste and overflow pipes from Tub.

Dimensions The Tubs are full 30 inches in width, with a massive 3 inch roll rim. Height of Tub on legs 23 inches. Depth inside 17 inches.

Fittings Each Tub is furnished complete as illustrated. Fittings consist of one nickel plated No. 4½ Fuller pattern combination bath faucet, with jewel cup, indexed for "Hot" and "Cold" water and special shampoo connection. Nickel-plated connected waste and overflow with patent trap above floor, especially designed for high grade Outlets. The trap on this connected waste and overflow is made of heavy cast brass, with clean-out plug and is heavily nickel-plated all over. The Tub has two nickel-plated ½ inch off-set, supply pipes with nickel-plated floor flange. Has nickel-plated chain and rubber stopper. You will note the above Tub is complete with all trimmings necessary above the floor. These Tubs are shipped direct from our factory in Southern Wisconsin.

PRICE OF BATH TUB COMPLETE WITH CONNECTIONS FOR LEAD PIPE.				
Order No.	5-C-221	5-C-223	5-C-225	5-C-227
Length	4½ ft.	5 ft.	5½ ft.	6 ft.
Appr. Wt.	250 lbs.	300 lbs.	350 lbs.	400 lbs.
Price	\$23.00	\$25.00	\$28.50	\$29.00



Be sure to add \$1.00 if you desire iron pipe connections.

ENAMELED IRON ONE PIECE LAVATORIES

Guaranteed Strictly "A" Grade - At Reduced prices

ENAMELED HALF CIRCLE LAVATORY \$7.45 COMPLETE "A" GRADE

This Lavatory can be furnished with trap and supply pipes to floor instead of to wall without extra charge.

Design. Lavatory is all cast in one piece and is of the finest grade of gray enamel. It is heavily coated with pure white Porcelain Enamel.


Dimensions. Size of slab 16 x 19 inches. Height of back 6 inches. Size of bowl 10x14 inches.

Fitted Complete with two nickel-plated compression faucets. Has one 1 1/2 inch nickel-plated "P" trap with outlet to wall and two nickel-plated 3/4 inch supply pipes to wall, with nickel-plated wall flanges. Has nickel-plated chain and rubber stopper. Has a depressed soap cup and recessed over-flow. Lavatory is attached to wall by concealed wall hanger. (See following page for description of wall hangers.) Shipping weight about 70 lbs.

5-C-401. Lavatory complete, with all fittings above floor as described above, fitted with lead pipe connections.

Price.....\$7.45

5-C-403. Lavatory, same as above, except fitted with iron pipe connections. Price...\$8.20



ENAMELED HALF CIRCLE LAVATORY \$8.10 COMPLETE "A" GRADE

This is a larger Lavatory than our 5-C-401. Is cast in one piece from the finest grade of gray cast iron. Heavily coated with pure white Porcelain Enamel. A decided bargain at our price.

Dimensions. Size of slab is 18 x 21 inches. Back 8 inches. It has a "D" pattern bowl 10x14 inches.

Fitted Complete

with two nickel-plated compression faucets. Has one 1 1/2 inch nickel-plated "P" trap with outlet to wall, and two nickel-plated 3/4 inch supply pipes to wall, with nickel-plated wall flanges. Has nickel-plated chain and rubber stopper. Has a depressed soap cup and recessed overflow. Lavatory is attached to wall by concealed wall hanger. Weight about 85 lbs.

5-C-405. Lavatory complete with all fittings above the floor fitted with lead pipe connections. Price.....\$8.10

5-C-407. Lavatory same as above, except fitted with iron pipe connections. Price.....\$8.85



ENAMELED IRON DEEP APRON LAVATORY

\$9.55 Complete "A" Grade

This handsome Lavatory is an ornament to any bath-room. It is strictly up-to-date, being cast in the piece, of the finest grade of gray cast iron, heavily coated with pure white enamel. Guaranteed "A" Grade and perfect.

Dimensions It has half circle slab with a round corner deep apron. Size of slab 18x21 inches. Height of back 8 inches, with a "D" pattern bowl 10x14 inches. Has a depressed soap cup in the surface of the slab and recessed over-flow cast in the bowl.

Fitted complete with two nickel-plated semi low-down compression faucets with china tops marked "Hot" and "Cold." Has one 1 1/2 inch nickel-plated "P" trap with outlet to wall, with nickel-plated wall flange. Has two 3/4 inch nickel-plated supply pipes to wall with nickel-plated wall flanges. Has nickel-plated chain and rubber stopper. Attached to wall by means of concealed wall hanger. (See following page for description of wall hangers. Shipping weight about 90 lbs.)

5-C-411. Porcelain Enamelled Lavatory complete, with all fittings above the floor as described above, fitted with lead pipe connections. Price.....\$9.55

5-C-413. Lavatory complete, same as above, fitted with iron pipe connections.\$10.30



ENAMELED IRON DEEP APRON LAVATORY

\$12.55 Complete "A" Grade

This Lavatory is the latest improvement, being fitted with Ideal Roman Waste, which does away with the nickel-plated chain and rubber stopper. By lifting the top of the Ideal Roman waste you rapidly empty the bowl. It is absolutely sanitary.


Design This Lavatory is cast all in one piece from the best grade of gray cast iron. It is heavily coated with pure white porcelain enamel.

Dimensions Size of slab 18x21 inches. Height of back 8 inches. Bowl 10x14 inches. Has round cornered deep apron. Has two nickel-plated compression

semi low-down faucets with china tops, indexed "Hot" and "Cold." Has two 3/4 inch nickel-plated supply pipes to wall, with off-set nickel-plated air chambers. Has nickel-plated Ideal Roman Waste with china top, marked Waste. Has one 1 1/2 inch nickel-plated "P" trap to wall with nickel-plated flanges. Attached to wall by means of concealed wall hangers.

5-C-421. Porcelain Enamelled Lavatory complete, with all fittings above the floor, as described above, fitted for lead pipe connections.....\$12.55

5-C-423. Lavatory complete, same as above, fitted with iron pipe connections.....\$13.30



ENAMELED IRON DEEP APRON LAVATORY

\$13.10 COMPLETE "A" GRADE ONE PIECE

A strictly modern up-to-date Lavatory. Must be seen to be appreciated.


Design. All cast in one piece, having a square slab with a "D" pattern bowl, with the round corner deep apron. Heavily coated with the finest grade porcelain enamel, baked on to an exceptionally high degree of hardness, giving it a beautiful gloss and easy to clean.

Dimensions. Size of slab 18 x 24 inches, height of back 10 inches, size of bowl 11 x 15 inches.

Fitted Complete. Has two nickel-plated semi low-down compression faucets with china top, marked "Hot" and "Cold." Has one 1 1/2 inch nickel-plated "P" trap to wall with wall flange. Has two 3/4 inch n.p. supply pipes to wall with n.p. air chambers. Depressed soap cup with overflow. N-P. chain and stopper.

5-C-431. Porcelain Enamelled Lavatory complete, with all fittings above floor as described above, fitted with lead pipe connection.....\$13.10

5-C-433. Lavatory complete, same as above fitted with iron pipe connections.....\$13.85



\$15.30 COMPLETE "A" GRADE ONE PIECE

Nothing finer ever produced in a wall Lavatory, complete in every detail, with the special feature of the Ideal Roman waste, doing away with nickel-plated chain and rubber stopper, leaving a free open bowl.


Design. The Lavatory is cast in one piece, has a round corner deep apron. Heavily coated with pure white porcelain enamel. Has concealed wall hangers, doing away with unsightly brackets.

Dimensions. Size of slab 18 x 24 inches, height of back 10 inches. Size of bowl 11x15 inches.

Fitted Complete. Has two nickel-plated semi low-down compression faucets with china tops, marked "Hot" and "Cold." Has two 3/4 inch nickel-plated supply pipes to wall with nickel-plated off-set air chambers. Has nickel-plated Ideal Roman waste with china top, marked waste. Has 1 1/2 inch nickel-plated "P" trap to wall with nickel-plated wall flange. Shipping weight about 120 lbs.

5-C-441. Porcelain Enamelled Lavatory, with all fittings to floor, as described above, complete with lead pipe connections.....\$15.30

5-C-443. Lavatory complete, same as above, fitted with iron pipe connections.....\$16.05



ONE PIECE ROLL RIM SINKS

CAST IRON PORCELAIN ENAMELED
Most Up-to-Date, Sanitary and Durable Sinks Manufactured

These One-Piece Roll Rim Porcelain Enameled Sinks represent the latest and most sanitary design of sink produced. Sink and back being cast in one piece, there are no crevices or joints to catch dirt and produce unsanitary and unclean conditions. Are attached to wall by means of strong concealed hangers. There are no unsightly brackets, and at the same time, every nook and corner under the sink can easily be reached and kept clean without difficulty. The heavy enameled roll rim gives the sink an artistic and finished appearance, does away with wooden framework, and meets fully the present day demand for sanitary, open-work plumbing installation.

Sinks Furnished Complete. The prices listed below include all fittings necessary for their installation, viz.: nickel plated strainer, sink collar, ½-inch faucets, 1½ inch lead trap and concealed wall hangers. Please bear this in mind in comparing our prices with those of other houses.


Important—Read Carefully

Faucets. While these sinks are illustrated equipped with Fuller faucets, we recommend compression faucets on account of providing a freer flow of water, as well as their greater durability under

high water pressure, as well as doing away with pipe pounding so ruinous to Fuller faucets where no air-chambers are provided in the piping. Unless Fuller faucets are preferred, we will always send compression faucets with these sink outfits.

Trap. We will send you 1½ lead P trap to wall, as shown in illustration, unless you specify in your order that you want S trap to floor. There is no difference made in price of sink outfit for either form of trap but you can avoid delay incident to exchange by being careful to specify in your order kind of trap desired.

Iron Pipe Connections. If you intend to install sink yourself, be sure to specify iron pipe connections. We furnish you flanged faucets with female thread to screw to supply pipe, and trap is furnished especially fitted with nipple on inlet end, and brass coupling at outlet end, together with sink collar threaded for 1½ pipe. Simplest thing in the world to attach trap. The nipple is simply screwed into the collar, and the coupling is then in place for attachment to waste pipe. We make a nominal charge of only 50 cents for providing these iron pipe connections.



\$8⁷⁰ Roll Rim
One Piece

How Made. Only the best quality of gray cast iron is used in the manufacture of this Sink. It is cast all in one piece and heavily coated on the inside and over rim and back with pure white porcelain enamel, baked on to the highest degree of hardness possible to obtain, giving it a highly polished finish, very attractive and neat.

Fitted Complete. We furnish this Sink equipped complete as shown in illustration with all fittings above the floor. This is important in comparing our prices with others. The trimmings consist of two nickel-plated ½-inch flange plain faucets. Has nickel plated Silk Strainer with one 1½-inch lead "P" trap with outlet to wall. It is attached to wall by means of our concealed wall hanger, easy and simple to erect, which does away with unsightly and unsanitary brackets, as used on old style Sinks.

5-C-1631. Complete, 18 x 24 inch Sink. \$8.70
 5-D-1631½. Complete, 20 x 24 inch Sink. 9.25
 5-C-1635. Complete, 18 x 30 inch Sink. 9.60

5-C-1639. Complete, 20 x 30 inch Sink. \$ 9.60
 5-C-1643. Complete, 20 x 36 inch Sink. 11.70

Important. If you intend to install sink yourself, be sure to specify for iron pipe connection and add 50 cents to above prices.

NOTE: Can be furnished with two aluminum bronzed adjustable legs at \$1.00 additional



\$11¹⁰ One Piece
Roll Rim

Porcelain Enameled Sink

Furnished Complete with Enameled Drainboard

Same as above, with addition of cast iron porcelain enameled, reversible Drainboard and Bracket.

5-C-1675. Outfit Complete, 18x24 Sink, with 18x18 Drainboard. \$11.10
 5-C-1677. Outfit Complete, 18x30 Sink, with 18x24 Drainboard, 12.70
 5-D-1678. Outfit Complete, 20x24 Sink, with 20x24 Drainboard, 13.70
 5-C-1679. Outfit Complete, 20x30 Sink, with 20x24 Drainboard, 13.70
 5-C-1681. Outfit Complete, 20x36 Sink, with 20x24 Drainboard, 14.70

Important. At above prices, sink is fitted for lead pipe connection. If you intend to install sink yourself, be sure to specify Iron Pipe Connection and add 50 cents to price.

Furnished Complete

All One Piece Sinks can be Furnished with Adjustable Legs at \$1.00 Addition

Sink, Back and Drain Board In One Piece


The very latest design of Combination Sink, Back and Drainboard, all cast in one piece. Wide, handsome roll rim; beautiful Ivory white, glossy finish; easily kept clean; no crevices or corners to catch grease and dirt, and easily attached to wall by means of strong, concealed wall hangers.

Fitted Complete Prices given below include faucets, trap, strainer, collar, concealed wall hangers, etc. Can be equipped with two aluminum bronzed, adjustable legs at additional charge of only \$1.00.

NOTE—Can be furnished with Drainboard on either left or right hand side. Unless you specify otherwise, we will always send left hand as shown in illustration.

5-C-1791. Sink Complete, entire length, 44 inches. Price.....\$16.70
 5-C-1793. Sink Complete, entire length, 48 inches. Price.....18.70
 5-C-1795. Sink Complete, entire length, 52 inches. Price.....19.70

Important The above prices are for Sink fitted for lead pipe connection. If you intend to install yourself, be sure to specify Iron Pipe Connection and add 50 cents to price.



Lead S trap to Floor Instead of "P" Trap to Wall If So Specified.

\$16⁷⁰


100 Let us quote you on a heating plant for your home.



CHICAGO HOUSE WRECKING CO.
 35th & Iron Streets, Chicago.

\$11²⁵ HIGH AND LOW DOWN CLOSET OUTFITS \$11²⁵

\$11²⁵ BUYS THIS SYPHON WASH DOWN CLOSET OUTFIT.



Closet tank is made of highly polished wood, lined with copper, fitted with latest improved Douglas pattern rubber ball flush valve, compound lever ball cock and is operated by nickel plated push lever placed on the side of the tank. A slight touch of this lever raises the rubber valve, releases the water and gives a strong flush.

Seat and cover highly polished to match tank and is attached direct to bowl, with heavy nickel plated offset post hinges. Closet bowl is of latest improved syphon wash down pattern made of

Vitreous china highly glazed inside and out. Always carries a deep water seal, which is a protection against the escape of sewer gas. A modern sanitary outfit in every respect. We also furnish nickel plated supply pipe from floor to tank, nickel plated closet screws to fasten bowl to floor, floor flange for supply pipe and tank is connected to bowl with two inch nickel plated slip joint elbow.

Special Note. We furnish this outfit in natural oak, golden oak or birch mahogany finish. In ordering be sure to specify style of finish wanted.

5-F-801. Wash down closet outfit complete with all fittings above floor **\$11.25**
as described.
5-F-811. Same outfit with Syphon Jet Bowl. **\$14.25**

\$15⁷⁵ SYPHON WASH DOWN CLOSET WITH WHITE CHINA LOW TANK



This Closet Outfit is designed especially for use in the finest of homes, high class Apartments and Office Buildings. The white China Low Tank makes it exceptionally rich in appearance and is an ornament wherever used. It is "The Show Outfit" in all the leading plumbing establishments. Commands the usual retail price of \$25.00. You can easily appreciate the saving we offer at our low price of **\$15.75**. Every item that goes to make up this Outfit is strictly "A" grade, perfect material. Nothing finer produced.

These Outfits are furnished with handsome white China Tank, as shown in illustration, rich and massive in appearance, made of the best vitreous earthenware, heavily glazed on the outside, giving it a highly polished surface, most striking in appearance, exceptionally easy to keep clean.

It has the latest improved rubber ball valve. All fittings are made of heavy brass and copper. Valve is operated by a China lever in front of Tank. A very slight pull of the lever releases the valve and causes a strong, positive flush in the bowl. Tank has holes drilled in the back so as to fasten to the wall.

An elegant heavy Golden Oak Seat and Cover are included in this Outfit. They are attached to bowl with off-set nickel-plated hinges, being made so strong they will stand the hardest of usage. Have rubber bumpers where necessary.


Is the latest design in Syphon Wash-Down Bowls, made of the finest grade of vitreous china-ware, glazed inside and out, guaranteed strictly "A" grade. Nothing finer produced in this design; easily kept clean. This Closet Outfit is furnished complete with all trimmings necessary above the floor. Has 1-inch nickel-plated supply pipe from tank to floor with nickel-plated floor flanges. Tank is connected to bowl with 2-inch nickel-plated elbow, made of heavy brass with slip joint connections. Bowl is fastened to floor with our special nickel-plated head floor screws and washers.

We offer this Outfit with supply pipe fitted with lead pipe connections, also supply pipe fitted with iron pipe connections. If you intend to install the Outfit yourself, do not neglect to order the Outfit fitted with iron pipe connections. This is important and we must impress upon you not to overlook same when ordering.

5-C-1001. Syphon Wash-Down Closet, with white China Low Tank complete. **\$15.75**
5-F-1021. Same outfit, with white China Low Tank, but with Syphon Jet, Closet Bowl **\$18.50**

\$11²⁵ TOP SUPPLY WASH DOWN CLOSET OUTFIT WITH HIGH TANK.

We show here standard type high tank closet outfit. Still very popular because of strong positive flush always secured with a high tank outfit. Also preferred where space is limited, because can be roughed in closer than a low tank outfit.



Best Quality This entire outfit is made up only in strictly "A" grade, perfect goods: every item guaranteed to be entirely satisfactory to you, or money refunded. You take no chance when ordering this outfit under this liberal and binding guarantee.

50% Saving Our prices represent a saving of at least 50 per cent, besides you get absolutely the best quality of materials in this entire outfit.

The Bowl furnished with this outfit is strictly "A" grade, wash down bowl made of white vitreous china earthenware, highly glazed inside and out. Easy to keep clean and perfectly sanitary in operation.

Seat Seat and cover has high golden oak finish, and furnished complete. Cover is attached to seat with nickel plated hinge. The materials in the construction of the seat and cover is of the very highest character.

Tank This outfit can be furnished for either top or bottom supply. Equipped with Golden Oak finished Wood, copper lined and fitted with improved valve, operated by nickel-plated chain and pull. Has a positive strong flush, and rapidly empties the bowl.

The tank is attached to wall by means of all wood concealed wall hangers as illustrated on next page. It is a very simple and easy matter to attach this tank, requiring only a few minutes time.

Fitted Complete

This outfit is complete with all trimmings above the floor, including 1 1/4 in. nickel-plated flush pipe with 1 1/4 in. nickel-plated elbow connecting tank to bowl. Flush pipe has nickel-plated brace with rubber bumper. Bowl has nickel-plated head floor screws with washers; in fact, the outfit is complete and furnished exactly as shown in the illustration.

Special Note:

We furnish tank for either top or bottom supply. In ordering be sure to specify which is wanted. We also send top supply tank unless otherwise specified.

5-F-1111. High tank closet outfit complete with all trimmings above the floor, as illustrated and described. **\$11.25**
5-F-1211. HIGH TANK CLOSET OUTFIT, COMPLETE SAME AS ABOVE, EXCEPT WITH SYPHON JET CLOSET BOWL, PRICE. **\$14.25**

Illustration Shows Wash Down Top Supply Outfit.

WRITE FOR OUR COMPLETE PLUMBING CATALOGUE. SEND US SKETCH OF YOUR HOUSE FOR COMPLETE PLUMBING ESTIMATE. NO CHARGE MADE. FULL INFORMATION CHEERFULLY FURNISHED BY OUR PLUMBING EXPERTS

\$29.60 BUYS OUR CAST IRON PERFECTION BOILER

Write for Our Complete Heating Catalog—
Free for the asking

CAST IRON BOILERS ARE MOST EFFICIENT

Cast iron is certainly the proper material to use for manufacturing boilers for house heating. It is all right to make boilers of steel when you are compelled to. Steel is the only practical material to use when you are building a boiler for power purposes and one which will have to stand up to a pressure of 100 to 200 or sometimes 300 pounds; but when it comes to a house heating boiler, in which the pressure will at the most never exceed 10 pounds, it is certainly advisable to sacrifice the mere matter of tensile strength of the material for more desirable advantages, such as durability, more efficient design, etc., which are features of our cast iron Perfection Boilers.


THESE BOILERS BURN ANY KIND OF COAL

You can burn any kind of coal in these cast iron boilers; hard coal or soft coal. The great advantage which these boilers have as a soft coal burner lies in the ease with which they can be cleaned. The entire cleaning of the flues is done from the front of the boiler; simply open the clean-out door and run the flue brush through each flue opening two or three times, and the flues are bound to be cleaned in the most thorough manner possible. When this is done once every two or three days the utmost efficiency of the fuel will be obtained. Here is the great disadvantage of many boilers. When soft coal is used and a large amount of soot is generated, it is a very hard matter to keep the flue surfaces properly cleaned at all points so that the full amount of heat will be taken up from the fuel. The simplicity of the flue arrangement and also the ease with which these boilers can be cleaned, are their strongest points. Note that the entire fire pot is surrounded by water. The cold water being supplied to the bottom of the boiler gradually becomes heated, rises to the top and is taken off here with proper arrangement of piping to supply the various radiators.

THE ROCKING GRATES

Every grate bar in our boilers is mounted on an axis and connects with a common connecting bar underneath. This connecting bar is attached to a lever located at the side of the boiler as shown in these illustrations and by operating this lever every grate bar in the entire boiler can be made to rock and the top of the grate surface on which the fire bed rests is converted into a veritable grinding machine when these grates are being shaken and it only takes very little shaking of these grates to get all of the surplus ashes out of the fire bed and get the fire going with a bright red heat through the entire grate surface of the boiler. These grates positively prevent any dead corners in these boilers, as any ashes that might collect in these corners will always find its way down, and once it reaches these grinding grates, it is bound to be discharged into the ash box.

The Boiler illustrated on this page is our No. 17-D-178 (eight sections) with complete steam trimmings.



The Top Notch of Perfection

PRICES AND DIMENSIONS OF OUR PERFECTION CAST IRON BOILERS

Number	Size of Fire Pot	Size of Smoke Pipe	Floor Space Including Smoke Box	Tappings at Flow and Return	Height to Water Line (In Steam Boiler)	Direct Water Radiation	Direct Steam Radiation	Shipping Weight in lbs.	Price for Water	Price for Steam
17-D-64	13x12	7	22x20	2-2	38½	300	150	590	\$ 29.60	\$ 39.00
17-D-65	13x15	7	22x24	2-2	38½	400	225	675	44.00	52.00
17-D-66	13x18	7	22x28	2-2	38½	500	300	835	55.00	63.00
17-D-67	13x21	7	22x32	3-2	38½	600	375	915	58.50	66.00
17-D-175	17x17	9	27x28	2-2½	48	700	425	941	64.00	72.00
17-D-176	17x21½	9	27x32	2-2½	48	900	525	1123	78.00	86.00
17-D-177	17x26½	9	27x36	3-2½	48	1050	625	1305	92.00	100.00
17-D-178	17x30	9	27x40	3-2½	48	1250	725	1487	110.00	118.00

Above Prices are all F. O. B. our Factory in Western Pa. We will Quote Freight Prepaid, or F. O. B., Chicago. Prices on request

OUR LINE OF HOT AIR FURNACES

\$30⁵⁰
BUYS THIS FURNACE COMPLETE

BURNS ANYTHING COMBUSTIBLE

The great feature of this furnace is that it will burn anything combustible. The large firing door and large roomy fire pot, the peculiar shape of the radiator dome permits you to burn anything from large logs, tree stumps, etc., to cobs, rubbish, broken boxes, etc., or anything that you may have to burn and get rid of. Here is a furnace that will never require cleaning. It is practically self-cleaning. Should any soot, etc., collect around the radiator drum in this furnace, it is bound to burn off of its own accord, with the result that the radiator drum of this furnace is always absolutely clean, making it the most efficient heating furnace on the market.

WHIRLING DRAFT

You can start a brisk fire in this furnace in a few minutes with light fuel, such as cobs, newspapers, shavings, or anything of that kind and in five minutes you can feel the result in your rooms. Here is another great feature of this furnace which distinguishes it and puts it in a class by itself. As a red hot rapid heater, it has no equal. Fire pot of this furnace is cast iron, cast in two separate pieces as shown, to provide for expansion and contraction, etc. The diving flue creates a whirling draft which keeps all parts of the radiator drum evenly heated at all times.

THE HIGH ASH PIT

Like our Economy Furnace, we have equipped this furnace with a special high ash pit which renders burning out of the grates a practical impossibility. Each furnace furnished complete with casing, pitch bonnet trimmings, etc., including cast iron water pan, doors, etc., with the exception of the smoke pipe and shoe. These will come extra.



Estimates for Complete Hot Air Heating Plants Furnished Free of Charge. Send us Plan of Your House at once. We Claim to Furnish Better Hot Air Plants at Lower Cost than Any Other Concern in the Country. Let Us prove It TO YOU.

WHIRLPOOL DRAFT FURNACE—FOR WOOD AND SOFT COAL

No.	Size of Fire-Pot	Capacity in Cubic Feet	Shipping Weight Including Casing	Price with Double Lined Casing
17-B-434	20-in.	10000	525 lbs.	\$30.50
17-B-438	22-in.	15000	750 lbs.	37.50
17-B-442	24-in.	20000	825 lbs.	43.75
17-B-446	26-in.	35000	970 lbs.	55.25
17-B-448	28-in.	50000	1125 lbs.	62.50
17-B-458	30-in.	75000	1275 lbs.	81.50

"OUR ECONOMY FURNACE"—FOR HARD AND SOFT COAL

No.	Size of Fire-Pot	Capacity Cu. Feet	Wt. Lb.	Price with Double Lined Casing
17-D-13	20-in.	10000	700	\$33.75
17-D-14	22-in.	15000	850	40.75
17-D-15	24-in.	20000	1000	45.75
17-D-16	26-in.	35000	1200	58.50
17-D-17	28-in.	50000	1400	67.50
17-D-18	30-in.	75000	1600	87.50

CHICAGO HOUSE WRECKING CO.
 35th & Iron Streets, Chicago.



Let Us Figure on Your New Home or Barn.



WROUGHT PIPE, CASING AND BOILER TUBES

STANDARD IRON PIPE

NEW GAS, WATER AND STEAM PIPE

6-G-1. This pipe is brand new, fully tested and guaranteed.

The very best quality made, and easy to cut and thread when desired. The size of the pipe is always determined by its inside diameter. It comes in random lengths ranging from 16 to 21 feet, that is, we sell it only in full lengths just as it comes from the mill and any specifications calling for exact lengths must be charged for, extra for threading as per specifications shown below. We will, however, fill your order for lengths as nearly as possible according to your requirements. Each length threaded on both ends, fitted with coupling on one end.

The following prices are for full lengths only and where it is ordered in cut or specified lengths there will be an additional charge for the threading at both ends. (See table below.) No couplings are furnished, with pipe cut or ordered in special lengths. Our quotations below are based on latest market prices and are exceedingly low. We cannot make a firm price on pipe, and all quotations made are subject to market changes.

Our prices are for quantities up to 1,000 feet. We solicit special inquiries in large quantities. We will quote freight prepaid prices on application.

ORDER BY LOT NO. 6-G-1

Inside Diameter Inches	Outside Diam. In.	Weight, Per Ft., Lbs.	Price Per Ft., Black	Price Per Ft., Galv.	Extra Threads Each
One-eighth	0.40	0.24	\$0.02	\$0.03	\$0.02
One-quarter	0.54	0.42	.02	.03	.02
Three-eighths	0.67	0.56	.02	.03	.02
One-half	0.84	0.84	.02	.03	.02
Three-quarters	1.05	1.12	.03	.04	.02
One	1.31	1.67	.04	.06	.03
One and one-quarter	1.66	2.24	.06	.08	.03
One and one-half	1.9	2.68	.07	.10	.04
Two	2.87	3.61	.09	.13	.05
Two and one-half	2.87	5.74	.15	.21	.06
Three	3.5	7.54	.20	.27	.07
Three and one-half	4	9.00	.26	.36	.10
Four	4.5	10.66	.31	.41	.12
Four and one-half	5	12.49	.38	.49	.18
Five	5.56	14.50	.42	.55	.27
Six	6.02	18.76	.52	.71	.35

We can furnish all sizes up to 12 in. Write for prices on larger sizes.

PIPE CASINGS

6-G-7. We have a large quantity of overhauled lap welded wrought casing which is as good as new. The threads are newly cut and each length is fitted with a new coupling. It is not as heavy as the standard pipe, but it will stand equally as much and even greater pressure.

This casing can be used for almost any purpose for which standard black pipe is used, and it is especially recommended for water, gas, and oil lines. Owing to the fact that it is lighter than the standard pipe, it has finer threads. Regular casing threads 14 to the inch. In connection with this casing we can furnish a full line of standard fittings which you will find quoted under the head of "Casing Fittings." These fittings being made to work in connection with the casing.

ORDER BY LOT NO. 6-G-7

Inside Diam. Inches	Outside Diam. Inches	Approx. Weight per ft. lbs.	Price per ft.
One and three-quarters	2	2	\$0.05
Two and three-quarters	3	3	.08
Three	3 1/2	4	.10
Three and one-quarter	3 1/2	4 1/2	.11
Three and three-quarters	4	5	.12
Four and one-quarter	4 1/2	6	.17
Five and five-eighths	6	10 1/2	.25
Six and one-quarter	6 1/2	13	.35
Seven and five-eighths	8	15	.45

BOILER TUBES FOR RE-TUBING PURPOSES

6-G-9. We offer below an opportunity to purchase overhauled selected boiler tubes at prices that mean an enormous saving to you. These tubes are carefully inspected before shipment, and we guarantee them absolutely satisfactory for retubing boilers of any kind.

We ship them forward with the understanding that you will be satisfied with them, and give you the privilege, upon inspection, to return them to us, provided you do not find them up to our representations.

We cut these tubes to lengths. They have square ends, are straight, and are practically free from rust and scales.

Outside Diam. In.	Thickness Inches	Weight per ft.	Price per ft.
Two	.095	1.92	\$0.07
Two and one-quarter	.095	2.17	.09
Three	.109	3.25	.10
Three and one-quarter	.120	4.50	.11
Three and one-half	.120	4.32	.12
Four	.134	5.47	.14
Four and one-half	.134	6.17	.19
Six	.165	10.50	.26

OVERHAULED IRON PIPE

6-G-5. For steam, water, gas, oil, railroad and general purposes.

This pipe is known as "Rejuvenated" overhauled pipe, that is, it represents material that comes to us in connection with various contracts we have, and before shipment is put through our shops and thoroughly overhauled, bad ends cut off, properly re-threaded where necessary and furnished with good couplings throughout. Each length is therefore complete with threads and couplings, unless instructed to the contrary. We paint this pipe with a combination asphalt and graphite paint before shipment. It can be used for all general purposes. It is straight and free from material defects. It comes in random lengths. Prices named below are based on ordinary requirements ranging up to 1,000 feet. On application we will quote freight prepaid prices in ordinary quantities, or if you are in the market for a carload or more of this material, write for special freight prepaid prices.

All pipe sold at the following prices is on the basis of pipe furnished in random lengths and not where ordered in specified lengths. In such cases, we charge extra for cutting as per specifications shown below. Pipe ordered cut to length is not furnished with couplings. We will furnish pipe in any specified length with plain ends, subject to stock on hand, and will charge for cutting at one half (1/2) the rate we charge for extra threads; for instance,

1 inch pipe cut to 4 foot, threaded two ends; our price is 3 1/2¢ per foot, making 14¢ for the foot; plus the cost of 2 threads at 3 1/2¢ each, 7¢ making a total cost of 21¢. We could furnish a piece of pipe 1 inch diameter 4 foot long, without threads for 14¢; in other words we will charge on the basis of one-half the cost of threading.

Our stock of overhauled pipe includes practically every size known. We list, however, only the regular staple sizes and suggest when you are in the market for a large quantity of pipe or for pipe in very large sizes that you write us fully as to your requirements. We cannot furnish overhauled pipe in galvanized material. It comes in black only.

ORDER BY LOT NO. 6-G-5

Inside Diameter Inches	Outside Diam. Inch	Weight per ft. Lbs.	Price per ft. Black	Extra Threads Each
One-eighth	0.40	0.24	\$0.01	\$0.02
One-fourth	0.54	0.42	.01	.02
Three-eighths	0.67	0.56	.01	.03
One-half	0.84	0.84	.02	.02
Three-quarters	1.05	1.12	.02	.02
One	1.31	1.67	.03	.03
One and one-quarter	1.66	2.24	.04	.03
One and one-half	1.9	2.68	.05	.03
Two	2.37	3.61	.06	.05
Two and one-half	2.87	5.74	.10	.06
Three	3.5	7.54	.15	.07
Three and one-half	4	9.00	.18	.10
Four	4.5	10.66	.20	.12
Four and one-half	5	12.49	.25	.18
Five	5.56	14.50	.28	.27
Six	6.02	18.76	.35	.35
Seven	7.62	23.27	.45	.50
Eight	8.62	28.18	.58	.75

Prices on larger sizes on application

NEW BOILER TUBES

6-G-10. For tubing purposes.

We can furnish these tubes either in regular lengths or cut to length, as per schedule shown below. These tubes are absolutely A-1 in every particular. When ordered in specified lengths, add 10% for cutting.

The sizes mentioned below are all Outside Diameter.

Outside Diameter Inches	Weight per foot Inches	Price per foot	Extra for cutting contrary to sizes in stock, per cut.
One	.09	\$0.21	\$0.04
One and one-quarter	1.12	.20	.04
One and one-half	1.40	.19	.04
One and three-quarters	1.66	.14	.04
Two	1.90	.12	.04
Two and one-quarter	2.17	.14	.05
Two and one-half	2.75	.16	.05
Two and three-quarters	3	.16	.05
Three	3.33	.19	.06

Prices on larger sizes on application

We have the following lengths in stock:

SIZE - Inches	LENGTH IN STOCK
One	12-foot
One and one-quarter	10, 12 and 14-foot
One and one-half	6, 10, 12, 14 and 16-foot
One and three-quarters	2, 3, 3 1/2, 4, 5, 6, 7, 8, 10, 12, 14, 15, 16, 18-foot
Two	2, 2 1/2, 3, 3 1/2, 4, 4 1/2, 5, 5 1/2, 6, 6 1/2, 7, 7 1/2, 8, 9, 10, 11, 12, 13, 14, 15, 16, 18-foot
Two and one-quarter	10, 12, 14, 16 and 18-foot
Two and one-half	3, 4, 5, 5 1/2, 6, 6 1/2, 7, 7 1/2, 8, 9, 10, 12, 14, 16 and 18-foot
Two and three-quarters	10, 12, 14, 16 and 18-foot
Three	4, 5, 6, 7, 7 1/2, 8, 9, 10, 11, 12, 13, 14, 15, 18, 20-foot

Where you require tubes cut to different lengths than those carried in stock, we charge extra for cutting as shown above and also charge for the waste in cutting the tube from the nearest size we have in stock. For instance: If you want a 1 1/2" tube cut to 5' 4" long, we must cut this out of stock tube 6 foot long and we charge you for one 1 1/2" tube 6' long at 14¢ per foot, 84¢, and extra for cutting 4 1/2¢, making one 1 1/2" tube cut to 5' 4" long cost you 88 1/2¢.

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

READY MADE PUMP OUTFITS TO FIT YOUR WELL


The illustrations below are intended to give you an idea of how we propose to fit up, upon order, any pump in our line that you may select to suit your well of whatever kind or depth. Our pumps are described as lift pumps and force pumps, hand pumps and combined windmill and hand pumps.

Lift Pumps Will Raise Water from any depth well set down to within 20 feet of the water, but will discharge it no higher than the spout of the pump.

Force Pumps Can be Fitted for any depth well by placing the cylinder at proper distance from the water and will force the water to any desired height or distance from the pump, viz., away to the barn, to a distant field, into the house and up into the second or third story, into an elevated tank, etc.

All Three-Way Force Pumps are designed to discharge water through three-way cock underground through a line of pipe which should be laid below frost line in cold climates.

Premier Standard Pumping Outfit




Our Premier Hand Lift Pump Outfit, consists of our Leader, No. 4-D-2267 Anti-Freezing Hand Lift Pump with 3x10 inch Cylinder and 1 1/2 inch Galvanized Suction Pipe, as per different depths of wells as listed below. This pump has a revolving head so that handle can be operated at any angle from the spout. Has a large water way, powerful handle, cast brace tap pipe inside of the stand suited for the set length pipe as a protection from breakage of the cast stand by frost. The Cylinders are our very best grade cast Cylinders.

These Outfits are easily installed. We propose to furnish complete outfit for your pump, that is, of Pipe cut to length and of Pump Rod cut to length with the necessary couplings. With our illustrations as a guide in installing the pump, you will find that you will have no trouble whatever in getting your pump to work to your entire satisfaction. All outfits furnished with 1 1/2 Galv. Pipe, Galv. Pump Rod and Strainer.

- 4-D-2101. Pump and Outfit complete for 0 foot well. Weight approximately 85 pounds. Price **\$3.43**
- 4-D-2103. Pump and Outfit complete for 5 foot well. Weight approximately 98 pounds. Price **\$3.93**
- 4-D-2105. Pump and Outfit complete for 10 foot well. Weight approximately 110 pounds. Price **\$4.43**
- 4-D-2107. Pump and Outfit complete for 15 foot well. Weight approximately 120 pounds. Price **\$4.93**
- 4-D-2109. Pump and Outfit complete for 20 foot well. Weight approximately 130 pounds. Price **\$5.43**
- 4-D-2111. Pump and Outfit complete for 25 foot well. Weight approximately 170 pounds. Price **\$6.83**
- 4-D-2113. Pump and Outfit complete for 30 foot well. Weight approximately 190 pounds. Price **\$8.23**

The Premier Double Acting Under-ground Three-Way Force Pump Outfit for Any Depth Well.



This illustration shows the pump in a drilled well with dry or sub-well 4 1/2 feet deep, which should always be made over a drilled or driven well, so that easy access can be had to the cylinder for repairs. The well driller can arrange to have the casing cut to within 4 1/2 feet of the surface, or it can be cut off with a cold chisel after sub-well is dug. It can then be closed water tight around the pump with a Sanitary well cap or heavy block of wood to prevent any foreign substance from falling into the well.

With any of these deep well outfits we furnish our No. 4-E-2437 Pump, fully described on page 799 Galvanized Pipe and Rod to set the Cylinder within 15 feet of the water. Suction Pipe from the bottom of the Cylinder down into the water and strainer for bottom of the pipe. Pipe and rods are all cut and threaded with couplings. Rods shipped inside of the pipe and plainly marked as to how they are to be coupled together so that any one without experience can easily install the outfit in well of any depth. The Outfit includes one of our very best and highest priced Pumps; in fact, there is not a better Double Acting Force Pump furnished than our No. 4-E-2425. You can operate it with any kind of power, in any kind of depth well, no matter how deep and deliver water to any distance or height you wish.

The pump is enamel green with gold stripings. It is Brand New Galvanized; in fact, everything connected with this outfit is of the best. Remember 3x10 Brass Tube Cylinder furnished with this pump.

- 4-E-2141. Pump and Complete Outfit for 20 foot well. Weight about 110 pounds. Price **\$10.10**
- 4-D-2143. Pump and Complete Outfit, for 30 foot well. Weight about 160 pounds. Price **\$11.30**
- 4-D-2145. Pump and Complete Outfit for 40 foot well. Weight about 200 lbs. Price **\$12.80**
- 4-D-2147. Pump and Complete Outfit for 50 foot well. Weight about 230 lbs. Price **\$14.30**
- 4-D-2149. Pump and Complete Outfit for 60 foot well. Weight about 250 lbs. Price **\$15.80**

The three-way cock or distributing valve is operated by a cam lever at top of pump, changing the flow of water from spout of pump to the discharge pipe underground or from underground discharge to pump spout instantly while pump is working.


Bear in mind that all Windmill Pumps can also be operated by hand, but hand power pumps are not fitted with windmill connection. Therefore it is always well to buy a combined windmill and hand pump if you may expect to operate it with windmill, gasoline engine, or any kind of power any time in the future.

For Convenience to our Customers

We have arranged these outfits showing several of our most popular selling pumps, used in connection with the outfits, but should you prefer some other pump from that as shown, you will note that we give the catalog number of each pump and you may select any pump which you choose from the following pages and add this to the price of the outfit, as given below, deducting the price of the pump which we furnish regularly with this outfit and in this way it will give you the net price of your complete outfit with any pump which you may desire.

Perfection Hand Lift Pump.

Closed Top Anti-Freezing. Simple, Handy and Cheap




The accompanying illustration shows a cheap, simple and durable hand pump for ordinary open or dug wells, drilled wells or driven wells. In every case, however, the well must be arranged in such a position that you can have your cylinder within 20 feet of the water. This pump is in great demand for shallow wells where a large amount of water is required. We furnish with this 4-E-2281 Single Acting Lift, Pump, pipe for the required depths of wells as listed below, a 3x10 polished Iron Cylinder and Wire Gauge with Brass Jacket well point, as shown in this illustration. We furnish pump rod sufficient to reach to your cylinder, threaded and with proper couplings.

This pump can be used to great advantage where you wish to drive or drill a shallow well. It is necessary in all cases to have a sub-well at least 4 1/2 feet deep in which to place your cylinder. Then you can drill or drive your pipe for 20 to 25 feet below this and have a perfectly serviceable well. Prices as quoted below are for these pumps arranged in this way, but in all cases, understand, you must have your cylinder within 20 feet of the water. Prices as follows:

- 4-E-2153. Pump and Complete Outfit, with 1 1/2 inch Galvanized Pipe for 20 foot well. Weight 100 pounds. Price **\$5.85**
- 4-E-2155. Pump and Complete Outfit, with 1 1/2 inch Galvanized Pipe for 30 foot well. Weight 130 pounds. Price **\$6.70**
- 4-E-2157. Pump and Complete Outfit, with 1 1/2 inch Galvanized Pipe for 40 foot well. Weight 165 pounds. Price **\$7.60**
- 4-E-2159. Pump and Complete Outfit, with 1 1/2 inch Galvanized Pipe for 50 foot well. Weight 190 pounds. Price **\$8.50**

If brass lined cylinder is wanted add \$1.00.

Windmill and Hand Force Pump



It is to the back outlet of the pump to any tank to which you wish to supply water and by forcing it through the pipe, you may pump directly into this tank. The spout is fitted for 1 inch hose and thus you may use a hose direct from the pump. This pump can be used in dug wells as deep as 100 feet if desired, merely lower your cylinder to within 15 feet of your water. However, it cannot be used in drive wells more than 25 feet deep, as the cylinder must be at all times within 15 feet of your water.

Bear in mind that we cut and thread all pipe and pump rod furnished with this outfit. Furnish all necessary couplings. Prices given below are for complete outfits, consisting of: Pump, 3x10 Cylinder, 1 1/2 inch Galvanized Pipe and Pump Rod and Strainer.

- 4-E-2121. Pump and complete outfit for 20 foot well. Weight 135 lbs. Price **\$7.85**
- 4-E-2123. Pump and complete outfit for 30 foot well. Weight 180 lbs. Price **\$8.75**
- 4-E-2125. Pump and complete outfit for 40 foot well. Weight 220 lbs. Price **\$9.65**
- 4-E-2127. Pump and complete outfit for 50 foot well. Weight 250 lbs. Price **\$10.55**
- 4-E-2129. Pump and complete outfit for 60 foot well. Weight 280 lbs. Price **\$11.55**
- 4-E-2131. Pump and complete outfit for 75 foot well. Weight 325 lbs. Price **\$13.05**

If brass lined cylinder is wanted add \$1.00.

Metal Roofing, Siding and Ceiling


THE BEST AND MOST LASTING COVERING MADE

FLAT STEEL SHEETS.




Used for roofing, siding, ceiling and flooring; also lining grain bins.

CORRUGATED SHEETS.



Used for roofing, siding, ceiling and fire proof partitions. Strongest forms of sheet material.

"V" CRIMPED SHEETS.



Used for roofing only. Very simple style and one we recommend.

STANDING SEAM STEEL SHEETS.



Used for roofing on flat roofs or roofs of slight pitch.

Above illustrations are some of the various forms of metal sheets.

See next page for prices.

100 Years' Experience Proves

That Metal Steel and Iron Covering is the best Covering that exists for Roofing, Siding and Ceiling purposes.

The ordinary plain painted sheet iron has been in use for over a century and by every comparison has proved itself the best for all purposes, where full protection combined with durability and economy are sought. It excels all other coverings and is practically without fault.

There are many instances where iron roofs in first class state of preservation now exist, that were laid from twenty to fifty years ago and outside of painting them once every three to five years, have been practically without repair. Of course very much depends on the thickness of the iron and whether the roofing is made of painted or galvanized material. We fully described on the bottom of this page, the painted and galvanized steel sheets.

Its Merits Are Numerous

The particular advantages of the use of Metal Roofing are:

PRICE. Metal Roofing is cheaper than Wood Shingles. Our low prices put it practically on an equal basis with Felt or Tarred Roofing.

ENDURANCE. It is proven by instances on record that Steel Roofing will last as long as fifty years, while the so-called Ready Roofings, now being introduced to the public, have never had an opportunity to prove their value or lasting quality. As compared to Ready Roofing, whether rubber surfaced or felt, cost considered. Metal Roofing will outlast it five to one.

Furthermore, Patents Prepared or Composition Roofing cracks and curls with age and Tarred roofings rot and spoil. Most Ready Roofings soften in the warm air or sunshine and stick to your feet when walked upon.

FIRE PROOF. While a great many fires originate on a wood shingle roof or a felt roof, Steel Roofing is fire proof. This special point is reason enough to show the vast superiority of Steel Roofing.

LIGHTNING PROOF. The use of Metal Roofing is strongly advocated by underwriters. A building covered with iron or steel, struck by lightning, has never been known to be damaged. The reason for this is the bolt striking the metal scatters the electricity and this leaves no damaging effects whatever. Farmers who require a good roof on their barn ought to appreciate this. Take it as a rule, their barns are full of grain and hay at certain seasons of the year and cannot always be covered by insurance.

SIMPLICITY OF LAYING. Steel Roofing is easy to lay, requiring no experience. We illustrate on the following pages the simple manner of laying the different styles of Steel Roofing. Except in the case of the Standing Seam Roofing, no tools beyond an ordinary hatchet or hammer are required.

Slate Roofing requires a steep pitch and a heavy, expensive structure to support it. It weighs almost seven times as much as steel Roofing. It breaks in freezing and thawing and from heat of nearby fires. It costs twice as much and is exceedingly expensive to keep in repair.

BRICK STEEL SIDING.



Used for siding only. After applied gives the same appearance as Philadelphia pressed brick.

BEADED CEILING AND SIDING.



Used for ceiling; also siding. Gives a splendid appearance.

WEATHER BOARD STEEL SIDING.



Used for siding only. Looks exactly like wood weather board sometimes called clap-boards.

STEEL SHINGLES.



Used for roofing and siding. Comes in sheets and easily applied. A splendid roof or siding.

Above illustrations are some of the various forms of metal sheets.

See next page for prices.

WHICH TO USE? UNPAINTED, PAINTED OR GALVANIZED STEEL SHEETS.

Unpainted Steel Sheets or Plain Surface are the bare sheets, just as when rolled at the rolling mill and generally used when our customers wish to coat them with white wash or a special color of paint.

Painted Steel Sheets are the plain surfaced sheets covered with a heavy coat of pure red-oxide mineral paint. They are the standard of metal roofing and good enough for all ordinary purposes.

Galvanized Steel Sheets are rust proof. They are plain or unpainted sheets covered with a coating of zinc and tin, which makes the sheets lasting and permanent. (See description below)

WE RECOMMEND GALVANIZED STEEL SHEETS; "THEY ARE RUST PROOF."

From over thirty years practical experience in the metal roofing trade and having seen roofing of various forms under the most critical tests, we unhesitatingly recommend to our patrons Galvanized Rust-Proof Steel Roofing, in preference to the unpainted or painted steel roof and advise our patrons by all means to buy the galvanized.

HOW OUR STEEL SHEETS ARE GALVANIZED.

To our many customers, who are not familiar with the galvanizing process, we deem it best to herewith give a brief description with a crude illustration how steel sheets are galvanized.

Steel Sheets when in the process of being rolled to proper thickness, accumulate more or less scale which adheres to the sheet and in time peels off and naturally after the sheet has been painted it will carry away the coating when a scale peels off after a roof is laid, so the steel sheets before galvanized are placed in a tank, containing a solution of sulphuric acid and water which pickles the sheets and removes all the scales and foreign substances and any surface rust that might have accumulated, cleaning the sheet so that the pores in the metal are open.

The next process is taking the sheets from the pickle vat, washing them off in a tank of clean water, removing any traces of acid from the pickling process.



Above shows the method of pickling or removing the scale from steel sheets; but for lack of room we do not illustrate the washing of sheets or emerging in the bath of muriatic acid.

The third operation is placing the washed sheets into a vat containing a solution of muriatic acid which acts as a flux or a binder when the sheet is being coated with spelter, that is being galvanized.

The fourth operation is drying the sheet after being dipped in the muriatic acid bath.

In the fifth operation the sheet is dipped into a pot or tank containing a molten body of spelter (which is zinc) and a small percentage of pure tin, which sinks into the pores and readily adheres to the steel sheets, result being that the steel sheets get a heavy coating of this anti-rust metal, viz: spelter and tin, spelter being a form of zinc. When the steel sheet comes from the bath and strikes the air, it gets spangled and bright appearance. After the sheets are taken from the bath of molten metal, they are patent leveled which removes all buckles.

As described above, all our steel sheets are heavily galvanized by the hand, old style process which gives a very heavy and absolutely the best coating.



The galvanizing pot containing molten metal; heated to about 830 degrees Fahrenheit, into which sheets are dipped and coated.

SEE FOLLOWING PAGES FOR SIZES AND PRICES

NO PREVIOUS
EXPERIENCE
— IS —
NECESSARY

How To Apply Metal Coverings

HAMMER
OR
HATCHET
ONLY TOOL
USED

Easy to Lay. No experience is necessary as any ordinary man can do a good, perfect job in a short time, only tool being used is a hammer or hatchet.


We Illustrate how to apply different forms of Metal Coverings, with brief descriptions of easiest manner to lay properly and secure a water tight roof.

LAYING
CORRUGATED
SHEETS



Corrugated Steel Sheets. Begin to lay the sheets from the eave, at lower left hand corner, projecting one corrugation over side with two to four inch projection over eaves. Hammer projecting side corrugation down against edge of sheathing, nailing it in place. Nail across sheet near the eaves. Place second sheet to the left of first sheet, lapping one corrugation. Continue until row is finished, then start on the second row, and so on until job is done.

LAYING
V CRIMPED
SHEETS



"V" Crimped Steel Sheets are most simple to apply. We recommend place sheathing 4 inches apart under the "V" Crimped Roofing and by using wooden "V" sticks, you make a perfectly water proof roof.
To lay, begin at the lower corner of the eave and end of the building and lay the sheets from the eave to the ridge and nail through the crimp every 8 inches. At the end laps, use four nails to the lap.

APPLYING
BRICK SIDING
STEEL SHEETS



Steel Brick Siding is very easy to lay. First take a level and chalk line and strike level of the building. Start at the lower corner of the building, allowing 8 inch space for the corner brick finish, as shown on next page, thus allowing the trueing up of the corner in case the building is out of plumb. Then complete the first course of sheets, continuing until the job is completed, lapping each sheet so that the course of the bricks in the sheets are uniform.

APPLYING
BEADED CEILING
AND
SIDING SHEETS



Beaded Steel Sheets. This material can be applied directly to studding or if preferred, can be laid on sheathing boards. Sheets should be lapped one to two inches at end and over one bead at side. Can be applied perpendicularly or horizontally as preferred. When applied to studding or joists, these should be placed the proper distance apart. Many of our customers also lay Beading Ceiling or siding over old plaster. Gives a store a very neat appearance.

LAYING OUR
STEEL SHEET
SHINGLES



Steel Sheet Shingles We recommend wood sheathing roof before laying steel shingles or if to be laid on a wood shingle roof, it is best to remove the wood shingles. Ends of sheets are lapped over one course of the shingles. Sides of the sheets are nailed to wood "V" strips.
To lay begin at the left hand corner of eaves and end of building and lay the sheets from the eave to the ridge and nail through crimp. Nail all end laps.

LAYING
STANDING
SEAM
SHEETS



Standing Seam Steel Sheets This is the most complicated form of Steel Roofing to apply. Special tools are needed which we loan you free of charge. (See next page.) Standing Seam Sheets are generally used on roofs of very slight pitch.
To lay this roof properly, extreme care must be used. However, we send explicit instructions with every order, so that you can lay the roofing without any trouble.

ROOFING PRICES



Smashed!

**CORRUGATED
- IRON -
\$1.25 PER 100 SQ. FT.**

THIS CORRUGATED ROOFING THAT WE OFFER AT \$1.25 PER SQUARE, is our light weight, small sized sheet covering. It is new and free from defects. Sheets are all 22" wide by 24" long and is 1 1/4" corrugated. It is unpainted. Our prices quoted are for 100 square feet, not including lap and note carefully, that at this price we do not pay the freight. Our quotation is delivered on board cars at Chicago. Do not be confused by our freight prepaid offers published elsewhere in this catalog, or in our advertisements and literature.

In ordering this lot mention **7-D-15. Per 100 Square Feet**..... **\$1.25**

Read this Special Freight Prepaid Offer

Our two best selling grades of roof covering, namely, our No. 10 painted and unpainted, and our No. 18 rust proof, galvanized material. They are both guaranteed brand new, and first-class in every particular.

OUR NO. 10 STEEL COVERING.

Used for roofing, siding, ceiling, flooring and lining purposes. Light in weight but made of best quality material. Comes painted red on two sides as well as unpainted. Price is per square flat measurements and does not include lap. Comes in flat, corrugated, "V" crimped, standing seam brick siding and beaded ceiling or siding. Price per square as follows: Flat sheets, size of sheets, 24" wide by 6-8' long..... **\$1.65**

In ordering mention Lot No. 7-G-10-F.
1 1/4" Corrugated, "V" crimped, standing seam, size of sheets, 22" wide by 6-8' long..... **\$1.85**
In ordering mention Lot No. 7-G-10.

NOTE: We will furnish unpainted any of the above sheets at a reduction of 10c per square.
Be sure to designate style wanted.

OUR NO. 18 GALVANIZED RUST PROOF COVERING

Used for roofing, siding, ceiling, flooring and lining purposes. Light in weight but made of best quality of galvanized material. Prices named below are prices for 100 square feet, not including lap. Flat sheets, size of sheets 26" wide by 6-7' long..... **\$3.40**

In ordering, mention Lot No. 7-G-18F.
1 1/4" Corrugated, "V" Crimped, standing seam, size of sheets, 24" wide by 6-7' long... **\$3.50**

In ordering, mention Lot No. 7-G-18.
Be sure to designate style wanted.

Our special freight prepaid offer on the No. 10 and No. 18, as quoted above, means that for every order of two squares of the material or more, we will prepay the freight in full to points east of the Mississippi River.

ROOFING--SIDING--CEILING--SPECIAL LOW PRICES

"PAINTED STEEL SHEETS" ARE MADE, VIZ.:

GRADE No. 10. These steel sheets are light weight, brand new and perfect. Made from the best quality of steel. Covered with a heavy coat of pure red-oxide mineral paint. These light weight sheets have given our patrons universal satisfaction and are exceedingly popular, especially at the extremely low prices which make a big saving to our customers.

GRADE No. 11. Standard weight steel sheets, the same as our light weight sheets, except heavier in weight and naturally thicker. Painted with a heavy coat of red-oxide mineral paint, which preserves the steel and prolongs the life of the roof. They make a splendid roof. Will give long and satisfactory service.

GRADE No. 12. Extra heavy weight steel sheets. Made from the best quality of basic open hearth steel and they are very heavy weight. Makes an exceptionally strong and permanent roof. They are painted with red-oxide mineral paint, which preserves the steel and enhances the lasting qualities.

If you live near ocean or sea shore, use our Grade No. 18 or No. 16 Galvanized Steel Sheets.

PRESSED BRICK SHEET STEEL SIDING

Painted or Galvanized

Absolutely fire-proof. Gives the appearance of Philadelphia Pressed Brick. Size of each single brick is $2\frac{1}{2} \times 8\frac{1}{4}$ inch.



GRADE No. 10. Pressed Brick Painted Steel Sheets, light weight, 24 inch wide by 60 inch long. Per 100 sq. ft.	\$1.90
GRADE No. 11. Pressed Brick Painted Steel Sheets, standard weight, 24 inch wide by 60 inch long. Per 100 sq. ft.	\$2.35
GRADE No. 12. Pressed Brick Painted Steel Sheets, extra heavy weight, 23 to 28 inch wide by 60 inch long. Per 100 sq. ft.	\$2.70
Deduct 10 cents per square from above prices if sheets are unpainted.	
GRADE No. 18. Pressed Brick Galvanized Rust-Proof Steel Sheets, Standard weight, 24 inch wide by 60 inch long. Per 100 sq. ft.	\$3.55
GRADE No. 16. Pressed Brick Galvanized Rust-Proof Steel Sheets, extra heavy weight, 24 to 28 inch wide by 60 inch long. Per 100 sq. ft.	\$3.80

MEMO. Add 10 % to surface measurements for side and end laps.

Corner and Pilaster Finish

When laying Brick Steel Siding, we recommend using the Corner Finish, also Pilaster, as illustrated.

Lot 7-B-610. Corner Finish each face 13 inch wide by 2 ft. high. Painted, each,28c. Galvanized, each,36c

Lot 7-B-611. Pilaster, face 13 inch wide, by 2 feet high. Painted, each,29c. Galvanized, each,37c

Read Freight Prepaid Offer Printed Below

SPECIAL FREIGHT PREPAID OFFER

On Steel Siding, etc.,
as quoted on this page.

FOR THE NEXT THIRTY DAYS WE ARE MAKING THE FOLLOWING FREIGHT PREPAID OFFER.

Provided your order is for at least 200 square feet and two squares, at the prices named on this page, the Freight is prepaid by us in full to all parts of the United States east of the Mississippi River.

At an advance of 10c per square we will prepay the freight to all points lying between the eastern boundary line of the State of Colorado and the Mississippi River, except Oklahoma and Texas.

At an advance of 25 Cents per square we will prepay the freight in full to Oklahoma and Texas.

At an advance of 50 Cents per square we will prepay the freight to any point in states of Montana, Wyoming, Colorado, New Mexico, Arizona, Utah, Idaho, Washington, Oregon and California.

At an advance of 75 cents per square we will prepay the freight into the state of Nevada.

SPECIAL FREIGHT PREPAID PRICES ON ROOFING

Are shown in our special Roofing Catalog which we mail you without obligation. Also see opposite page for our wonderfully low prices on our No. 10 and No. 18 Grades.

CHICAGO HOUSE WRECKING CO.
85th & Iron Streets, Chicago.

"GALVANIZED RUST-PROOF" SHEETS ARE MADE, VIZ.:

GRADE No. 18. Galvanized rust-proof, standard weight steel sheets. These standard weight sheets are all galvanized by the hand-dipped process, giving them a heavy coating of galvanizing. They are unpainted although after the roof is laid you can for appearance paint these sheets if you so desire.

As explained on the previous pages, galvanized sheets will outlast from three to four times that of painted sheets and they are the only kind of a sheet that we recommend using if you live near salt water. The coating on them is just as heavy as our grade No. 18 mentioned hereafter and we have no hesitancy in recommending our grade No. 18, standard weight steel sheets for use under the most trying conditions for roofing, siding or ceiling.

GRADE No. 16. Galvanized rust-proof, extra heavy steel sheets, made of the best quality basic open hearth steel and galvanized with a heavy coat of pure spelter and shipped unpainted. These galvanized, rust-proof, extra heavy steel sheets, are largely used on warehouses and factories. They make a perfect, permanent and most satisfactory roof.

NOTE.—The numbers referred to have nothing to do with the thickness or gauge of iron but are used for convenience, so we can correctly fill your order and know just what you are ordering.

BEADED CEILING AND SIDING SHEETS.



The beads or corrugations are $\frac{1}{2}$ inch wide by $\frac{1}{4}$ inch deep, spaced 3 inch from center to center. Used in stores, factories, halls and public buildings.

Add 10 per cent to surface measurements for side and end laps.

GRADE No. 10. Beaded, Painted Steel Sheets, Light Weight, 22 inches wide, in 2 to 8 ft. lengths. Per 100 sq. ft.	\$1.90
GRADE No. 11. Beaded, Painted Steel Sheets, Standard Weight, 22 inch wide, in 2 to 8 ft. lengths. Per 100 sq. ft.	\$2.35
GRADE No. 12. Beaded, Painted Steel Sheets, Extra Heavy Weight, 22 to 28 inch wide, in 4 to 8 ft. lengths. Per 100 sq. ft.	\$2.70
Deduct 10c per square from above prices if sheets are ordered unpainted.	
GRADE No. 18. Beaded, Galvanized Rust-Proof Steel Sheets, Standard Weight, 22 to 24 inch wide, 2 to 7 ft. lengths. Per 100 sq. ft.	\$3.55
GRADE No. 16. Beaded, Galvanized Rust-Proof Steel Sheets, Extra Heavy Weight, 26 inch wide, in 4 to 10 ft. lengths. Per 100 sq. ft.	\$3.80

WEATHERBOARD SHEET STEEL SIDING.



PAINTED OR GALVANIZED

Made of best quality open-hearth steel. Used for Siding only. Looks exactly like wood weather boarding, sometimes called clap-boards.

28 Gauge Painted Weatherboard Steel Siding, extra heavy weight, in sheets 24 inch wide, by 5 to 10 ft. long.	
28 Gauge Galvanized Weatherboard Rust-Proof Steel Siding, extra heavy weight, in sheets 24 inch wide, by 5 to 10 ft. long.	

MEMO. Add 10 per cent to surface measurements for side and end laps.

WRITE FOR PRICES

Extras for Steel Roofing, Siding and Ceiling

All prices for Coverings are made without following articles. Price Per square

7-B-600. Gal. Nails, sufficient to lay 100 sq. ft. Roofing	5c
7-B-601. Lead Washers, quantity sufficient to lay one square.	10c
7-C-602. Wooden "V" Sticks for "V" Crimp and Shingles	10c
7-C-603. Wooden "V" Sticks for 3 "V" Crimped Roofing	20c
7-B-604. Tin Cleats, used when applying Standing Seam Roofing	10c
7-B-605. Dry Paint, red enough to cover one square	3c
7-B-607. Ready Mixed Roofing Paint, in buckets of 5 to 10 gallons, red or black. One gallon is sufficient to cover 200 square feet of surface, one coat. Price per gallon in quantities of 5 gallons or more.	44c



"Our Roofing Book"

Guide For Roofers, Builders, Owners, Architects.

If you intend covering any of your buildings with either steel or prepared roofing, you should send at once for our Great 1911 Roofing Book.

It illustrates, describes and quotes wonderful bargains in Steel Roofing, Prepared Roofing, all styles of Siding and Ornamental Ceiling and Roofers' Sundries.

Our prices enable you to save 30 to 50 per cent and the book contains simple instructions of how to lay Roofing, so that you can make a big saving on labor.

We are Fashion Headquarters for New Ideas

ORNAMENTAL METAL CEILINGS AT 50% SAVING!

Used extensively in Churches, Hotels, Cafes, Halls, Stores, etc. It adds 100% to the appearance of any room in which it is used, reduces insurance and is fire and dust proof.

Metal Ceilings are the most economical—they eliminate all danger of falling plaster—they can easily be kept clean. We ship them painted with a priming coat of grey which will save you the necessity of giving them this priming coat. One coat of paint will give you a beautiful finish. A fresh coat of paint each year will change the whole appearance of the room.

Turkish Pattern

Illustration shows OUR DESIGN No. 1272 Turkish Pattern popular and handsome.

As an example of the low price we are quoting on Metal Ceilings, we furnish this design complete with ceiling plates, border, cornice, mitres, and nails; each piece marked showing where to go and with blue prints to set up by, viz:

Design No. 1272. Metal Ceiling complete for room 15x20, cost about **\$15.00**


Design No. 1272. Metal Ceiling complete for room 20x40, cost about **\$36.00**

Design No. 1272. Metal Ceiling complete for room 25x60, cost about **\$60.00**

For delivered prices send us sketch of your room, and we will make you a freight delivered price and send you choice of about 20 various designs from which you can make your selection. See below for other designs.


Send for our Special Roofing catalogue in which we show many designs, and explain how easy it is to apply to the ceiling.

No experience needed as any handy man can put up the Metal Ceiling in a very short time.




Metal Ceiling Design No. 1272

"Roman" Pattern



Metal Ceiling Design No. 8265.


Send us a sketch of your room with measurements and we will quote freight prepaid price that will save you at least 50 per cent.



Wall Design No. 1157.

For other designs of Metal Ceiling, write for our special Roofing Catalogue, it will save you money. This book is sent free upon request

"Greek" Pattern



Metal Ceiling Design No. 8047.

ORNAMENTAL METAL CEILING

This is a very attractive pattern and is easily put on; comes in one size sheets only. Size: width, 24 inches; length, 96 inches; made with dustproof beaded lap joints, which makes a neat, workmanlike job and can be applied by any one. No special tools required. The use of this ceiling will greatly improve the appearance of your store room and enable you to rent it to better advantage.



Showing Ceiling No. 8045.

You can finish it in any color desired. If you desire a border strip, we can furnish a 6-inch strip of the same pattern to break the ceiling and wall joint, which makes a very much better appearing job. Border is not furnished nor included in price quoted in the ceiling, but is charged for extra. (Shipped direct from factory in Central Ohio.) (See 7-C-8046 for border for this design.) 7-C-8045. Price per 100 square feet **\$2.40**



Showing Border No. 8046.

Above we show 4-inch Border Strip or Cornice Projects on Ceiling 3-inches, Drops on Wall 4-inches which we can furnish with ceiling design 8045. By using this you can give your room a finished appearance.

7-C-8046 4 inch Border, per running foot **6c**

EXPANDED METAL LATH

For use in any building where wood lath is ordinarily used. Contraction and expansion caused by moisture are directly responsible for plaster cracking—this is entirely overcome by the use of Metal Lath.

This Lath is used extensively in making cement coated houses and is much superior to wood lath. Sheets are 18 inches wide by 96 inches long. There are 15 sheets to a bundle and 20 square yards to a bundle.

	Plain	Painted
7-D-1112. 27 gauge .114 c	per sq. yd. .13 c	
7-D-1113. 26 " .13 c	" " .15 c	
7-D-1114. 25 " .14 c	" " .16 c	
7-D-1115. 24 " .15 c	" " .17 c	


CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

110 Write for our prices on Blacksmith Outfits.



"RAWHIDE RUBBER ROOFING" \$1²² AND UP PER ROLL

**RAWHIDE
RUBBER ROOFING
IS FIRE, HAIL AND
WEATHERPROOF.
NOT AFFECTED
BY HEAT OR COLD.
CAN BE SAFELY
USED IN ANY
CLIMATE.**



**MADE IN
ONE, TWO
AND THREE PLIES
GUARANTEED
FOR SIX, NINE
AND TWELVE YEARS.
RECOMMENDED
BY FIRE
UNDERWRITERS.**

YOU DO NOT TAKE A CHANCE IF YOU BUY RAWHIDE RUBBER ROOFING.

There is a reason and it is not a trade secret why rawhide roofings are superior to all others. You are entitled and we want you to know just how rawhide roofing is made and why it will outlast all others. All Prepared Roofings are made on a wool felt base, which should be manufactured from woolen rags, but unfortunately felt can be mixed with paper and the cost reduced to the extent of enabling the unscrupulous manufacturer putting out an inferior roofing that to all superficial appearance is as good as honestly made roofing. Such felt will not take as much saturation as an absolutely pure wool felt and lacks the long fiber that gives it wear, resisting qualities and toughness that is so necessary to the life of roofing.

"RAWHIDE ROOFING IS AS TOUGH AS ITS NAME"

Because It is Made of Pure Wool Felt and Saturated with Pure Asphalt.

Pure asphalt saturation is absolutely necessary to make a strictly high grade lasting roofing. It is here that manufacturers have another chance to lower the grade, and you will only know it when your roof shows early signs of wear and proves generally unsatisfactory. Do not condemn Prepared Roofing on account of having had an experience of this kind. If you have never used prepared roofing or are skeptical, don't pay for experience—it is not necessary. We safeguard your interests. You cannot go wrong if you buy rawhide roofing. It is guaranteed to be saturated with pure Asphalt.

Rawhide Roofing contains absolutely no tar, oil or any other substitutes for asphalt. Tar cracks in cold weather and melts under the heat of the summer sun. Oil quickly evaporates, leaving the roofing dry and brittle. Therefore, it is bound to buckle and crack. There is no satisfactory substitute for Asphalt.

We control the entire output of Rawhide Roofing and keep close watch to see that not an ounce of inferior material is used. Every car of felt and asphalt is put under the most rigid test and is rejected if found in any way inferior to our standard, which means, one hundred per cent pure.

We Buy, Pay For and Accept Only the Best Material, That is Why You Get the Best Roofing Possible to Produce When You Order Our Rawhide Roofing.

Why we are able to supply a better roofing at a lower price than you can possibly buy elsewhere: Our ability to dispose of immense quantities makes it possible to negotiate very favorable contracts. All manufactured lines have their seasons. Our output is assured and our capital is large, enabling us to contract for material sufficient for the entire year, when the market is low and the manufacturer needs both money and business to keep his factory running. There is another and bigger advantage in being able to contract in this manner, and that is, the factories not being crowded with orders, more care is taken in the manufacture of material and insures a uniform run and properly seasoned roofing. In addition, enables us to make prompt shipments.

The appearance of the surface of Our Rawhide Rubber Roofing is like rubber. This surface is made by a heavy coat of strictly pure Asphalt being applied to the saturated wool felt and passed between heavy hot rolls under a great pressure, the surface being exactly the same on both sides.

The cost of laying Rawhide Roofing is a very small item. In fact, a knife and a hammer are the only tools required.

Rawhide Rubber Roofing can be laid over shingles and put on flat or pitched roofs.

Each roll contains 108 square feet, sufficient to cover one square, including laps.

We Furnish Free large head nails and sufficient Asphalt Cement for laps packed securely in each roll of our Rawhide Rubber Roofing.

We guarantee that every roll of Rawhide Rubber Roofing is made on an all wool felt base of the highest grade that is saturated and surfaced with pure asphalt and does not contain coal tar. If laid in accordance with our simple directions we will replace without cost to you any Rawhide Rubber Roofing that may prove defective within the following terms of years:

1-Ply Rawhide Rubber Roofing, Six Years. 2-Ply Rawhide Rubber Roofing, Nine Years. 3-Ply Rawhide Rubber Roofing, Twelve Years.

We do not impose any impossible conditions. All that is required is that it be laid smoothly and properly nailed and cemented at the laps. Anyone can do this. Our guarantee does not cover any roofing that becomes torn or is blown off by the wind.

Rawhide Roofing will outlast our guarantee by many years. With proper care Rawhide Rubber Roofing will last longer than any other rubber surfaced roofing now on the market. Write for free samples of this Guaranteed Roofing.

13-G-50. 1 Ply Rawhide Rubber Roofing, per roll of 108 square feet, complete with large head nails (no caps needed) and liquid asphalt cement for laps. Weight about 35lbs. Price per roll **\$1.20**

13-G-51. 2 Ply Rawhide Rubber Roofing, per roll of 108 square feet, complete with large head nails (no caps needed) and liquid asphalt cement for laps. Weight about 45lbs. Price per roll **\$1.40**

13-G-52. 3 Ply Rawhide Rubber Roofing, per roll of 108 square feet, complete with large head nails (no caps needed) and liquid asphalt cement for laps. Weight about 55lbs. Price per roll **\$1.70**

WEIGHT PREPAID at the above prices to states of Ohio, Indiana, Illinois, Iowa, Wisconsin and Michigan. Write us for delivered prices to other states.

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

See Our Exact Color Reproduction of Rugs

RAWHIDE STONE FACED

"GOLD MEDAL" ROOFING

13 PER ROLL
2108 SQ FT

Our Guarantee is that the materials used in the construction of Rawhide Stone Faced Gold Medal Roofing are pure and first class in every particular, and that it contains no coal tar.

If laid in accordance with our simple directions we will replace any of this roofing that proves defective in quality any time within **TWENTY YEARS**.

We Pay The Freight

At \$2.13 per square we prepay the freight in full to all railroad stations in the states of Illinois, Indiana, Iowa, Ohio, Wisconsin and Michigan.

Write for our freight prepaid prices to other states.

Special Features

This roofing will resist Fire and Lightning. Requires no paint when first laid, and will give long and lasting service.

LARGE HEAD NAILS AND

LIQUID ASPHALT CEMENT

FREE

Here is a roofing which, in our judgment, will outwear and out-last any other Ready Roofing on the market.

It is the result of years of careful thought and experiment on the part of manufacturers who are recognized in the Roofing field as being peers in their line.

We consider it the finest material to use on Homes, Barns, Ware-houses, Stores and in fact on buildings of every kind where long service is desired, and where economy must be given consideration. The Price is surely reasonable enough—the quality is the best—Read carefully the description which follows.

How Made "RAWHIDE STONE FACED GOLD MEDAL ROOFING" is made from the finest and best long fibre woolen felt obtainable. It is of an extra heavy weight and strength. Each of these fibres is carefully and mechanically saturated with the greatest water proofing compound known to the Roofing World—Pure Asphalt.

After the process of Pure Asphalt saturation is completed it is given an additional mechanical treatment requiring great time and care to make it still more water proof and durable.

It then passes to a bath of especially prepared high-grade coating which protects the fibres from the weather wear. Thereafter it is coated on both sides with a fine powdered marble, which gives the beautiful appearance shown in illustration and so much admired by those who have purchased it in the past. This coating also materially adds to its fire proofing qualities.

The expensive nature of the coating used to protect the long fibre woolen felt is one of the real causes for its lasting qualities. This coating is free from any oils that will discolorize the beautiful surface.

Great care is used in the manufacture of this Roofing, as it is necessary that the fine marble surfacing is so well imbedded into the coating as to make it difficult to remove or rub off this marble effect.

Good For 20 Years We strongly recommend the purchase of this Roofing, it will add to the appearance of any building—it is of the highest quality manufactured—it is manufactured from Pure Asphalt it is far superior and less expensive to apply than shingles or any other kind of roofing—it will retain indefinitely its beautiful appearance—its water proofing qualities are the best—the direct rays of the sun have but little effect because of the careful refining to which the asphalt coating is subjected—there is nothing which can be drawn out of the saturation that will discolorize the fine marble finish—our **TWENTY YEAR GUARANTEE** protects you.

It is Easy to Lay No previous experience is needed in laying this roofing. Simple, yet complete instructions are sent with each roll. It can be laid either horizontally or up and down. It requires no painting after it is put on the roof. We furnish all needed supplies, that is, cement for the laps and large headed nails to lay.

Each Roll Complete We furnish this roofing in one thickness and one weight only, and that the best.

It is put up 108 square feet to a roll, each roll contains large headed nails and cement. It weighs approximately 58 pounds to the roll. It is 32 inches in width.

13-C-211. Rawhide Stone Faced "Gold Medal" Roofing, put up in rolls containing 108 square feet sufficient to lay 100 square feet or (one square), complete with large head nails and liquid cement for laps. Approximate weight 58 pounds to the roll. Price per roll complete.

\$2.13

Freight Prepaid at above price to States of Illinois, Indiana, Iowa, Ohio, Wisconsin and Michigan. Write us for delivered prices to other states.

RAWHIDE PEBBLE COAT ROOFING \$1.83 AND UP PER ROLL

Never Requires Painting or Recoating

Not Affected by the Heat or Cold and will not Blister or Crack

ABSOLUTELY FIRE PROOF

GUARANTEED FOR 10 YEARS

A BROAD STATEMENT BUT A TRUE ONE—Rawhide PEBBLE Coat Roofing is Much More Serviceable than any other style of Gravel, Grit, Flint or other kinds of rough surfaced felt roofings on the market.

RAWHIDE PEBBLE COAT ROOFING IS SURFACED WITH LAKE MICHIGAN PEBBLES Washed, screened and of uniform size. Other roofing, surfaced with crushed Granite, Grit, Marble, Slate, rough irregular size Gravel, cannot commence to stand the wear nearly as well as RAWHIDE PEBBLE COAT ROOFING.

The Reason Why

BECAUSE THE PEBBLE COAT SURFACING IS NOT MADE OF CRUSHED MATERIAL, having sharp edges that cut into the felt and thereby weaken the fiber. So that you will fully understand the superiority of RAWHIDE PEBBLE COAT ROOFING, it is necessary for you to know how roof surfacing is applied, which is as follows: The saturated felt is run through a special heavy hot coating asphalt. The surfacing is then put on and the roofing passes through heavy rolls under great pressure, imbedding the surfacing into the asphalt. Your own good judgment will tell you if surfacing has sharp edges (and all crushed material has), that it is bound to cut through the asphalt into the felt. In addition to this, it is impossible to crush it to a uniform size. Therefore, the surface is not smooth or evenly covered. The finer particles do not adhere as well to the asphalt and soon wear off and the result is an unsatisfactory roof.

HOW MADE Rawhide Pebble Coat Roofing is built in three separate layers—the first layer being extra weight pure wool felt, saturated with pure asphalt—the second layer being asphalt and the third being a pebble coat finish. Put up in rolls of 108 square feet; complete with large head nails, and liquid cement for laps.

EASY TO LAY You can lay Pebble Coat, Rawhide Roofing as easily as any other prepared Roofing. It is made with an improved smooth edge, 24 inches wide, without the pebble coat surface. When laid, it has a solid pebble coat surface. The seams can scarcely be seen.

WE GUARANTEE Rawhide "Pebble Coat" Roofing for 10 years. All the materials that enter into the construction of this Roofing, are the same high grade as used in Rawhide Rubber Roofing. We guarantee that it does not contain any coal tar. If laid in accordance with our simple directions, we will replace without cost to you, any Rawhide Pebble Coat Roofing that may prove defective within 10 years from date of purchase.

WE DO NOT IMPOSE ANY IMPOSSIBLE CONDITIONS. All that is required is that it be laid smoothly and properly nailed and cemented at laps. Any one can do this. Our guarantee does not cover any roofing that becomes torn or is blown off by the wind.

RAWHIDE PEBBLE COAT ROOFING WILL LONG OUTLAST OUR GUARANTEE. With proper care it should easily last from fifteen to twenty years.

13-B-53. 3 Layer Rawhide Pebble Coat Roofing, put up in rolls containing 108 sq. ft., sufficient to lay one square (100 sq. ft.), **\$1.83** furnished complete with large head nails (no caps needed) and liquid cement for laps. Weight, 60 lbs. Price per roll. **FREIGHT PREPAID** at the above prices to states of Ohio, Indiana, Illinois, Iowa, Wisconsin and Michigan. Write us for delivered prices to other states.

"Rubberized Galvo" Roofing 90c to \$1.20 Per 108 Sq. Ft.

Our "Rubberized Galvo" Roofing is of superior quality. It is practically the same as our Rawhide Rubber Roofing, being made from pure asphalt and positively contains no coal tar. It is furnished direct from the manufacturers and is a regular grade made by them with exception of that instead of a continuous piece as Rubber Roofing generally comes, it is put up 2 or 3 pieces to the roll, commonly termed, "mill ends." This does not in any sense injure same from the standpoint of service. The fact that it is not made in one piece, does not lessen its wearing qualities or make any difference in its appearance.

We guarantee it to be a strictly high grade class of Roofing. Owing to confidential reasons, we cannot tell you the name of the manufacturers as it would lessen the sale of their regular brands.

The quality of this roofing is far superior to most of the Rubber Roofing that is being generally offered. This gives you an opportunity of buying otherwise perfect roofing at prices that mean a big saving to you.

"Rubberized Galvo" Roofing has a rubber surface on both sides and is pliable and wear resisting. It is weather and lightning proof and can be used in any climate, as it is not affected by heat or cold, acids, alkali or gases and will not taint rain water.

When roof has been laid about one to two years, it should have a coating of our "Protecto Asphalt Paint," which will protect the roof and cause it to last for many years.

It is adapted for roofs of any kind and the 3 ply can be laid safely over shingles. No tools required to lay, beyond a hammer and a pocket knife. Each roll is complete with large head nails and liquid cement for laps. It is put up in 1 and 2 square rolls, sufficient to lay 100 or 200 square feet with a liberal allowance for laps.

13-B-56. ONE-PLY. Suitable for barns, sheds and dwellings. Weighs about 35 pounds per square. Furnished complete with large head nails and sufficient cement for the laps. Price..... **90c**
13-B-57. TWO-PLY. For dwellings, factories, warehouses and for all general roofing purposes. Weighs about 45 pounds per square. Furnished complete with large head nails and sufficient cement for the laps. Price..... **\$1.05**
13-B-58. THREE-PLY. Used on any kind of building where a heavy, durable roofing is required. Weighs about 55 pounds per square. Furnished complete with large head nails and sufficient cement for the laps. Price..... **\$1.20**

FREIGHT PREPAID at the above prices to the states of Ohio, Indiana, Illinois, Iowa, Wisconsin and Michigan. Write for delivered prices to other states.



Money Saving Prices in Sheathing Paper, Felt and Roofing Sundries

"PREMIER" RED ROSIN SIZED SHEATHING PAPER.



We guarantee the quality of our Red Rosin Sized Sheathing Paper to be absolutely the best. It is rosin sized by a special process and is vermin and damp proof. Put up in rolls 36 inches wide containing 500 square feet.

WEIGHT AND PRICE PER ROLL.

13-G-10. 20 lbs. **37c**
13-G-11. 30 lbs. **55c**
13-G-12. 40 lbs. **72c**

"PERFECTION" TABBED STRAW BOARD SHEATHING.



This is a very popular sheathing paper and is made of heavy straw board thoroughly saturated with distilled coal tar. It is put up in rolls 32 inches wide and weighs about 16 lbs. to the 100 sq. ft. Rolls weigh from 50 to 75 lbs.

13-B-18. Price per lb. **1 1/2c**

"PERFECTION" TARRIED FELT



Made of the best grade of wool felt, thoroughly saturated with distilled tar. Warranted to unroll freely without sticking.

Grade No. 1 is our heaviest and is used as a sheathing paper for all general purposes; also between floors for deadening purposes.

Grade No. 2 is of medium weight and makes an excellent sheathing paper.

Put up in rolls 32 inches wide, weight approx. 60 lbs. each.

13-G-13. Grade No. 1. No. of sq. ft. to the roll 225.

Price per roll... **99c**
13-G-14. Grade No. 2

No. of sq. ft. to the roll 450. Price per roll... **99c**

"PREMIER" WOOL DEADENING FELT



Made of the very finest selected grade of wool felt, soft and pliable. It is used to deaden sound between floors and walls. We recommend that it be used under every floor as it adds greatly to the warmth of the building. Put up in rolls 36 inches wide.

13-G-19. Weight per square yard, 1 lb.; approximate 50 square yds. to roll. Price per roll **\$1.19**

13-G-99. Weight per square yard, 1 1/2 lbs.; approximate 75 sq. yds. to roll. Price per roll **\$1.55**

"PERFECTION" SLATER'S FELT.



This is the ideal sheathing paper and is also used largely under metal and slate roofs. It can be used in place of Red Rosin or any other of the sheathing papers we offer.

It is put in rolls 36 inches wide, each roll containing 500 sq. ft. Weight per roll approximately 35 pounds.

13-B-15. Price per roll... **69c**

"PERFECTION" ASBESTOS ROLL MILL BOARD.



Same as mill board in sheets except put up in rolls 36 inches wide. It is made a little softer than the sheets and can be used for the same purposes as the sheet mill board. Adapted to fire proofing ceilings over boilers or other surfaces that are in close contact with excessive heat. Comes in rolls weighing 50 lbs.

Thick Inches Wt. per 100 sq. ft.

13-B-27. 1-32 6 lbs.

13-B-28. 1-16 8 "

13-B-29. 3-32 10 "

13-B-30. 1-8 14 "

Price per lb. **3 1/4c**

"PREMIER" BLUE PLASTER BOARD.



We guarantee this to be the best grade of Plaster Board manufactured. It is a strong, tough paper used under clap boards for sheathing and on walls in place of plaster. When used for this purpose it is tacked to the studding and wall paper can be placed over it, making a very satisfactory body. It is put up in rolls 36 inches wide.


13-G-16. Contains 250 sq. ft. Weight 30 lbs.

Price per roll... **65c**

13-G-17. Contains 500 sq. ft. Weight 60 lbs.

Price per roll **\$1.25**

"PERFECTION" ASBESTOS BUILDING FELT.



This material is made of asbestos and is fire proof. Is used for linings of floors, partitions and for wrapping hot water pipes, etc. Put up in rolls 36 inches wide. Weighs approximately 10 lbs. to 100 sq. ft. Weight of roll 50 lbs.

13-B-20. Price per roll **\$1.59**

EAGLE BRAND COATING



A black, protective coating manufactured by a special process from a refined pitch fluxed with mineral oil. One gallon covers about 100 square feet and dries

in 24 hours. Eagle Brand is especially valuable for preserving felt roofs or surfaces exposed to water or dampness. It can be used with good result on any exposed surface and will keep your roof in good shape. We recommend its use in connection with prepared tarred felt roofing. It is not as durable as our Protecto Asphalt Paint which we guarantee to be the best preservative paint on the market.

Price per pkg. 13-B-32. 1 gal. ... **\$0.30** 13-B-35. 10 gal. ... **\$1.68**
13-B-33. 2 " ... **.48** 13-B-36. 25 " ... **2.59**
13-B-34. 5 " ... **.95** 13-B-37. 50 " ... **4.75**

ROOFING PITCH.

THE VERY BEST GRADE OF REFINED COAL TAR ROOFING PITCH. Used by the largest roofing contractors for coating tarred felt roofs. Will also be found very desirable for coating foundations to effectually keep out the moisture. Can also be used to excellent advantage in painting anything that is to be placed in the ground. In addition to being water proof, it acts as a preservative. Comes in solid form and requires melting so that it can be applied to the surface. Sold only in full barrels weighing 300 or 400 pounds.

13-B-38. ROOFING PITCH. Price per 100 pounds. **65c**

PREMIER REFINED ASPHALT.

USED FOR RE-COATING GRAVEL, METAL OR COMPOSITION ROOFS.



Also for coating reservoirs and cisterns and water proofing the foundations of buildings. This Asphalt is 99 per cent pure and melts at 208 degrees Fahrenheit. Compared with coal tar, it has much greater covering surface. One ton contains about 250 gallons as against 166 gallons to one ton of coal tar. For all water-proofing work, such as foundations, it requires about 30 pounds to the square and for recoating roofs about 40 pounds to the square. When melted, this Asphalt can be easily applied.

13-B-49. PREMIER REFINED ASPHALT. PRICE PER HALF BARREL CONTAINING ABOUT 250 POUNDS. **\$3.75**

13-B-49. PREMIER REFINED ASPHALT. PRICE PER BARREL CONTAINING ABOUT 400 POUNDS. **\$6.00**

SEND FOR OUR SPECIAL ROOFING CATALOG

in which we show one hundred different styles and grades of roofing and quote net delivered prices on same.

If you have a building which you wish to cover or a room for which you wish ceiling, send us dimensions or diagram of same and we will be glad to quote you.

NEW GROCERY CATALOG every 60 days—Is Your Name on our mailing list?

RAWHIDE OILED, INSULATED SHEATHING.

This as well as all material bearing this brand is of the very highest quality. We know that in our Rawhide, we are offering the very best building paper that was ever put on the market. It is absolutely Air, Water and Vermin Proof, and will undergo the severest heat tests without becoming hard or brittle. It is put up in rolls weighing approximately 25 lbs. and guaranteed to contain 400 square feet. Is 36" wide.

13-C-100. Rawhide Building Paper, Per roll. **\$1.00**



ROOFING BRUSHES.

The kind used by the roofing trade, and the best brush for the purpose manufactured. Heavy, stiff bristles, properly cemented into head of selected, air dried hard maple. Each knot is very full and wire bound. Can be used for applying Asphalt, Pitch and roof coating.

13-B-47. 2-Knot Brush. Price. **37c**

13-B-48. 3-Knot Brush. Price. **67c**

EVER READY ROOF MENDER.

Can be used in repairing leaks in any kind of roofing. Guaranteed to save its cost many times over. An elastic compound in stick form for mending leaks in all kinds of roof, tin, iron, felt, slate, etc., also for eaves troughs, iron or wood tanks and many other places where leaks occur. It is always ready for use and will not dry out. Made in black only.

13-B-42. Price each. **\$0.20**
Price for six. **1.10**

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Galvanized Eave Troughs, Conductor Pipe, Gutters and Fittings

Galvanized Eaves Trough.

Improved Slip Joint Style.



7-G-401.

Can be put together without soldering. When ordering be sure and state whether right or left hand is wanted. Right hand will discharge water at the right hand end of trough. Left hand discharges water at left end of trough. Made of No. 28 gauge galvanized steel and furnished in 10 foot lengths only. We do not supply cut lengths. Slip joint is on one end of each length.

Size, inches	3 1/2	4	4 1/2	5	6
Wght. per lgth.	5 1/2	6	6 1/2	7 1/2	8 1/2
Price per Lgth	\$0.25	\$.28	\$.32	\$.33	\$.40
Price per crate	250 feet..\$5.75..	6.75..	7.50..	7.75..	9.50

Galvanized Corner Miters.


These corners are made with inside and outside bead. Be sure to order according to number.



7-G-403. Outside corner slip joint, right hand.
7-G-405. Outside corner slip joint, left hand.
7-G-407. Inside corner slip joint, right hand.
7-G-409. Inside corner slip joint, left hand.

Size, inches	3 1/2	4	4 1/2	5	6
Price, each	\$0.12..\$.13..\$.14..\$.14..\$.17				

Galvanized Conductor Pipe.



Made of No. 28 gauge, strictly first quality galvanized sheets and guaranteed to be the best on the market.
Galvanized Corrugated Conductor Pipe, made in 10 ft. lengths, without cross seams. Will not burst when full of ice. Furnished only in full lengths.

Size of Conductor to use with Eaves Trough.

Size of Eaves Trough, inches	3 1/2	4	4 1/2	5	6	7
Size of Conductor, inches	2	2	2	3	3	4

7-G-411. Galvanized Corrugated Conductor.

Size, inches	2	3	4	5
Wt. per length lbs.	4 1/2	6	8	10
Price per length	\$0.27..\$.32..\$.43..\$.54			
Price per crate 250 ft.	\$6.50..	7.75..	10.50..	13.25

GALVANIZED LAP JOINT EAVES TROUGH.



Made of No. 28 gauge steel in 10 foot lengths. Lap Joint Eaves Trough must be soldered at joints.

7-G-413.

Size, inches	3 1/2	4	4 1/2	5	6
Price per Lgth	\$0.22..\$.26..\$.29..\$.31..\$.36				
Price per crate	250 ft. . 5.50..	6.50..	7.00..	7.25..	8.50

METAL HIP SHINGLES.

These shingles are much more ornamental than the wood hip caps and are easily laid. Size of shingle 4x9 inches.



7-G-415. Painted tin hip shingles.
Price each\$0.02
Price per 100 1.10
7-G-417. Galvanized hip shingles.
Price each\$0.02
Price per 100 1.50

ADJUSTABLE OUTLET.



★7-G-419. These fittings consist of a short piece of about 6 inches of eaves trough, with slip joint on one end and drop outlet soldered on bottom close to the other end to connect to the conductor pipe. The end is closed with slip joint end cap, but is not included in prices quoted.

★7-G-419. Adjustable outlet to fit eaves trough.

Size, inches	3 1/2	4	4 1/2	5	6
Fitted for Conductor, inch.	2	2	3	3	4
Price each	\$.09..\$.10..\$.11..\$.11..\$.12				

END CAP SLIP JOINT.

★7-G-421. Made in one piece. Used to close ends of eaves trough and adjustable outlets.

Size Inches	Price each
3 1/2	5c
4	5c
4 1/2	6c
5	6c
6	7c



RAIN WATER CUT OFF. For Corrugated Conductor.

★7-G-422.

Size Inches	Price each
2	14c
3	16c
4	22c



ELBOWS AND SHOES.




No. 1-45° No. 2-60° No. 4-90°
Galvanized Corrugated.
When ordering always mention number.
★7-G-423. Conductor Elbow Angle No. 1.
★7-G-425. Conductor Elbow Angle No. 2.
★7-G-427. Conductor Elbow Angle No. 4.

Size Inches	Price each	Price per doz.
2	6c	\$0.65
3	7c	.75
4	9c	.85
5	16c	1.70

CONDUCTOR SHOE.

★7-G-429.

Size Inches	Price each
2	7c
3	8c
4	12c
5	20c



CONDUCTOR FUNNEL.

★7-G-431. Conductor Funnel are used for running two Conductors into one outlet. Size given is size of lower sprout.

Size inches	2	3	4	5
Price each	15c	20c	25c	35c



CONDUCTOR STRAINERS.

★7-G-433. Galvanized Wire Conductor Strainers. To be placed in the outlet of Eaves Trough, preventing leaves, etc., from stopping up the Conductor. Size given indicates the size of the outlet Strainers will fit.

Size, inches	2	3	4	5
Price, each	4c	5c	6c	9c
Per dozen	40c	55c	72c	\$1.00

WIRE EAVES TROUGH HANGERS.

★7-G-435. Made of galvanized wire, and are the most simple and satisfactory hanger on the market.

Size Inches	Price per doz.
3 1/2	12c
4	12c
4 1/2	13c
5	15c
6	16c



PERFECTION CONDUCTOR PIPE FASTENERS.

★7-G-437. Suitable for wood or brick buildings. Superior to any other style of conductor pipe hooks or fasteners. Made of heavily galvanized twisted wire. The principal features are, that owing to the construction of this hanger it keeps the pipe from coming in contact with the building, making it possible to paint behind the conductor pipe preventing the moisture from rotting the siding and corroding the pipe. They are easily applied; simply require nailing and tightening up with a common plier. There is no danger of splitting the siding as is the case when using the conductor hooks that have to be driven in.




Size of Conductor Pipe (Inches) 2 3 4 5 6
Gauge of Wire..... 12 12 11 10 9
Price per dozen..... 12c 14c 16c 19c 22c

★7-G-439. Tinned Conductor Hooks for Corrugated Conductor.

CONDUCTOR HOOKS.

Size Inches	Price per doz. for Wood	Price per doz. for Brick
2 1/2	14c	18c
3	20c	22c
4	30c	35c
5	40c	45c



GALVANIZED ROOF GUTTERS.



Made of No. 28 gauge steel, beaded and formed with patent slip joints. Anyone can put it on. Requires no soldering. Made in 10 ft. lengths in one piece. Illustration shows slip ends in position. Prices are for gutter only. Regular Corrugated Conductor is used in connection with this gutter. Sold only in full lengths.

7-G-441. Size 14-inch girt, roll 3 inches high, flat surface 9 inches. Wt. per length 10 lbs. Price per length.....60c

7-G-443. Size 20-inch girt, roll 4 inches high, flat surface 13 inches. Wt. per length 13 lbs. Price per length.....85c

GALVANIZED SLIP ENDS.

★7-G-445. To be used with Galvanized Roof Gutter. For 14 inch gutter. Price, each 15c



7-G-447. For 20 inch gutter. Price each ... 17c

GALVANIZED SPOUT ENDS.

To be used with Galvanized Roof Gutter.

★7-G-449. For 14 inch gutter. Price each 16c

★7-G-451. For 20 inch gutter. Price each 18c



GALVANIZED BOX GUTTERS.



Made of No. 28 gauge galvanized steel and furnished in 10 foot lengths, both ends open.

Style J.

	Girth	Wt. per 100 Ft.	Size	Depth	Foot	Price per
7-G-501.	18 inch.	108 lbs.	6 inch.	5 1/2 inch.	11c	
7-G-503.	20 inch.	120 lbs.	7 inch.	6 1/2 inch.	13c	
7-G-505.	24 inch.	144 lbs.	9 inch.	8 inch.	15c	

Extra for any of the above sizes one end closed, 35c

GALVANIZED BOX GUTTER MITERS.



	For	Price each,
7-G-507.	For 18-inch girth.	45c
7-G-509.	For 20-inch girth.	53c
7-G-511.	For 24-inch girth.	60c

STRAP HANGERS FOR BOX GUTTERS.



Be sure to mention girth.

★ 7-G-122. Price each 2c

GALVANIZED RIDGE ROLL. Plain Apron.



A neat water proof cap for the ridge of roofs. Is made in 10 foot lengths and can be used on shingles or any other kind of roofing. We do not furnish cut lengths.

Size of Roll	Width of Apron	Wt. per 10 Ft.	Price per
Inches	Inches	Lbs.	Length
7-G-513....1 1/2	2	8	27c
7-G-515....2	3	10	30c
7-G-517....3	3 1/2	14	50c

GALVANIZED RIDGE ROLL. With Corrugated Apron.



Made to be used on Corrugated Iron Roofs. Size of corrugations 1 1/2 and 2 1/2 inches. In ordering be sure and state width of corrugation. Comes in 10 foot lengths. We do not furnish cut lengths.

Size of Roll	Width of Apron	Girth	Price per
Inches	Inches	Inches	Length
7-G-519....2	2 1/2	10	65c
7-G-521....3	3 1/2	14	75c

GALVANIZED ROOF CRESTING.



This Cresting we can furnish, either 8 or 10 inches high. The part over the roll is made of double thickness metal and is therefore very durable as well as ornamental. This Cresting comes in 5 and 10 foot lengths.

7-G-523	Price per ft. 8 inches high.....	8c
7-G-525	Price per ft. 10 inches high.....	11c

BLOCK FINIALS.



★ 7-G-527 Used in connection with roofing cresting, and can also be used with the 1 1/2 and 2 inch Ridge Roll. Height is 10 1/2 inches.

Price each..... 20c

VALLEY TIN.



Made of High Grade Tin Plate in a continuous length, locked and soldered. Full lengths are 50 feet long. Will furnish any length desired. Painted one side.

Width	Wt. per	Price	Price
Inch	Roll	50 ft. Roll	Per Lineal Ft.
7-G-529....14	30 lbs.	\$1.75	4c
7-G-531....20	48 lbs.	2.35	6c
7-G-533....28	60 lbs.	3.40	8c


GALVANIZED VALLEY.

Made of No. 28 Gauge Galvanized Steel.

7-G-535.	Length of roll 25 feet.	
7-G-537.	Length of roll 50 feet.	\$1.20
7-G-539.	Galvanized Valley, cut to desired length. Price per lineal foot.....	6c

TIN SHINGLES AND FLASHINGS.

Made of roofing tin. Used for repairing old roofs and making tight joints around chimneys.




7-G-541.	Size 5x7 inches. Wt. per 100 pcs., 11 1/2 lbs.	
	Price each.....	1c
	Price per 100.....	70c
7-G-543.	Size 7x10 inches. Wt. per 100 pcs., 20 lbs.	
	Price each.....	\$0.02
	Price per 100.....	1.40

TINNERS' SNIPS.

Best quality. Hand forged Tinner's Snips, fully guaranteed.

★ 7-G-545.	2 1/2 inch cut.	
	Price each.....	79c
★ 7-G-547.	3 inch cut.	
	Price, each.....	89c



TINNERS' SNIPS.

Cast steel Tinner's Snips. Intended for light work, such as cutting stove pipe or other light sheet iron.

★ 7-G-549. 3 inch cut. Price each..... 20c



SHEET TIN.

I. C. Roofing Plates. Full weight, with coating evenly distributed. Prices subject to market changes.

Size inches	7-G-551.	
No. of sheets in box.....	14x20	112
Weight per box.....		100 lbs.
Price per box.....		\$4.75
Price per sheet.....		.06

Size inches	7-G-553.	
No. sheets in box.....	20x28	112
Weight per box.....		200 lbs.
Price per box.....		\$9.50
Price per sheet.....		.10

GALVANIZED ROOF VENTILATORS.

Made of Heavy Galvanized Iron.



For removing smoke, dust, impure air from halls, churches, schools, factories, stables, etc.; prevents down draft and improves smoky chimneys.

★ 7-G-555.	4-inch... Wt. about 2 lbs.	\$0.60
★ 7-G-557.	6-inch... Wt. about 4 lbs.	1.15
★ 7-G-559.	7-inch... Wt. about 5 lbs.	1.37
★ 7-G-561.	8-inch... Wt. about 8 lbs.	1.56
★ 7-G-563.	9-inch... Wt. about 8 1/2 lbs.	1.78
★ 7-G-565.	10-inch... Wt. about 9 lbs.	1.93
★ 7-G-567.	12-inch... Wt. about 12 lbs.	2.25

GALVANIZED LINTEL CORNICE



Made of heavy galvanized iron, used for covering wood or iron lintels, making a neat finished job.

Height	Projection	Girth	Per Foot
7-G-569.....4 1/2	3 1/2	12	8c
7-G-571.....7	4 1/2	16	10c
7-G-573.....8	6	20	12c

GALVANIZED SHEET METAL WORK—CORNICHE—SKYLIGHTS



Strongly made of heavy galvanized iron.

A Cornice adds 50% to the appearance of a building, and at the extremely low price at which we are offering a cornice you cannot afford to omit it from your building plans. If desired we can furnish these cornices with raised block letters, for which there would be an additional charge. Advise us what you want and we will be glad to quote you prices. The prices quoted below are for the plain cornices, per running foot, and do not include the end blocks as shown in illustration. These are quoted below separately.

Height	Projection	Weight per ft.	Price
		Crated Lbs.	Per Foot
7-G-593....16	10	5	\$0.72
7-G-594....20	12	6	.92
7-G-595....24	12	6 1/2	1.06
7-G-596....30	15	7 1/2	1.42

GALVANIZED END BLOCKS.

For Use with Cornice Above Described.

Height, Inches.	Price.
7-G-597. 16 and 20.....	\$3.85
7-G-598. 24 and 30.....	4.12



Style 11 Single Pitch Skylights



Style 21 Double Pitch Skylights

Prices quoted are for Skylights complete with the Ribbed Skylight Glass Ventilators only with sizes required. Approximate weight Skylights with Glass, 6 1/2 pounds per square foot.

Size from out to out	Single Pitch	Double Pitch	Hipped
Size 3x3 feet.....	Style 11	Style 21	Style 31
7-G-575	\$4.60	\$6.25	\$6.75
7-G-577	3x4	6.20	7.30
7-G-579	3x5	7.25	8.55
7-G-581	3x6	8.55	10.60
7-G-583	4x4	7.50	9.35
7-G-585	4x5	8.75	10.45
7-G-587	4x6	10.65	12.50
7-G-589	4x8	13.95	14.75

Odd and larger sizes at the following prices:


Single Pitch	20 sq. ft. or less.....	63c per sq. ft.
	21 " " or more.....	58c " " "
Double Pitch	20 sq. ft. or less.....	75c per sq. ft.
	21 " " or more.....	66c " " "
Hipped	20 sq. ft. or less.....	76c per sq. ft.
	21 " " or more.....	67c " " "

If Skylights furnished with 1/2 inch Ribbed and Wired Glass, add..... 22c per sq. ft.




Style 31 Hipped Skylights

GALVANIZED WINDOW AND DOOR CAPS



Cap-7-G-591



Cap-7-G-592

We make Window Caps and Door Caps of any design you may desire.

For Prices, send us blue print or drawing showing style and size. It is always necessary to have the width of each door and window on which cap is to be used, in order to quote intelligently.

\$1.35 BUYS 5 FOOT HERCULES TROUGH

HEAVIEST AND STRONGEST

FOR HOGS, SHEEP, HORSES AND CATTLE
Especially Adapted for BREEDERS and STOCK RAISERS



Thickness of ordinary trough
Actual thickness of Hercules Trough.

These Troughs are made of Heavy Galvanized Steel painted before shipment—the cross bar and legs are of heavy 1 inch bar steel riveted securely to trough—spaced close enough to keep animal from crowding—no animal can break nor injure it if they stand or walk on it—will last a life time—can be set any place—no need of building platform to stand on—impossible to tip—are sanitary—can easily be cleaned on account of having round bottom, will not rust—Freezing will not affect them—ice can be chopped out without injuring the trough.

Order No.	Width	Depth	Length	Weight	Capacity	Price Each	Price each in lots of 6
8-F-305.	12	6	5	40	10 gal.	\$1.35	\$1.25
8-F-307.	12	6	8	60	16 gal.	2.50	2.35
8-F-308.	12	6	10	75	20 gal.	2.95	2.75
8-F-325.	14	7	5	45	11½	1.60	1.50
8-F-328.	14	7	8	70	18	2.75	2.50
8-F-330.	14	7	10	90	22½	3.00	2.75

Note—Freight on 50-lb. Troughs is the same as 100 pounds. Better make up your order for 100-pound shipment, or more.

"Hercules" Boiler Steel Troughs for Sheep, Horses and Cattle

No.	Width Inch.	Depth Inch.	Length Feet.	Weight Lbs.	Price.
8-D-164.	19	9	5	65	\$ 5.15
8-D-166.	19	9	8	95	6.70
8-D-168.	19	9	10	115	8.00
8-D-170.	24	12	5	115	7.50
8-D-172.	24	12	8	165	9.80
8-D-174.	24	12	10	190	11.25
8-D-176.	28	14	5	125	7.95
8-D-178.	28	14	8	185	10.30
8-D-180.	28	14	10	210	11.85
8-D-182.	30	20	5	180	9.90
8-D-184.	30	20	8	250	12.60
8-D-186.	30	20	10	290	14.60
8-D-188.	32	16	5	140	9.55
8-D-190.	32	16	8	205	12.15
8-D-192.	32	16	10	230	13.95
8-D-194.	36	18	5	180	10.10
8-D-196.	36	18	8	250	12.95
8-D-198.	36	18	10	290	14.90

MADE SAME AS ABOVE TROUGHS EXCEPT IN LARGER SIZES

CROSS BARS ARE HEAVY 1" BAR STEEL CATTLE TROUGH BOUND WITH STEEL ANGLES



\$5.15

Special sizes to order. Also special design for scalding dogs. Write us what you want. State size and send sketch.



\$5.50 Stock and Storage Tanks

With Heavy Flat Galvanized Hoops and Lugs

Durability For many years Washington Fir has been used throughout the Northwest in the manufacture of tanks of all kinds, also in the construction of large water flumes, and on account of its wonderful durability it is fast becoming the recognized standard tank timber. The great Railroads throughout the country are using Washington Fir Tanks almost exclusively, and this after thorough tests in competition with all kinds of timber that have heretofore been used, and it has been demonstrated that the Washington Fir is superior to any other timber for tank construction.

These Tanks Cannot Be Injured by animals kicking or wagons running into them, which destroys steel Tanks.

Construction Made of strictly clear Washington Fir, with Heavy Galvanized Steel Hoops and Lugs. This is a feature that you will not find in tanks of other manufacture. Galvanized hoops and lugs are used owing to the fact that they are practically imperishable, and will outlast the ordinary black hoops, therefore in furnishing the galvanized hoops and lugs on our Washington Fir Tanks, it makes a combination that will defy the ravages of time and weather.

The Joints of our Tanks Both bottoms and staves are jointed on a special machine, which enables the operator to cut the joint absolutely true, making a much better joint to hold water than the tongued and grooved joint. Owing to the nature of Washington Fir, the saw, when cutting the joint, leaves the edges slightly fuzzy, and, when the edges are clamped together and drawn up tight by the hoops, this joint is of a velvet appearance and makes a first-class packing.


No Tongues or Grooves to Break Off Tongued and grooved joints depend on the swelling of the wood to make them water tight and are liable to be damaged in transit or may be accidentally split off in erecting the tank, hence we claim that the joint used in the construction of our tanks is much better.

Size 1½ in. stock is dressed to about 1½ in. thick and 2 in. stock is about 1¾ in. thick. On tanks 8 feet or larger in diameter we recommend that they be made of the 2 in. stock.

Free Sample On request we will be pleased to mail you sample of Washington Fir. We ship tanks Knock Down direct from factory located in Wisconsin.

Order Number.	Diameter, Feet.	Length of Staves, feet.	No. of Hoops.	Capacity, Gallons.	Weight, 1½ inch., lbs.	Price, 1½ inch.	Weight, 2 inch., lbs.	Price, 2 inch.
4-F-2001	4	2	2	138	200	\$ 5.50	260	\$ 7.65
4-F-2003	4	4	3	277	300	9.10	390	11.75
4-F-2005	5	2	2	221	225	7.19	263	9.10
4-F-2007	5	5	4	575	550	14.79	715	17.70
4-F-2009	6	2	2	324	300	9.00	390	11.40
4-F-2011	6	2½	2	421	375	10.15	487	12.75
4-F-2013	7	2	2	446	400	10.29	520	13.70
4-F-2015	7	2½	2	580	475	12.42	627	15.50
4-F-2017	8	2	2	588	455	12.90	591	16.00
4-F-2019	8	2½	2	764	485	15.00	630	18.30
4-F-2021	10	2	2	931	600	18.00	780	22.90
4-F-2023	10	2½	2	1210	700	20.90	910	24.20
4-F-2025	6	6	4	1100	695	19.30	1903	24.30
4-F-2027	6	8	5	1490	900	26.00	1170	32.50
4-F-2029	8	6	4	1950	975	27.90	1267	33.60
4-F-2031	8	8	5	2700	1150	35.80	1495	44.75
4-F-2033	10	10	7	5400	1375	56.30	1787	71.30
4-F-2035	12	10	7	7600	1750	60.95	2275	79.30
4-F-2037	12	12	10	8900	2000	64.76	2600	102.80

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.



If You Want Garden Hose Write Us.

BARGAINS IN MIXED, GALVANIZED AND COMMON WIRE NAILS

75c BOX

33 $\frac{1}{3}$ Lbs.

\$1.35 BOX

66 $\frac{2}{3}$ Lbs.

\$1.50

PER KEG

100 Lbs.

THESE SIZES FIT
EVERY PERSON'S
NEED.



An assortment of wire nails, ranging in sizes from 3's to 40's, all standard, clean wire nails, sizes that are being used every day. An assortment of wire nails is something that every man, no matter what his position should have as nails are used a dozen times every day and this is the way to buy them. The same quantities bought at retail in the regular way would cost twice what we are asking for them. When making a shipment you will often find that it is impossible to make up sufficient weight of other material. We are therefore offering these nails in three different size packages: 33 $\frac{1}{3}$ pound boxes, 66 $\frac{2}{3}$ pound boxes and 100 pound kegs. With this range of weights it will be very easy for you to get just such an assortment of nails as you will need. We guarantee that we will give an assortment of regular standard nails which are being used every day, and no matter what your business you will find that this assortment of nails will come in handy. Prices as follows. Don't forget to include this bargain in your next order.

4-BM-4051.	33 1-3 lb box of mixed nails. 3d to 40d.	75c
4-BM-4053.	66 2-3 lb box of mixed Nails. 3d to 40d.	\$1.35
4-BM-4055.	100 lb. keg of mixed Nails. 3d to 40d.	\$1.50

**A BIG
SNAP**

GALVANIZED WIRE NAILS


**ORDER AT
ONCE**

Here's the biggest bargain ever offered in Nails. The Bargain of Bargains. 10,000 Kegs of genuine Galvanized Wire Nails—will outlast all other kinds. Put up regularly in kegs, on which we quote the following prices:

Lot No. 2-BM-4000.	10d Nails. Per 100 lbs.	\$2.00
Lot No. 2-BM-4002.	8d Nails. Per 100 lbs.	\$2.10
Lot No. 2-BM-4004.	6d Nails. Per 100 lbs.	2.15
Lot No. 2-BM-4006.	Shingling Nails. Per 100 lbs.	3.00
Lot No. 2-BM-4008.	Roofing Nails. Per 100 lbs.	3.50

Where ordered in smaller quantities, our prices are 50c per 100 lbs. higher. No order filled at these prices for less than 25 lbs. Get in now and don't lose this grand opportunity.

CEMENT COATED WIRE NAILS



They Will Save You Money. Because---

**They Drive Easier
They Hold Better**

**They Last Longer
They are Waterproof**

**They Do More
They Cost Less**

CEMENT COATED wire nails will last longer than common wire nails. It is a well-known fact that being CEMENT COATED they will hold better than any other nail made. They actually will not work loose, neither will they rust. Think of what it means to use nails which cannot be loosened.

CEMENT COATED are cheaper than common wire nails, last longer, and hold better than any nail made. "CEMENT COATED" are $\frac{1}{8}$ -inch shorter than common wire nails, and are made of one gauge lighter stock. Thus you will see that, although we guarantee that there is exactly the same number of nails by actual count in a keg of "CEMENT COATED" the kegs weigh only about 80 lbs. Thus showing you a saving in freight of about 20%. Besides they are cheaper. Remember, however, that we guarantee that each keg contains the same number of nails as a keg of common nails. We know that a satisfied customer is our best advertisement, and we know if you buy a keg of "CEMENT COATED" that you will be more than pleased, and always use them. Sold in full keg lots only.

PRICES AS FOLLOWS

4-BM-4059. Sizes	60d	50d	40d	30d	20d	10d
Number of Cement Coated Nails to Keg	1,100	1,300	1,800	2,400	3,100	6,600
Price of Cement Coated Nails, per Keg	\$1.95	\$1.95	\$1.95	\$1.95	\$1.95	\$2.22
Price of Cement Coated Finish Nails, per keg						2.37
Price of Cement Coated Casing Nails, per keg						2.27

WIRE NAILS AT MONEY SAVING PRICES FOR OUR CUSTOMERS

These prices are for our customers only when bought in connection with other material. Prices are always subject to market changes. Should nails go up we charge you accordingly, should they go down we give you the advantage of the drop in price. We do not sell less than a keg of nails at the keg price.


4-BM-4001. COMMON WIRE NAILS					
Size	2d	3d	3d	6d	8d
No. of nails to keg		54,300	29,800	17,900	10,100
Price, per keg	\$2.80	\$2.50	\$2.40	\$2.30	\$2.20
Price, per lb.	4c	4c	3 $\frac{1}{2}$ c	3 $\frac{1}{2}$ c	3 $\frac{1}{2}$ c
4-BM-4003. WIRE FINISH NAILS.					
Size	4d	6d	8d	10d	
No. of nails to keg	6,600	3,100	2,400	1,800	1,100
Price per keg	\$2.15	\$2.10	\$2.10	\$2.10	\$2.10
Price per lb.	3c	3c	3c	3c	3c
4-BM-4005. WIRE CASING NAILS.					
Size	4d	6d	8d	10d	
No. of nails to keg					
Price, per keg	\$2.80	\$2.70	\$2.50	\$2.40	\$2.30
Price, per pound	4c	4c	4c	4c	3 $\frac{1}{2}$ c
4-BM-4007. WIRE FLOORING NAILS.					
Size	4d	6d	8d	10d	
No. of nails to keg					
Price, per keg	\$2.80	\$2.70	\$2.50	\$2.40	\$2.30
Price, per pound	4c	4c	4c	4c	3 $\frac{1}{2}$ c
4-BM-4008. WIRE FENCING NAILS.					
Size	4d	6d	8d	10d	
No. of nails to keg					
Price, per keg	\$2.80	\$2.70	\$2.50	\$2.40	\$2.30
Price, per pound	4c	4c	4c	4c	3 $\frac{1}{2}$ c
4-BM-4009. FINE WIRE OR LATH NAILS.					
Size	2d	3d	4d	6d	
No. of nails to keg					
Price, per keg	\$3.10	\$2.70	\$2.40	\$2.30	\$2.20
Price, per pound	4c	4c	4c	4c	3 $\frac{1}{2}$ c
4-BM-4013. GALVANIZED SHINGLE NAILS.					
Size	3d	4d	6d	8d	
No. of nails to keg					
Price, per keg	\$3.75	\$3.50	\$3.40	\$3.30	\$3.20
Price, per pound	4 $\frac{1}{2}$ c	4 $\frac{1}{2}$ c	4 $\frac{1}{2}$ c	4 $\frac{1}{2}$ c	4 $\frac{1}{2}$ c



ALL-STEEL "FIREPROOF" BUILDINGS

**\$91.00 BUYS
ALL STEEL GARAGE
READY TO ERECT.**

**STORAGE SHEDS
AUTO GARAGES
BLACKSMITH SHOPS, Etc.**



GENERAL SPECIFICATIONS AND DESCRIPTION OF MATERIAL WE FURNISH FOR THE CONSTRUCTION OF OUR STEEL BUILDINGS.

Material List

Our list of material is complete. Plans will show exactly where each piece of material is used in the building, each item being numbered and correspondingly numbered on the plans. All material is properly punched and fabricated. It does not require an expert to erect these buildings; any one handy with tools can do it.

Steel Frame

We furnish the complete steel frame consisting of steel trusses, columns, steel roof purlins, girths, braces, plates, bolts and rivets, all material properly punched, made up and ready to erect.

Roofing and Siding

We supply the required quantity of extra heavy corrugated galvanized roofing and siding, $1\frac{1}{2}$ or $2\frac{1}{2}$ " corrugation, of such lengths as are necessary, rivets or bolts, lead washers and steep strips for fastening roofing to steel stringers; also galvanized corrugated apron ridge roll for ridge of roof.

Easy to Erect

It does not require an expert to erect these buildings. With the complete information and the clear drawings which we furnish, anyone reasonably familiar with building construction or handy with tools can erect them.

Be sure and get our prices before purchasing.

Stock Sizes and Prices of Steel Buildings we can Furnish for Quick Shipment

18-C-500.	18 ft. wide,	24 ft. long,	11 ft. 9 in. high at eaves....	\$ 342.50
18-C-501.	20 ft. wide,	30 ft. long,	11 ft. 9 in. high at eaves....	425.00
18-C-502.	24 ft. wide,	40 ft. long,	11 ft. 9 in. high at eaves....	585.00
18-C-503.	24 ft. wide,	50 ft. long,	13 ft. 9 in. high at eaves....	700.00
18-C-504.	30 ft. wide,	50 ft. long,	11 ft. 9 in. high at eaves....	795.00
18-C-505.	30 ft. wide,	60 ft. long,	15 ft. 6 in. high at eaves....	945.00
18-C-506.	40 ft. wide,	75 ft. long,	15 ft. 6 in. high at eaves....	1,347.00
18-C-507.	40 ft. wide,	100 ft. long,	17 ft. 6 in. high at eaves....	1,750.00
18-C-508.	50 ft. wide,	100 ft. long,	15 ft. 6 in. high at eaves....	2,285.00
18-C-509.	50 ft. wide,	150 ft. long,	15 ft. 6 in. high at eaves....	3,300.00
18-C-510.	50 ft. wide,	200 ft. long,	19 ft. 0 in. high at eaves....	4,300.00

Above quotations are net, f. o. b. cars Chicago.

Sash and Doors

We furnish all doors and sash as specified. The doors we can furnish in wood or made of heavy galvanized corrugated steel, reinforced with angle iron frame and fitted with rollers, track rail and door latches. We also supply the necessary framing lumber for the sash and doors. This material we furnish only in stock sizes and lengths; same must be cut and fitted on job.

All material we furnish you for the construction of these buildings is brand new.

Free Plans

We furnish our customers complete drawings, specifications and bills of material. All we require is a deposit of \$2.00. This amount will be placed to your credit if you purchase the building.

Our steel buildings are designed and the plans are prepared by expert steel engineers, great care being used to design the best construction as simple as possible so any one reasonably familiar with building construction can erect them.

Any information required will be furnished by our Engineering Department.

FIRE-PROOF STEEL GARAGES, COMPLETE READY TO SET UP

Our fire-proof garages are constructed entirely of steel. The frame is made of heavy angles and channels, cut to the proper lengths, punched and marked. Any one, handy with tools can set it up or take it down in a few hours.

The covering which we furnish for these garages is made of No. 24 Gauge Heavily Galvanized Corrugated Material, $1\frac{1}{2}$ inch corrugation. This construction makes these buildings absolutely fire-proof.

Each garage is furnished complete with a double door in the front end, a small door in the rear end, two windows on each side and all other necessary material required for this construction with the exception of the flooring.

We furnish complete erecting plans free with order.

Stock Sizes, Ready for Immediate Shipment:

No. 18-C-512.	10 ft. wide, 16 ft. long, 10 ft. high ...	\$ 91.00
No. 18-C-513.	12 ft. wide, 16 ft. long, 10 ft. high ...	105.00
No. 18-C-514.	12 ft. wide, 20 ft. long, 10 ft. high ...	117.50

Delivered prices quoted on application

PLANS FOR \$2.00

Plans, specifications, bills of material furnished for \$2.00 which amount will be allowed on the purchase price of the building.



STEEL GIRDERS:

We fabricate any of the Girders shown below. When writing for prices please send sketch, stating the height, length, style and quantity of Girders required. The workmanship is of the highest character, material the best and our prices will bring your trade.



- Style A.** Above Girder is made of 2-"I" Beams with Bolts and Separators.
- Style B.** Composed of 2-"I" Beams and 1 Channel with Bolts and Separators.
- Style C.** Made of 1-"I" Beam and 1 Channel and angle riveted as shown with Bolts and Separators.
- Style D.** Made of 1 Channel and angle bolted to lower outside of channel. Used over doors and windows.




Style E.

Style E. Girder is composed of 2-"I" Beams of uniform size provided with bolts, separators, rosettes and beam blocks. Used to carry brick work on store fronts.

Merchants Steel Bars.

We carry a large stock of round square and flat steel bars. Also twisted bars or concrete workers. For prices, state quantity, size, shape and length



Style K

Style L

Style M

ILLUSTRATIONS OF THE FRAMING OF BEAMS AND GIRDERS TO CARRY FLOORS



Style O

Style P

Style V

Style S

STRUCTURAL STEEL SHAPES



Steel "I" Beams
Illustration shows "I" Beams which are made in standard sizes, ranging from 3 to 24 in. high.



Steel Channels
Cut shows Steel Channels, which are made in standard sizes ranging from 3 to 15 in. high.



Steel Angles
Illustration shows Angle Steel, made with equal and unequal legs, ranging from 1x1 to 8 x 8 in.



Steel Tees
Cut shows Steel Tees made with equal and unequal legs, ranging from 1x1 to 4x4 in.

No. 18-A-21.

STEEL TUBULAR COLUMNS

"A New Feature in Steel Columns."

To meet the growing demand for a low priced Steel Tubular Column, we are now prepared to furnish a column of this kind, which will meet with the most varied requirements.

We furnish these columns made of Standard Pipe, also of Light Tubing.

HOW TO GAIN ADDITIONAL STRENGTH.

The columns made of light tubing are generally used, where it is intended to fill them with concrete. Any column can be filled with concrete at a very small expense and when so filled they are stronger than any cast iron column of the same size.

The standard pipe columns can be treated in a like manner, although where it is intended that they be filled with concrete, we recommend using the light tubular columns, which are less expensive and will answer just as well as the pipe columns under these conditions.

The light tubular columns are very desirable where a light load is to be carried and in such an event it is not necessary to fill them with concrete.

SPECIAL CAPS AND BASES.

In connection with these columns we can furnish special recessed cast iron caps and bases. These caps and bases are made of 3/4 inch and 1 inch thick cast iron plates, on which there is ring cast, forming a recess, into which the ends of the column rest, forming a very satisfactory and substantial bearing.

NOTE. Contractors and architects should keep in mind these columns as it means a big saving in both first cost and freight.

Price quoted on Columns does not include Caps and

Cap and Base. Bases.

No. 18-B-22.

NEW STD. PIPE COLUMNS.

Inside Diam.	Outside Diam.	Weight per ft.	Price per ft.
3 in.	3 1/2 in.	7 1/2 lbs.	\$0.22
3 1/2 in.	4 in.	9 lbs.	.32
4 in.	4 1/2 in.	10 1/2 lbs.	.36
5 in.	5 1/2 in.	14 1/2 lbs.	.50
6 in.	6 1/2 in.	18 1/2 lbs.	.65
8 in.	8 1/2 in.	28 lbs.	1.07

USED TUBULAR COLUMNS.


Inside Diam.	Outside Diam.	Weight per ft.	Price per ft.
2 1/2 in.	3 in.	3 1/2 lbs.	\$0.08
3 1/2 in.	4 in.	3 1/2 lbs.	.10
3 1/2 in.	4 in.	5 1/2 lbs.	.12
5 1/2 in.	6 in.	10 lbs.	.25

SPECIAL RECESSED CAPS AND BASES FOR TUBULAR COLUMNS.

DESCRIPTION.	Size of Plates	Price Per Set.
For 3 in. Standard Pipe and for 3 1/2 in. O. D. Casing.	7x7x8	\$1.00
For 3 1/2 in. Standard Pipe and for 4 in. O. D. Casing.	7x7x8	1.00
For 4 in. Standard Pipe and for 4 1/2 in. O. D. Casing.	8x8x8	1.25
For 6 in. Standard Pipe and for 6 1/2 in. O. D. Casing.	10x10x17	2.25
For 8 in. Standard Pipe.	12x12x17	3.00

At times, we have used Pipe Columns at 25% less above price.

CAST IRON COLUMNS



18-B-90.

18-B-91. Round Columns

18-B-92.

18-B-93. Sq. Col.

18-B-94. Plaster

We have an immense stock of all sizes and patterns of Cast Iron Columns, both round and square. (See above designs)

For prices, write quantity, diameter, length and style of column; we will quote low prices for prompt shipment.

SIZES AND PRICES OF CAST IRON COLUMNS.

18-B-90.	5 in. diam., 1/2 in. metal cast column, price.....	\$1.00 per foot
18-B-91.	5 in. diam., 1 in. metal cast column, price.....	1.00 per foot
18-B-92.	5 in. diam., 1 in. metal cast column, price.....	1.05 per foot
18-B-90.	6 in. diam., 1 in. metal cast column, price.....	1.45 per foot
18-B-91.	6 in. diam., 1 in. metal cast column, price.....	1.45 per foot
18-B-92.	6 in. diam., 1 in. metal cast column, price.....	1.50 per foot
18-B-93.	4 in. face, 1 in. metal, 6 in. deep cast column, price	1.25 per foot
18-B-93.	5 in. face, 1 in. metal, 6 in. deep cast column, price	1.40 per foot
18-B-93.	6 in. face, 1 in. metal, 6 in. deep cast column, price	1.55 per foot
18-B-93.	6 in. face, 1 in. metal, 8 in. deep cast column, price	1.95 per foot

Prices on other sizes upon application.

Miscellaneous Steel Products at 30% Saving

STEEL TRUSS RODS AT BARGAIN PRICES

Style I. 18-B-23. Style I. Lateral rods with welded eyes and turn buckles in center.

Style J. 18-B-24. Style J. Truss rods threaded on both ends, fitted with nuts, and with turn buckles in the center.

18-B-25. Style K. Plain Rods threaded on both ends, fitted with nuts.

18-B-26. Style L. Anchor Bolts used for foundations, etc., made up in any length and of any size iron. Prices on application. Be sure and state length and diameter of bolt.

Write size, style and quantity truss rods needed for Bargain Prices.

JOIST ANCHORS

For Prices on Joist Anchors, write us quantity, style and lengths, when we will quote low prices.

18-B-11. (Twisted Joist Anchors) 18-B-10. (Plain Joist Anchors) 18-B-18. (Pin Strap Anchors)

18-B-27. Star Cast Iron Washers. (Write for prices.)

Diameter of Bolts, Inches	1 1/2	1 3/4	2
Diameter Washers, Inches	6	9	10
Thickness, Inches	1	1 1/2	1 3/4

18-B-28. Standard Cast Washers. (Write for prices.)

Diameter of Bolt	1 1/2	1 3/4	2
Outside Diameter	2 3/4	3 3/4	4 3/4
Thickness, Inches	1 1/2	1 3/4	1 3/4
Weight in lbs.	1 1/2	2 1/2	3 1/2

PLAIN CAST IRON SIDEWALK COVERS

18-B-34. Style Q. Plain sidewalk covers and frames for cement sidewalk. Frame measures 25 inches square; cover measures 20 inches square; depth of flange 2 inches; weight of frame and cover combined 135 pounds. We have approximately 200 of this lot which have been used, but in strictly first-class condition.

\$2.75

SIDEWALK COAL HOLE COVERS

18-B-30. Style M. Plain Cover; diam. 18 ins. weight, 24 pounds. Price, each. **\$1.25**

18-B-31. Style N. Bull's Eye Glazed covers; 8 lights; diam. 18 ins. weight, 25 lbs. Price, each. **\$1.85**

SIDEWALK LIGHTS

18-B-35. Style R. For use over basements, slides, sidewalks, elevators, etc. Send sketch showing opening or area to be covered and we will quote prices.




Illustration Showing Chute Open

STANDARD AUTOMATIC COAL CHUTES

The Standard Automatic Coal Chutes are designed to be placed in the cellar wall the same as a window for depositing coal, wood or other articles into the basement. No modern building is now complete without a heating system that requires the storage of fuel in the basement and if you pass fuel through an ordinary cellar window it soon becomes disfigured, if not tetotally demolished. The building is also soiled by this method.

The body of this chute is made of heavy steel and the door and frame of the best quality of gray cast iron. All parts are thoroughly painted before shipment. The hopper can be moved if desired. When the door closes the hopper swings back into the body of the chute and allows the door to close against the wall.


We furnish these Coal Chutes in the following sizes:

SIZE OF OPENING IN THE WALL.			
No. 18-F-52.	22 in. wide, 16 in. high, 13 in. deep.		\$ 8.50
No. 18-F-53.	27 in. wide, 16 in. high, 13 in. deep.		10.75
No. 18-F-54.	33 in. wide, 22 in. high, 18 in. deep.		16.50

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Write Us For Prices on Steel Fence Posts

STANDARD FLUSH HINGE SIDEWALK DOORS




18-F-55

The standard door as illustrated we furnish in size 4 foot by 4 foot, double fold. This door is made of smooth steel plates, 3-16 of an inch thick with lock bar underneath, all painted one coat. In addition to this style we can furnish any size door desired, single or double, made of rough or smooth rolled plates and with or without guard chain. These doors are provided if so ordered with rack and pinion opening apparatus so that they may be opened to any desired point, the device automatically locking them in any position.

Price for Standard Size Door as Illustrated. **\$17.50**

Prices on other sizes quoted on application.



18-F-56

ASH PIT DOORS

Our Ash Pit Doors are extra heavy cast iron. We use much care in fitting so that they are absolutely tight. Are finished in black enamel.

Number	Size Opening	Price.
1	8 x 8	\$0.55 Each
2	8 x 10	.60 "
3	10 x 12	.90 "
4	10 x 14	1.00 "

TWISTED BARS FOR REINFORCED CONCRETE WORK

18-E-38. We carry on hand a complete stock of the following sizes of Twisted Square Bars. We can make immediate shipment of any orders for this material: 6 to 30 feet.

Diameter Inches: 3/8 7/8 1 1/2 1 3/4 1 7/8 2 1/4 2 3/4 3 1/2 4 1/2 5 1/2 6 1/2 7 1/2 8 1/2 9 1/2 10 1/2 11 1/2 12 1/2 13 1/2 14 1/2 15 1/2 16 1/2 17 1/2 18 1/2 19 1/2 20 1/2 21 1/2 22 1/2 23 1/2 24 1/2 25 1/2 26 1/2 27 1/2 28 1/2 29 1/2 30 1/2

Weight per foot: 0.478 0.651 0.850 1.1 1.35 1.95 2.66 3.50

Crimped Wire for Reinforcing



OUR REINFORCEMENTS CAN BE USED FOR ALL PURPOSES. such as columns, beams, porch floors, reinforced concrete floors of all descriptions, furniture, silos, watering troughs, tanks, reservoirs, and in fact all different kinds of reinforced concrete work. It is easily handled, easily bent, and can be used in any position for any purpose.

Special advice and directions for using this wire for any manner of reinforcement will be furnished on application.

This wire is made of heavy galvanized wire, cut to any length, all ready for use.

2-E-30. Price per 100 lbs. **\$2.50**

We also furnish this reinforcement wire in bundles of two or three sizes to the bundle—usually 8 to 12 gauge mixed, cut to lengths suitable for your work.

2-E-31. Price per 100 lbs. **\$2.25**

We also quote on this Crimped Wire not cut to length. It comes 100 pounds to a bundle, miscellaneous gauges and different lengths—varying about from 8 to 12 gauge and from 3 to 10 feet long.

Lot No. 2-E-32. Price per 100 pounds. **\$1.75**

GIRDER RAIL BEAMS

Exceptionally fine material that can be used to a good advantage in constructing concrete floors in buildings, bridges, sidewalks or for reinforcement or concrete work of any kind.

2-E-33. These rails are 7 in. high, they weigh 25 lbs. per foot and we can furnish them in any length up to 30 feet. Price per lb. **1c**

We can furnish any size rails which may be required for any class of work. If interested, write us for our low prices.





Illustration Showing Chute Closed

Steel Bridge Work at Enormous Saving!!

\$32⁵⁰


BUYS A COMPLETE BRIDGE—14 FT. WIDE,
12 FT. LONG.



Here is a
Money Sav-
ing Propo-
sition

IF YOU NEED anything in the line of Structural Steel or Builders Iron Work, be sure to get our prices before buying elsewhere. No orders too large and none too small for our careful and prompt attention.

Corrugated Curved Sheets




We have unexcelled facilities for manufacturing Corrugated Curved Steel Sheets.

These sheets are used for train sheds, awning, roofs over station platforms, but mainly are they used for fireproof floors and sidewalks; also tanks and

cisterns. Illustration shows a sheet of Corrugated Curved Steel. Sheet can be curved to any radius desired.

Illustration shows a fireproof floor, showing the Corrugated Curved Sheet in position and method of filling in concrete.


When used for floors or sidewalks, the curved arch is set on lower flange of Steel Beams (see illustration), and crushed stone mixed with cement completes the floor. We furnish quotations on receipt of specifications ONLY. (Also can quote on I Beams, etc.)



When writing for prices or ordering curved sheets show the exact measurements as marked by the dotted lines.

Curved sheets are sold by the square, full width after corrugating and full length before curving.

Riveted Extra Heavy Steel Culverts Pipe Less than Cost to Manufacture



18-A-48. We have a large stock of heavy steel culverts which are of interest to township and road commissioners. These culverts range in size from 6 to 72 inches in diameter, and in lengths up to 20 feet. These culverts are very strong and very durable. Write us for special prices on sizes that you want. We guarantee to save you big money and supply culverts that will be in every way satisfactory.

200 pieces, 10-inch diameter, approximate weight, 20 pounds per foot. Lengths, 14 to 18 feet. Price, per foot.....30c

35 pieces, 12-inch diameter, approximate weight, 40 pounds per foot. Lengths, 8 to 16 feet. Price, per foot.....60c

18 pieces, 14-inch diameter, approximate weight, 50 pounds per foot. Lengths, 8 to 18 feet. Price, per foot.....75c

15 pieces, 20-inch diameter, thickness of steel, about 1/2-inch. Approximate weight, 60 pounds per foot. Lengths, 10 to 20 feet. Price, per foot....90c

25 pieces, 24-inch diameter, thickness of steel, about 1/2-inch. Approximate weight, 70 pounds per foot. Lengths, 10 to 20 feet. Price, per foot.\$1.00

8 pieces, 36-inch diameter, thickness of steel 1/2-inch. Approximate weight, 120 pounds per foot. Lengths, 12 to 16 feet. Price, per foot.....\$1.75

12 pieces, 42-inch diameter, thickness of steel, 5-16 inch. Approximate weight, 150 pounds per foot. Lengths, 14 to 16 feet. Price, per foot...\$2.00

10 pieces, 48-inch diameter, thickness of steel, 5-16 inch. Approximate weight, 180 pounds per foot. Lengths, 14 to 16 feet. Price, per foot...\$2.25

8 pieces, 54-inch diameter, thickness of steel, 5-16 inch. Approximate weight, 200 pounds, per foot. Lengths, 14 to 16 feet. Price, per foot.\$2.50

6 pieces, 60-inch diameter, thickness of steel, 3/4-inch. Approximate weight, 250 pounds per foot. Lengths, 16 feet. Price, per foot.....\$3.00

12 pieces, 66-inch diameter, thickness of steel 3/4-inch. Approximate weight, 300 pounds per foot. Lengths, 16 to 18 feet. Price, per foot...\$3.50

12 pieces, 72-inch diameter, thickness of steel, 3/4-inch. Approximate weight, 350 pounds per foot. Lengths, 18 to 20 feet. Price, per foot...\$4.00

We Guarantee to Save You Money on any of this Kind of Material and Supply Culverts that Will in Every Way Prove Satisfactory.


18-B-29. We can supply common bridges of short spans from 6 to 40 ft. that do not require truss work. Send us sketches and we will submit estimate for all material required, cut to proper lengths, fitted and punched, all ready to be put together including necessary Bolts, Plates, etc. (We can also include the necessary Timbers and Planking when so desired.)

When writing for prices be sure and state the width and length and heaviest load your bridge will have to carry. Also state if bridge will be built with Concrete or Plank Floor.

Township Officials and Road Commissioners should pay especial attention to these bridges.

7c Per Foot.

New Steel "T" Rail.



Cross Section
of full size of
12-lb. rail.


In Stock
Lengths
15, 20, 24, 30
Feet.

We furnish complete Industrial Railway Systems for mines, brick yards, stone quarries, contractors' outfits and for all other purposes. We have all sizes of rails in stock and can make immediate deliveries.

No.	Wt. Per Yd.	Price, Per Ft.
18-F-112.	12 lbs.	7c
18-F-116.	16 lbs.	8 1/2c
18-F-120.	20 lbs.	10 1/2c
Fish plates and bolts for these rails, per set 16c.		
No. 18-F-39.	Per set.....	16c
Spikes. No. 18-F-40.	3x1/4. Per lb.....	12 1/2c

We also have at all times, relaying rails, sizes 12, 16, 20, 30, 40, 50, 60, 70 and 80 lb. If interested in any of this material it will pay you to get our prices.

Bargains in Car Wheels



-C.H.W.CO.-
-Car Wheel-


We have at all times a large quantity of Car Wheels and Axles of various diameter, for standard and narrow gauges of track. Send us list of your wants for special prices.

18-S-3030. 80 sets of good, second-hand Car Wheels. Diameter of wheels, 13 inches, size of axle, 2 in., size of axle at journal ends, 1 1/2 in., 20-in. gauge.


Price, per set of 4 wheels, 2 axles and 4 journals.....\$10.00

18-S-3035. 75 set of 8-in. diameter Car Wheels, 15 in. gauge, diameter of axle, 1 1/2 in.
Price, per set of 4 wheels, 2 axles and 4 journals.....\$4.50

Two Side Dump Cars APPROXIMATE CAPACITY 1/2 YARD



We have ready for immediate shipment, 75 of these concrete two-side dump cars, all steel, mounted on 12-inch diameter flanged car wheels, fitted for 24-inch gauge track.



DIMENSIONS:

Length of body at the top	4 feet.
Width of body at the top	3 feet.
Height of car from top of rail	3 1/2 feet.
Approximate weight	800 pounds.
Price, each	\$18.50

\$13.85 BUYS CELEBRATED KONKRETE KING Cement Block Machine

Latest Design

The "Konkrete King" Block Machine has all of the good features of other machines and in addition has improvements that make it the most perfect Block Machine on the market today. It has a wrought iron adjustable rocker arm with an eccentric handle which when drawn down prevents the mould from getting out of square, insuring a perfectly true block. There are hundreds of other machines offered for sale but none of them are equipped so that a square block is assured each time without spending valuable time in adjusting and truing up the machine.

Construction

The "Konkrete King" Block Machine makes blocks on the face down principle. In this way the blocks can be made with a cement face of a mixture of three to one or two to one, and the balance of the block made of a mixture of 5 to 1. The face of the block is the part that is exposed to the weather and concrete with a large proportion of cement, affords better resistance to frost and dampness. However, the entire block can be made of one mixture. Also, when it is desired to color the face of the block, this can be done and the balance of the block made without coloring, saving the expense of coloring the entire block.

There are no cogs, no springs or other devices to get out of order in the "Konkrete King" Block Machine. It operates so simple that a boy can understand it and use the machine without previous experience. Frame and flasks are made of a very high grade of tough gray cast iron, strongly bolted and braced, making the machine most durable. All lugs on the face plates are of chilled iron, giving them the needed strength so as not to break when subjected to rough handling. Flask consists of front and back wall, two core end doors, face plates, two improved rocker arms and pallet fitted in the most workmanlike manner. End doors are hinged to the face plates, which opens easily when releasing the block.

Capacity

The capacity of the "Konkrete King" Machine varies as to skill and experience of operator, also whether concrete is mixed by hand or machinery. One man can turn out on an average of 100 blocks a day and two men can easily turn out 250 blocks. Practice increases speed. The faster the material is delivered to the block makers, the larger the output.

Most for the Money

THE "KONKRETE KING" IS THE MOST COMPLETE OUTFIT for the money. It is a complete factory in itself and has a widely varied range of work. With it you can make more different sizes and faces of blocks with a fewer number of parts than any other machine on the market. We invite comparison and believe you will be convinced that we are giving the greatest value ever offered in Concrete Block Machinery.

Single or double Core

We furnish the KONKRETE KING BLOCK MACHINE with either single or double core flask as ordered, unless otherwise stated machine is equipped with a single core flask. KONKRETE KING is made in three sizes and so constructed that any one of the three flasks can be used on one standard, which is a great advantage should you wish to make blocks of different size. All that is necessary is to order flask attachment wanted. Are furnished either single or double core, in three different sizes for making blocks 8x8x16, 8x10x16 and 8x12x16 inches.

4-C-3. "Konkrete King" Building Block Machine. Complete for making 8x8x16 inch blocks. Wt. 175 lbs. Price, F. O. B. Factory, Cen. Wis. **\$13.85**

4-C-4. "Konkrete King" Building Block Machine. Complete for making 8x10x16 inch blocks. Wt. 200 lbs. Price, F. O. B. Factory, Cen. Wis. **\$18.75**

4-C-5. "Konkrete King" Building Block Machine. Complete for making 8x12x16 inch blocks. Wt. 235 lbs. Price, F. O. B. Factory, Cen. Wis. **\$21.95**



\$13.85

Buys Complete Outfit for Making 8x8x16 inch and Fractional Size Building Blocks.

Guarantee

The "Konkrete King" Block Machine is positively guaranteed to produce a greater number of perfect blocks in the same length of time than any other machine of a similar kind manufactured.

Ten days free trial given to everyone in order to test the machine and compare it with any other used in your locality, and if you do not find it to be the best machine from all standpoints and just as represented, or if for any reason it should not be satisfactory to you (of which matters you are to be the sole judge) you can return it to our factory and we will refund your money and all freight charges you have paid. We guarantee the safe delivery of the machine to your shipping point. It is all set up and ready to operate and furthermore we warrant that you will have the most liberal and courteous treatment from us so that you need have no hesitancy about sending us your order or writing us regarding Concrete Machinery or other information you desire.

Profitable

No other line of industry today offers you such big opportunity to engage in trade with such little capital as the manufacture of Concrete Blocks and other Concrete products. Requires no previous experience and is a big and sure money making proposition. At a small outlay you can buy a machine from us and the accessories and with but very little labor you can be assured of a profit from \$7.00 a day upwards.

As example: 100, 8x8x16 inch Concrete Blocks made in the proportion of five parts of sand and gravel to one part of cement requires two barrels of cement at \$2.00 per barrel. **\$4.00**

And one and one-half yards of sand and gravel at 70c per cubic yard... **1.05**
With an allowance of **2.00**
For yourself or hired man for labor, making a total cost of..... **7.05**

YOUR PROFIT

For the 100 Blocks which readily retail at 15c each, making a profit to you of **\$7.95**

In addition to the above you can secure big prices for the extras, such as Porch Columns, Sills, Caps, Steps, Lintels, Water Tables, Chimney Blocks, Pier Blocks and Tile Blocks.

See next page for special attachments for "KONKRETE KING" Block Machines.


Regular Outfit

Consists of the machine with rock face plate, two dividing plates, one gable dividing plate, two return end doors, two core gates, two joists block attachments, one face plate for making half and quarter blocks, one striker, one double end tamper and one sample pallet. With this outfit you can make a whole or fractional size block; in fact, the machine is in every sense complete and the equipment can be added to from time to time and you can make any face or anything desired for an ordinary dwelling except mill work. We can furnish face plates in the following designs: plain, rock, panel, cobblestone, tooled margin bush hammer, tooled face, tooled margin rock face, ashler face in six different designs, whirlwind scroll face, which are illustrated in the following pages. Unless otherwise specified the Machine is equipped with rock face design.

Pallets

With each machine a sample wooden pallet is furnished. You can easily make more yourself at a small expense with simple carpenter's tools.

EXTRA FLASKS FOR "KONKRETE KING" BLOCK MACHINES



Single Core Flask.

All flasks are made to fit one stand. The illustrations show both single and double core and as explained before these flask attachments can be used on any KONKRETE KING stand and are attached without difficulty. For instance if you should order an 8x8x16 inch KONKRETE BLOCK MACHINE and wish to make 8x10x16 inch blocks, it is not necessary to order a complete new machine, but just the flask attachment of that size; or if you wish to make the two sizes of blocks order the Machine and one extra flask attachment. We recommend making the two different sizes as the larger blocks can be used for foundations and the smaller blocks for the upper portion of the wall. (Shipped from factory Central Wisconsin.)

4-C-7. 8x8x16 Flask for "KONKRETE KING" Block Machines. Wt. 100 lbs. Price..... **\$4.29**

4-C-8. 8x10x16 Flask for "KONKRETE KING" Block Machines. Wt. 135 lbs. Price..... **\$5.17**

4-C-9. 8x12x16 Flask for "KONKRETE KING" Block Machines. Wt. 160 lbs. Price..... **\$6.00**



Double Core Flask.

SEE SPECIAL CATALOG FOR SPECIAL ATTACHMENTS FOR "KONKRETE KING" MACHINES


CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.



Write Us for Prices on Gasoline Engines. 123

FINE LOCK SETS AND BUILDERS' HARDWARE

Our Lines are Complete and Represent the Product of the Best Known Manufacturers. We Offer More Real Value for the Money In These Lines Than Can Possibly Be Secured Elsewhere.
Every Article Is Strictly First Quality and Cannot Be Excelled In Material, Workmanship or Finish.



EDGEWATER DESIGN LOCK SETS

Genuine wrought bronze. A very popular pattern.

EDGEWATER DESIGN CYLINDER FRONT DOOR LOCK SETS

The Best Cylinder Lock Manufactured
5-pin tumbler cylinder, non-pickable. Lock size 5½x4 inches. 2½-inch knobs. ½ inch swivel spindle. 3 German silver keys. Outside escutcheon 3x9½ inches; inside escutcheon 2½x7 inches. Cylinder, bolts, strike, escutcheons and all trimmings are genuine wrought bronze. Reversible for right or left hand doors, 1½ to 2½ inches thick. Complete with screws to match.

4-E-3001. Antique copper finish, polished. Price per Set.....\$5.00
4-E-3003. Old or Lemon brass finish. Price per Set.....\$5.00

EDGEWATER DESIGN FRONT DOOR LOCK SETS

Size of lock 4½x3½ inches. 2 nickel plated steel night keys and 1 lock key. Outside escutcheon 3x9½ inches; inside escutcheon 2½x7 inches. 2½ inch knobs. ½ inch swivel spindle. Escutcheons, knobs, bolts, strike and all trimmings are genuine wrought bronze. Reversible for right or left hand doors. Complete with screws to match.

4-E-3005. Antique copper finish, polished. Price per Set.....\$2.00
4-E-3007. Old or lemon brass finish. Price per Set.....\$2.00

EDGEWATER DESIGN WROUGHT STEEL FRONT DOOR LOCK SETS

As described above, except furnished with bronze plated wrought steel knobs, escutcheons and trimmings.

4-E-3006. Antique copper finish, polished. Price per Set.....\$1.40
4-E-3008. Old or lemon brass finish. Price per Set.....\$1.40

NOTE—Above lock sets also furnished with one key operating back bolts.

EDGEWATER DESIGN INSIDE DOOR LOCK SETS

A Real Beauty and a Very Popular Lock Set

Size of lock 3½x3½ inches. Escutcheons 2½x7½ inches. 2½ inch knobs. Nickel plated steel key. Escutcheons, knobs, bolts, strike and trimmings are all genuine wrought bronze. Reversible for right or left hand doors. Complete with screws to match.

4-E-3009. Antique copper finish, polished. Price per Set.....95c
4-E-3011. Old or lemon brass finish. Price per Set.....95c

EDGEWATER DESIGN WROUGHT STEEL INSIDE DOOR LOCK SETS

As described above, except furnished with bronze plated wrought steel knobs, escutcheons and trimmings.

4-E-3010. Antique copper finish, polished. Price per Set.....45c
4-E-3012. Old or lemon brass finish. Price per Set.....45c

EDGEWATER SLIDING DOOR LOCK SETS

Size of lock 4½x3½ inches. Escutcheons 7½x2½ inches. Escutcheons and all trimmings are genuine wrought bronze. Single door sets have two flush cup escutcheons; double door sets have four. For flat front doors only. Complete with screws to match.

4-C-3013. Antique copper Finish, polished. For Single Doors. Price per Set.....\$1.39
4-C-3015. For double doors. Price per Set.....\$2.05
4-C-3017. Old or lemon brass finish. For single doors. Price per Set.....\$1.41
4-C-3019. For double Doors. Price per Set.....\$2.07

EDGEWATER DESIGN PUSH PLATES


Genuine wrought bronze metal with screws to match. Size 3x9½ inches.

4-C-3021. Antique copper finish, polished. Price each.....51c
4-C-3023. Old or lemon brass finish. Price each.....52c

EDGEWATER DESIGN DOOR BELLS

Bronze metal plate 1½x4 inches. Complete with ¾ inch nickel plated bell metal gong.

4-C-3025. Antique copper finish, polished. Price.....71c
4-C-3027. Old or lemon brass finish. Price.....72c



COLONIAL DESIGN LOCK SETS

A very pleasing pattern which has proven to be our largest seller, being often specified in connection with our highest priced house designs. COLONIAL DESIGN CYLINDER FRONT DOOR LOCK SETS.

Heavy beaded edges, finely finished. 5-pin tumbler cylinder, non-pickable. Lock size 5½x4 inches. 2½-inch knobs. ½-inch swivel spindle. 3 German silver keys. Outside escutcheon 2½x9½ inches; inside escutcheon 2½x7 inches. Cylinder, bolts, strike, escutcheons, knobs and all trimmings are genuine wrought bronze. Reversible for right or left hand doors. 1½ to 2½ inches thick with screws to match.

4-C-3031. Antique copper finish, polished. Price per Set.....\$5.43
4-C-3031. Old or lemon brass finish. Price per Set.....\$5.45

COLONIAL DESIGN GENUINE BRONZE FRONT DOOR LOCK SETS

An ornament to any door. Size of lock 4½x3½ inches. 2 Nickel plated steel night keys and 1 lock key. Outside escutcheon 3x9½ inches; inside escutcheon 2½x7 inches. 2½ inch knobs. ½ inch swivel spindle. Knobs, bolts, strike and all trimmings are genuine wrought bronze. Reversible for right or left hand doors. Complete with screws to match.

4-C-3033. Antique copper finish, polished. Price per Set.....\$1.79
4-C-3035. Old or lemon brass finish. Price per Set.....\$1.81

COLONIAL DESIGN WROUGHT STEEL FRONT DOOR LOCK SETS.

As above described, except are furnished with bronze plated wrought steel knobs, escutcheons and trimmings.

4-C-3037. Antique copper finish, polished. Price per Set.....\$1.43
4-C-3039. Old or lemon brass finish. Set.....\$1.45

COLONIAL DESIGN GENUINE BRONZE INSIDE DOOR LOCK SETS

A very pleasing design. Size of lock 3½x3½ inches. Escutcheons 2½x7 inches. Nickel plated steel key. Escutcheons, knobs, bolts, strike and all trimmings are of genuine wrought bronze. Reversible for right or left hand doors. Complete with screws to match.

4-C-3041. Genuine wrought bronze metal antique copper finish, polished. Price per Set.....\$1.07
4-C-3043. Old or lemon brass finish. Price per Set.....\$1.09

COLONIAL DESIGN WROUGHT STEEL INSIDE DOOR LOCK SETS

As above described except are furnished with bronze plated wrought steel knobs, escutcheons and trimmings.

4-E-3045. Antique copper finish, polished. Price per Set.....50c
4-E-3047. Old or lemon brass finish. Set.....50c

COLONIAL DESIGN GENUINE BRONZE SLIDING DOOR LOCK SETS

Size of lock 4½x3½ inches. Escutcheons 7x2½ inches. Escutcheons and all trimmings are genuine wrought bronze. Single door sets have two flush cup escutcheons; double door sets have four. For flat front doors only. Complete with screws to match.

4-C-3049. Antique copper finish, polished. For single doors. Price per Set.....\$1.40
4-C-3051. For double doors. Price per Set.....\$2.07
4-C-3053. Old or lemon brass finish. For single doors. Price per Set.....\$1.41
4-C-3055. For double doors. Price per Set.....\$2.09

COLONIAL DESIGN WROUGHT STEEL SLIDING DOOR LOCK SETS

As above described except are furnished with bronze plated wrought steel escutcheons, bolts and trimmings.

4-C-3057. Antique copper finish, polished. For single doors. Price per Set.....\$1.23
4-C-3059. For double doors. Price per Set.....\$1.79
4-C-3061. Old or lemon brass finish. For single doors. Price per Set.....\$1.25
4-C-3063. For double doors. Price per Set.....\$1.81

COLONIAL DESIGN PUSH PLATES

Genuine bronze metal with screws to match. Size 9½x2½ inches.

4-C-3065. Antique copper finish, polished. Price each.....49c
4-C-3067. Old or lemon brass finish. Price each.....51c

COLONIAL DESIGN DOOR BELLS

Bronze metal plate 1½x3½ inches. Complete with ¾ inch nickel plated bell metal gong.

4-C-3069. Antique copper finish, polished. Price.....71c
4-C-3071. Old or lemon brass finish. Price.....72c

Stove Door Handles and Lock Sets—Rim Locks and Latches

WROUGHT STEEL ELECTRO BRONZE PLATED STORE DOOR HANDLE AND LOCK SET.

4-C-3351. Antique copper finish. Size of lock $4\frac{1}{2} \times 3\frac{1}{2}$ inches. Size of plates 3×12 inches. 2 bar handle grips, one for either side of door. Two nickel plated flat steel keys. Reversible for right or left hand doors. Complete with screws to match. Price per set.....**\$2.45**

GENUINE WROUGHT BRONZE STORE DOOR LOCK AND HANDLE.

4-C-3353. Same as above described except that plates, grips, strike, bolts and trimmings are genuine bronze metal. Complete with screws to match. Price per Set.....**\$4.11**

WROUGHT STEEL ELECTRO BRONZE PLATED STORE DOOR HANDLE AND LOCK SETS.

4-C-3359. Antique copper finish. Size of lock $4\frac{1}{2} \times 3\frac{1}{2}$ inches. Size of plates 3×12 inches. 2 handles one for either side of door. 2 nickel plated flat steel keys. Reversible for right or left hand doors. Complete with screws to match. Price per Set.....**\$2.09**

GENUINE WROUGHT BRONZE PLATED STORE DOOR LOCK SET AND HANDLE.

4-C-3361. Same as 4-B-1661 except plates, handles, bolts, strike and trimmings are genuine wrought bronze with screws to match. Price per Set.....**\$3.50**

GENUINE WROUGHT BRONZE CYLINDER STORE DOOR LOCK AND HANDLE.

4-C-3355. Antique copper finish. Size of lock $5 \times 3\frac{1}{2}$ inches. 5-pin tumbler cylinder, non-pickable. Size of plates 3×12 inches. 2 bar handle grips, one for either side of door. 3 German silver keys. Reversible for right or left hand door. Complete with screws to match. Price per Set.....**\$6.98**

GENUINE WROUGHT BRONZE CYLINDER STORE DOOR LOCK AND HANDLE.

4-C-3363. Antique copper finish. Size of lock $5 \times 3\frac{1}{2}$ inches. 5-pin tumbler cylinder, non-pickable. Size of plates 3×12 inches. 2 handles, one for either side of door. 3 German silver keys. Complete with screws to match. Price per Set.....**\$6.81**

MORTISE DOOR LOCKS

Japanned Case, $3\frac{1}{2} \times 3\frac{1}{2}$ inch. Iron bolts, lacquered from and strike, tinned key. Japanned escutcheons with screws

4-C-3453. Locks only without knobs. Per dozen \$1.50. Each.....**13c**

4-C-3455. With brown mineral knobs. Per dozen \$2.21. Each.....**19c**

4-C-3457. With jet knobs. Per dozen \$2.43. Each.....**22c**

Japanned Case, $3\frac{1}{2} \times 3\frac{1}{2}$ inch. Brass front and bolts, plated strike, nickel plated steel key, japanned escutcheons with screws.

4-C-3459. Locks only without knobs. Per dozen \$2.83. Each.....**28c**

4-C-3461. With brown mineral knobs. Per dozen \$3.53. Per set.....**33c**

4-C-3463. With jet knobs. Per dozen sets \$3.98. Per set.....**36c**

MORTISE DOOR LATCHES.

Japanned iron case, $1\frac{1}{2} \times 3\frac{1}{2}$ inches iron bolts, front and strike.

4-C-3465. Latch only without knobs. Per dozen 69c. Each.....**6c**

4-C-3467. With brown mineral knobs. Per dozen sets \$1.40. Per set.....**12c**

4-C-3469. With jet knobs. Per dozen sets \$1.83. Per set.....**15c**

Japanned iron cases, $1\frac{1}{2} \times 3\frac{1}{2}$ inches. Brass front, bolt and strike.

4-C-3471. Latch only without knobs. Per dozen \$1.63. Each.....**14c**

4-C-3473. With brown mineral knobs. Per dozen sets \$2.50. Per set.....**22c**

4-C-3475. With jet knobs. Per dozen sets \$2.85. Per set **25c**

Rim Lock

Heavy Japanned Cases. Best of construction and finished in a superior manner. Reversible for right or left hand doors. Packed complete with screws, japanned keyhole escutcheons. Each lock fully warranted. The best lock values ever offered.

UPRIGHT RIM KNOB LOCK

Size $4 \times 3\frac{1}{2}$ inches with stop, iron bolts and tinned malleable key.

4-C-3409. Lock only without knob. Per doz. \$1.10. Each.....**10c**

4-C-3411. With brown mineral knob. Per dozen sets \$1.92. Per set.....**17c**

4-C-3413. With jet knob. Per dozen sets \$2.18. Per set.....**19c**

UPRIGHT RIM KNOB LOCK

Size $4 \times 3\frac{1}{2}$ inches, 3 brass plated bolts, nickel plated steel key.

4-C-3415. Lock only without knob. Per dozen \$2.47. Each.....**21c**

4-C-3417. With brown mineral knob. Per dozen sets \$3.27. Per set.....**28c**

4-C-3419. Black jet knob. Per dozen sets \$3.40. Per set.....**30c**

HORIZONTAL RIM KNOB LOCK.

Size $3\frac{1}{2} \times 4\frac{1}{2}$ in. With iron bolts, tinned malleable key.

4-C-3421. Lock only without knob. Per dozen \$1.10. Each.....**10c**

4-C-3423. With brown mineral knob. Per dozen sets \$1.92. Per set.....**17c**

4-C-3425. With jet knob. Per dozen sets \$2.18. Per set.....**19c**

HORIZONTAL RIM KNOB LOCKS

Size $3\frac{1}{2} \times 4\frac{1}{2}$ inches, 3 brass bolts, nickel plated steel key.

4-C-3427. Lock only without knob. Per dozen \$2.57. Each.....**22c**

4-C-3429. With brown mineral knob. Per dozen sets \$3.39. Each.....**28c**

4-C-3431. With jet knob. Per dozen sets \$3.51. Per set.....**31c**

HORIZONTAL RIM DEAD LOCKS.

Size $2 \times 2\frac{1}{2}$ in. Japanned iron case and escutcheons iron key Complete with screws.

4-C-3433. Lock only without knobs. Per dozen \$1.12. Each.....**10c**

4-C-3435. With brown mineral knobs. Per dozen sets \$1.93. Per set.....**17c**

4-C-3437. With jet knobs. Per dozen sets \$2.05. Per set.....**19c**

HORIZONTAL RIM KNOB LATCHES.

Size $2\frac{1}{2} \times 3\frac{1}{2}$ in. Japanned case, iron bolt and hub, with screws reversible.

4-C-3443. Latch only without knobs. Per dozen \$1.15. Each.....**10c**

4-C-3445. With brown mineral knobs. Per dozen sets \$1.92. Per set.....**17c**

4-C-3447. With jet knobs. Per dozen sets \$1.96. Per set.....**19c**

STORE DOOR RIM DEAD LOCK.

4-C-3439. Strong and durable. Japanned iron case, $5 \times 3\frac{1}{2}$ inches. Heavy iron bolt, wrought steel inside bolts, 2 nickel plated steel folding keys. Complete with Screws. Price.....**53c**

TUBULAR RIM NIGHT LATCH.

4-C-3449. Japanned iron case, size $3\frac{1}{2} \times 2\frac{1}{2}$ inches. For doors up to $1\frac{1}{2}$ inches thick. Japanned case, iron bolts, nickel plated flat steel keys, bronze metal escutcheons, beveled strike with screws reversible. Price.....**33c**

CLARKE'S GRAVITY BLIND HINGES.

4-C-3441. For frame houses. Throws blind $1\frac{1}{2}$ inches from casing. Set includes four hinges and two fasteners. Flat head screws are to be used with these sets. Per doz. Set, 75c. Per set.....**7c**

PRESSED STEEL SHELF BRACKETS.

4-C-3451. Strong and unbreakable, Japanned finished without screws.

Size in.	4x5	6x8	7x9
Per pair.....	4c	7c	8c
Per doz. Pairs	39c	72c	87c
Size in.	8x10	10x13	12x14
Per Pair.....	9c	13c	18c
Per Doz. Pairs	\$1.00	\$1.43	\$2.12

DOOR KNOBS.

Rim Knobs **Mortise Knobs**

Strictly first quality. Japanned shanks and roses. Knobs $2\frac{1}{2}$ inches in diameter with $\frac{1}{2}$ inch spindles. Price includes one pair knobs complete with connecting spindle. Mineral knobs are brown mottled; porcelain knobs are white, jet knobs are black.

4-C-3477. Mineral knobs for rim locks. Per dozen 70c. Each.....**7c**

4-C-3479. Porcelain knobs for rim locks. Per dozen 82c. Each.....**8c**

4-C-3481. Jet knobs for rim locks. Per dozen 92c. Each.....**9c**

4-C-3483. Mineral knobs for mortise locks. Per dozen 70c. Each.....**7c**

4-C-3485. Porcelain knobs for mortise locks. Per dozen 82c. Each.....**8c**

4-C-3487. Jet knobs for mortise locks. Per dozen 92c. Each.....**9c**

CYLINDER RIM NIGHT LATCH.

4-C-3489. A durable lock which affords the utmost security. Japanned iron case, size $3\frac{1}{2} \times 2\frac{1}{2}$ inches, with genuine bronze metal bolts, cylinder, escutcheon, knob and stop, 3 Yale pattern German silver keys, suitable for doors up to 3 inches thick. Complete with screws. Price.....**98c**

SAFETY DOOR FASTENERS.

Can be instantly thrown into and out of position. When in position door can be left ajar for the purpose of ventilation, without fear of intruders, as the door cannot be opened further than the length of the bolt, making it absolutely impossible for any one to force his way in. When locked at night it is as secure as any bolt. When thrown out of position the door can be operated in the usual manner and the fastener is not in the way.

4-C-3491. Malleable iron, antique copper finish polished. Price.....**37c**

4-C-3493. Malleable iron, old or lemon brass finish. Price.....**39c**


4-C-3495. Solid bronze antique copper finish. Price.....**49c**

4-C-3497. Solid bronze old or lemon brass finish. Price.....**51c**

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Stock and Poultry Troughs listed in this catalog are the best on the market.

WILMETTE DESIGN LOCK SETS



CYLINDER FRONT DOOR LOCK.

- 4-F-3201. Antique copper finish, polished. **\$4.45**
Price, per set.
4-F-3203. Old or lemon brass finish. Price, per set. \$4.45

BIT-KEYED FRONT DOOR LOCK.

Also furnished with one key to operate both bolts.

- 4-F-3205. Genuine bronze, antique copper finish, polished. Price, per set. **\$1.70**
4-F-3207. Genuine bronze, old or lemon, brass finish. \$1.70
4-F-3209. Wrought steel, antique copper finish, polished. \$1.25
4-F-3211. Wrought steel, old or lemon, brass finish. \$1.25

INSIDE DOOR LOCK.

- 4-F-3213. Genuine bronze, antique copper finish. **85c**
4-F-3215. Genuine bronze, old or lemon, brass finish. Price, per set. \$0.85
4-F-3217. Wrought steel, antique copper finish, polished. Price, per set.40
4-F-3219. Wrought steel, old or lemon, brass finish. Price, per set.40

SLIDING DOOR LOCKS. GENUINE BRONZE.

- 4-F-3221. Antique copper finish. For single doors. Price, per set. **\$1.41**
4-F-3223. Antique copper finish. For double doors. Price, per set. \$2.07
4-F-3225. Old or lemon, brass finish. For single doors. Price, per set. 1.43
4-F-3227. Old or lemon, brass finish. For double doors. Price, per set. 2.09

SLIDING DOOR LOCKS. WROUGHT STEEL.

- 4-F-3229. Antique copper finish. For single doors. Price, per set. **\$1.07**
4-F-3231. For double doors. Price, per set. \$1.80
4-F-3233. Old or lemon, brass finish. For single doors. Price, per set. 1.09
4-F-3235. For double doors. Price, per set. 1.62

BRONZE METAL PUSH PLATES.

- 4-F-3237. Antique copper finish, polished. Price, each. **53c**
4-F-3239. Old or lemon, brass finish. Price, each. 55c

BRONZE METAL DOOR BELLS.

- 4-F-3241. Antique copper finish, polished. Price, each. **71c**
4-F-3243. Old or lemon, brass finish. Price, each. 72c

EVANSTON DESIGN LOCK SETS

CYLINDER FRONT DOOR LOCK.

- 4-F-3101. Antique copper finish, polished. **\$4.70**
Price, per set.
4-F-3103. Old or lemon, brass finish. Price, per set. \$4.70

BIT-KEYED FRONT DOOR LOCK.

Also furnished with one key to operate both bolts.

- 4-F-3105. Genuine bronze, antique copper finish, polished. Price, per set. **\$1.70**
4-F-3107. Genuine bronze, old or lemon, brass finish. \$1.70
4-F-3109. Wrought steel, antique copper finish, polished. 1.35
4-F-3111. Wrought steel, old or lemon, brass finish. 1.35

INSIDE DOOR LOCK.

- 4-F-3113. Genuine bronze, antique copper finish, polished. Price, per set. **90c**
4-F-3115. Genuine bronze, old or lemon, brass finish. Price, per set. \$0.90
4-F-3117. Wrought steel, antique copper finish, polished. Price, per set.40
4-F-3119. Wrought steel, old or lemon, brass finish. Price, per set.40

SLIDING DOOR LOCKS. GENUINE BRONZE.

- 4-F-3121. Antique copper finish, polished. **\$1.32**
For single doors.
4-F-3123. Antique copper finish. For double doors. \$1.89
4-F-3125. Old or lemon, brass finish. For single doors. 1.33
4-F-3127. Old or lemon, brass finish. For double doors. 1.91

SLIDING DOOR LOCKS. WROUGHT STEEL.


- 4-F-3129. Antique copper finish, polished. **\$1.14**
For single doors.
4-F-3131. For double doors. Price, per set. \$1.79
4-F-3133. Old or lemon, brass finish. For single doors. 1.15
4-F-3135. For double doors. 1.80

BRONZE METAL PUSH PLATES.


- 4-F-3137. Antique copper finish, polished. **51c**
Price, each.
4-F-3139. Old or lemon, brass finish. Price, each. 52c

BRONZE METAL DOOR BELLS.

- 4-F-3141. Antique copper finish, polished. **71c**
Price, each.
4-F-3143. Old or lemon, brass finish. Price, each. 72c



ARGYLE DESIGN LOCK SETS



CYLINDER FRONT DOOR LOCK.

- 4-F-3301. Antique copper finish, polished. **\$4.70**
Price, per set.
4-F-3303. Old or lemon, brass finish. Price, per set. \$4.70

BIT-KEYED FRONT DOOR LOCK.

Also furnished with one key to operate both bolts.

- 4-F-3305. Genuine bronze, antique copper finish, polished. Price, per set. **\$1.75**
4-F-3307. Genuine bronze, old or lemon, brass finish. \$1.75
4-F-3309. Wrought steel, antique copper finish, polished. \$1.25
4-F-3311. Wrought steel, old or lemon, brass finish. \$1.25

INSIDE DOOR LOCK.

- 4-F-3313. Genuine bronze, antique copper finish, polished. **80c**
4-F-3315. Genuine bronze, old or lemon, brass finish. Price, per set. \$0.80
4-F-3317. Wrought steel, antique copper finish, polished. Price, per set.40
4-F-3319. Wrought steel, old or lemon, brass finish. Price, per set.40

SLIDING DOOR LOCKS. GENUINE BRONZE.

- 4-F-3321. Antique copper finish, polished. For single doors. Price, per set. **\$1.39**
4-F-3323. Antique copper finish. For double doors. Price, per set. \$2.07
4-F-3325. Old or lemon, brass finish. For single doors. Price, per set. 1.41
4-F-3327. Old or lemon, brass finish. For double doors. Price, per set. 2.09

SLIDING DOOR LOCKS. WROUGHT STEEL.

- 4-F-3329. Antique copper finish, polished. For single doors. Price, per set. **\$1.14**
4-F-3331. For double doors. Price, per set. \$1.79
4-F-3333. Old or lemon, brass finish. For single doors. Price, per set. 1.16
4-F-3335. For double doors. Price, per set. 1.81

BRONZE METAL PUSH PLATES.

- 4-F-3337. Antique copper finish, polished. Price, each. **51c**
4-F-3339. Old or lemon, brass finish. Price, each. 52c

BRONZE METAL DOOR BELLS.

- 4-F-3341. Antique copper finish, polished. Price, each. **71c**
4-F-3343. Old or lemon, brass finish. Price, each. 72c

OAK PARK DESIGN LOCK SETS

CYLINDER FRONT DOOR LOCK.

- 4-F-3245. Antique copper finish, polished. **\$5.50**
Price, per set.
4-F-3247. Old or lemon, brass finish. Price, per set. \$5.50

BIT-KEYED FRONT DOOR LOCK.

Also furnished with one key to operate both bolts.

- 4-F-3249. Genuine bronze, antique copper finish, polished. Price, per set. **\$1.90**
4-F-3251. Genuine bronze, old or lemon, brass finish. \$1.90
4-F-3253. Wrought steel, antique copper finish, polished. 1.40
4-F-3255. Wrought steel, old or lemon, brass finish. 1.40

INSIDE DOOR LOCK.

- 4-F-3257. Genuine bronze, antique copper finish, polished. Price, per set. **\$1.00**
4-F-3259. Genuine bronze, old or lemon, brass finish. Price, per set. \$1.00
4-F-3261. Wrought steel, antique copper finish, polished. Price, per set.43
4-F-3263. Wrought steel, old or lemon, brass finish. Price, per set.43

SLIDING DOOR LOCKS. GENUINE BRONZE.

- 4-F-3265. Antique copper finish, polished. **\$1.41**
For single doors.
4-F-3267. Antique copper finish. For double doors. \$2.09
4-F-3269. Old or lemon, brass finish. For single doors. 1.43
4-F-3271. Old or lemon, brass finish. For double doors. 2.11

SLIDING DOOR LOCKS. WROUGHT STEEL.

- 4-F-3273. Antique copper finish, polished. **\$1.17**
For single doors.
4-F-3275. For double doors. Price, per set. \$1.95
4-F-3277. Old or lemon, brass finish. For single doors. 1.19
4-F-3279. For double doors. 1.87

BRONZE METAL PUSH PLATES.

- 4-F-3281. Antique copper finish, polished. **51c**
Price, each.
4-F-3283. Old or lemon, brass finish. Price, each. 52c

BRONZE METAL DOOR BELLS.

- 4-F-3285. Antique copper finish, polished. **71c**
Price, each.
4-F-3287. Old or lemon, brass finish. Price, each. 72c



AUSTIN DESIGN



Best moderate price lockset front door lock, size 4 1/2 x 3 1/2 in. Outside escutcheon 2 1/2 x 8 in. Reversible for right or left hand door.
4-F-3345. Price per set. **\$1.21**
Austin Design Inside Lock
4-F-3357. Per set. **31c**
Price per dozen, \$3.50.
Austin Design Door Bell
4-F-3347. Price each. 52c
Austin Design Store Door Lock
4-F-3349. Bronze Plated Iron Door Lock and Handle, 2 handle, 1 for either side of door, reversible for Right or Left Hand Door. Price per set. **\$1.79**

ELECTRO PLATED STEEL SASH LOCKS.

The strongest and most durable sash lock made. Holds sash closely together and prevents rattling. Finely finished. Complete with screws.

4-C-3801. Antique copper polished finish. Per dozen 48c Each.
4-C-3803. Old or lemon brass finish. Per dozen.....50c Each.....50c

AUSTIN DESIGN BRONZE PLATED SASH LOCKS.

4-C-3805. Black background, raised surface, polished bronze finish. Complete with screws. Per dozen.....95c Each.....90c

SIDE SASH LOCKS.

Holds as firm as a vise, prevents rattling of windows. Locks sash securely at any desired height, affording excellent ventilation.

4-C-3607. Antique copper finish. With screws to match. Per dozen.....90c Each.....80c

ELBOW CUPBOARD CATCHES.

Used on double cupboard doors.

4-C-3609. Iron japanned finish. Per dozen.....21c Each.....30c

4-C-3811. Iron bronze finish. Per dozen.....45c Each.....40c

LETTER BOX PLATES.

4-C-3613. For use on doors. Black background, raised surface, polished bronze finish. Length 7 1/2 inches. With screws to match. Per dozen \$3.40 Each.....30c

MORTISE DOOR BOLTS.

Strong and secure. With "T" handle thumb piece. Plates and screws to match.

4-C-3615. Antique copper polished finish. Price.....13c

4-C-3617. Old or lemon brass finish. Price.....14c

WINDOW SETS FOR BASEMENT, DORMER AND ATTIC WINDOWS.

A great time saver. For carpenters and builders. Hinged to swing. Strong and durable. Presses the sash tightly into the frame, excludes the cold and prevents rattling.

4-C-3619. For sash hinged at side. Set consists of one pair 2 1/2 inch wrought steel butts, one japanned steel sash fastener. Packed in box complete with screws. Per set.....10c

4-C-3621. For sash hinged at top. Set consists of one pair 2 1/2 inch wrought steel butts, one japanned steel sash fastener, one hook and eye. Packed in box complete with screws. Per set.....12c

WROUGHT STEEL DRAWER PULLS.

Wrought steel electro plated with screws to match. Length 3 1/2 inches.

4-C-3823. Antique copper polished finish. Per dozen.....27c Each.....30c

4-C-3825. Old or lemon brass finish. Per dozen.....27c Each.....30c

4-C-3827. Antique copper finish. Per dozen.....79c Each.....70c

4-C-3829. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3831. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3833. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3835. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3837. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3839. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3841. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3843. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3845. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3847. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3849. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3851. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3853. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3855. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3857. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3859. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3861. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3863. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3865. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3867. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3869. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3871. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3873. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3875. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3877. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3879. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3881. Old or lemon brass finish. Per dozen.....79c Each.....70c

4-C-3883. Old or lemon brass finish. Per dozen.....79c Each.....70c

SPRING SASH BALANCES.

4-D-3637. Used instead of sash weights and cord. Easy to apply and do not require box frames. Springs are made of special tempered steel, heavily coppered to prevent rust. Warranted to retain their full strength. Set consists of four balances, two each for top and bottom sash.

Size Number	Weight of each Sash	Height of each Sash	Wt. Per Set of 4 Balances	Price Per Set of 4 Balances
6	4 to 6 lbs.	34 in.	6 lbs.	\$0.85
8	6 to 8 lbs.	34 in.	6 lbs.	1.00
10	8 to 10 lbs.	34 in.	7 lbs.	1.15
12	10 to 12 lbs.	44 in.	7 lbs.	1.30
14	12 to 14 lbs.	44 in.	7 1/2 lbs.	1.45
16	14 to 16 lbs.	44 in.	7 1/2 lbs.	1.65
18	16 to 18 lbs.	48 in.	9 1/2 lbs.	1.85
20	18 to 20 lbs.	48 in.	10 lbs.	2.00
22	20 to 22 lbs.	48 in.	11 lbs.	2.15
24	22 to 24 lbs.	48 in.	13 lbs.	2.25
26	24 to 26 lbs.	50 in.	13 lbs.	2.32
28	26 to 28 lbs.	50 in.	13 1/2 lbs.	2.40
30	28 to 30 lbs.	50 in.	14 lbs.	2.50
32	30 to 32 lbs.	50 in.	14 lbs.	2.65
34	32 to 34 lbs.	50 in.	14 lbs.	2.70
36	34 to 36 lbs.	50 in.	14 lbs.	2.80

VENTILATING SASH FASTENER.

Permits the windows to be left open at the top, bottom, or both top and bottom with perfect security against intrusion. Strong and durable and easily applied. Electro bronze plated, with screws to match.

4-C-3639. Antique copper polished finish. Per dozen.....\$1.41 Each.....13c

4-C-3641. Old or lemon brass finish. Per dozen.....\$1.41 Each.....14c

SASH WEIGHTS.

4-C-3643. Four weights are required to hang each window. Weights range from 3 to 9 pounds by half pounds. Heavier than 9 pounds graduate by pounds. Per pound.....13c

SASH CORD.

Made of special selected long fiber cotton firmly braided. The strongest and most durable manufactured. Put up in bundles of 100 feet.

4-C-3645. No. 7, 7/8 inch diameter. Per bundle.....54c

4-C-3647. No. 8, 1 inch diameter. Per bundle.....67c

STEEL SASH PULLEY.

4-C-3649. Electrically welded and cannot break. Require no screws. Simply bore three holes and drive the pulley in. Diameter of wheel 2 inches. Per dozen.....23c

COMMON SENSE STEEL SASH PULLEYS.

Superior to cast iron. Will not break. 4-C-3651. Mortised in with 1 inch bit. Easily applied and held fast by screws. Diameter of wheel 2 inches. Per dozen.....25c

NOISELESS SASH PULLEYS.

4-C-3653. Made and finished in a superior manner. With 2 1/2 inch turned wheel. Steel axle, plated antique copper polished face. Per dozen.....\$1.08

DOOR BUTTONS.

4-C-3655. Japanned finish. Without screws or plates. Length 1 1/2 inches. Per gross.....24c Per dozen.....30c Length 2 inches, Per gross.....38c Per dozen.....40c

STOP SCREWS AND WASHERS.

4-C-3657. Antique copper finish. Per gross.....68c Per dozen.....80c 4-C-3659. Old or lemon brass finish. Per gross.....73c Per dozen.....70c

CAST IRON FOOT SCRAPER.

Japanned finish. 4-C-3661. Each.....30c

COAT, HAT AND UMBRELLA HOOKS.

4-C-3663. Single pattern. Electro polished antique copper finish. With screws to match. Height 7 inches. Projects from wall 4 inches. Per dozen.....\$1.25 Each.....11c 4-C-3665. Double pattern. Height 9 inches. Projects from wall 4 1/2 inches. Spread 10 inches. Per dozen.....\$3.30 Each.....28c

COAT AND HAT HOOKS.

4-C-3667. Made of copper plated spring steel wire. Gimlet pointed screws. Length 3 inches. Per gross.....58c Per dozen.....60c

CLOSET AND WARDROBE HOOKS

4-C-3669. Made from heavy copper plated plain steel wire. Will not rust. Gimlet pointed screws. Length 3 inches. Per gross.....77c Per dozen.....70c

JAPANNED COAT AND HAT HOOKS.

4-C-3671. Heavy iron hooks. Suitable for schools and public coat rooms. Japanned finish. Strong and durable. Length 3 inches. Per gross.....\$1.80 Per dozen.....18c

COAT AND HAT HOOKS.

4-E-3674. Japanned Iron, a strong durable hook with screw end. Per gross.....81c Per dozen.....70c

SCREEN DOOR SETS.

4-C-3673. Consists of one pair japanned hold back spring hinges, one steel door pull, one hook and eye, complete with screws. Per set.....10c

SCREEN DOOR CATCHES.

4-C-3675. Vienna bronze finish for doors 1/2 to 1 1/2 inches thick. To be used on doors opening outwards. Furnished complete with stop, knobs and screws. Per dozen sets.....\$1.29 Per set.....12c 4-C-3677. Electro bronze plated raised surface, dull background. Complete with stop, knobs and screws. Per dozen sets.....\$2.69 Per set.....23c

SCREEN DOOR HINGES.

4-C-3679. Hold back spring hinges, the strongest and best manufactured. Japanned case. Screws not furnished. Per dozen pairs.....85c Per pair.....80c

TORREY'S READY DOOR SPRING.

4-C-3681. Steel rod door spring. Furnished with a special wrench with each set for adjusting tension. Length 39 inches. Per dozen.....\$1.25 Each.....12c

SPIRAL DOOR SPRINGS.


4-C-3683. Made from special grade highly tempered steel wire, fastened securely to the bracket and spring holder. Adjustable tension. Length 10 inches. Per dozen.....85c Each.....90c

WARNER SCREEN DOOR SPRINGS.

4-C-3685. Made of heavy spring steel wire, copper plated. Per dozen.....57c Each.....50c

ELECTRO PLATED DOOR PULLS.

4-C-3687. Wrought steel antique copper finish. Length 4 1/2 inches. Per dozen.....23c Each.....20c



HIGH GRADE ELECTRO PLATED POLISHED WROUGHT STEEL BALL TIPPED BUTTS.

Guaranteed to be the best finished wrought steel butts manufactured. Heavy, highly polished and finely finished. Furnished with screws to match.

4-C-3501. Antique copper polished finish.

Inch.....	2x2	2 1/2x2 1/2	3x3	3 1/2x3 1/2	4x4	4 1/2x4 1/2	5x5
Per pair.....	\$0.21	\$0.24	\$0.26	\$0.30	\$0.34	\$0.39	\$0.42
Per doz. pairs.....	2.27	2.60	2.81	3.24	3.78	4.12	4.59

4-C-3503. Old or Lemon Brass Finish.

Inch.....	2x2	2 1/2x2 1/2	3x3	3 1/2x3 1/2	4x4	4 1/2x4 1/2	5x5
Per pair.....	\$0.22	\$0.25	\$0.27	\$0.31	\$0.35	\$0.39	\$0.43
Per Doz. Pairs.....	2.38	2.70	2.92	3.35	3.78	4.22	4.65

ELECTRO PLATED PLANISHED BALL TIPPED BUTTS.

Electro Plated Planished. Made of the same grade steel and generally sold as a polished butt. In every sense equal to the high grade Butts, except not as finely finished. Furnished with screws to match.

4-C-3505. Antique copper Finish.

Inch.....	2x2	2 1/2x2 1/2	3x3	3 1/2x3 1/2	4x4	4 1/2x4 1/2	5x5
Per pair.....	\$0.12	\$0.13	\$0.15	\$0.17	\$0.19	\$0.28	\$0.29
Per Doz. Pair.....	1.37	1.49	1.71	1.94	2.17	2.53	3.31

PLANISHED WROUGHT STEEL BUTTS.

4-C-3507. Old or Lemon Brass Finish.

Inch.....	2x2	2 1/2x2 1/2	3x3	3 1/2x3 1/2	4x4	4 1/2x4 1/2	5x5
Per pair.....	\$0.13	\$0.14	\$0.16	\$0.18	\$0.20	\$0.24	\$0.30
Per Doz. Pair.....	1.41	1.59	1.83	2.05	2.28	2.74	3.42

SINGLE ACTING ADJUSTABLE TENSION SPRING HINGES.

4-C-3509. Swings one way. Reversible for right or left hand doors. Black Japanned finish.

Size, Inches.	For Doors Thickness, Inches.	Price, Per Pair
3.....	1 to 1 1/2	\$0.39
4.....	1 1/2 to 2	.52
5.....	2 to 2 1/2	.65
6.....	2 1/2 to 3	.82
8.....	3 to 4	1.57



DOUBLE ACTING ADJUSTABLE TENSION SPRING HINGES.

4-C-3541. Swings both ways. Reversible for right or left hand doors. Black japanned finish.

For Doors Thickness, Inches.	Price, Per Pair.
3 to 1 1/2	\$0.80
4 to 2	1.03
5 to 2 1/2	1.26
6 to 3	1.73
8 to 4	2.97

DOUBLE ACTING ADJUSTABLE FLOOR HINGES.

Easily put on and adjusted to proper tension, complete with directions.

4-C-3543. Japanned finish.	For Doors 1 to 1 1/2 in. thick.....	\$1.00
	For Doors 1 1/2 to 2 in. thick.....	\$1.25
4-C-3545. Antique Copper Finish.	For Doors 1 to 1 1/2 in. thick.....	\$1.35
	For Doors 1 1/2 to 2 in. thick.....	1.65
4-C-3547. Old or Lemon Brass Finish.	For Doors 1 to 1 1/2 in. thick.....	\$1.37
	For Doors 1 1/2 to 2 in. thick.....	1.67



HINGES.


For cabinets, China Closets, etc. Wrought steel beautifully finished, strong and durable. Fast pin. Size, 2 1/2 inches. Packed with screws to match.

4-C-3537. Antique Copper Finish.	Per dozen pair.....	\$1.14
4-C-3539. Old or Lemon Brass Finish.	Per pair.....	10c



AUSTIN DESIGN BRONZE PLATED CAST BUTTS.


4-C-3575. Black background, Polished raised surface, complete with screws to match.	3x3	3 1/2x3 1/2	4x4	4 1/2x4 1/2
Per pair.....	\$0.26	\$0.32	\$0.37	\$0.42



JAPANNED LOOSE PIN BALL TIPPED STEEL BUTTS.

4-C-3577. Made of heavy steel, nicely japanned. Screws not included.

Inch.....	2x2	2 1/2x2 1/2	3x3	3 1/2x3 1/2
Per Pair.....	\$0.05	\$0.06	\$0.07	\$0.09
Per Doz. Pair.....	.59	.71	.83	.99
Inch.....	4x4	4 1/2x4 1/2	5x5	
Per Pair.....	\$0.11	\$0.14	\$0.16	
Per Doz. Pair.....	1.25	1.59	1.81	



NARROW FAST PIN WROUGHT STEEL BUTTS.

4-C-3579. Plain Finish, without screws.

Inch.....	1	1 1/2	2	2 1/2	3
Per Doz. Pair.....	10c	14c	17c	22c	29c 37c



ELECTRO PLATED POLISHED TRANSMO BUTTS.

Heavy wrought steel, fast pin, finely finished, with screws to match.

4-C-3581. Antique Copper Finish.	3x3	3 1/2x3 1/2	2 1/2x3 1/2
Per Pair.....	\$0.18	\$0.22	\$0.27
Per Dozen Pair.....	2.10	2.55	3.15



Size 2 1/2x9 1/2 inch finely finished with screws to match.

4-C-3583. Antique copper finish. Ea. 45c	
4-C-3584. Old or lemon brass finish. Ea. 46c	
4-C-3585. Antique Copper finish. Ea. 13c	
4-C-3586. Old or Lemon brass finish. Ea. 20c	

ELECTRO PLATED POLISHED WROUGHT STEEL CHAIN BOLTS.

Length 6 inches with 2 feet of chain. Screws to match.

4-C-3511. Antique Copper Finish.	Price.....	35c
4-C-3513. Old or Lemon Brass Finish.	Price.....	37c

ELECTRO PLATED POLISHED WROUGHT STEEL FOOT BOLTS.

Finely finished, spring release. Length, 6 inches, with screws to match.

4-C-3515. Antique Copper Finish. Price.....	33c
4-C-3517. Old or Lemon Brass Finish. Price.....	34c



TRANSMO LIFTERS.

Used in connection with transoms, hinged at top, bottom or pivoted in the middle. By means of this lifter transoms can be opened and locked at any angle, affording ample means of ventilation. The strongest transom lifter on the market.

4-C-3519. Plain Coppered Finish.

Length, feet.....	3	4	5	6
Price, each.....	9c	11c	21c	26c

4-C-3521. Electro Bronze Plated Antique Copper Finish.

Length, feet.....	3	4	5	6
Price, each.....	18	21c	32c	37c

HOOK SASH LIFTS.

Heavy High Grade Bevel Edges. Finely finished. Size, 1 1/2 inches. With Screws to match.

GENUINE WROUGHT BRONZE METAL.

4-C-3523. Antique Copper Polished Finish.	Per dozen.....	44c
4-C-3525. Old or Lemon Brass Finish.	Per dozen.....	44c

ELECTRO BRONZE PLATED WROUGHT STEEL.

4-C-3527. Antique Copper Polished Finish.	Per dozen.....	17c
4-C-3529. Old or Lemon Brass Finish.	Per dozen.....	17c

AUSTIN DESIGN BRONZE PLATED CAST HOOK SASH BOLTS.

4-C-3531.	Per dozen.....	33c
	Each.....	33c

AUSTIN DESIGN BRONZE PLATED IRON CHAIN AND FOOT BOLTS.

Black background and polished raised surface. Length, 6 inches. Chain bolt fitted with 2 feet of copper chain. Screws to match.

4-C-3549. Chain Bolt. Price.....	24c
4-C-3551. Foot Bolt. Price.....	23c

TRANSMO CATCHES.

Electro Plated Wrought Steel. Bronze metal ring with screws to match. Size, 2 1/2x1 1/2 inches.

4-C-3553. Antique Copper Polished Finish.	Doz. 98c	Each.....	9c
4-C-3555. Old or Lemon Brass Finish.	Doz. 98c	Each.....	9c

BAR SASH LIFTS.

Electro Plated Wrought Steel. Length of handle, 2 inches; length over all, 4 inches.

4-C-3557. Antique Copper Finish.	Doz. 67c	Each.....	6c
4-C-3559. Old or Lemon Brass Finish.	Doz. 67c	Each.....	6c

GENUINE WROUGHT BRONZE BAR SASH LIFTS.

With Screws to match.

4-C-3561. Antique Copper Finish.	Doz. \$1.29	Each.....	12c
4-C-3563. Old or Lemon Brass Finish.	Doz. \$1.29	Each.....	12c

WINDOW SPRING BOLTS.

4-C-3565. Japanned Bolt, Tin Case. Per gross.....92c Per dozen.....8c

FLUSH SASH LIFTS, BRONZE PLATED WROUGHT STEEL.

Size 1 1/2x3 1/2 complete with screws.

4-C-3567. Antique Copper Finish.	Doz. 45c	Ea. 4c
4-C-3569. Old or Lemon Brass Finish.	Doz. 45c	Ea. 4c

GENUINE WROUGHT BRONZE FLUSH SASH LIFTS.

size 1 1/2x3 1/2 With Screws.

4-C-3570. Antique Copper Finish.	Doz. 80c	Ea. 8c
4-C-3571. Old or Lemon Brass Finish.	Doz. 80c	Ea. 8c

REVERSIBLE CASEMENT FASTENERS.

Electro Plated, Finely Finished for Casement or French Window. Size, 1 1/2x1 1/2 inches. Complete with screws to match.

4-C-3587. Antique Copper Finish.	Price, each.....	22c
4-C-3588. Old or Lemon Brass Finish.	Price, per Set.....	23c

GENUINE BRONZE METAL, HIGHLY POLISHED.

4-C-3589. Antique Copper Finish.	Price, each.....	39c
4-C-3590. Old or Lemon Brass Finish.	Price, per Set.....	40c

CUPBOARD CATCHES.

Electro Plated, Polished Wrought Steel with screws to match.

4-C-3591. Antique Copper Finish.	Per dozen.....	64c
4-C-3592. Old or Lemon Brass Finish.	Per dozen.....	64c

GENUINE WROUGHT BRONZE CUPBOARD CATCHES.

4-C-3593. Antique Copper Polished Finish.	Doz. \$1.52	Ea. 14c
4-C-3594. Old or Lemon Brass Finish.	Doz. \$1.52	Ea. 14c

AUSTIN DESIGN BRONZE PLATED CUPBOARD CATCH.

4-C-3595. With Screws.	Per dozen.....	\$1.83
	Price, each.....	16c

CUPBOARD TURNS. Electro Plated, Polished Wrought Steel.

4-C-3596. Antique Copper Polished Finish.	Per dozen.....	\$1.12
4-C-3597. Old or Lemon Brass Finish.	Per dozen.....	\$1.12

GENUINE WROUGHT BRONZE CUPBOARD TURNS.

4-C-3598. Antique Copper Finish.	Doz. \$2.75	Each.....	24c
4-C-3599. Old or Lemon Brass Finish.	Doz. \$2.75	Each.....	24c

RUBBER TIPPED HARDWOOD BASE KNOBS.

4-C-3572. Screws well pointed.	Per dozen.....	13c
	Each.....	2c

METAL BASE KNOBS, WROUGHT STEEL, BRONZE PLATED. Extra Long Heavy Screws, Heavy Rubber Tip, Length 2 1/2.

4-C-3573. Antique Copper Finish.	Doz. 65c	Ea. 6c
4-C-3574. Old or Lemon Brass Finish.	Doz. 65c	Ea. 6c

BALL BEARING PARLOR DOOR HANGERS AND TRACK.

Full ball bearing noiseless vulcanized fiber wheels. Hangers made entirely of steel and easily adjustable. Track is made of special cold rolled steel, rigid and firm. The strongest and best parlor door fixtures made. Full directions packed with each set.

Prices are for hangers complete with track.

4-C-3701. For double doors. Size opening, feet. \$3.19 \$3.33 \$3.47 \$3.61

4-C-3703. For single doors. Size opening, feet. \$1.69 \$1.91 \$2.21 \$2.67

FIBER TREAD NOISELESS BALL BEARING PARLOR DOOR HANGERS AND TRACK.

The heaviest, strongest and best hanger of its kind on the market. Made entirely of steel, with full ball bearing fiber tread rollers. Furnished complete with hangers, track and all necessary fixtures. Easy to put up and simple in adjustment.

4-C-3705. For double doors. Complete with 14 feet of steel track and fixtures. Per Set, \$3.11

4-C-3707. For single doors. Complete with 8 feet of steel track and fixtures. Per Set, \$1.63

ELECTRO PLATED SWINGING DOOR HOLDERS.

Spring release. Operated with foot. Rubber tipped bolt. Will not mar floor or injure the carpet. Holds door at any angle. Strong and durable.

4-C-3709. Japanned finish. Price. 41c

4-C-3711. Antique copper polished finish. Price. 47c

4-C-3713. Old or lemon brass finish. Price. 48c

STORM THRESHOLDS.

4-C-3715. Will prevent rain and snow beating under the door. Made of best quality gray iron. Size given is length between jambs.

4-C-3717. Rubber weather strip. Effectually seals cracks around window and door, keeping out the cold. Made of the best grade of rubber, and will give excellent service.

4-C-3719. Felt weather strip. Made of strong, durable black wool felt. 1 inch width for windows; 1 inch width for sides and tops of doors; 1 inch width for bottoms of doors. Put up in packages containing 50 feet. Easily and quickly applied.

RURAL FREE DELIVERY MAIL BOXES.

Without extra charge we put customer's name on each box and include with shipment a heavy paper stenciled name, which can be used to excellent advantage for making implements, bags, etc. When ordering in quantities give the names for marking of each box with which stencils will be included.

A substantial, well constructed square bottom mail box. One of the best values ever offered. Made of heavy galvanized steel, painted with rustproof aluminum paint. Edges nicely turned and finished. Riveted joints, sloping cover which overhangs, making it absolutely weatherproof. Fitted with automatic flag signal for out going mail, hasp for pad lock. Length 18 inches, width 6 inches, depth 6 inches.

4-C-3721. Price each, without coin holder. 45c

4-C-3723. Price each, with coin holder. 51c

We save you 30 to 50% on Fencing

CHICAGO HOUSE WRECKING CO. 35th and Iron Sts., Chicago.

PADLOCKS

We offer a line of strictly high grade pad locks made and finished in the best possible manner. All locks are spring shackled, self-locking. Measurements given are of the body only and do not include shackle. Each lock is fully warranted.

SOLID STEEL PAD LOCK.



Stronger and more durable than the old style wrought iron pad locks. Generally sold at the price at which we offer the steel locks. Case is made of annealed steel. Contains no rivets or loose parts. Japanned finish polished shackles, with two keys. Width 2 1/2 inches.

4-C-3725. Price. 7c


SOLID STEEL PAD LOCK WITH BRASS DROP.



Brass drop over key hole. Case made of annealed steel. Contains no rivets or loose parts. Shackles made of highest quality malleable iron polished. A strong, durable lock, which will give excellent satisfaction. Japanned case with two keys. Width 2 1/2 inches.

4-C-3727. Price. 9c

ORNAMENTAL STEEL PAD LOCK.




One of our best values. Ornamental brass plated steel case, strong spring shackle, self-locking, with two flat steel keys. Width 1 1/2 inches.

4-C-3729. Price. 13c

STRICTLY HIGH GRADE PAD LOCK.

GOOD ENOUGH FOR ANY PURPOSE.



Genuine gun, bronze metal case. Solid hard brass inside work. Extra strong self-locking shackle and locking bolts. Dustproof plunger, cylinder key hole guide, handsomely finished. A strictly first class, high grade lock in every particular, with two nickel plated flat steel keys. Width 2 inches; height, including shackle, 2 1/2 inches.

Furnished with and without chain. 57c

4-C-3731. Without Chain. Price. 57c

4-C-3733. With 9-inch steel chain. 67c

as shown in illustration.

PERFECTION ROUND BOTTOM MAIL BOXES.

Made of heavy galvanized sheet steel painted with rustproof aluminum paint. Heavy seamed joints, edges nicely turned and finished. Sloping cover which overhangs, making it absolutely weatherproof. Fitted with automatic flag signal for out going mail, hasp for pad lock. The strongest and best constructed round bottom box manufactured. Length 18 inch, width 6 inch, depth 6 inch.

4-C-3735. Price each, without coin holder. 58c

Price per Dozen. \$6.93

4-C-3737. Price with coin holder. 65c

Price per Dozen. \$7.75


A STRONGER AND BETTER LOCK THAN HAS HERETOFORE BEEN OFFERED AT THE PRICE.



Solid wrought steel case, heavily brass plated and handsomely finished. Six secure levers, all brass inside work. Self-locking spring shackle. Easily worth double the price of any iron lock of the same style. Two flat steel keys. Width 2 1/2 inches.

4-C-3739. Price. 19c

CASE IS MADE OF GUN BRONZE METAL.



Phosphor bronze springs. Full six lever solid hard brass inside work. Cannot rust or corrode. Two flat keys. Strong and secure. One of the best locks made for outdoor use. Width 2 1/2 inches.

4-C-3741. Price. 37c

LONG SHACKLE, FULL 6-LEVER, GUN BRONZE METAL, CASE, PHOSPHOR BRONZE SPRINGS.



With 9 inch steel chain. Designed especially for gates, store doors, etc. Solid hard brass inside work. No amount of exposure will cause rust or corrosion. Width 2 1/2 inches. Height, including shackle, 3 inches.

4-C-3743. Price. 45c

THREE LEVER SOLID BRASS PAD LOCK.



A strong secure lock, suitable for outside use. Heavy spring shackle, self-locking. Width 2 inches.

4-C-3753. Price. 21c

A STRONG, SECURE RUST-PROOF LOCK WITH EIGHT LEVERS.



Wrought steel case, brass plated inside and out, heavy self-locking shackle. 2 double bitted barrel keys. Width 2 1/2 inches.

4-C-3755. Price. 26c


SOLID WROUGHT STEEL PAD LOCK.



Heavy brass plated, heavy self-locking spring shackle. Six secure levers, 2 double bitted barrel keys. A strong, durable lock and an exceptional value.

4-C-3757. Price. 17c


SOLID BRONZE BICYCLE LOCK.



4-C-3745. Extra strong shackle and bolts. Self-locking spring shackle. Furnished with 10 inches nickel plated steel chain with solid steel ring. Two keys. A strictly first class lock, fully guaranteed.

Price each. 23c

RURAL FREE DELIVERY SOLID BRASS PAD LOCK.



Solid hard brass inside work. Will not rust or corrode. Automatic spring shackle that flies to quarter turn position when unlocked. Price includes two keys with each lock. One master key for use of mail carrier furnished with each dozen locks. Width of lock 1 1/2 inches. Height of lock, including shackle, 2 1/2 inches. The best mail box lock manufactured.

4-C-3747. Without chain. Price each. 19c

Price per dozen. \$2.16

4-C-3749. With 6-inch brass chain. 23c

Each. \$2.70

4-C-3751. Extra Master Keys. 10c

Note.—The government requires all master keys to be delivered by us to the postmaster or office at which rural route originates. In ordering give name and address of postmaster to whom master key is to be sent.

Carry Complete Line of Pumps at Lowest Prices.

ROLLER BEARING TROLLEY BARN DOOR HANGERS.

Wheels run inside of hollow steel track and are weather and sleet proof. Cannot bind or jump the track. Suitable for doors 1½ to 2½ inches thick. A set consists of two hangers, two end brackets and one center bracket. Complete with screws and bolts. Center brackets should be spaced not more than 3 feet apart.

4-C-3901. Price per set, complete, without track.....\$1.25
TROLLEY TRACK.

4-C-3903. Trolley track for above hangers, brackets not included. Lengths, 4, 5, 6, 8 and 10 feet. Price, per foot.....10c

STEEL CENTER BRACKET FOR TROLLEY TRACK.

4-C-3905. Steel Center Brackets for above track. Japanned Finish, complete with lag screws for attaching. Price, each.....10c

GALVANIZED HITCHING RINGS.



4-C-3985. 2½-inch Malleable Ring, wrought steel screw. Price, per dozen.....44c
Price, each.....5c



BARN DOOR BOLT.

4-C-3907. Heavy Pattern, suitable for stables and out-houses. Length, 8 inches. Price, each.....14c

WROUGHT HOOKS AND STAPLES.



4-C-3923. Strictly first-class, fully warranted. Length, 4 inch. Price, each.....2c
Price, per six.....8c
Length, 6 inches. Price, each.....3c
Price, per six.....12c

POLISHED WIRE HOOKS AND EYES.




4-C-3925. Heavy Wire, Sharp pointed Screws. Length, inches. 2 3 4
Price, each..... 1c 1c 2c
Price, per dozen 6c 6c 10c

WROUGHT STEEL HINGES AND HASPS.

Strictly First Quality, Full Size. Standard sizes and weights. Fully Warranted.

LIGHT WROUGHT STEEL "T" HINGES.



Perfectly Manufactured, Full Standard Weight. Size given in measurement from joint to end of hinge. Without Screws.

4-C-3927.
Size, Inches. 3 4 6 8
Price Per Pair.....\$0.03 \$0.03 \$0.04 \$0.05
Price Per Dozen Pair..... 0.24 0.29 0.40 0.50

HEAVY WROUGHT STEEL "T" HINGES.

The Best and Most Serviceable "T" Hinge Made. Size given in measurement from joint to end of hinge. Without Screws.



4-C-3909.
Size, Inches. 6 8 10 12 14
Per Per Pairs.....\$0.06 \$0.07 \$0.11 \$0.15 \$0.20
Price Per Dozen pair..... 0.88 0.78 1.25 1.71 2.37

BARN DOOR STAY ROLLERS.



4-C-3911. Reversible for inside and outside doors. Adjustable for any thickness of door. Diameter of wheel, 2 inches. Price, each.....8c

WROUGHT STEEL HASPS AND STAPLES.



Heavy wrought steel with double Hook.

4-C-3913.
Length, Inches. 6 8 10
Per Dozen..... 15c 19c 27c
Each..... 2c 2½c 3c


WROUGHT STEEL HINGE HASPS.



Heavy Wrought Steel, without screws.

4-C-3935.
Length, Inch. 3 6 8 10
Per Dozen .. 33c 54c 70c 93c
Each..... 3c 5c 6c 9c

SECURITY COMBINATION HASP AND HOOK.



4-C-3939. Wrought Steel, Length, 8 inches. Per Dozen.....39c Each.....4c

YANKEE DOOR CATCH.



4-C-3915. For holding open swinging doors. Made of cast iron, japanned. Each.....3c

DOUBLE PIVOTED GATE HANGER.

4-C-3937. A strong practical gate hanger for a common farm gate. Weight of gate hangs on center at its strongest point. Can be easily raised to clear snow or other obstacles. Strong and durable and cannot get out of order. Is fastened to post with two lag screws. Made of steel, japanned. Price, including lag screws...38c



ANTI-FRICTION ROLLER BEARING BARN DOOR HANGERS.

Made entirely of steel except the wheel. The axle is of hardened steel. Both the wheel and axle are covered and protected from the weather. 5-16 inch bolts are used to put up these hangers and prices do not include bolts.

4-C-3917. Size of wheel, 3½ inch. For small and medium size doors.

Per dozen pairs, \$4.50. Per pair, 40c.

4-C-3919. Size of wheel, 4 inch. Suitable for the largest size doors.

Dozen Pairs.....\$5.00. Per pair.....45c



HINGE JOINT ROLLER BEARING BARN DOOR HANGERS.

Can be used on any size door or any length of run. Hinge joint makes it possible to swing the door in or out. Provided with a guard, making it impossible to jump the track. Has chilled roller bearings. Wheel, axles and bearings are fully protected from the weather. Can be used only with rail No. 4-B-2295.

4-C-3921. Price, per pair.....54c



LOOSE AXLE ANTI-FRICTION BARN DOOR HANGERS.

Guaranteed not to bind or jump the track. Wheels are mounted on hardened steel axles and owing to the construction of the hangers they are protected from the weather. Our prices do not include bolts.

4-C-3941. For doors 6 foot run. Diameter of wheel, 3 inches. Require 5-16 inch bolts. Price Per Pair.....46c

4-C-3943. For doors 8 foot run. Diameter of wheel, 4 inches. Require ¾ inch bolts. Price Per Pair.....57c

4-C-3945. For doors 10 foot run. For large heavy doors. Diameter of wheel, 5 inches. Require 1 inch bolts. Price Per Pair.....79c



STEEL BARN DOOR TRACK.



not included Price, per foot.....3½c

4-C-3947. Strong and rigid. Suitable for any ordinary door. Size, 3-16 x 1 inch. Comes in lengths, 4, 6, 8 and 10 feet. Screws


EXTRA HEAVY STEEL BARN DOOR TRACK.



that will carry heavy loads. Come in lengths, 4, 6, 8 and 10 feet. Prices do not include screws. Price, per foot.....4½c

4-C-3949. For use with hinge joint or other style of barn door hangers. Made of steel, size, 1½ x 1 inch. Strong, rigid back

WROUGHT STEEL BARN DOOR LATCH.



door lock made and easily applied. Screws not included. Price, per set.....27c

4-C-3951. Reversible. Can be opened from either side. Suitable for swinging or sliding doors. Arranged so pad lock can be used in locking. Cannot be tampered with as screws are concealed. Best barn

SELF-CLOSING GATE HINGE.



4-C-3953. Will swing both ways. Do not require spring or weight. Wrought upper hinge, cast lower hinge. Japanned finish. Per set.....24c

DOUBLE ACTING STEEL GATE HINGE.



4-C-3955. Self-Closing. Made entirely of steel. The strongest and best hinge manufactured. Per set.....40c

GATE LATCH.



4-C-3957. For right or left hand gates. Also gates that swing both ways. Adjustable to meet any sag in the gate. Each.....6c

GRAVITY GATE LATCH.




4-C-3959. Overcomes shrinking and sagging of gate posts. Made of steel and malleable iron. Easily applied and warranted to give satisfaction. Price, each.....18c

TINNED SAFETY GATE HOOKS AND STAPLES.



4-C-3981.
Length, inch..... 4 6
Each..... 4c 6c
Per dozen..... 47c 64c

BARN DOOR PULLS.



4-C-3983. Extra heavy cast iron. Each.....20c

Our Tool Sets represent unusual values

130 We Carry a Special Assortment of Screws, Bolts, etc.--Write us.

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

BOX OR TRUCK CASTERS.

4-C-3801. Heavy Iron Stationary Box or Truck Casters. Strong and substantial. Price does not include screws.

3 in. Wheel, per doz. \$1.35. Each. 12c

4 in. Wheel, per doz. \$1.80. Each. 16c

SWIVEL IRON BOX OR TRUCK CASTERS.

4-C-3803.

3 in. Wheel, per Doz. \$1.60 Each. 14c

4 in. Wheel, per Doz. 2.00 Each. 18c

ROLLER BEARING IRON BOX OR TRUCK CASTERS.

For Trucks, Boxes, Chests or any other purpose where a Strong, Heavy Caster is required.

Size Wheel Plate Per Dozen Set of Four

4-C-3805. 1 1/2 1 1/2 x 1 1/2 \$1.80 15c

4-C-3806. 1 1/2 2 1/2 x 1 1/2 2.23 19c

4-C-3807. 1 1/2 2 1/2 x 2 2.91 25c

4-C-3808. 2 2 1/2 x 2 3.56 31c

4-C-3809. 2 1/2 4 1/2 x 2 7.78 65c

4-C-3810. 4 4 1/2 x 3 10.73 92c

EASY RUNNING BALL CASTERS.

Most Practical, Easiest Running and Noiseless Casters on the market.

Will save wear and tear of your rugs, carpets and floors.

The weight is sustained entirely by a large nickel plated ball which runs under a set of ball bearings, making it possible

to move the heaviest piece of furniture with but very little effort.

Balls made of special chilled steel. Brackets and frame made of best malleable iron. Diameter of large ball, 1 1/2 in. Guaranteed Fully in Every Particular.

4-C-3125. With Stem and Socket, Set of Four. 58c

4-C-3126. With Round Plate and Screws, Set of Four. 57c

4-C-3127. With Wood Plugs for Iron Beds.

Size Plugs, inches 1/2 1 1/2

Per Set of Four. 58c 81c

ANTI-FRICTION ROLLER BEARING CASTERS.

Revolves upon a Series of Steel Rollers or Discs.

Saves wear and tear on carpets; does not mar the floors.

Size Wheel In. Doz. Sets. Set of Four

4-C-3811. 1 1/2 \$1.49 13c

4-C-3812. 1 1/2 1.95 17c

4-C-3813. 1 1/2 2.85 25c

4-C-3814. 1 1/2 3.30 29c

"FAULTLESS" PHILADELPHIA SHORT STEM STEEL HORN CASTERS.

4-C-3815. Faultless Philadelphia Short Stem Steel Horn Casters. 3/4 in. sockets, hard maple wheels.

Size Wheel Inches 1 1/2 1 1/2 1 1/2

Price Per Set 9c 10c 11c

Price Per Dozen Set \$1.02 \$1.12 \$1.24

4-C-3816.

Size Wheel Inches 1 1/2 1 1/2 1 1/2

Price Per Set 10c 12c 13c

Price Per Dozen Set \$1.12 \$1.37 \$1.50

"FAULTLESS" BED CASTERS.

Faultless Bed Casters and Sockets for Iron Beds.

Steel horn, maple wheels.

4-C-3817. To fit Tubing 3/4 in. outside Diam.

Size of wheel 1 1/2 in. Price per set. 13c

Price Per Dozen Sets. \$1.50

4-C-3818. To fit Tubing 1 in. outside Diam.

Size of wheel 1 1/2 in. Price per set. 15c

Price Per Dozen Sets. \$1.70

4-C-3819. To fit Tubing 1 1/4 in. outside Diam.

Size of wheel 1 3/4 in. Price per set. 17c

Price Per Dozen Sets. \$1.93

BED CASTERS.

4-D-3821. Bed Casters, Iron Copper Bronze.

1 1/2 in. in Diam. 7c

Per Set of 4. 81c

4-D-3822. Bed Casters. 1 1/2 in. porcelain wheel.

Per Set of 4. 7c

Per Doz. sets of 4. 81c

4-D-3823. Bed Casters, Applewood wheels.

2 in. in Diameter. 9c

Per set of 4. 103c

Per Doz. sets of 4. \$1.03

FURNITURE CASTERS, PHILADELPHIA PATTERN.

4-D-3828. Furniture Casters, Philadelphia Pattern.

3/4 in. bronzed iron wheels. Strong and durable.

Per Doz. sets of four. 85c

Per set of four. 8c


STOVE OR FURNITURE CASTERS.

Just the thing for putting your stove away in the Spring. Heavy stoves could be easily moved around the house with a set of these Casters. They are also heavy enough for use with other furniture of heavy weight. Can be attached to a box or platform.

4-D-3829. Price per set of 4. 68c

CHICAGO HOUSE WRECKING CO.


35th and Iron Sts., Chicago.



CHEST HANDLES.
4-D-3830. Japanned Iron Chest Handles. Size, 4 in. without Screws. Per dozen pairs. 94c
Per Pair. 7c



DRAWER LOCKS.
4-D-3831. 2 1/2 in. wide. Has two secure levers for wood 1/2 in. thick. Each Lock furnished with one key. Per Dozen. \$3.25 Each. 29c
4-D-3832. Brass Drawer Locks. Same as above. Per Dozen. 4.75 Each. 41c




SELF LOCKING CHEST LOCKS.
4-D-3833. All Iron with Brass Keyhole Escutcheon Double bitted keys. Width, 2 1/2 inches. Per Dozen. \$4.35 Each. 37c



BRASS PICTURE CHAINS WITH HOOKS. Length, 36 inches. Can be easily shortened. 4-D-3836. For light picture frames. Per Dozen Pairs. \$1.10 Per Pair. 10c
4-D-3837. For heavy picture frames. Per Dozen Pairs. \$1.35 Per Pair. 12c



PICTURE NAILS.
4-D-3838. White Porcelain head, gilt rim, coppered nails. Heads removable for driving. Per dozen. 8c
BRIGHT BRAIDED PICTURE WIRE.
4-D-3839. Heavily Tinned. Coils guaranteed to contain full 75 feet. Per Dozen Coils. 45c Per Coil. 4c




BRIGHT WIRE SCREW EYES.
4-D-3850. Gimlet Pointed Screws. Perfectly formed eyes. Size No. Length. Per Dozen. Per Gross. 105 2 4c 35c 108 1 3/2 21c 110 1 1/2 17c 112 1 1/2 12c 114 1 1/2 11c 214 1 2c 10c

BARREL BOLTS.
4-D-3855. Wrought Steel Japanned Bolts. Polished steel bolt, brass knob. Length of bolt, in. 3 4 5 6 Each. 3c 4c 5c 6c Per dozen. 34c 45c 55c 65c


WROUGHT STEEL ELECTRO COPPER PLATED BARREL BOLTS
complete with screws to match. 4-D-3856. Antique Copper finish. 4-D-3857. Old or Lemon Brass finish. Length, inch 3 4 5 Each. 7c 8c 10c Per dozen. 78c 85c \$1.12

AUTOMATIC STOCK WATERER.
4-D-3858. Can be readily connected to barrel or tank. Equipped with automatic valve, will not rust, which shuts off supply of water when bowl is filled. Fills up as fast as the stock is watered, insuring a fresh supply of water, preventing waste. Capacity about 4 quarts. Size of connection, 3/4 inch. Weight, about 12 pounds. Price. \$1.29


CYLINDER STEEL DRAWER LOCK.
4-D-3834. Brass Cylinder strong and secure. For wood 1/2 inch thick. Width, 1 1/2 in. with 2 Nickel Plated Flat Steel Keys. Per Dozen. \$2.60 Each. 22c




CAST BRASS KEYHOLE ESCUTCHEON.
4-D-3840. Complete with Pins. Per Dozen. 21c Per six. 12c




DRAWER DROP HANDLES.
4-D-3842. Black Enameled Handles. Brass plate, nicely finished. Per Dozen. 45c Per Four. 16c



CAST BRASS KNOBS.
4-D-3844. 1 1/2 in. in Diameter. Per Dozen. 55c Per Four. 19c




BRASS DRAWER HANDLES.
4-D-3846. Bolts 3 in. from center to center. Heavy stamped brass. Per Dozen. 53c Each. 5c




PICTURE MOLDING HOOKS.
4-D-3848. Brass Plated. Per Dozen. 5c




SOLID BRASS PICTURE MOLDING HOOKS.
4-D-3849. Per Dozen. 20c




WARDROBE AND CUPBOARD LOCKS.
4-D-3835. Two Secure Levers. For right or left hand door. Wide Bolt. Width, 1 1/2 in., length, 3 in. With one Fancy Bow Key. Per Dozen. \$2.60 Each. 22c




STAMPED BRASS KEYHOLE ESCUTCHEON.
4-D-3841. Complete with Pins. Per dozen. 10c




CAST BRASS KNOBS.
4-D-3843. 1 1/2 inch in diameter. Finely finished. Per dozen. 35c Per Four. 14c




STAMPED BRASS DRAWER HANDLE.
4-D-3845. Bolts 3 in. from center to center. Per Dozen. 31c Each. 3c




CAST BRASS DRAWER HANDLE.
4-D-3847. Hand-some design. Bolts 3 in. from center to center. Per Dozen. 81c Each. 8c




PICTURE KNOBS.
4-D-3850. White Porcelain Knobs. Round head, gimlet pointed screws. Per Dozen. 13c



SCREW AND CUP HOOKS.
Polished Brass, Full Size. Either kind same price. Be sure to state Number and Size required.



WAREHOUSE TRUCK.
Suitable for heavy trucking. Capacity, 1,000 lbs. Made of second growth white oak. Handles are well proportioned, 46 inches long by 1 1/2 x 1 1/2 inches. With four extra strong cross braces instead of three which are used on all other trucks. Three horizontal cross braces are tenoned, the style of construction which adds rigidity and strength and is not found in other trucks of this style. Heavily ironed and bolted. Guaranteed not to spread. Wheel 6 in. in diameter; heavy iron nose, width, 12 inches. Well finished and varnished. Wt. 25 lbs. 4-D-3859. Price. \$1.75



BAG HOLDING TRUCK.
4-D-3860. Saves the labor of one man. Bag holder is adjustable for different lengths of sacks. Will hold the sack without tearing. The wheels and axles made to swing out like an easel and hold the truck in a self-sustaining upright position (as shown in illustration), while filling sack. The bag holder can be removed from the truck and attached to the side of the bin or elsewhere and used for filling sacks equally as well as on the truck. Indispensable for the farm, store or warehouse. The handles are all proportioned 46 inches long by 1 1/2 by 1 1/2 inches. Width of truck at nose, 12 inches. Well ironed and can be used as a handy truck. Wt. 25 lbs. Price. \$2.27

Ask for Samples and Actual Colors of Men's High Grade Suits.

2³/₄
PER POUND \$

Mixed Bolts


2³/₄
PER POUND \$

JUST WHAT YOU NEED

Convenient for Factory, Shop, Farm and any one who has an occasion to use a bolt. Each box consists of an assortment of carriage, machine, tire, plow and stove bolts, ranging in size from $\frac{1}{4}$ inch to $\frac{3}{4}$ inch in diameter up to 8 inches in length. These bolts are taken from regular stock bolts where the paper package has become broken and instead of putting them up again in packages, they are put in with the mixed bolts. These bolts if bought from any jobber or dealer would cost you three times what we are selling them at.

GREATEST BARGAIN EVER OFFERED FINE HANDY ASSORTMENT

**YOU CANNOT BUY ON EVERY \$1⁰⁰ WORTH
BOLTS AT THIS
LOW PRICE
FROM ANY
OTHER
FIRM
IN THE
WORLD**



**YOU BUY
OF THESE
BOLTS
YOU
SAVE**

\$2.00

**ABOUT ONE-THIRD
OF REGULAR PRICE**

No. 4-D-4083

**PRICE FOR 500 pounds or more, per lb....\$0.02 $\frac{1}{2}$
PRICE FOR 100 pound box, per box.....3.50
PRICE FOR 50 pound box, per box.....1.98**

ORDER NOW


The price on bolts at the present time is the lowest they have ever been. Take advantage of this opportunity.

45¢ 100 CARRIAGE BOLTS 45¢

IN ASSORTED SIZES
18 Sizes to the Box
THE HANDIEST
ASSORTMENT OF BOLTS EVER OFFERED
AT THIS LOW PRICE

List of Sizes in each box

Diam.	Length
x	1 1/2
x	2
x	2 1/2
x	3
x	3 1/2
x	4
x	4 1/2
x	5
x	6



List of Sizes in each box

Diam.	Length
x	3 1/2
x	4
x	2 1/2
x	3
x	3 1/2
x	4
x	5
x	6

Worth 85c

Our Price 45c

YOU NEED THIS BOX OF BOLTS

This assortment of carriage bolts is made up especially to meet the requirements of Farmers, Mechanics, Blacksmiths and Liverymen for repairing wagons, buggies, plows, engines, various farm implements and other items to numerous to mention; also for anyone who has occasion to use bolts for various purposes.

Each box contains an assortment of 18 lengths and sizes ranging from the smallest size 1/2" Dia. x 1 1/2" long to the largest 1" Dia. x 6" long. This assortment will cover all requirements for ordinary repair work. These bolts made up and boxed at our factory.

Include one of these packages in your order for other goods. It will help to make up weight.

No. 4-D-4075. This Box for..... **45c**

ORDER NOW

\$2.40 300 BOLTS 300 WASHERS 5LBS. RIVETS 20LBS. NAILS \$2.40

THE ABOVE ASSORTMENT

- 300 Carriage Bolts in 18 sizes ranging in size from 1/2" Dia. x 1 1/2" long to 3/4" Dia. x 6" long.
- 300 Washers to fit above Bolts.
- 5 pounds mixed Rivets ranging in sizes from 1/8" Dia. x 1/4" long to 3/8" Dia. x 3/4" long.
- 20 pounds mixed Wire Nails ranging in sizes from 3d to 60d.

**You
Need
This
Assortment**



\$2.40

**It Will
Answer
Every
Purpose**

This assortment is one of the best and handiest ever offered our customers. The same assortment if bought of your local dealer would cost you at least \$4.00. It will pay for itself many times over, as often times you will require a certain size bolt, rivet or nail, you may need only a few of this size, now if you go to your local dealer, for such a small quantity he will charge you an exorbitant price. In our assortment you will always find the size you need. This package weighing 50 pounds will help make up shipping weight on any order for other goods you may place with us.

No. 4-D-4079. This box shipping weight 50 lbs. **\$2.40**

CHICAGO HOUSE WRECKING CO.
 35th & Iron Streets, Chicago.

Our Furniture Stock is Complete. Write for New Special Catalog.

\$249 Buys "OUR GEM" TOOL SET

Specially Selected for Household or Farm Use. Consists of 19 first-class tools for which you have daily requirement. Each tool is fully warranted, thoroughly practical, and will do the work for which it is designed.

This Set is a Real \$3.50 Value



- 1 24-Inch Crucible Steel Hand Saw.
- 1 Steel Nail Hammer.
- 1 Bit Brace, 8-inch sweep.
- 3 Auger Bits, cast steel, double spur, one each size, $\frac{3}{8}$, $\frac{1}{2}$, $\frac{5}{8}$ inch.
- 4 Gimlet Bits, double cut, assorted sizes.
- 1 $\frac{1}{4}$ -Inch Leather-tipped Socket Firmer Chisel.

- 1 14-Inch Screw Driver, Champion pattern.
- 1 7-Inch Iron Block Plane.
- 1 2-foot 4-fold Boxwood Rule.
- 1 Shingling Hatchet.
- 1 Combination Anvil and Vise, $\frac{1}{4}$ -inch jaws.
- 1 8-Inch Monkey Wrench.
- 1 6-Inch Steel Tri-Square.
- 1 14-Inch Taper File with Handle.

4-C-4601 "Our Gem" Tool Set. Complete. You would pay \$3.50 at retail for tools of such high-grade quality as we offer above. **\$249**

\$657 "OUR ROUGH AND READY" TOOL SET

A Better and More Complete Selection of Good Tools than Ever Before Offered at Anything Like our Price. This set is especially desirable for those who have use for tools in and around the home and is an unusually good assortment for the beginner. You will find by carefully reading our description of this set that it contains just the tools you will require for any ordinary work. Each tool is strictly first class and can be depended upon to do the work for which they are intended.

The Tool Chest which we furnish is made of Hardwood, nicely finished, and is furnished with tray and a secure lock, and is sufficiently large to hold other tools that you may buy from time to time.

Our Rough and Ready Tool Set Consists of the Following Tools:

- 1 "Chicago Special" Hand Saw, 22 inches long.
- 1 Adjustable Wood Bottom Smooth Plane, length, 8 inches.
- 1 Bit Brace, nickel-plated, 10-inch sweep.
- 5 Double Spur Auger Bits, one each size, $\frac{3}{8}$, $\frac{1}{2}$, $\frac{5}{8}$, 1 and 1 1/2 inch.
- 1 Guaranteed Steel Nail Hammer.
- 1 Compass Saw, spring steel.
- 1 Pair of Carpenters' Pincers, length, 6 inches, claw on one handle, screw driver on other.
- 1 Drawing Knife, length, 8 inches.
- 1 High Grade Shingling Hatchet.

- 1 Carpenters' Pencil.
- 1 Champton Pattern Screw Driver, 5-inch steel blade.
- 1 2-foot Four-fold Boxwood Rule.
- 1 Pair Button Pliers, length 6 inches.
- 1 Tri Square, 6-inch.
- 1 Combination Anvil and Vise, $\frac{1}{4}$ inch jaws.
- 1 Mill File, with handle, 6 inches.
- 2 Socket Firmer Chisels, leather-tipped handles, one each size, $\frac{3}{8}$ and 1 inch.
- 1 Oil Stone, 6-inch, mounted in hardwood case.
- 1 Monkey Wrench, length 6 inches.

4-C-4605 "Our Rough and Ready" Tool Set. Complete with chest. **\$657**

OUR "TRIUMPH" TOOL SET \$14.95

The Best Value Ever Offered in a High Grade Tool Set

Each item represents the very best of their respective kinds. Every tool is selected from our regular stock and is fully guaranteed and adapted to the use of the skilled mechanic. Our price on this set is very much lower than if you bought these tools one at a time and the assortment is perfect.

The Tool Chest is of Hardwood and is strongly made and nicely finished, fitted with sliding tray, handles and a secure lock.


Inside Dimensions of Chest: 31 inches long, 16 inches wide, 9 1/2 inches deep, and is sufficiently large to hold other tools which you may add to it.

Our Triumph Tool Set consists of the following tools:

- 1 Premier Extra High Grade Hand Saw, length, 26 inches.
- 1 Favorite Rip Saw, length, 26 inches.
- 1 Compass Saw, 12-inch, spring steel blade.
- 1 Iron Block Plane, length, 5 1/2 inches.
- 1 Adjustable Iron Jack Plane, length, 15 inches.
- 1 Morrell Pattern Saw Set.
- 1 Japanned Iron Saw Vise, length of jaws, 9 1/2 inches.
- 1 Slim Taper File, length, 5 inches.
- 1 Flat Mill File, length, 8 inches.
- 1 Malleable Iron File and Tool Holder.
- 1 Carpenters' Steel Square, No. 7, with Essex board measure. Length of body, 24 inches; 16-inch tongue. Both sides marked in 8ths, 4th and 1 inch.
- 1 Oil Stone, length 8 inches, mounted in hardwood case.
- 1 Pair Carpenters' Pincers, length, 8 inches. Claw on one handle, screwdriver on other.
- 1 Knurled Nail Set, tempered at both ends.
- 1 Spring Tube Punch for punching holes in leather.
- 1 Marking Gauge.
- 1 Wing Divider, polished steel, length, 8 inches.
- 1 Tri-Square.
- 1 Adjustable Plumb and Level. Polished cherry finish, arched top plates, two brass-tipped side views, length 28 inches.
- 1 Zig Zag Folding Rule, length, 5 feet.
- 1 Carpenters' Pencil.
- 1 Sliding T Bevel, rosewood handle, brass tipped, 8-inch blade.
- 5 Premier Socket Firmer Chisels. Leather tipped handles, one each size, $\frac{3}{8}$, $\frac{1}{2}$, $\frac{5}{8}$, 1 and 1 1/2 inches.
- 1 Ratchet Brace, nickel plated, polished hardwood head and handle, 10-inch sweep.
- 1 Hollow Handle Tool Set, polished cocobola handle, with 10 hand forged finely tempered tools.
- 1 Premier Drawing Knife, length of cut 10 inches.
- 1 Monkey Wrench, length 8 inches.
- 1 Cold Chisel, perfectly tempered, 1/2-inch cut.
- 6 Jennings' Pattern Auger Bits, high grade. One each size, $\frac{3}{8}$, $\frac{1}{2}$, $\frac{5}{8}$, $\frac{3}{4}$ and 1 inch.
- 1 Combination Side Cutting Plier, length 6 inches. End of one handle can be used as screwdriver; the other is pointed and can be used as a reamer.
- 4 German Pattern Gimlet Bits, extra quality. One each size, 1-16, $\frac{1}{8}$, 5-32, and 3-16.
- 1 Combination Anvil and Vise, 1 1/2-inch jaws.
- 1 Premier Shingling Hatchet, 3 1/4-inch cut.
- 1 Forged Steel Nail Hammer, size No. 1 1/2.
- 1 Chalk Line Reel and Awl.
- 1 Plumb Bob, nickel plated.
- 3 Hanks Braided Chalk Line.
- 6 Cakes Carpenters' Chalk.
- 1 Small Head Counter Sink, for wood.
- 1 Mallet, hickory head, size, 6 1/2 x 2 1/4 x 3 1/4 inches, with handle.
- 100 Assorted Tubular Rivets.
- 12 Sheets Sandpaper, assorted.

4-C-4603 Triumph Tool Set. Complete with chest. **\$14.95**

\$10⁶⁵ OUR "EXCELSIOR" TOOL SET



We offer this Set of Carefully Selected High-Grade Tools to meet the requirements of those who have any kind of general or repair work. This tool set will prove invaluable for house or farm work. If your boy has any mechanical instinct, encourage him by buying this set of tools. Every tool contained in this set is first-class and Fully Warranted.

The Tool Chest is Made of Hard Wood and is Very Substantial. It is fitted with a sliding tray and a secure lock, and is sufficiently large to hold other tools that you may wish to add from time to time.

Our Excelsior Tool Set Consists of the Following Tools:

- | | |
|---|--|
| 1 Chicago Special Hand Saw, 24 inches long. | 1 Carpenters' Steel Square, No. 1, with Essex board measure; 24-inch body, 16-inch tongue. Marked on both sides. |
| 1 Chicago Special Rip Saw, 26 inches long. | 1 Pair Combination Pliers, nickel-plated, length 5 inches. |
| 1 Iron Block Plane, length, 5½ in. | 1 Monkey Wrench, length, 10 inches. |
| 1 Adjustable Wood Bottom Jack Plane, length, 15 inches. | 1 Slim Taper File, length, 5 inches. |
| 1 Ratchet Brace, 10-inch sweep, Nickel-Plated. | 1 Mill File, length, 8 inches. |
| 1 2-foot Four-fold Rule. | 1 Iron File and Tool Holder. |
| 1 Sliding T Bevel, rosewood handle, brass-tipped, 8 inch blade. | 1 Wrought Steel Nail Hammer. |
| 3 German Pattern Gimlet Bits, one each size, 1-16, ¼ and 3-16-inch. | 1 Oval Head Marking Gauge. |
| 1 Oil Stone, length, 6 inches, mounted in hardwood case. | 3 Socket Firmer Chisels, leather-tipped handles, one each size, ¼, ½ and 1 inch. |
| 4 Extension Lip Auger Bits, one each size, ¼, ½, ¾ and 1 inch. | 1 Knurled Nail Set. |
| 1 High-Grade Shingling Hatchet, width of bit, 3¼ inches. | 1 Champion Pattern Screw Driver, 4-inch steel blade. |
| 1 Premier Drawing Knife, length of cut 10 inches. | 1 Plumb and Level, polished cherry, length, 28 inches. |
| 1 Screw Driver Bit. | 1 Carpenters' Pencil. |
| | 1 Rose Head Countersink Bit. |
| | 1 Small Head Countersink Bit. |
| | 1 Square Reamer Bit. |

4-C-4701 Excelsior Tool Set. Complete with Chest.

Retails at \$15 to \$20. Our Price

\$10⁶⁵

\$27⁹⁵ OUR "NEW EXPERT" TOOL SET

The Most Excellent and Complete Assortment of Strictly High-Grade Tools Heretofore Offered.

Every tool in this set is the best, and guaranteed to give entire satisfaction. Never before has the tool-buying public had an opportunity to purchase as fine an assortment of high-grade tools which represent a complete outfit suitable for the use of any mechanic or others who require and appreciate the value of first-class tools.


Our Fair Offer: Seeing is Believing. We appreciate the fact that notwithstanding our description it is almost impossible to fairly judge the unusual big value we are offering in this set without having an opportunity of seeing the tools and judging for yourself. Therefore we ask you to send us your order and if you are not entirely satisfied or do not consider this set to be the best value that you have ever seen, you may return it to us and we will immediately return your money.

The Tool Chest is Made of Selected Hardwood, nicely finished, has sliding tray and handles, and is fitted with a secure lock.

Inside Dimensions of Chest: 32 inches long, 18 inches wide and 12 inches deep.

Our New Expert Tool Set Consists of the Following High-Grade Tools:

- 1 Premier Extra High-Grade Hand Saw, length, 26 inches.
- 1 Premier Extra High-Grade Rip Saw, length, 28 inches.
- 1 Premier Extra High-Grade Panel Saw, length, 18 inches.
- 1 Nest of Saws, consisting of 1 handle, 3 high-grade saws, 1 each of keyhole blade, compass blade and pruning blade. All interchangeable.
- 1 Hack Saw, strong iron frame, complete with 8-inch blade.
- 1 Saw Vise, adjustable ¾-inch jaws.
- 1 Morrill Pattern Saw Set, for setting hand, rip, panel, buck and band saws.
- 4 Planes, 1 adjustable iron smooth plane, length, 9 inches; 1 adjustable iron jack plane, length, 14 inches; 1 adjustable iron fore plane, length, 18 inches; 1 double end iron block plane, length, 8 inches.
- 1 Ratchet Bit Brace, 10-inch sweep, nickel plated, polished cocobola head and handle.
- 26 Bits, for use in brace. 13 Irwin Pattern Auger Bits, carefully headed and hand filed, full polished. One each size, ¼, 5-16, ¾, 1-16, ¾, 9-16, ¾, 11-16, ¾, 13-16, ¾, 15-16 and 1 inch; 6 German Pattern Gimlet Bits, one each size, 1-16, 3-32, ¼, 5-32, 3-16 and 7-32-inch; 3 Straight Shank Twist Drills, one each size, ¼, 3-16, ¾-inch; 3 Countersink Bits, 1 rose head for metal, 1 small head for wood; 1 Square Reamer Bit; 1 Screwdriver Bit, length, 4½ inches.
- 1 Steel Square No. 3. Polished. Size of body, 24 x 2 inches, size of tongue, 16 x 1½ inches, marked in 16ths, 12ths and 8ths. Also has Essex board and brace measure.
- 1 Combined Try and Mitre Square, rosewood stock, brass lined, 7½ inches, steel blade, graduated by 8ths.



- 1 Wing Divider, polished steel, length 8 inches.
- 1 Sliding T Bevel, rosewood stock, brass tipped, 10-inch steel blade.
- 6 Premier Bevel Socket Firmer Chisels, leather tipped handles: one each size, ¼, ½, ¾, 1, 1½ and 2 inches.
- 1 Hammer, Premier, Size No. 1½. Finest hammer made. Octagon neck and poll, full nickel plated, ebonized finished handle.
- 1 Drawing Knife, Premier quality, 10-inch cut.
- 1 Shingling Hatchet, Premier high-grade, 3¼-inch cut.
- 1 Monkey Wrench, length, 8 inches.
- 1 Oil Stone, size, 8 x 2 inches, mounted in nicely finished hardwood case.
- 1 Slim Taper File, length, 6 inches.
- 1 Flat Mill File, length, 10 inches.

- 1 File and Tool Holder, malleable iron.
- 1 Bench Screw, wrought iron, 1½ inches in diameter, with patent collar and wood handle.
- 1 Pair Button Pliers, high-grade, length, 8 inches.
- 1 Pair Carpenters' Pinchers, length, 9 inches, claw on one handle, screwdriver on other.
- 4 Nail Sets, knurled handles, tempered ends, cup points, assorted sizes.
- 1 Mallet, hickory head, size, 6½ x 2½, x 3¼ inches, with mortised handle.
- 1 Screw Driver, Champion pattern, 6-inch steel blade, imitation rosewood handle.
- 1 Plumb and Level, adjustable, polished cherry finish, brass-arched top plates, two brass-tipped side views, proved glasses, length, 28 inches.

- 1 Marking Gauge, beechwood, steel points, accurately graduated.
- 1 Bench Stop, screw adjustment, reversible.
- 1 Scratch Awl.
- 1 Pair Malleable Clamps, with steel screw swivel heads, open 5 inches.
- 1 Tape Line, length, 50 feet, leather case.
- 1 Cold Chisel, octagon steel, ¾-inch cut.
- 1 Spoke Shave, iron handle, 2-inch adjustable steel cutter.
- 1 Zig Zag Folding Rule, length, 4 feet.
- 1 Revolving Spring Punch, 4 tubes, each of a different size.
- 100 Assorted Tubular Rivets.
- 1 Plumb Bob, full nickel-plated.
- 12 Cakes Carpenters' Chalk.
- 6 Hanks Braided Chalk Line.
- 1 Chalk Line Reel and Awl.

4-C-4703 Our New Expert Tool Set.

Complete with Chest, at retail this set would cost you \$35 to \$40. Our Price


\$27⁹⁵

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago

Ornamental Wire Fence and Gates at Wrecking Prices.

THE "PREMIER" HAND SAWS

EXTRA HIGH GRADE



PREMIER HAND SAWS

Premier Saws are hand made, hand smithed, hand blocked, hand filed and hand set. The material, workmanship and finish is far superior to the popular brand saws. Every detail in the manufacture is perfect and no saw leaves the factory that is not carefully inspected and tested. We want your saw orders and fully realize that in face of competition we must furnish a saw that will be entirely satisfactory to the most critical mechanic. Premier Hand Saws will do this, as they are made in the most careful and approved manner by the best sawsmiths in the trade.

4-C-4801. Premier extra high grade straight back, panel or hand saws.
Length Points to the inch Each
18-inch panel..9, 10, 11, or 12 \$1.15
20-inch panel..9, 10, 11, or 12 1.25
22-inch panel..9, 10, 11, or 12 1.35
24-inch hand..8, 9, 10 or 11 1.40
26-inch hand..7, 8, 9, 10 or 11 1.50
28-inch hand..6, 7 or 8..... 1.70

4-C-4803. Premier extra high grade, straight back, Rip saws.
Length Points to the inch Each
24-inch 5, 5½, 6 or 6½ \$1.40
26-inch 5, 5½ or 6 1.50
28-inch 4, 4½, 5, 5½ or 6 1.70
30-inch 4½ or 5 1.80

WARRANTED

to give satisfaction or they can be returned to us and the full purchase price will be promptly refunded. The blades are of special refined spring steel, perfectly tempered, full taper ground, thin back. The teeth are full beveled, hand filed and hand set and will hold a fast cutting edge; will not bind and will run with very little set. The handles are correct in shape, giving the proper hang. Made of selected, seasoned apple wood. 26 and 28-inch saws have five brass screws and the smaller sizes have four. Each Premier Hand Saw is fully warranted and is recommended for use by the mechanic and those who appreciate a good tool.

4-C-4823. Premier extra high grade skew back, panel or hand saws.
Length Points to the inch Each
18-inch panel..9, 10, 11 or 12 \$1.15
20-inch panel..9, 10, 11 or 12 1.25
22-inch panel..9, 10, 11 or 12 1.35
24-inch hand..8, 9, 10 or 11 1.40
26-inch hand..7, 8, 9, 10 or 11 1.50
28-inch hand..6, 7 or 8..... 1.70

4-C-4825. Skew Back Premier extra high grade Rip saws.
Length Points to the inch Each
24-inch 5, 5½, 6 or 6½ \$1.40
26-inch 5, 5½ or 6 1.50
28-inch 4, 4½, 5, 5½ or 6 1.70

"Chicago Special" Hand Saws

The best general purpose Saw ever offered. Made of high grade crucible saw steel, smithed and blocked by hand. Full taper ground, thin back. Teeth are full beveled, hand filed and hand set, ready for use. Strictly first class in every particular and are used largely by mechanics, who find them superior to saws sold elsewhere at prices ranging from \$1.25 to \$1.75. Selected cherry handles. Four brass screws. Made only with wide straight back thin ground.

4-C-4805. Chicago Special panel or hand saws.
Length Points to the inch Each
18-inch panel..9, 10, 11 or 12 \$0.89
20-inch panel..9, 10, 11 or 12 0.99
22-inch panel..9, 10, 11 or 12 1.09
24-inch hand..8, 9, 10 or 11 1.14
26-inch hand..7, 8, 9, 10 or 11 1.21
28-inch hand..6, 7 or 8..... 1.37

4-C-4807. Chicago Special Rip Saws.
Length Points to the inch Each
24-inch 5, 5½, 6 or 6½ \$1.19
26-inch 5, 5½ or 6 1.26
28-inch 4, 4½, 5, 5½ or 6 1.42

C. E. Jennings & Co.'s No. 70½ Narrow Blade Hand Saw

Ground thin on back and guaranteed to run without set. The special grinding on this saw is such that assists it to run without set. Full concave taper ground and adapted for rapid, smooth cutting.

Blade is of special saw steel, strictly hand made and is very popular with carpenters.

4-C-4827. Jennings' No. 70½ panel or hand saws.
Length Points to the inch Each
22-inch panel..10, 11 or 12 \$1.70
24-inch hand..8, 9 or 10 1.85
26-inch hand..7, 8, 9 or 10 2.00

4-C-4829. Jennings' No. 70½ rip saws.
Length Points to the inch Each
26-inch rip..5 or 6..... \$2.05
28-inch rip..4½, 5 or 5½ 2.2

Favorite Hand Saws

Made of good grade saw steel, set sharpened and ready for use. Hardwood handle, brass screws. A saw which will give excellent satisfaction for house and general use. It is not intended for carpenters' or mechanics' use.

4-C-4809. Favorite panel or hand saws.
22-inch panel, 10 or 12 points to the inch. Price..... 52c
24-inch hand, 8, 9 or 10 points to the inch. Price..... 57c
26-inch hand, 8, 9, or 10 points to the inch..... 62c

4-C-4811. Favorite rip saws.
26-inch rip, 5½ or 6 points to the inch. Price..... 67c
28-inch rip, 5, 5½ or 6 points to the inch. Price..... 72c

Genuine Henry Disston Hand Saws

Disston "D" 8 Hand Hammered Saws. The best known popular brand saw on the market. Guaranteed to be strictly first quality and perfect in every particular. Each saw bears the maker's name. Spring steel patent ground and tempered. Skew-back, applewood handle. Five improved brass screws. When ordering be sure and specify the number of points.

4-C-4831. 26-inch Hand Saw. 8, 9, and 10 points. Price... \$1.52
4-C-4833. 28-inch Rip Saw. 5 or 5½ points. Price... \$1.65

Nail Cutting Saw

4-C-4835. Will cut nails, pipe, bolts, soft sheet metal. Can be filed but does not require setting, being taper concave ground. Length of blade 18 inches. Price... \$1.43

Jennings Kit of Saws

For Plumbers', Electricians' and Carpenters' use. Consists of one 14-inch nail cutting, one 14-inch compass blade, one 12-inch keyhole blade. Adjustable handle. All blades interchangeable.
4-C-4837. Price..... 93c

Nest of Saws

Consisting of one 14-inch panel saw, one 14-inch compass saw, one 12-inch keyhole saw. All interchangeable.
4-C-4839. Price..... 68c

COMMON COMPASS SAWS

4-C-4813. Made of good grade cast steel. Spring tempered, filed and set. Beechwood handles.
Length, inches..... 12 14
Price..... 12c 14c

HIGH GRADE COMPASS SAWS

4-C-4815. Thin back, evenly tempered. Full bevel, filed and set. Beechwood handle, two screws.
Length, inches, 10 12 14 16
Price..... 20c 23c 25c 28c

STEEL FRAME COPING SAW

4-C-4817. Nickel plated steel frame. Depth of cut 4 inches. Complete with 13 6-inch tempered steel blades. Price... 14c

BEECHWOOD SAW HANDLES.

4-C-4819. For Hand and Rip Saws. Price, each..... 9c
4-C-4821. For Panel Saws. Ea. 9c

BRASS SAW HANDLE SCREWS.

4-C-4841. Each... 2c
4-C-4843. Each... 4c

"Premier" High Grade Hatchets

Strictly First Quality.


Especially adapted for the mechanic's use and are regularly sold at prices one-half higher than quoted below. Forged from high grade tool steel, carefully tempered, and have double refined cutting bits.

Guaranteed

to be perfect in material, workmanship and finish and to give satisfaction. Gold Bronze finish, polished heads and bits. Every hatchet is sharpened ready for use. Weights stated do not include handles.


Handles are of first quality second growth white hickory, properly wedged in.

36 CENTS AND UP




4-E-5001.
Premier High Grade Shingling Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Each
1	3 1/2	17	36c
2	3 3/4	23	38c
3	4 1/4	29	39c



4-E-5003. Premier High grade claw Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
1	3 1/2	19	40c
2	3 3/4	25	42c
3	4 1/4	31	45c




4-E-5005. Premier High Grade Half Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
1	3	15	37c
2	3 1/2	20	39c
3	3 3/4	27	42c



4-E-5007. Premier High Grade Lathing Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
1	2 1/2	14	38c
2	2 3/4	17	38c




4-E-5009. Broad Premier High Grade Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
2	4 1/2	21	56c
3	5	23	62c
4	5 1/2	24	62c
5	6	25	71c

"Premier Special" Bell Poll Hatchets

The best Hatchet that it is possible to produce. Hand forged from extra quality tool steel. Have double refined crucible bits, properly tempered. Built especially for the mechanic and are guaranteed to give absolute satisfaction. Adze Eye Octagon Neck and poll beautiful gun-metal finish which protects them from rust. Polished heads and bits. Handles are of the best quality second growth hickory, properly wedged in. Every hatchet sharpened ready for use. Weights do not include handles.




4-E-5011. Premier Special Bell Poll Shingling Hatchet.

Sizes	Width of Bit, inches	Weight, ozs	Price
1	3 1/2	3P	50c
2	3 3/4	17	52c



4-E-5013. Premier Special Bell Poll Half Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
1	3	15	50c
2	3 1/2	20	54c



4-E-5015. Premier Special Bell Poll Lathing Hatchets.

Size	Width of Bit, Inches	Weight, Ozs.	Price
1	3 1/2	14	49c
2	2 1/2	17	52c



4-E-5029. Premier Special Underhill Pattern Lathing Hatchet.

white hickory, carefully fitted. Weight not including handle, 15 ounces. Price, 65c.



4-E-5031. Premier Special Haines Pattern Lathing Hatchet.


Nothing better made. Properly balanced and justly popular with the mechanic. Forged from extra tool steel, properly tempered and full polished. Head is nicely milled. Handles are selected first quality white hickory carefully fitted. Width of bit, 2 inches. Weight, not including handle, 14 ounces. Price, 69c.

PREMIER SPECIAL NAIL HAMMERS




4-C-5033. The highest grade finest finished and easily the best hammer manufactured. Forged from extra tool steel, carefully tempered. Octagon poll, full nickel plated finish. Handle second growth selected hickory, polished, ebonyized finish. Carefully fitted and wedged to head and will not become loose. Properly balanced. Made with the greatest care to meet the demand of the most exacting mechanic. Claws carefully forged and tempered. Will draw large nails and small brads equally as well. These hammers are guaranteed to prove satisfactory or money refunded.

Size	Weight, not including handle, pounds	Price
1	1 1/2	68c
2	2	67c




4-C-5017. Forged from special high grade steel, properly tempered and polished. Fitted with selected hickory handle.

Size	Weight	Price
1	1 1/2	20c
2	2	27c




HOUSEHOLD HAMMER.

4-C-5021. Cast from special tough gray iron, gun metal finish. Fitted with hardwood handle. Weight, 16 ozs. Not intended for mechanics use. Price, 15c.



CARPENTERS' ADZES.

4-C-5025. Forged from high grade steel. Properly tempered, and guaranteed to take and hold a fine cutting edge. Polished bronze finish. Handles not included. Width cut, in..... 3 1/2 4 4 1/2 Weight Pounds..... 3 1/2 4 4 1/2 Price..... 96c 97c 98c



CAST STEEL NAIL HAMMERS.

4-C-5019. Strictly first class Hammer. Will give good service. Nicely finished, fitted with selected hardwood handles 16 ounces. Price, 21c.



TACK HAMMER WITH CLAW.

4-C-5023. Made of special tough gray iron, highly polished. Hardwood handle with claw. Length, 11 inches. Price, 6c.




SHIP CARPENTERS' ADZES.

4-C-5027. Made in the same careful manner as our carpenters' adzes. Each tool fully guaranteed. Handles not included. Width Cut, inches..... 4 1/2 4 1/2 Price..... \$1.05 \$1.07




ADZE EYE NAIL HOLDING HAMMER.

4-C-5035. With groove on side to hold Nails, size 10 penny and smaller. With this hammer nails can be driven at a greater height than ordinary reach. Made of the highest crucible steel, properly tempered. Handles of first selected second growth hickory, properly fitted and wedged to head and will not become loose. Fully guaranteed. Weight, 19 ounces, not including handle. Price, 79c.



PREMIER SPECIAL BELL FACED HAMMER.

4-E-5037. Made of the highest grade Crucible Steel, properly tempered. Handles are selected second growth hickory, properly fitted and wedged to head. Every hammer fully guaranteed. Size..... 1 1/2 2 3 3/4 Weight..... 20 16 13 7 Price..... 44c 43c 42c 36c



"DANDY" COMBINATION HATCHET.

The most convenient combination tool manufactured. May be used as a hatchet, hammer, wire cutter, plier, staple puller, nail claw, leather punch, screwdriver and chisel. A strong, durable tool, drop forged from solid tool steel, properly tempered and nicely finished. The handiest tool ever manufactured. For farm or home use. Length, 12 inches. Weight, about 2 1/2 pounds. **4-C-5039.** Price, 69c.

ALUMINUM LETTERS AND FIGURES.

Finely polished, cannot rust or tarnish. With prongs for fastening to wood. Used largely for signs, house lockers, room and automobile numbers. **4-C-5041.** Size 2 inches, any letter. Price, \$0.05. **4-C-5043.** Size 3 inches, any letter. Price, .07. **4-C-5045.** Commas. Price, .02. **4-C-5047.** Periods. Price, .02. **4-C-5049.** Size 2 inches, any figure. Price, .05. **4-C-5051.** Size 3 inches, any figure. Price, .06. **4-C-5053.** Size 4 inches, any figure. Price, .08.

F.E.N. 715

Genuine "Langdon Acme" Mitre Boxes.

"Langdon Acme" mitre boxes possess all the features heretofore embodied in similar styles of boxes but with the following improvements:

The guides are 1-inch longer thus holding the saw steadily when drawn up to its highest capacity. These guides are provided with elevators so the saw is held stationary above the work when desired. In addition, it notches for the positive angles commonly used. The acme box has a graduated arc in front with the various degrees marked thereon. The index plate is furnished with each machine, so there can be no mistake in cutting the various degrees. The saw can be secured at any intermediate or positive angle by means of a small thumb lever in front of box, supporting guides for holding work in place. Guides can also be used for cutting angles more acute than 45 degrees. Provided with lever gauge for duplicate lengths and with steel bottom boards roughened to prevent work from slipping. Polished parts are nickel plated. Prices include a high grade guaranteed back saw.

Size No. 1. Capacity at right angles 7½ inches. Capacity at mitres 5 inches.
 Sizes No. 2 and 2½. Capacity at right angles 10½ inches. Capacity at mitres 7 inches.
 4-C-4901. Size No. 1. 24x4 inch saw.... \$ 8.70 4-C-4905. Size No. 2½. 28x5 inch saw... \$12.13
 4-C-4903. Size No. 2. 26x4 inch saw.... 10.44 4-C-4907. Size No. 2½. 30x5 inch saw... 12.62

PERFECTION PATTERN MITRE BOXES.

4-C-4909. A strong serviceable mitre box made of hardwood with metal guide which can be readily detached and folded to carry in tool chest. Saw guide can instantly be set at angles of 22½, 30 and 45 degrees. Back saw, panel or hand saw can be used. For cutting to exact depths, use a back saw.



\$2.32

IMPROVED SEAVEY MITRE BOX AND SAW GUIDE.

Adjustable to cut square or at angles of 22½, 30 and 45 degrees. Lightest, most simple and accurate mitre box manufactured. Does not require a special saw. You can use a panel or hand saw. Specially adapted for cutting mouldings of any width or depth. Can be folded and carried in a tool chest.

4-C-4911. Price, without saw \$2.00

MITRE BOX SAWS.

4-C-4913. Extra refined crucible steel, carefully hardened and tempered. Evenly ground, hand filed, set ready for use. Heavy steel back polished. Beech handles, 3 brass screws. Width of blade under back 4 inches.

Length, inches..... 22 24 28
 Price..... \$1.60 \$1.80 \$2.05

BACK SAWS.

4-C-4915. Extra fine crucible steel. Stiff steel back, polished beech handles, with 3 brass screws. Hand filed and set ready for use. Each saw fully guaranteed.

Length, inches..... 10 12 14 16
 Price..... \$0.85 \$1.00 \$1.10 \$1.25

SAW JOINTER AND SKATE SHARPENER.

4-C-4917. Adjustable to any thickness saw blade. In jointing the teeth squarely, can be used with any flat file.

Price..... 34c

MORRELL'S PATTERN SAW SET.


4-C-4919. Morrell's pattern saw set. For hand, band, buck and jig saws. Has hardened steel anvil and plunger, and tempered steel spring. Guaranteed to be a strictly first class tool.

Price..... 29c

IMPROVED ANVIL SAW SET.

4-C-4921. Lever on lower side. With this tool the teeth of a saw can be set with great rapidity and little effort. The anvil and plunger are hardened, the spring is of tempered steel. Polished nickel plated finish.

Price..... 42c



\$8.70

REVOLVING ECCENTRIC ANVIL SAW SET.

4-C-4923. Shows the required bevel and length of all saw teeth ranging from 4 to 16 teeth to the inch. Figures on the dial indicate the number of teeth to the inch. Indicator is in plain sight, making the work much easier and does it correctly. Anvil and plunger made of hardened steel with tempered steel spring.

Price..... 72c

ADJUSTABLE SAW VISE.

4-C-4925. For attachment to work bench. This vise has a malleable iron screw clamp and lever and cam for holding it in position. Width of jaws 9½ inches. Japanned finish. Price..... 35c

WENTWORTH PAT- TERN SAW VISE.

4-C-4927. Flexible rubber cushion between jaws, preventing vibration and renders the saw filing noiseless. Designed to screw on bench. Width of jaws 11 inches. Japanned finish.

Price..... 44c

FOLDING ADJUSTABLE SAW VISE.

4-C-4929. Attached or detached without screwing or clamping. The most convenient and complete saw vise manufactured. It is easily folded and placed in a tool box or kit. Length of jaws 14 inches.

Price..... 51c

HANDY KIT OF TOOLS.

4-C-4931. Handy practical combinations of tools consisting of key hole saw and pad, chisel screw driver, two wrenches, awl, bit handle, made of good quality steel.

Price per Set..... 14c

SPRING STEEL FRAME HACK SAWS.

4-C-4933. Nickel plated steel frame, black enamel handle. Complete with 1 blade.

Length, inches..... 8 10
 Price..... 11c 12c

EXTENSION NICKEL PLATED HACK SAW FRAME.

4-C-4935. Adjustable for blade to be set at four different angles. Takes blades from 8 to 12 inches and holds them rigid and firm. Our price is about one-half the usual price.

Price, complete with one 8-inch blade... 49c

HACK SAW BLADES.

Fast Cutting Hack Saw Blades, made of Special High Carbon Steel Properly Tempered, and are Guaranteed to give First Class Satisfaction. Suitable for cutting tool steel and other metals.

4-C-4937. Length, inches..... 8 9 10 12
 Price, per dozen..... 30c 35c 45c 50c

Hack Saw Blades for Cutting Brass, Common Pipe and Tubing of all kinds. 24 teeth to the inch. Specially tempered.

4-C-4939. Length, inches..... 8 9 10 12
 Price, per dozen..... 35c 40c 47c 52c

BALL AND SOCKET SAW VISE.



4-C-4941. Adjustable saw vise with bench clamp. By the use of this vise the saw can be filed at any angle as the operator may desire. Heavy pattern. Width of jaws 9½ inches. Japanned finish. Fully guaranteed.

Price..... 54c

IMPROVED FOOT POWER SAW SET.

4-C-4943. Positive uniformity of set can be obtained by the use of this tool. Will set a saw from the finest tooth to the two-man cross cut saw easily and quickly. The set is operated by means of a treadle leaving the operator's hands free to hold saw. Stroke of handle is adjustable by means of a thumb screw to strike a light or heavy blow. With a little practice an inexperienced person can set a saw as perfectly as when it came from the factory.

Price Complete..... 93c



COMBINATION CROSS CUT SAW TOOL.

4-C-4945. Cross cut saw filer, jointer, tooth gauge, setting block, and gauge. With this tool cross cut saws can be kept in perfect condition. Full directions with each set.

Price without file..... 29c

ADJUSTABLE SAW FILING GUIDE.

4-B-4947. Used for filing saw in any style bench vise. Can also be used in connection with the regular saw vise. Adjustable to file any angle or bevel and exact depth. Made of steel and iron nicely japanned. Steel parts are partly finished.

Price complete with file..... 99c



SAW FILING GUIDE AND VISE.

4-C-4949. With this device saw filing is made easy. An inexperienced person can file a saw correctly. The ball and socket which connects the clamp to vise permits the clamp to be turned in either direction. Jaws are 10½ inch faced with rubber strip which holds the saw firmly and deadens the sound. File and guide are adjustable in every direction. Packed in box with full directions.

Price complete with file..... \$1.72




ADJUSTABLE IRON FRAME HACK SAWS.

Strong Iron Frame, Adjustable. The blade can be set at four different angles. Strongest and best low priced hack saw on the market.

4-C-4951. Price, complete with one blade..... 14c

HEAVY, RIGID EXTENSION HACK SAW FRAME.

4-C-4953. Heavy Steel Nickel Plated Frame. Adjustable to take blades from 4 to 8 inches, which can be at four different angles. Price, with one 10 inch blade..... 85c




Adjustable Iron Bench Planes, Smooth and Corrugated Bottoms



Corrugated Bottom

The handles and knobs are genuine mahogany, highly polished. We guarantee these planes to give perfect satisfaction or they may be returned to us and we will promptly refund your money.



\$1.27

Adjustable iron smooth plane, 9 inches long, 2-inch cutter.

4-D-5201. Smooth bottom\$1.27

4-D-5203. Corrugated bottom\$1.28



\$1.84

ADJUSTABLE IRON FORE PLANE.

Adjustable iron fore plane, 18 inches long, 2½-inch cutter.

4-D-5209. Smooth Bottom.....\$1.84

4-D-5211. Corrugated Bottom.....\$1.85



\$1.49

Adjustable iron jack plane, 14 inches long, 2-inch cutter.

4-D-5205. Smooth bottom.....\$1.49

4-D-5207. Corrugated bottom.....\$1.50

Adjustable Iron Jack Plane.

ADJUSTABLE IRON JOINTER PLANE.

Adjustable Iron Jointer Plane, 22 inches long, 2½-inch cutter.

4-D-5213. Smooth Bottom.....\$2.18

4-D-5215. Corrugated Bottom.....\$2.19

4-D-5217. Set of four Smooth Bottom Adjustable Iron Bench Planes, one each as above. Per set.....\$6.54

4-D-5219. Set of four Corrugated Bottom Adjustable Iron Bench Planes, one each as above. Per set.....\$6.55

ADJUSTABLE WOOD BOTTOM BENCH PLANES.


Bottoms are made of thoroughly seasoned beechwood, finished absolutely smooth. Castings are made of special gray iron of unusual toughness. The cutters are made of high grade steel and are much heavier than the ordinary cutter. Suitable for either hard or soft wood and will not chatter in the hardest woods. Fitted with an adjustable lever, by means of which the iron can be easily adjusted sideways, giving an easy lateral adjustment.



4-D-5221. Adjustable Wood Bottom Smooth Plane. 8 inch long, 1½ inch cutter.....**75c**



4-D-5223. Adjustable Wood Bottom Handled Smooth Plane. 9 inches long, 2-inch cutter.....**95c**



ADJUSTABLE WOOD BOTTOM JACK PLANE.
4-D-5225. 15 inch long, 2-inch cutter.....**84c**
4-D-5226. 15 inch long, 2½-inch cutter.....**86c**



\$1.05

4-D-5227. Adjustable Wood Bottom Fore Plane. 20-inch long, 2½ inch cutter.....**\$1.05**



\$1.19

ADJUSTABLE WOOD BOTTOM JOINTER PLANE.
4-D-5229. 24 inch long, 2½ inch cutter.....**\$1.19**
4-D-5231. 26-inch long, 2½-inch cutter.....**\$1.36**

SET OF FOUR ADJUSTABLE WOOD BOTTOM JACK PLANES

4-D-5233. Set of four Adjustable Wood Bottom Planes: one each: 4-D-5221, 4-D-5225; 4-D-5227, 4-D-5229. Price.....**\$3.89**

BEECH WOOD PLANES.

Made of the most carefully selected seasoned beechwood. Special high grade double cutting irons, properly tempered and ground. Guaranteed to be the best wood planes manufactured.



56c

4-D-5235. Wood Smooth Plane. 8-inch long, 1½-inch cutter.....**56c**



63c

4-D-5237. Wood Jack Plane. 16-inch long, 2½-inch cutter.....**63c**



92c

4-D-5239. Wood Fore Plane. 22-inch long, 2½-inch cutter.....**92c**

SET OF FOUR BEECH WOOD PLANES

4-D-5243. Set of four Beechwood Planes. Price.....**\$3.89**

FANCY WOOD PLANES. STRICTLY HIGH GRADE. FULLY WARRANTED. HOLLOW AND ROUNDS. SKEW RABBIT PLANES.



4-C-5245. We do not break pairs. Price is per pair.
Works Per Pair.
1 inch\$0.84
1½ inch85
2 inch86
2½ inch87
3 inch88
3½ inch89
4 inch89
4½ inch1.02
5 inch1.03
5½ inch1.17



4-C-5247.

Works. Each.
1 inch\$0.48
1½ inch49
2 inch50
2½ inch51
3 inch52
3½ inch56
4 inch58
4½ inch70
5 inch80



NOSING PLANES.

4-C-5249.
Works. Each.
1 inch\$0.94
1½ inch95
2 inch96
2½ inch97
3 inch1.06
3½ inch1.07



4-C-5251.

Works. Price, each
1½ inches\$1.48
2 inches1.47



ADJUSTABLE PLANE GAUGE.

4-C-5253. For wood Planes only. By its use beveling or jointing can be done accurately without the use of a tri-square. Illustration shows gauge attached to plane. Price.....**72c**

ADJUSTABLE CIRCULAR PLANE.

\$1.82



4-C-5255. Fl-x-ime Steel Face. Can be quickly changed to either convex or concave form. Can also be used as a straight bottom plane. Length of face, 10 inches. Width of cutter, 1½ inches.**\$1.82**

TONGUING AND GROOVING PLANES.

Furnished with two separate cutters. To be used for making a tongue. By releasing the pin at the front of plane the fence is swung on a central pivot and reversed covering one cutter. The plane is then ready to be used for forming a groove to match the tongue. Nickel plated and finely finished.

4-C-5257. For ½ to 1½ inch Boards.

Price.....**\$1.71**

4-C-5259. For ½ to 2-inch Boards. Price.....**\$1.70**



DUPLEX RABBIT PLANE AND FILLISTER.


With two seats for Cutter. By inserting cutter in forward seat can be used as a bull nose rabbit plane. The arm is reversible and can be used on right or left hand side of plane. With adjustable spur and depth gauge. Length, 8½ inches. 1½ inch cutter.

4-C-5261. Price.....**99c**

IRON BLOCK PLANE.



Made of superior grade iron castings. Bottoms are perfectly smooth, cutters are made of high grade tool steel, properly tempered. Guaranteed to be strictly first class in every particular.

4-C-5263. Iron Block Plane. A useful household tool. 5 inches long, 1½ inch cutter. Price.....**8c**



4-C-5265. Iron Block Plane. 5½ inches long, 1½-inch cutter. Price.....**24c**

4-C-5267. Iron Block Plane. 7 inches long, 1½-inch cutter. Price.....**32c**





4-C-5269. Adjustable Block Plane. 5½ inches long, 1½ inch cutter. Price.....**33c**

4-C-5271. Adjustable Block Plane. 7 inches long, 1½-inch cutter. Price.....**43c**



4-C-5273. Double End Block Plane. With two slots and two seats for cutter. By changing the cutter and lever from one end to the other, it can be used to plane in close corners. Can also be used as a block plane. Length, 8 inches. 1½ inch cutter. Price.....**45c**

4-C-5275. Adjustable Block Plane with improved Throat Adjustment. For fine or coarse wood. Fitted with improved lateral adjustment for cutter. 6½ inches long, 1½-inch cutter. Price.....**72c**



4-C-5277. Knuckle Joint Lever, Improved Throat Adjustment. For fine or coarse wood. Fitted with improved lateral adjustment for cutter. 6½ inches long, 1½-inch cutter. Price.....**81c**

ADJUSTABLE PLANE GAUGE.

For either Iron or Wood Planes.
4-C-5279. For Planing Bevels of any angle or square joints, without use of a tri-square or bevel. Can be quickly attached or removed. Price.....**\$1.16**



PREMIER HIGH GRADE AXES

Premier High Grade Axes Excel all others in Material, Workmanship, Finish and Cutting Qualities. Perfectly tempered. Will hold a keen cutting edge that will satisfy the most experienced chopper.

We Guarantee Premier High Grade Axes Perfect in Material and Workmanship, Properly Tempered and Ground, and Otherwise Strictly First Class to Give Satisfactory Service in Every Particular or They May be Returned to us and We Will Refund Full Purchase Price.

PREMIER HIGH GRADE SINGLE BIT AXES.



Hand forged from the highest grade steel, Double refined crucible steel bits, properly shaped and tempered. Will take and hold a fine cutting edge. Each axe fully guaranteed. Full polished finish. Handles not included. When ordering be sure and state weight wanted.



4-E-5101. Wisconsin or Western Pattern.		4-C-5103. Michigan Pattern.	
Weight.	Each.	Weight.	Each.
3 pounds.....	57c	3 pounds.....	57c
3 1/2 pounds.....	57c	3 1/2 pounds.....	57c
4 pounds.....	60c	4 pounds.....	60c
4 1/2 pounds.....	63c	4 1/2 pounds.....	63c
5 pounds.....	66c	5 pounds.....	66c

PREMIER HIGH GRADE DOUBLE BIT AXES.



Hand forged, full polished finish, double refined crucible steel bits, properly tempered. Easily the best Double Bit Axe manufactured. Guaranteed to give entire satisfaction. Handles not included at prices quoted. When ordering be sure and state weight wanted.



4-E-5105. Wisconsin or Western Pattern.		4-C-5107. Michigan Pattern.	
Weight.	Each.	Weight.	Each.
3 1/2 pounds.....	81c	3 1/2 pounds.....	81c
4 pounds.....	84c	4 pounds.....	84c
4 1/2 pounds.....	87c	4 1/2 pounds.....	87c
5 pounds.....	90c	5 pounds.....	90c
5 1/2 pounds.....	93c	5 1/2 pounds.....	93c

PREMIER "HOMESTEADER" HANDLED AXES

The finest Axe ever offered and will be appreciated by those who are judges of fine tools. Premier "Homesteader" handled axes are the finest, easiest cutting axes ever produced.

Forged from the best grade of steel used in the manufacture of axes. The bits are double refined crucible steel, perfectly tempered and accurately ground. Beautifully polished and etched. Handles are selected clear, second growth white hickory, hand shaved, oval shape properly fitted and wedged. Every axe fully guaranteed. Your money back if not entirely satisfactory. Made in Michigan Pattern only, with phantom bevel.

When ordering, be sure and state weight wanted.

Weight, lbs.	3 1/2	4	4 1/2	5
Price.....	\$1.04	\$1.08	\$1.12	\$1.20

CHICAGO SPECIAL AXES

The best ever offered in strictly first class axes for all ordinary purposes. While the Chicago Special Axes are not as high grade as our Premier Axes, they will however give complete satisfaction for general work. Hand forged from high grade crucible steel, with double refined crucible steel bits of the highest quality, properly tempered and ground and will hold a keen cutting edge. You will pay at least one-third more for an axe of equal quality if purchased elsewhere.

CHICAGO SPECIAL SINGLE BIT AXES.

Hand forged double refined crucible steel bits, properly tempered and accurately ground.


A fine axe for farm, ranch and home. Will hold a fine cutting edge and is guaranteed to give satisfaction. Natural forge temper finish, polished edges. Handles not included at prices quoted. When ordering be sure and state weight wanted.



4-E-5111. Wisconsin or Western Pattern.		4-C-5113. Michigan Pattern.	
Weight.	Price.	Weight.	Price.
3 pounds.....	44c	3 pounds.....	44c
3 1/2 pounds.....	45c	3 1/2 pounds.....	45c
4 pounds.....	47c	4 pounds.....	47c
4 1/2 pounds.....	50c	4 1/2 pounds.....	50c
5 pounds.....	53c	5 pounds.....	53c

CHICAGO SPECIAL DOUBLE BIT AXES.

Axes of this grade are generally sold at \$1.25. They are strictly hand forged and properly proportioned. Bits are double refined crucible steel and will hold a perfect cutting edge. We guarantee these axes to give perfect satisfaction. Natural forge temper finish, polished edges. Handles not included at prices quoted. When ordering be sure and state weight wanted.



4-E-5117. Wisconsin or Western Pattern.		4-C-5119. Michigan Pattern.	
Weight.	Price.	Weight.	Price.
3 pounds.....	63c	3 pounds.....	63c
4 pounds.....	66c	4 pounds.....	66c
4 1/2 pounds.....	69c	4 1/2 pounds.....	69c
5 pounds.....	72c	5 pounds.....	72c

"EVER READY" HANDLED AXES



A better axe at a lower price than ever before offered. Generally sold for \$1.00. Each axe is guaranteed to be perfect in every way and to give entire satisfaction.

"Ever Ready" axes are carefully forged, properly shaped and have crucible steel cutting bits. Finished in a superior manner. Red poll, green phantom bevels, polished bits. Handles are selected hickory stained handsome golden oak color, properly fitted to the axe. Furnished only in the Michigan Pattern.

4-E-5115. Michigan Pattern Phantom Bevel "Ever Ready" Axes.

Weight, pounds.	3	4	4 1/2
Price.....	48c	51c	54c

MALLEABLE IRON AXE WEDGE.



4-C-5121. Made with screw which prevents handle from pulling out. Per dozen..... 18c Each..... 2c

"EVER READY" BOYS' HANDLED AXES.
4-E-5123. Strictly high grade axe, made from a high grade extra refined crucible steel, with crucible steel cutting edge. Beautifully finished phantom bevel, red poll, green bevels, full polished bit. This is an axe that any boy will appreciate and be proud of. Fitted with a 28-inch first quality hickory handle, stained a handsome golden oak color. Fully guaranteed.
Weight, including handle, 3 lbs. Price..... 42c

PREMIER HUNTERS' OR SPORTSMAN'S AXE.
Indispensable in camp and suitable for light chopping. The most sensible and best axe ever offered at the price. Forged from strictly high grade steel with crucible steel cutting edge, properly tempered and ground. Finished black poll, copper finished bit, which will not rust. Fitted with 14-inch hickory handle, stained handsome golden oak finish, properly fitted. Guaranteed to be a strictly first class high grade tool.
4-C-5125. Weight, not including handle, about 1 pound. Price..... 49c

PREMIER BROADAXES.
Round corner Canada Pattern. Broadaxes. The highest grade and best style of broadaxe ever produced. Made of the highest grade steel with double refined crucible steel cutting bits, carefully tempered and ground. Properly proportioned hand forged finish. Extreme care is taken throughout in the entire manufacturing process. We guarantee these axes to be strictly first class in every particular and to give perfect satisfaction. Furnished sharpened ready for use. Handles not included.
4-E-5127.
Weight, pounds..... 6 6 1/2 7 7 1/2 8 8 1/2
Width cut, inch..... 10 11 11 1/2 12 12 1/2 13
Each..... \$1.71 \$1.80 \$1.80 \$1.88 \$1.88 \$1.97

WOODCHOPPERS' WEDGES.
4-E-5129. Regular Pattern. Made from high grade steel, oil finished. Weight, pounds..... 4 5 Price..... 12c 15c
4-E-5131. Truckee Pattern. Made from high grade crucible steel, oil finished. Weight, lbs..... 4 6 8 Price..... 15c 20c 27c

IMPROVED PATTERN SAW WEDGES.
4-C-5133. Made of high grade tool steel, oil finished. Nothing better manufactured. Weight, pounds..... 1 1/2 2 1/2 Price..... 12c 17c

OREGON PATTERN MAULS.
4-C-5135. Made of high grade Crucible Steel, Oil Finished. Weight, lbs..... 6 7 8 10 Price..... 43c 48c 54c 67c

SUPERIOR CANT HOOK.
4-C-5137. The strongest and best Cant Hook on the market. Heavy hook of crucible cast steel. Strong, heavy clasp and extension toe ring. Handle made of strictly first quality hard maple. Size of handle, 2 1/2 inches. We guarantee these hooks to give perfect satisfaction. Price..... 78c


SELECTED CANT HOOK HANDLES.
4-C-5139. Strictly first quality straight grained hard maple. Nicely finished. Price, each..... 21c

Our Blacksmiths' Tools are High Grade—Our Prices are Real Money Savers.

Standard Cast Steel Auger Bits

Made of refined steel carefully tempered and polished and are excelled only by our premier superior quality Auger bits. For general purposes our standard Auger bits will give nearly as good satisfaction as any auger bits made, as special care is taken in the manufacture of these bits and they will give good service. For mechanics' use where bits are constantly used in boring in all kinds of woods we recommend our Premier superior quality bits described on this page.

Common Pattern Auger Bits



Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
Price each	6c	7c	7c	8c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
Price each	9c	10c	11c	12c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
Price each	13c	14c	15c	16c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$
Price each	13c	14c	15c	16c

COMMON PATTERN AUGER BITS IN SETS

4-C-5403. Set of Six Common Pattern Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set	56c
4-C-5405. Set of Eight Common Pattern Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set	79c
4-C-5407. Set of Thirteen Common Pattern Auger Bits. One each $\frac{1}{2}$ to 1 inch.	Price per set	\$1.36

JENNINGS' PATTERN EXTENSION LIP STANDARD AUGER BITS

4-C-5409. Jennings' Pattern Extension Lip Standard Auger Bits.	Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	8c	9c	10c	11c	12c	13c	14c	15c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	13c	15c	17c	19c	21c	23c	25c	27c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	20c	21c	23c	25c	27c	29c	31c	33c

JENNINGS' PATTERN AUGER BITS IN SETS

4-C-5411. Set of Six Jennings' Pattern Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set	95c
4-C-5413. Set of Eight Jennings' Pattern Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set	\$1.18
4-C-5415. Set of Thirteen Jennings' Pattern Auger Bits. One each $\frac{1}{2}$ to 1 inch.	Price per set	\$1.98

SOLID CENTER STANDARD AUGER BITS

4-C-5417. Solid Center Standard Auger Bits.	Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	13c	14c	15c	17c	19c	21c	23c	25c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	19c	21c	23c	25c	27c	29c	31c	33c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	27c	30c	31c	33c	34c	36c	38c	40c

SOLID CENTER AUGER BITS IN SETS


4-C-5419. Set of Six Solid Center Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set	\$1.35
4-C-5421. Set of Eight Solid Center Auger Bits. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set	\$1.63
4-C-5423. Set of Thirteen Solid Center Auger Bits. One each $\frac{1}{2}$ to 1 inch.	Price per set	\$2.89

CHICAGO HOUSE WRECKING CO.
35th & Iron Streets, Chicago.

Premier Superior Quality Auger Bits

Made to meet the requirements of the skilled mechanic, and are the best for shop, factory or home use. Forged from the highest quality crucible steel, properly tempered full length of twist. Each bit is carefully headed by improved methods absolutely straight and true to size. Screws are made by special automatic machinery, thus insuring perfect and uniform threads. Lips are carefully forged and properly shaped and are the most durable, fast cutting bits possible to produce. Heads and cutters are sharpened and finished by hand filing. Every bit is carefully tested before leaving the factory. Finely polished, finished and guaranteed to give entire satisfaction.

Premier Jennings' Pattern Extension Lip Auger Bits



The Best Jennings' Pattern Extension Lip Auger Bit Manufactured. Can be used for boring hard or soft wood and will bore through without splitting the wood. We recommend these bits for mechanics' use. Properly tempered, full length of twist. Lips are carefully forged and sharpened and will cut faster and outwear any other JENNINGS' PATTERN bit manufactured. Bit is perfectly straight and true to size. Full polished finish.


4-C-5425. Premier Jennings' Pattern Extension Lip Auger Bits.	Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	13c	14c	16c	18c	19c	21c	22c	23c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	26c	28c	30c	32c	34c	35c	39c	44c

Premier Jennings' Pattern Extension Lip Auger Bits in Sets

Put up in hardwood boxes nicely finished with brass hinges and catches.

4-C-5427. Set of Six. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set in box	\$1.53
4-C-5429. Set of Eight. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set in box	\$1.94
4-C-5431. Set of Thirteen. One each $\frac{1}{2}$ to 1 inch.	Price per set in box	\$3.29

Premier Solid Center Extension Lip Auger Bits



Solid Center Auger Bits. Extreme care is taken in the manufacture of these bits. Each bit is carefully tempered and absolutely straight and true to size. Each bit is hand forged from double refined crucible steel, properly tempered, full length of twist. Highly finished and fully guaranteed.


4-E-5433. Premier Solid Center Extension Lip Auger Bits.	Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	18c	18c	20c	23c	25c	28c	31c	34c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	31c	34c	37c	40c	43c	47c	49c	51c

Premier Solid Center Extension Lip Auger Bits in Sets

Put up in hardwood boxes nicely finished with brass hinges and catches.

4-C-5435. Set of Six. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set in box	\$1.61
4-C-5437. Set of Eight. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set in box	\$2.49
4-C-5439. Set of Thirteen. One each $\frac{1}{2}$ to 1 inch.	Price per set in box	\$4.23

Premier Single Twist Extension Lip Auger Bits



For rapid and easy boring in any kind of wood. Specially designed for work in the toughest hardwoods, knotty timber and end boring. Will bore more rapidly and with greater ease than other style of auger bit maker. The open twist affords ample clearance for the chips and cannot choke up. Made by highly skilled workmen. Tempered and finished in the finest manner and each bit is carefully tested and fully guaranteed.

4-C-5441. Premier Single Twist Extension Lip Auger Bits.	Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	17c	19c	21c	24c	26c	29c	31c	34c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{2}$
Price each	32c	35c	38c	41c	44c	48c	50c	53c


Premier Single Twist Extension Lip Auger Bits in Sets

Put up in hardwood boxes nicely finished with brass hinges and catches.

4-C-5443. Set of Six. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$ and 1 inch.	Price per set in box	\$1.89
4-C-5445. Set of Eight. One each $\frac{1}{2}$, $\frac{3}{4}$, 1, $1\frac{1}{4}$, $1\frac{1}{2}$, $1\frac{3}{4}$ and 1 inch.	Price per set in box	\$2.49
4-C-5447. Set of Thirteen. One each $\frac{1}{2}$ to 1 inch.	Price per set in box	\$4.25

Write us for Full Information on our Acetylene Light Propositions.


SHIP AUGER BITS



4-C-5449. Desirable for boring the toughest hardwoods, knotty timber and end boring. Made of double refined steel, finely finished. Fully guaranteed. Have $\frac{1}{2}$ to 6 inch twists.

Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	23c	24c	25c	26c	27c	28c	29c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	27c	29c	32c	35c	38c	41c	44c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	39c	42c	47c	50c	55c	58c	61c


CAR BITS



4-C-5451. For boring heavy timbers. Used by bridge builders and millwrights. Length of twist 12 inches.

Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	26c	27c	28	32c	34c	36c	38c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	36c	42c	47c	50c	55c	58c	61c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	55c	58c	62c	68c	74c	77c	80c


NUT AUGERS



4-C-5453. You cannot secure a smoother and easier cutting bit at any price. High grade cast steel, polished finish.

Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	20c	23c	25c	32c	40c	48c	55c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	46c	55c	75c	95c	1.25	1.57	1.87


SHIP AUGER CAR BITS



4-C-5455. Used by bridge or car builders, millwrights, etc., for boring in heavy timbers either soft or hard wood. Length of twist 12 inches. Guaranteed to give entire satisfaction.

Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	35c	38c	40c	43c	46c	48c	50c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	45c	48c	50c	54c	58c	60c	65c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	87c	90c	95c	100c	105c	110c	115c
Size, inches	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{3}{4}$	2
Price each	66c	72c	74c	77c	80c	83c	86c


PERFECTION HAND DRILLS



4-C-5457. Strong Mal-leable Frame. Spindle, cut gears and hollow cocobola handle containing 8 drill points $\frac{1}{8}$ to $1\frac{1}{2}$ inch. A strong, durable tool, nicely finished Length 10 $\frac{1}{2}$ inches. Price including 8 drill bits.

Price	\$1.08
-------	--------


STEEL FRAME HAND DRILL



4-C-5459. All Steel Nickel Plated Frame. Cut gear, improved three-jaw riveted chuck. Takes twist drill to $\frac{1}{2}$ inch. Hollow polished cocobola handle, which contains 8 drill points. Length 10 inches. Price including drill points.

Price	\$1.34
-------	--------

GOODELL'S DOUBLE GEARED HAND DRILL



4-C-5461. The finest hand drill on the market. Has double gears, cut teeth, two speeds, fitted with an improved chuck. Takes twist drills up to $\frac{1}{2}$ inch. Strong, iron frame, japanned. Hollow cocobola handle to hold drill points. Speed changed by simply turning nut on the frame. Spindle runs in highly hardened steel ball bearing. Length 14 $\frac{1}{2}$ inches. Price does not include drill points.

Price	\$2.39
4-C-5463. Set of drill points, 8 sizes: From $\frac{1}{8}$ to $1\frac{1}{2}$ inch. Price per set	34c

HIGH GRADE PLANE IRONS.



Made of high grade steel carefully tempered. All double irons have steel caps. Guaranteed to be the best it is possible to manufacture. When ordering, give number of plane and size of iron required. We sell irons only our regular line of planes.

IRONS FOR ALL IRON AND WOOD BOTTOM PLANES.

4-C-5301. Single Irons.	
Width, inches	13 2 2 2 2
Price	18c 20c 22c 26c 28c
4-C-5303. Double Irons.	
Width, inches	13 2 2 2 2
Price	31c 33c 35c 39c 42c

IRONS FOR BEECH WOOD PLANES.

4-C-5305. Single Irons.	
Width, inches	2 2 2
Price	28c 29c 35c
4-C-5307. Double Irons	
Width, inches	2 2 2
Price	52c 58c 68c

IRONS FOR BLOCK PLANES. 4-C-5309.

Width, inches	1 1 1
Price	12c 12c 15c

PLANE HANDLES.

Selected Beechwood well finished.




4-C-5311. Jack Plane Handle. Price, each.....3c

4-C-5313. Fore Plane Handle. Price, each.....5c



COMBINATION BALL BEARING RATCHET BRACE AND DRILL.



\$2.35

4-C-5315. A convenient tool which every mechanic should have, with which you can bore holes in close places. Has ball bearing head and forged steel alligator jaws. Will hold straight round shank drills, as well as regular drill bits. By removing the hand drill attachment, you have a fine ball bearing ratchet brace, 10-inch sweep. Steel cut gears, polished cocobola head and handle. Full nickel plated finish. Price.....\$2.47


BALL BEARING BREAST DRILL.

4-C-5317. Japanned Malleable frame, polished Cocobola Handles, Nickel Plated Chuck. Changeable gear, from even to speeded, about 3 to 1, with level attachment to show when drill is being held true. Steel alligator jaws, will take any size bit stock; also round shank drill bits up to 1/2 inch. A strong, durable tool, finely finished. Price.....\$2.34



BIT BRACES.

Carefully selected and representing the best values ever offered in this line. Each brace is carefully made, nicely finished and the best of their respective kinds. Guaranteed to be entirely satisfactory or they can be returned to us and your money refunded.



19c

4-D-5323. A substantial and satisfactory brace for all ordinary use. 7-16-inch cold drawn steel sweep, natural finish, polished head and handle. The best low priced brace ever offered.


Sweep, inches.....8 10
Price, each.....19c 24c



63c

4-C-5325. Ring Ratchet Brace. Finely polished. Cold drawn steel sweep. Alligator jaws, polished satinwood head and handle. Natural finish.

Sweep, inches.....10 12
Price, each.....63c 69c




44c

4-D-5327. A strong, durable Brace. Ebonized hardwood head and handle. Cold drawn steel sweep, heavily nickel plated. Steel alligator jaws. The best brace ever offered at the price.

Sweep, inches.....8 10 12

Price, each.....44c 48c 52c



85c

4-C-5329. Finest Medium Priced Brace on the market. Metal clad head, cold drawn steel sweep, ebonized hardwood head and handle. Hardened alligator jaws. Finely polished and nickel plated. A strong, substantial ratchet brace for all purposes.


Sweep, inches.....10 12

Price, each.....85c 95c



51c

4-D-5335. Guaranteed to be the best ratchet brace ever offered at the price. Strong, durable and well made. For ordinary use, 7-16 inch cold drawn sweep, hardened steel jaws. Hardwood head and handle, polished finish. 10-inch Sweep. Price.....51c



\$1.19

4-C-5337. Strictly high grade Ratchet Brace. Ball bearing dust-proof head, Machine made throughout. Cold drawn steel sweep. All metal parts highly polished and heavily nickel plated. Cocobola head and handle with improved metal capped head. Forged alligator spring jaws hardened. Will take square or round shank drills. The greatest value ever offered in a high grade brace. Sweep, inches.....8 10 12

Price, each.....\$1.19 \$1.25 \$1.31

SPOFFORD BRACES.



67c

4-C-5339. Great favorite with carriage builders, wooden workers and blacksmiths. Solid steel jaws and bows. Cocobola head and handle, nickel plated. Holds any square shank drill or bit. Sweep, inches 8 10 12 14

Price.....67c 74c 83c 94c

EXTRA HIGH GRADE BALL BEARING RATCHET BIT BRACE.



\$1.47

4-C-5331. The best ratchet brace it is possible to produce and will meet the requirements of the most critical mechanic. Solid steel chucks, hardened forged steel alligator jaws, which will hold all sizes square shank, as well as the small size round shank drills. 3/4-inch cold drawn steel sweep, finely polished and heavily nickel plated. Dustproof ball bearing metal clad head, polished cocobola head and handle, steel enclosed frame. Heavy brace. Fully warranted. If not entirely satisfactory can be returned and money refunded.

Sweep, inches.....8 10 12 14

Price.....\$1.47 \$1.52 \$1.63 \$1.73

DOUBLE GEARED BREAST DRILL.

4-C-5333. Ball Bearing with level attachment to show when tool is being held true. Nickel plated steel frame, 6-inch drive wheel, cut gears, cocobola handles. Alligator jaws, takes any size bit stock, also round shank drills from 1/4 to 3/4 inch. Strictly high grade, first class tool. Fully warranted. Price.....\$3.35




PRATT'S PATENT AUGER HANDLE OR RATCHET DRILL.

Used as an Auger Handle.

Handles in horizontal position. For use in close places; one handle can be removed and placed at right angle. Can also be used as a ratchet drill.

Price.....\$1.81




UTILITY BRACE AND BIT SET.



JUST WHAT IS REQUIRED FOR HOME OR FARM USE.

4-C-5319. A careful comparison will convince you that we offer more for the money than can be secured elsewhere. Set consists of: one ten inch nickel plated ratchet brace with alligator jaws. Eight standard double spur bits, sizes 1/4, 1/2, 3/4, 1, 1 1/4 and 1 1/2 inch. Three German pattern gimlet bits, 1/4, 1/2 and 3/4 inch. One high grade screwdriver bit. Put up in a neat, substantial hardwood box. Set complete.....\$2.39


MECHANIC'S FAVORITE BRACE AND BIT SET.



THE MOST CONVENIENT SET EVER OFFERED FOR MECHANICS' USE.

4-C-5321. Each item is carefully selected with the view of furnishing an outfit that we guarantee to give entire satisfaction. The set consists of: one ten-inch ball bearing dust proof head nickel plated ratchet brace with forged alligator jaws. Eight Irwin pattern auger bits, one each size: 1/4, 1/2, 3/4, 1, 1 1/4 and 1 1/2 inch. One Clark's pattern expansion bit, cutting 1/2 to 3 inches. One screwdriver bit. Three German pattern gimlet bits. Put up in a neat, strong hardwood box. Price per set.....\$4.59


ECONOMIC BRACE AND BIT SET.



A FIRST CLASS OUTFIT THAT WILL ANSWER ALL GENERAL REQUIREMENTS.

4-C-5343. A very satisfactory set for farm, shop and mechanic's use. A real bargain at the price which we quote. The set consists of: one ten inch nickel plated ratchet brace with alligator jaws. Eight Jennings pattern extension lip auger bits, sizes 1/4, 1/2, 3/4, 1, 1 1/4 and 1 1/2 inch. Three bit stock drills, sizes 1/4, 1/2 and 3/4 inch. Three German pattern gimlet bits, sizes 1/4, 1/2 and 3/4 inch. One Screwdriver bit. One flat countersink. One square reamer. Put up in a neat substantial hard wood box. Price per set.....\$3.37

EXPERT BRACE AND BIT SET.



THIS HIGH GRADE SET INCLUDES A FULL ASSORTMENT OF BITS NECESSARY IN GENERAL WORK.

4-C-5345. Each tool is strictly high grade and Warranted to give entire satisfaction. The set consists of: one ten inch extra high grade ball bearing ratchet bit brace with metal clad head. 8 single twist auger bits, one each size 1/4, 1/2, 3/4, 1, 1 1/4 and 1 1/2 inch. 8 German pattern gimlet bits, sizes 1/4, 1/2 and 3/4 inch. 1 Mephisto expansion bit, cutting 1/2 to 3 inches. 1 screwdriver bit. 1 square reamer. 1 bit gauge. 1 small countersink. 1 auger bit file. Packed complete in a nicely finished, substantial hardwood box. Price.....\$6.59



SPECIAL HIGH GRADE BEVELED EDGE, LEATHER TIPPED SOCKET FIRMER CHISELS

HAND HONED

PREMIER

SUPERIOR FINISH

"PREMIER HIGH GRADE BEVEL EDGE LEATHER TIPPED SOCKET FIRMER CHISELS.

Guaranteed to be the highest grade and most satisfactory chisels manufactured.

The best steel that it is possible to buy is used in the manufacture of our special high grade chisels. But of more importance is the hardening and tempering. By an improved process uniform hardness is secured, leaving the blade entirely free from soft spots, making it possible to

4-C-5801. Size, inches..... 27c 29c 31c 33c 35c 37c 40c 41c 43c 46c 48c 49c
Price, each.....

SPECIAL HIGH GRADE BEVELED EDGE, LEATHER TIPPED SOCKET FIRMER



THESE CHISELS ARE THE SAME
AS ABOVE DESCRIBED

4-C-5803. Set of six special high grade bevel edge leather tipped socket firmer chisels, one each size: 1, 1 1/2, 2, 2 1/2, 3, 4. Put up in a neat, nicely finished hardwood box. Price..... **\$2.63**




4-C-5605. Set of nine special high grade bevel edge leather tipped socket firmer chisels, one each size: 1, 1 1/2, 2, 2 1/2, 3, 4, 5, 6, 8. Put up in a neat, nicely finished hardwood box. Price..... **\$3.73**



4-C-5637. Set of twelve special high grade bevel edge leather tipped socket firmer chisels, one each size: 1, 1 1/2, 2, 2 1/2, 3, 4, 5, 6, 8, 10, 12, 14, 16, 18, 20. Put up in a neat, nicely finished hardwood box. Price..... **\$4.81**

PREMIER HIGH GRADE PLAIN EDGE SOCKET FIRMER CHISELS



4-C-5807. Made in the same careful manner and of the same high grade material as our special high grade bevel edge chisel above described. In fact, they are the same in every particular with the exception that they have plain edges. The process of hardening and tempering is the same. Each chisel is carefully sharpened. Handles are selected white hickory, leather tipped. We guarantee these chisels to give entire satisfaction.

Inch..... 1 1/2 2 1/2 3 1/2 4 1/2 5 1/2 6 1/2 7 1/2 8 1/2 9 1/2 10 1/2 11 1/2 12 1/2 13 1/2 14 1/2 15 1/2 16 1/2 17 1/2 18 1/2 19 1/2 20 1/2 21 1/2 22 1/2 23 1/2 24 1/2 25 1/2 26 1/2 27 1/2 28 1/2 29 1/2 30 1/2 31 1/2 32 1/2 33 1/2 34 1/2 35 1/2 36 1/2 37 1/2 38 1/2 39 1/2 40 1/2 41 1/2 42 1/2 43 1/2 44 1/2 45 1/2 46 1/2 47 1/2 48 1/2 49 1/2 50 1/2 51 1/2 52 1/2 53 1/2 54 1/2 55 1/2 56 1/2 57 1/2 58 1/2 59 1/2 60 1/2 61 1/2 62 1/2 63 1/2 64 1/2 65 1/2 66 1/2 67 1/2 68 1/2 69 1/2 70 1/2 71 1/2 72 1/2 73 1/2 74 1/2 75 1/2 76 1/2 77 1/2 78 1/2 79 1/2 80 1/2 81 1/2 82 1/2 83 1/2 84 1/2 85 1/2 86 1/2 87 1/2 88 1/2 89 1/2 90 1/2 91 1/2 92 1/2 93 1/2 94 1/2 95 1/2 96 1/2 97 1/2 98 1/2 99 1/2 100 1/2 101 1/2 102 1/2 103 1/2 104 1/2 105 1/2 106 1/2 107 1/2 108 1/2 109 1/2 110 1/2 111 1/2 112 1/2 113 1/2 114 1/2 115 1/2 116 1/2 117 1/2 118 1/2 119 1/2 120 1/2 121 1/2 122 1/2 123 1/2 124 1/2 125 1/2 126 1/2 127 1/2 128 1/2 129 1/2 130 1/2 131 1/2 132 1/2 133 1/2 134 1/2 135 1/2 136 1/2 137 1/2 138 1/2 139 1/2 140 1/2 141 1/2 142 1/2 143 1/2 144 1/2 145 1/2 146 1/2 147 1/2 148 1/2 149 1/2 150 1/2 151 1/2 152 1/2 153 1/2 154 1/2 155 1/2 156 1/2 157 1/2 158 1/2 159 1/2 160 1/2 161 1/2 162 1/2 163 1/2 164 1/2 165 1/2 166 1/2 167 1/2 168 1/2 169 1/2 170 1/2 171 1/2 172 1/2 173 1/2 174 1/2 175 1/2 176 1/2 177 1/2 178 1/2 179 1/2 180 1/2 181 1/2 182 1/2 183 1/2 184 1/2 185 1/2 186 1/2 187 1/2 188 1/2 189 1/2 190 1/2 191 1/2 192 1/2 193 1/2 194 1/2 195 1/2 196 1/2 197 1/2 198 1/2 199 1/2 200 1/2 201 1/2 202 1/2 203 1/2 204 1/2 205 1/2 206 1/2 207 1/2 208 1/2 209 1/2 210 1/2 211 1/2 212 1/2 213 1/2 214 1/2 215 1/2 216 1/2 217 1/2 218 1/2 219 1/2 220 1/2 221 1/2 222 1/2 223 1/2 224 1/2 225 1/2 226 1/2 227 1/2 228 1/2 229 1/2 230 1/2 231 1/2 232 1/2 233 1/2 234 1/2 235 1/2 236 1/2 237 1/2 238 1/2 239 1/2 240 1/2 241 1/2 242 1/2 243 1/2 244 1/2 245 1/2 246 1/2 247 1/2 248 1/2 249 1/2 250 1/2 251 1/2 252 1/2 253 1/2 254 1/2 255 1/2 256 1/2 257 1/2 258 1/2 259 1/2 260 1/2 261 1/2 262 1/2 263 1/2 264 1/2 265 1/2 266 1/2 267 1/2 268 1/2 269 1/2 270 1/2 271 1/2 272 1/2 273 1/2 274 1/2 275 1/2 276 1/2 277 1/2 278 1/2 279 1/2 280 1/2 281 1/2 282 1/2 283 1/2 284 1/2 285 1/2 286 1/2 287 1/2 288 1/2 289 1/2 290 1/2 291 1/2 292 1/2 293 1/2 294 1/2 295 1/2 296 1/2 297 1/2 298 1/2 299 1/2 300 1/2 301 1/2 302 1/2 303 1/2 304 1/2 305 1/2 306 1/2 307 1/2 308 1/2 309 1/2 310 1/2 311 1/2 312 1/2 313 1/2 314 1/2 315 1/2 316 1/2 317 1/2 318 1/2 319 1/2 320 1/2 321 1/2 322 1/2 323 1/2 324 1/2 325 1/2 326 1/2 327 1/2 328 1/2 329 1/2 330 1/2 331 1/2 332 1/2 333 1/2 334 1/2 335 1/2 336 1/2 337 1/2 338 1/2 339 1/2 340 1/2 341 1/2 342 1/2 343 1/2 344 1/2 345 1/2 346 1/2 347 1/2 348 1/2 349 1/2 350 1/2 351 1/2 352 1/2 353 1/2 354 1/2 355 1/2 356 1/2 357 1/2 358 1/2 359 1/2 360 1/2 361 1/2 362 1/2 363 1/2 364 1/2 365 1/2 366 1/2 367 1/2 368 1/2 369 1/2 370 1/2 371 1/2 372 1/2 373 1/2 374 1/2 375 1/2 376 1/2 377 1/2 378 1/2 379 1/2 380 1/2 381 1/2 382 1/2 383 1/2 384 1/2 385 1/2 386 1/2 387 1/2 388 1/2 389 1/2 390 1/2 391 1/2 392 1/2 393 1/2 394 1/2 395 1/2 396 1/2 397 1/2 398 1/2 399 1/2 400 1/2 401 1/2 402 1/2 403 1/2 404 1/2 405 1/2 406 1/2 407 1/2 408 1/2 409 1/2 410 1/2 411 1/2 412 1/2 413 1/2 414 1/2 415 1/2 416 1/2 417 1/2 418 1/2 419 1/2 420 1/2 421 1/2 422 1/2 423 1/2 424 1/2 425 1/2 426 1/2 427 1/2 428 1/2 429 1/2 430 1/2 431 1/2 432 1/2 433 1/2 434 1/2 435 1/2 436 1/2 437 1/2 438 1/2 439 1/2 440 1/2 441 1/2 442 1/2 443 1/2 444 1/2 445 1/2 446 1/2 447 1/2 448 1/2 449 1/2 450 1/2 451 1/2 452 1/2 453 1/2 454 1/2 455 1/2 456 1/2 457 1/2 458 1/2 459 1/2 460 1/2 461 1/2 462 1/2 463 1/2 464 1/2 465 1/2 466 1/2 467 1/2 468 1/2 469 1/2 470 1/2 471 1/2 472 1/2 473 1/2 474 1/2 475 1/2 476 1/2 477 1/2 478 1/2 479 1/2 480 1/2 481 1/2 482 1/2 483 1/2 484 1/2 485 1/2 486 1/2 487 1/2 488 1/2 489 1/2 490 1/2 491 1/2 492 1/2 493 1/2 494 1/2 495 1/2 496 1/2 497 1/2 498 1/2 499 1/2 500 1/2 501 1/2 502 1/2 503 1/2 504 1/2 505 1/2 506 1/2 507 1/2 508 1/2 509 1/2 510 1/2 511 1/2 512 1/2 513 1/2 514 1/2 515 1/2 516 1/2 517 1/2 518 1/2 519 1/2 520 1/2 521 1/2 522 1/2 523 1/2 524 1/2 525 1/2 526 1/2 527 1/2 528 1/2 529 1/2 530 1/2 531 1/2 532 1/2 533 1/2 534 1/2 535 1/2 536 1/2 537 1/2 538 1/2 539 1/2 540 1/2 541 1/2 542 1/2 543 1/2 544 1/2 545 1/2 546 1/2 547 1/2 548 1/2 549 1/2 550 1/2 551 1/2 552 1/2 553 1/2 554 1/2 555 1/2 556 1/2 557 1/2 558 1/2 559 1/2 560 1/2 561 1/2 562 1/2 563 1/2 564 1/2 565 1/2 566 1/2 567 1/2 568 1/2 569 1/2 570 1/2 571 1/2 572 1/2 573 1/2 574 1/2 575 1/2 576 1/2 577 1/2 578 1/2 579 1/2 580 1/2 581 1/2 582 1/2 583 1/2 584 1/2 585 1/2 586 1/2 587 1/2 588 1/2 589 1/2 590 1/2 591 1/2 592 1/2 593 1/2 594 1/2 595 1/2 596 1/2 597 1/2 598 1/2 599 1/2 600 1/2 601 1/2 602 1/2 603 1/2 604 1/2 605 1/2 606 1/2 607 1/2 608 1/2 609 1/2 610 1/2 611 1/2 612 1/2 613 1/2 614 1/2 615 1/2 616 1/2 617 1/2 618 1/2 619 1/2 620 1/2 621 1/2 622 1/2 623 1/2 624 1/2 625 1/2 626 1/2 627 1/2 628 1/2 629 1/2 630 1/2 631 1/2 632 1/2 633 1/2 634 1/2 635 1/2 636 1/2 637 1/2 638 1/2 639 1/2 640 1/2 641 1/2 642 1/2 643 1/2 644 1/2 645 1/2 646 1/2 647 1/2 648 1/2 649 1/2 650 1/2 651 1/2 652 1/2 653 1/2 654 1/2 655 1/2 656 1/2 657 1/2 658 1/2 659 1/2 660 1/2 661 1/2 662 1/2 663 1/2 664 1/2 665 1/2 666 1/2 667 1/2 668 1/2 669 1/2 670 1/2 671 1/2 672 1/2 673 1/2 674 1/2 675 1/2 676 1/2 677 1/2 678 1/2 679 1/2 680 1/2 681 1/2 682 1/2 683 1/2 684 1/2 685 1/2 686 1/2 687 1/2 688 1/2 689 1/2 690 1/2 691 1/2 692 1/2 693 1/2 694 1/2 695 1/2 696 1/2 697 1/2 698 1/2 699 1/2 700 1/2 701 1/2 702 1/2 703 1/2 704 1/2 705 1/2 706 1/2 707 1/2 708 1/2 709 1/2 710 1/2 711 1/2 712 1/2 713 1/2 714 1/2 715 1/2 716 1/2 717 1/2 718 1/2 719 1/2 720 1/2 721 1/2 722 1/2 723 1/2 724 1/2 725 1/2 726 1/2 727 1/2 728 1/2 729 1/2 730 1/2 731 1/2 732 1/2 733 1/2 734 1/2 735 1/2 736 1/2 737 1/2 738 1/2 739 1/2 740 1/2 741 1/2 742 1/2 743 1/2 744 1/2 745 1/2 746 1/2 747 1/2 748 1/2 749 1/2 750 1/2 751 1/2 752 1/2 753 1/2 754 1/2 755 1/2 756 1/2 757 1/2 758 1/2 759 1/2 760 1/2 761 1/2 762 1/2 763 1/2 764 1/2 765 1/2 766 1/2 767 1/2 768 1/2 769 1/2 770 1/2 771 1/2 772 1/2 773 1/2 774 1/2 775 1/2 776 1/2 777 1/2 778 1/2 779 1/2 780 1/2 781 1/2 782 1/2 783 1/2 784 1/2 785 1/2 786 1/2 787 1/2 788 1/2 789 1/2 790 1/2 791 1/2 792 1/2 793 1/2 794 1/2 795 1/2 796 1/2 797 1/2 798 1/2 799 1/2 800 1/2 801 1/2 802 1/2 803 1/2 804 1/2 805 1/2 806 1/2 807 1/2 808 1/2 809 1/2 810 1/2 811 1/2 812 1/2 813 1/2 814 1/2 815 1/2 816 1/2 817 1/2 818 1/2 819 1/2 820 1/2 821 1/2 822 1/2 823 1/2 824 1/2 825 1/2 826 1/2 827 1/2 828 1/2 829 1/2 830 1/2 831 1/2 832 1/2 833 1/2 834 1/2 835 1/2 836 1/2 837 1/2 838 1/2 839 1/2 840 1/2 841 1/2 842 1/2 843 1/2 844 1/2 845 1/2 846 1/2 847 1/2 848 1/2 849 1/2 850 1/2 851 1/2 852 1/2 853 1/2 854 1/2 855 1/2 856 1/2 857 1/2 858 1/2 859 1/2 860 1/2 861 1/2 862 1/2 863 1/2 864 1/2 865 1/2 866 1/2 867 1/2 868 1/2 869 1/2 870 1/2 871 1/2 872 1/2 873 1/2 874 1/2 875 1/2 876 1/2 877 1/2 878 1/2 879 1/2 880 1/2 881 1/2 882 1/2 883 1/2 884 1/2 885 1/2 886 1/2 887 1/2 888 1/2 889 1/2 890 1/2 891 1/2 892 1/2 893 1/2 894 1/2 895 1/2 896 1/2 897 1/2 898 1/2 899 1/2 900 1/2 901 1/2 902 1/2 903 1/2 904 1/2 905 1/2 906 1/2 907 1/2 908 1/2 909 1/2 910 1/2 911 1/2 912 1/2 913 1/2 914 1/2 915 1/2 916 1/2 917 1/2 918 1/2 919 1/2 920 1/2 921 1/2 922 1/2 923 1/2 924 1/2 925 1/2 926 1/2 927 1/2 928 1/2 929 1/2 930 1/2 931 1/2 932 1/2 933 1/2 934 1/2 935 1/2 936 1/2 937 1/2 938 1/2 939 1/2 940 1/2 941 1/2 942 1/2 943 1/2 944 1/2 945 1/2 946 1/2 947 1/2 948 1/2 949 1/2 950 1/2 951 1/2 952 1/2 953 1/2 954 1/2 955 1/2 956 1/2 957 1/2 958 1/2 959 1/2 960 1/2 961 1/2 962 1/2 963 1/2 964 1/2 965 1/2 966 1/2 967 1/2 968 1/2 969 1/2 970 1/2 971 1/2 972 1/2 973 1/2 974 1/2 975 1/2 976 1/2 977 1/2 978 1/2 979 1/2 980 1/2 981 1/2 982 1/2 983 1/2 984 1/2 985 1/2 986 1/2 987 1/2 988 1/2 989 1/2 990 1/2 991 1/2 992 1/2 993 1/2 994 1/2 995 1/2 996 1/2 997 1/2 998 1/2 999 1/2 1000 1/2 1001 1/2 1002 1/2 1003 1/2 1004 1/2 1005 1/2 1006 1/2 1007 1/2 1008 1/2 1009 1/2 1010 1/2 1011 1/2 1012 1/2 1013 1/2 1014 1/2 1015 1/2 1016 1/2 1017 1/2 1018 1/2 1019 1/2 1020 1/2 1021 1/2 1022 1/2 1023 1/2 1024 1/2 1025 1/2 1026 1/2 1027 1/2 1028 1/2 1029 1/2 1030 1/2 1031 1/2 1032 1/2 1033 1/2 1034 1/2 1035 1/2 1036 1/2 1037 1/2 1038 1/2 1039 1/2 1040 1/2 1041 1/2 1042 1/2 1043 1/2 1044 1/2 1045 1/2 1046 1/2 1047 1/2 1048 1/2 1049 1/2 1050 1/2 1051 1/2 1052 1/2 1053 1/2 1054 1/2 1055 1/2 1056 1/2 1057 1/2 1058 1/2 1059 1/2 1060 1/2 1061 1/2 1062 1/2 1063 1/2 1064 1/2 1065 1/2 1066 1/2 1067 1/2 1068 1/2 1069 1/2 1070 1/2 1071 1/2 1072 1/2 1073 1/2 1074 1/2 1075 1/2 1076 1/2 1077 1/2 1078 1/2 1079 1/2 1080 1/2 1081 1/2 1082 1/2 1083 1/2 1084 1/2 1085 1/2 1086 1/2 1087 1/2 1088 1/2 1089 1/2 1090 1/2 1091 1/2 1092 1/2 1093 1/2 1094 1/2 1095 1/2 1096 1/2 1097 1/2 1098 1/2 1099 1/2 1100 1/2 1101 1/2 1102 1/2 1103 1/2 1104 1/2 1105 1/2 1106 1/2 1107 1/2 1108 1/2 1109 1/2 1110 1/2 1111 1/2 1112 1/2 1113 1/2 1114 1/2 1115 1/2 1116 1/2 1117 1/2 1118 1/2 1119 1/2 1120 1/2 1121 1/2 1122 1/2 1123 1/2 1124 1/2 1125 1/2 1126 1/2 1127 1/2 1128 1/2 1129 1/2 1130 1/2 1131 1/2 1132 1/2 1133 1/2 1134 1/2 1135 1/2 1136 1/2 1137 1/2 1138 1/2 1139 1/2 1140 1/2 1141 1/2 1142 1/2 1143 1/2 1144 1/2 1145 1/2 1146 1/2 1147 1/2 1148 1/2 1149 1/2 1150 1/2 1151 1/2 1152 1/2 1153 1/2 1154 1/2 1155 1/2 1156 1/2 1157 1/2 1158 1/2 1159 1/2 1160 1/2 1161 1/2 1162 1/2 1163 1/2 1164 1/2 1165 1/2 1166 1/2 1167 1/2 1168 1/2 1169 1/2 1170 1/2 1171 1/2 1172 1/2 1173 1/2 1174 1/2 1175 1/2 1176 1/2 1177 1/2 1178 1/2 1179 1/2 1180 1/2 1181 1/2 1182 1/2 1183 1/2 1184 1/2 1185 1/2 1186 1/2 1187 1/2 1188 1/2 1189 1/2 1190 1/2 1191 1/2 1192 1/2 1193 1/2 1194 1/2 1195 1/2 1196 1/2 1197 1/2 1198 1/2 1199 1/2 1200 1/2 1201 1/2 1202 1/2 1203 1/2 1204 1/2 1205 1/2 1206 1/2 1207 1/2 1208 1/2 1209 1/2 1210 1/2 1211 1/2 1212 1/2 1213 1/2 1214 1/2 1215 1/2 1216 1/2 1217 1/2 1218 1/2 1219 1/2 1220 1/2 1221 1/2 1222 1/2 1223 1/2 1224 1/2 1225 1/2 1226 1/2 1227 1/2 1228 1/2 1229 1/2 1230 1/2 1231 1/2 1232 1/2 1233 1/2 1234 1/2 1235 1/2 1236 1/2 1237 1/2 1238 1/2 1239 1/2 1240 1/2 1241 1/2 1242 1/2 1243 1/2 1244 1/2 1245 1/2 1246 1/2 1247 1/2 1248 1/2 1249 1/2 1250 1/2 1251 1/2 1252 1/2 1253 1/2 1254 1/2 1255 1/2 1256 1/2 1257 1/2 1258 1/2 1259 1/2 1260 1/2 1261 1/2 1262 1/2 1263 1/2 1264 1/2 1265 1/2 1266 1/2 1267 1/2 1268 1/2 1269 1/2 1270 1/2 1271 1/2 1272 1/2 1273 1/2 1274 1/2 1275 1/2 1276 1/2 1277 1/2 1278 1/2 1279 1/2 1280 1/2 1281 1/2 1282 1/2 1283 1/2 1284 1/2 1285 1/2 1286 1/2 1287 1/2 1288 1/2 1289 1/2 1290 1/2 1291 1/2 1292 1/2 1293 1/2 1294 1/2 1295 1/2 1296 1/2 1297 1/2 1298 1/2 1299 1/2 1300 1/2 1301 1/2 1302 1/2 1303 1/2 1304 1/2 1305 1/2 1306 1/2 1307 1/2 1308 1/2 1309 1/2 1310 1/2 1311 1/2 1312 1/2 1313 1/2 1314 1/2 1315 1/2 1316 1/2 1317 1/2 1318 1/2 1319 1/2 1320 1/2 1321 1/2 1322 1/2 1323 1/2 1324 1/2 1325 1/2 1326 1/2 1327 1/2 1328 1/2 1329 1/2 1330 1/2 1331 1/2 1332 1/2 1333 1/2 1334 1/2 1335 1/2 1336 1/2 1337 1/2 1338 1/2 1339 1/2 1340 1/2 1341

IVES "MEPHISTO" EXPANSIVE BIT.



Has all the desirable features of the Clark's and other expansive bits. So constructed that the cutter will stand a severe strain without creeping, springing or loosening while boring, which is a common fault with other makes of expansive bits. The binding screw holds the cutter firmly in place and the small set screw prevents it from being forced in either direction, forming a double locking device, so that the cutter cannot move in the slightest degree until screws are released. Especially adapted to bore in hard wood. Made to bore any size holes up to 3 inches, and can be readily adjusted to a 32d of an inch. Stern a single piece drop forged tool steel. Cutters made of the highest grade of tool steel properly tempered and will hold a good cutting edge.

4-C-5501. A small size "Mephisto" Expansive Bit. With two cutters, one cutting $\frac{1}{2}$ to $\frac{3}{4}$ inch; the other $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 86c

4-C-5503. Large size "Mephisto" Expansive Bit. With two cutters, one cutting $\frac{1}{2}$ to $1\frac{1}{2}$ inches; the other $1\frac{1}{2}$ to 3 inches. Price..... \$1.05

4-C-5505. Extra cutters for small size Ives "Mephisto" Expansive Bit. Price..... 11c

Size No. 1. Cuts from $\frac{1}{2}$ to $\frac{3}{4}$ inch. Price..... 11c

Size No. 2. Cuts from $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 15c

4-C-5507. Extra cutters for large size Ives "Mephisto" Expansive Bit. Price..... 19c

Size No. 3. Cuts from $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 23c

Size No. 4. Cuts from $1\frac{1}{2}$ to 3 inches. Price..... 23c

CLARK'S PATTERN EXPANSIVE BIT.



Superior to Expansive Bits of this kind offered by others.

Cutters are made of high grade tool steel properly tempered. Great care is taken in the fitting of this tool and it is guaranteed to give satisfactory service.

4-C-5509. Small Size Clark's Pattern Expansive Bit. With two cutters, one boring from $\frac{1}{2}$ to $\frac{3}{4}$ inch; the other from $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 52c

4-C-5511. Large Size Clark's Pattern Expansive Bit. With two cutters, one boring from $\frac{3}{4}$ to $1\frac{1}{2}$ inches; the other from $1\frac{1}{2}$ to 3 inches. Price..... 73c

4-C-5513. Extra Cutters for Small Size Clark's Pattern Expansive Bit. Price..... 9c

Size No. 1. Cuts from $\frac{1}{2}$ to $\frac{3}{4}$ inch. Price..... 13c

4-C-5515. Extra Cutters for Large Size Clark's Pattern Expansive Bit. Price..... 17c

Size No. 2. Cuts from $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 19c

Size No. 3. Cuts from $\frac{3}{4}$ to $1\frac{1}{2}$ inches. Price..... 19c

Size No. 4. Cuts from $1\frac{1}{2}$ to 3 inches. Price..... 19c

AUGER BIT GAUGE

4-C-5517. Will fit any Bit. Gauges exact depth of hole. Price, without Bit..... 21c

ADJUSTABLE AUGER HANDLES

4-C-5519. Fits all sizes Nut Augers. Can be quickly removed. Price..... 18c

ROSE HEAD COUNTERSINK BITS

4-C-5521. Forged from High Grade Tool Steel properly tempered. For use in metal. Size, $\frac{1}{2}$ inch. Price..... 17c

Size, $\frac{3}{4}$ inch. Price..... 18c

REVERSIBLE COUNTERSINK AND DOWEL POINTER

4-C-5523. Reversible Head. Can be used for sharpening pins or dowels. Cutter made of high grade tool steel. Price, each, 15c

SCREW DRIVER BITS

4-C-5525. High Grade Tempered Crucible Steel. Size, Small Medium Large Extra. Price, 15c 18c 20c 22c

EXTENSION BIT HOLDERS

4-C-5527. For Boring Through Floors, Partitions and other places that cannot be reached with an ordinary Bit. Will follow $\frac{1}{2}$ inch or larger bits. Length, inches, 12 18 24. Price..... \$0.39 \$0.93 \$1.05

COMMON AUGER HANDLES

4-C-5529. Selected hardwood. Price for three, 10c Each. 4c

SNAIL HEAD COUNTERSINK BITS

4-C-5531. For Wood. High grade tool steel, properly tempered. Size, $\frac{1}{2}$ inch. 16c Size, $\frac{3}{4}$ inch. 15c

COUNTERSINK BIT WITH GAUGE

4-C-5533. To Regulate Depth of Cut. For wood only. High grade tool steel. Fully warranted. Price..... 21c

SQUARE REAMER BITS

4-C-5535. High Grade Tool Steel, Properly Tempered. Concave ground. Price..... 19c

4-C-5537. Cast Steel, Properly Tempered and Ground. Price..... 9c

KNURLED CENTER PUNCH

4-C-5539. High Grade Cast Steel, Tempered at Both Ends. Diameter $\frac{1}{2}$ inch. Price..... 7c

"PERFECT" HANDLE SCREW DRIVER



4-C-5541. Will Stand More Abuse Than Any Other Screwdriver Made. The Only Screwdriver that can be used as a Hammer, to force point of screw into the wood. The blade, bolster handle, flattened hammer head are drop forged from one piece of the toughest steel that can be made, the handles being pocketed on each side of the drop forging in such a manner and so securely that they cannot be split or broken off. Is properly balanced and perfectly tempered. Fully warranted. There is absolutely nothing better made.

Length of blade, inches. 4 6 8 10. Price each..... 20c 29c 40c 49c

INDESTRUCTIBLE SQUARE SHANK SCREWDRIVER

4-C-5543. For Mechanics' use. Square shank for use with wrench for tightening or loosening screws or other heavy work. Blade, shank and head a steel. Shank extending through handle is flattened, forming a cap, making it impossible to turn, or the handle to come off. The steel ferrules are put on under heavy pressure and are guaranteed to remain in place. Handles tire satisfaction or money refunded. Each tool warranted to give entire satisfaction.

Length of blade, inch. 4 6 8 10. Price each..... 14c 18c 26c 34c 42c

GENUINE CHAMPION SCREWDRIVER

4-C-5545. A favorite of many years standing. Blades are forged from the highest grade steel, properly tempered and is fastened securely in handle and cannot pull out. Selected hardwood handle, cherry finish. Length blade, inches. 3 4 5 6 8 10. Price each..... 13c 17c 22c 25c 32c 40c

CHAMPION PATTERN SCREWDRIVER

4-C-5547. Best value screwdrivers ever offered at the price. Blades are forged from high-grade crucible steel. Selected hardwood handles, steel ferrules. Guaranteed to give excellent satisfaction. Length blade, inches. 3 4 5 6 8 10 12. Price each 7c 9c 10c 13c 15c 17c 20c

GOODELL'S AUTOMATIC INTERCHANGEABLE SCREWDRIVER

4-C-5549. Can be used as a spiral ratchet or plain screwdriver. Practical, strong, durable tool. Will not get out of order. Furnished with three forged steel bits. Selected finished hardwood handle. Length extended, 14 inches. Length closed, 7 inches. Price..... 69c

GOODELL'S REVERSIBLE INTERCHANGEABLE SCREWDRIVER

4-C-5551. With two distinct spirals. For driving and drawing screws automatically. Finished hardwood handle, furnished with three forged steel bits; length extended 16 inches, length closed 9 inches. Price..... \$1.11

DRILL ATTACHMENT FOR GOODELL'S INTERCHANGEABLE SCREWDRIVERS

Can be readily applied to Goodell's Interchangeable Screwdrivers, converting the driver into an automatic drill, thus combining two tools in one. 4-C-5553. Fitting Automatic Screwdriver No. 4-B-3285. Price for chuck and eight drill points..... 47c

4-C-5555. Fitting Reversible Screwdriver, No. 4-B-3287. Price for chuck and eight drill points..... 51c

GOODELL'S RATCHET SCREWDRIVERS

4-C-5557. The strongest, most durable ratchet screwdriver on the market. Blades, dogs and spring, which make up the ratchet mechanism, made of a high grade tool steel. The ratchet teeth are deeply cut directly into the stem. Changes from right to left are made by simply turning the knurled ferrule. Each tool fully warranted. Length of blade, inches. 4 5 6 8 10. Price each..... 35c 40c 48c 51c 58c

GERMAN PATTERN GIMLET BITS

4-C-5559. The finest gimlet bits manufactured. Special high grade steel, properly tempered, especially adapted to those who work in hard woods. Sizes, 2-32, 3-32, 4-32, 5-32, 6-32, 7-32, 8-32, 10-32. State size. Per doz..... 69c. Any size, each..... 6c

4-C-5561. Set of eight of the above bits, one each size. Price..... 46c

STANDARD GERMAN PATTERNS GIMLET BITS

4-C-5563. Tempered cast steel. Suitable for any ordinary work. Sizes, 2-32, 3-32, 4-32, 5-32, 6-32, 7-32, 8-32, 10-32. Per doz..... 52c. Each..... 6c

4-C-5565. Set of eight of the above bits, one each size. Price..... 35c

KNURLED NAIL SETS

4-C-5567. Superior Cast Steel, Tempered at Both Ends. With hollow or cup points. Size, points. Price, each, any size..... 5c

Price, per dozen..... 53c

Set of four, one each size..... 18c

KNURLED PRICK PUNCH

4-C-5571. Superior Cast Steel, Tempered at Both Ends. Diameter $\frac{1}{2}$ inch. Price..... 7c

UNIVERSAL BALL BEARING RATCHET HANDLE

4-C-5569. Shifter Operating Ratchet Mechanism, which can be set for either right or left hand work. Ball bearing lignum vitae head. Socket has square taper hole with set screw for fastening bit to screw driver or nut wrench. Iron handles 8 inches long. Price..... 97c

CHICAGO HOUSE WRECKING CO. 35th & Iron Streets, Chicago.

If you want a warm meal at any time buy a Vac Jac Cooker.

CARPENTERS' STEEL SQUARES

Our line of squares are the most accurate, strongest and best finished squares possible to produce. Both body and tongue are tapering, the ends being thinnest, giving the squares the proper hang. The graduations are clearly marked and are most accurate. Each square is guaranteed to give entire satisfaction.

MECHANICS' OXIDIZED COPPER FINISHED SQUARE.

4-C-5701. No. 100 R. O. C. Oxidized copper finished square. Will please any mechanic who appreciates first-class tools. Oxidized copper, giving it the appearance of a gun metal finish and is the best rust resisting finish known. The graduations and figures are white enamel clear and distinct. Has hardened corners, which will not wear round when used for marking spaces. Body 24x2 in. size of tongue 16x1 in. marked on face, 1/2, 1/4 and 1/8 in. spaces; on back, 1/2, 1/4 and 1/8 in. spaces. Has brace measure, eight square, 1/8 scale and after table for buildings of any width or pitch and as shown in illustration; furnished complete with directions. Price. **\$1.44**



SMALL STEEL SQUARES

4-C-5719. Gun metal finish; size of body 18x1 1/2 in. size of tongue 12x1 in.; a very popular size for mechanic's tool boxes. Made with tapering ends and hardened corners; face marked 1/2, 1/4 and 1/8 in. spaces. Back marked 1/2 in. and 1/4 in. spaces. Price. **73c**

4-C-5721. Nickel plated steel square, hardened corners. Size of body 12x1 1/2 in.; size of tongue 8x1 in. convenient size for tool chest and for home use; absolutely accurate and a strictly first class tool. Face marked 1/2, 1/4 and 1/8 in.; back marked 1/2 and 1/4 in. Price. **51c**


4-C-5723. Nickel plated steel square; size of body 12x1 in.; size of tongue 7x1 in.; accurately marked and a most convenient tool for ordinary work. Marked on both sides 1/2 and 1/4 in. spaces. Price. **12c**

JENNINGS TAKE 'DOWN SQUARE

Jennings take-down square. What every mechanic has long desired. Occupies space 4x24 inches and is absolutely accurate and thoroughly practical. Tongue and groove is accurately milled to fit tight and make a perfectly true joint. Has no bolts or screws to become loose or lost. The spring takes up any wear. Long bearings in grooves combined with the square shoulders insure an accurate fit. Sizes of body, 24x2 inches. Size of tongue, 16x1 1/2 inches. Face marked 1/2, 1/4 and 1/8 in. spaces; back marked 1/2 and 1/4 in. spaces. Has Essex Board Measure and brace measure. Figures and graduations are deep and plainly marked. Fully warranted. Price. **\$2.20**

4-C-5725. Blued finish with canvas case. Price. **\$2.20**

4-C-5727. Polished finish with canvas case. Price. **\$1.90**



PLUMBS AND LEVELS

Each instrument is carefully tested as to its accuracy before it leaves the manufacturer. The woodwork is thoroughly seasoned and polished. We offer this line to those who want accurate instruments and the best value possible to secure. Absolute satisfaction is guaranteed or money refunded.

SOLID ROSEWOOD PLUMB AND LEVEL.

4-C-5713. A strictly high grade level. Designed for mechanic's use. Made in the finest possible manner, perfectly finished and warranted to be perfectly accurate. Made of selected, highly polished rosewood, heavy trimmings. Built in such a manner that it will not warp or get out of plumb, requiring no adjustment. Has brass arch top plate, brass lipped side views, heavy brass ends. Lengths, 26, 28 and 30. In ordering state length desired. Price. **\$2.24**

ADJUSTABLE PLUMB AND LEVEL.

4-C-5729. Solid Cherry, highly polished adjustable plumb and level. With graduated adjustments to work at any angle or elevation. Specially desirable for cutting rafters and braces and has brass arch top plate, brass lipped side views, heavy solid brass ends. Made and finished in the best possible manner and fully warranted. Length, 28 inches. Price. **\$1.31**

POLISHED CHERRY PLUMB AND LEVEL

4-C-5715. Brass arch top plate, two side views, proved glasses. Fully warranted. Lengths, 26, 28 and 30 inches. State length wanted. Price. **\$2.53**

ADJUSTABLE CHERRY PLUMB AND LEVEL WITH EXTENSION LEVEL SIGHTS.

4-C-5731. When not in use the sides are depressed flush with the surface of the level and raised into position by merely pressing the button. The sights are accurately adjusted and may be relied upon to extend the horizontal line to any distance required. The level is highly polished and has brass arch top plate, brass lipped side views and heavy brass ends. Length, 28 inches. Price. **\$1.89**

MASONS' PLUMB AND LEVEL.

POLISHED CHERRY ADJUSTABLE PLUMB AND LEVEL

4-C-5717. An excellent level for mechanics' use. Brass arch top plate, brass ends, two side views. Lengths, 26, 28 and 30 inches. State length wanted. Price. **\$2.26**

4-C-5733. High grade level for brick and stone masons. Is adjustable. Has brass arch top plate, two side views and can be used with plumb, bob and line. Price. **\$1.70**

ADJUSTABLE IRON PLUMB AND LEVEL.


4-C-5735. With double plumbs. Carefully and accurately machined. Japanese finish, nickel plated trimmings. Warranted accurate. Length, inches. 12 18 24 Price. **\$1.29 \$1.45 \$1.57**

POCKET LEVEL.

4-C-5737. Can be readily attached to steel square or straight edge. Iron body, brass top plate, proved glasses. Warranted true. Price. **9c**


BRASS LINED TRY SQUARES.

4-C-5739. Made in a superior manner. Oxidized steel blade, accurately marked. Selected beechwood handle, brass lined. Fully warranted. Size represents length of blade. Size, inches. 4 6 7 9 Price. 10c 12c 14c 16c




COMBINED TRY AND MITER SQUARE.

4-C-5741. Brass lined rosewood handle, steel blade. Graduations plainly and accurately marked. A first class mechanics' tool, fully warranted. Size represents length of blade. Size, inches. 4 6 7 9 Price. 23c 26c 30c 36c



METAL TRY SQUARES.

4-C-5743. A first class tool at a moderate price. Steel blades, graduations accurately marked. Nickel plated iron handles, fully warranted. Size represents length of blade. Size, inches. 6 8 10 12 Price. 18c 24c 32c 37c



SLIDING "T" BEVELS.

4-C-5745. Brass tipped, solid rosewood handle. For right or left hand use. Length, inches. 6 8 10 12 Price. 16c 18c 20c 22c



METAL SLIDING "T" BEVEL

4-C-5747. Polished steel blade, nickel plated iron handles. Carefully and accurately made. Length, inches. 6 8 10 Price. 38c 41c 43c



NICKEL PLATED POCKET BUTT GAUGE.

4-C-5749. Setting outer cutter for gauging edge of door. The cutter on other end gauges distance from back of jamb. Second bar gas steel cutter for gauging thickness of butt. A convenient tool which saves its cost several times over in hanging a few doors. Price. **54c**



ROTARY BUTT GAUGE.

4-C-5751. One end marks thickness and the other for width of butts. A very useful tool, polished steel, nicely finished. Price. **28c**



BOXWOOD MARKING GAUGES.

4-C-5753. Oval head and bar. Steel points, brass thumb screw. Nicely finished and accurately marked. Price. **16c**



MAHOGANY MORTISE AND MARKING GAUGE.

4-C-5755. Plated head. Screw slide, brass thumb screw, steel points. Price. **42c**



LEVEL SIGHTS.


4-C-5757. Can be readily attached to any wood level. With which the user has accurate means of leveling from one given point to another at a long distance. Price, per pair. **55c**

4-B-3459. Level sights for iron levels. Price, per pair. **58c**




NICKEL PLATED POCKET LEVEL.

4-C-5761. Hexagon Pocket level. Proved glasses. Warranted accurate. Length, inches. 2 3 4 Price. 23c 26c 29c



IMPORTED HARDWOOD POCKET LEVEL.

4-C-5759. Brass Top Plate. Glass can be viewed from top or side. Warranted true. Length, 5 1/2 inches. Price. **9c**



MACHINISTS TOOLS.

Carefully selected and the Product of the most reputable tool makers in the market. Each tool is warranted accurate and guaranteed to meet every requirement of the most skilled mechanic.

STARRETT'S YANKEE CALIPERS

With Spring or Solid Nut.
4-C-5901. Outside Caliper,
Starrett's No. 79.

4-C-5903. Inside Caliper,
Starrett's No. 73.

Size, inch	2 1/2	3	4
Solid Nut,	43c	47c	50c
Spring Nut,	53c	57c	60c
Size, inch	5	6	8
Solid Nut,	55c	58c	69c
Spring Nut,	65c	68c	79c

STARRETT'S FAY PATENT CALIPERS

With Solid or Spring Nut.
4-C-5909. Outside Caliper,
Starrett's No. 75.

4-C-5911. Inside Caliper,
Starrett's No. 74.

Size, inch	2 1/2	3	4
Solid Nut, price	69c	72c	79c
Spring Nut, price	79c	82c	89c
Size, inch	5	6	8
Solid Nut, price	83c	84c	
Spring Nut, price	93c	\$1.04	

STARRETT'S IMPROVED FIRM JOINT CALIPERS

Adjusted by means of a Screw.
Far superior to the old style
riveted joint calipers.

4-C-5917. Outside Caliper,
Starrett's No. 26.

4-C-5919. Inside Caliper,
Starrett's No. 27.

Size, inch	3	4	5	6	8
Either Style	27c	34c	39c	46c	55c
Size inch	10	12	14	16	
Either Style	64c	72c	\$1.04	\$1.23	

HERMAPHRODITE CALIPERS

4-C-5923. Firm Joint, Starrett's No. 41

Size, inch	4	6	8	10
Each	44c	55c	68c	82c

4-C-5925. Lock Joint, Starrett's No. 42

Size, inch	4	6	8	10
Each	69c	78c	93c	\$1.12

IMPROVED EXTENSION DIVIDER AND CALIPERS

4-C-5927. Starrett's No. 85. Head and arms
are best malleable iron, hardened steel points.
The 7 inch size scribes a 22-inch circle. Caliper
11 inches outside and 13 inches inside. The 9-
inch size scribes a 30-inch circle. Caliper 14
inches outside and 16 inches inside.

Size, inch	7	8
Price	\$1.62	\$1.81

STARRETT'S PERFECTED FIRM JOINT CALIPERS

Screw adjustable for fine measure-
ments.

4-C-5931. Outside Caliper,
Starrett's No. 34.

4-C-5933. Inside Caliper, Star-
rett's No. 35.

Size inch	4	6	8	10	12
Price	\$0.62	\$0.71	\$0.89	\$1.06	\$1.23
Size, inch	14	16	18	20	24
Price	\$1.42	\$1.59	\$1.76	\$1.98	\$2.46

STARRETT'S YANKEE SPRING DIVIDERS

4-C-5935. Starrett's No. 83. Spring or
solid nut.

Size, inches	2 1/2	3	4	5	6	8
Price solid nut	44c	48c	52c	58c	61c	76c
Price spring nut	54c	58c	62c	68c	71c	88c

REGULAR OUTSIDE CALIPER

4-C-5937. Solid nut.

4-C-5939. Spring nut.

Size, inches	3	4	5
Price solid nut	48c	51c	55c
Price spring nut	58c	61c	65c

STARRETT'S LOCK JOINT CALIPERS

4-C-5905. Outside caliper, Star-
rett's No. 38

4-C-5907. Inside Caliper, Star-
rett's No. 39.

Size, inch	4	6	8
Either style	\$0.61	\$0.67	\$0.66
Size, inch	10	12	
Either style	\$1.03	\$1.24	

EXTENSION DIVIDERS

4-C-5913. Malleable Iron stock. Tempered
steel points and wing. Pencil can be used in
place of movable points. Accurately adjusted,
nicely polished and finished. FULLY WAR-
RANTED.

Size, inch	6	8	10
Scribes circle	32	41	50
Price	83c	99c	\$1.17

WING DIVIDERS

4-C-5915. Tempered Spring. Brass joints,
hardened points, nicely polished. Fully war-
ranted.

Size, inch	6	8	10
Price	14c	19c	25c

REGISTERING CALIPERS

4-C-5921. Suitable for Outside and Inside
Measurements. [Nickel Plated. Fully Warranted.

Size, inches	4	6
Caliper	2 inches	4 inches
Price, each	38c	57c

STARRETT'S SPEED INDICATORS

Indicators show number of revolutions at which shaft is
turning, and are a great convenience when figuring out the
proper size pulleys required on machinery and line shafts.



4-C-5943. High Speed Indicator. Starrett's No. 104. Nickel
Plated with Metal Handle.
Price, with two rubber tips..... 82c

4-C-5945. Improved Speed Indicator. Starrett's No. 106.
Nickel Plated, with Rosewood Handle. Graduation Shows Every
Revolution.
Price, with two rubber tips..... \$1.10

4-C-5947. Registering Speed Indicator. Starrett's No. 107.
Automatically Registers Hundreds as Well as Units and Tens.
Nickel Plated, with Hard Rubber Handle.
Price, with two rubber tips..... \$2.40

4-C-5949. Leatherette Case for Either of the above In-
dicators.
Price..... 40c


IMPROVED SCREW PITCH GAUGE

4-C-5951. Starrett's No.

40.	Has 22 pitches, 9 to 40. 82c
4-5953. Starrett's No.	
4.	Has 24 pitches, 4 to 40..... 97c

STARRETT'S COMBINATION SETS.

4-C-5955. The Most Practical Combination Set for Machinists' Use.
Have hardened steel blades, graduated on both sides, the figures reading
both ways. Complete with miter head, bevel protractor head, square, scale and
level attachment. Each head can be instantly removed
or replaced and used interchangeably with the scale,
forming the most useful combination set of tools ever
offered.



\$2.67

9-inch set complete.	Price.....	\$2.67
12-inch set complete.	Price.....	2.84
18-inch set complete.	Price.....	3.39
24-inch set complete.	Price.....	3.74

SPRING TEMPERED CENTER GAUGE

4-C-5957. Used for grinding and
setting screw cutting tools. Gradu-
ations, 32nds, 24ths, 20ths, and
14ths..... 29c

HOLLOW HANDLE TOOL SETS

EXTRA HIGH GRADE HANDLE TOOL SET



4-C-5959. Set consists of: 10
forged steel tools, hollow polished
cocobola handle, in which the tools
are contained. Chuck is nickel plated.
Entire tool nicely finished and is a
decided bargain at the price at
which we offer it.
Price..... 29c



4-C-5961. The most convenient
and best hollow handle tool set
made. An absolute necessity in
every household and will soon save
its cost several times over. Consists
of 11 high grade handy tools, highly
polished cocobola handle, heavily
nickel plated, knurled sleeve and
chuck which will hold the tools rig-
idly. The smaller tools are 4 inches
long and keyhole saw 8 inches long,
all made of high grade steel, care-
fully tempered and fully guaran-
teed. Length of handle
7 1/2 in. Price..... 99c

STARRETT'S INTER-CHANGEABLE SCRIBERS.

Fine Steel, Nicely Tem-
pered Knurled Stock.
Length, short bent point 9
inches. Length, long point
12 inches.


4-C-5941. Starrett's No.
87: Complete with long
and short bent points.
Price..... 35c

4-C-5963. Set consists
of: 9 tools
specially
selected,
forged from high grade tool steel
properly tempered. Polished co-
cobola handle, improved nickel
plated chuck. Each tool is nicely
finished and guaranteed to give
entire satisfaction.
Price..... 72c

MECHANICS' POCKET RULE.

Made of carefully selected boxwood, finely finished solid brass trimmed. The graduations and figures are made with special automatic machinery, which insures accuracy. They are strictly first quality and fully warranted.


TWO FOOT FOUR-FOLD BOXWOOD RULES.



DEFIANCE SHOVELS, SPADES AND SCOOPS

Strong and durable. Made of high grade shovel steel. Selected handles. Best ever offered for general purposes. Fully warranted.

"D" HANDLE SQUARE POINT SHOVEL.



4-C-7401. Plain back, full polished. Size 9½x12 inch.48c

"D" HANDLE ROUND POINT SHOVEL.




4-C-7403 Full polished. Size 9½x12 inch.48c

"D" HANDLE SQUARE POINT SPADE.



4-C-7405. Plain back, full polished. Size 7½x12 inch.48c

"D" HANDLE GRAIN SCOOP.



4-C-7407. Western Pattern hollow back. Full polished. Size, No. 6 7 8 9 10
Length, inch. 16½ 17 17½ 18 19
Price. 58c 64c 68c 72c 75c

"D" HANDLE COAL SHOVELS



4-C-7409. Hollow back. Natural Forge Finish. Size, in. 13½x14 14½x14½ 14½x15½
Price. 49c 53c 56c

"D" HANDLE STEEL DRAIN SPADE.



4-C-7411. Strongly made to stand rough usage. Length 18 inch. Full polished. Price.92c

STEEL DITCHING OR TILING SPADES.



4-C-7413. Specially adapted for mucky and sticky soil. Fully warranted. Size 6x18 inch.\$1.58

"D" HANDLE COKE FORKS.




Superior quality. Oval tines. Fully warranted.
4-C-7415. 10 tines, 16½ inch long, 14½ inch wide.\$1.36
4-C-7416. 12 tines, 17½ inch long, 17½ inch wide.\$1.58

CAST IRON POST MAULS.




4-C-7417. Full weight, with 3-foot hickory handles.
Wt., lbs. 10 13 16 18 20
Price. 27c 33c 39c 41c 46c

LONG HANDLE SQUARE POINT SHOVEL.



4-C-7419. Plain back, full polished. Size 9½x12 inch.48c

LONG HANDLE ROUND POINT SHOVEL.



4-C-7421. Plain back, full polished. Size 9½x12 inch.48c

LONG HANDLE SQUARE POINT SPADE.



4-C-7423. Plain back, full polished. Size 7½x12 inches.48c

"D" HANDLE FURNACE SCOOPS.



4-C-7425. Hollow back, black finish. Size 9x14 inches.48c

STEEL SNOW SHOVELS.




4-C-7427. Long handle. Light, strong and durable. Makes an excellent general purpose shovel. Superior quality. Fully warranted.37c

"D" HANDLE STEEL POST HOLE SPADE.




4-C-7429. Strongly constructed. Full polished. Concave blade. 6 inches at point, length 18 inches.92c

STEEL TILE DRAIN CLEANER.




4-C-7431. Adjustable. Handle can be placed at any angle by adjusting the spring. When the spring is in position the blade is locked tightly and will not move or have a side motion. Blades are concave.
Size of blade 4x15 inch.55c
Size of blade 5x15 inch.58c
Size of blade 6x15 inch.60c

"D" HANDLE SPADING FORK



For handling and screening dirt from potatoes, heavy beets and other vegetables. Special crucible steel tines.
4-C-7433. Plain Ferrules.57c
4-C-7434. Strapped Ferrules.64c

"D" HANDLE SCOOP FORK.



For handling and screening dirt from potatoes, beets and other vegetables. Special crucible steel tines.
8 tines, 11 in. wide, 14 in. long.\$1.24
10 tines, 14 in. wide, 15 in. long.1.29
12 tines, 18 in. wide, 16 in. long.1.73

"D" HANDLE SCOOP FORK.




4-C-7435. For handling and screening dirt from potatoes, beets and other vegetables. Special crucible steel tines.
8 tines, 11 in. wide, 14 in. long.\$1.24
10 tines, 14 in. wide, 15 in. long.1.29
12 tines, 18 in. wide, 16 in. long.1.73

PREMIER SHOVELS AND SPADES.


Superior in quality, workmanship and material. Guaranteed to be the best shovels it is possible to produce.

PREMIER "D" HANDLE SQUARE POINT SHOVEL.



4-C-7437. Best crucible steel solid socket, full polished blade, 9½x12 inch.92c

PREMIER LONG HANDLE ROUND POINT SHOVEL.



4-C-7441. Best crucible steel solid socket, full polished blade, 9½x12 inch.92c

PREMIER "D" HANDLE ROUND POINT SHOVEL.



4-C-7439. Best crucible steel solid socket, full polished blade, 9½x12 inch.92c

PREMIER "D" HANDLE SQUARE POINT SPADE.



4-C-7443. Best crucible steel solid socket, full polished blade, 7½x12 inch.92c

POSTHOLE DIGGERS AND AUGERS.

EUREKA POST-HOLE DIGGERS.

4-C-7445. Nothing better of its kind made. 9-inch cast steel blade, properly tempered, malleable iron shank, selected split, hardwood handles. Length 5 feet. Weight about 9 lbs.65c




EASY POSTHOLE AUGER.

4-C-7449. The easiest and quickest digging auger in a u f a c t u r e d. Blades are made of high grade tool steel, properly tempered. Can be readily sharpened when they become dull. Suitable for any soil and will not clog. Height 44 inches. Weight about 10 lbs.
Size 8 inches. \$1.25
Size 9 inches. 1.30



IWAN'S POST-HOLE AUGER.

4-C-7453. Works easy and more rapidly than any auger made. Can be used in any kind of soil, regardless of whether wet or dry. Especially adapted for boring shallow wells. Weights range from 8½ to 24 pounds. Lengths from 4 to 6 feet, depending on diameter of auger.
Size, in. 6 8 10 11
Price \$1.90 \$2.00 \$2.15 \$2.50 \$6.00



INVINCIBLE POST-HOLE DIGGER.

4-C-7447. Blade and shanks are drop forged from one solid piece of steel. Length of blade 9 inches. Fitted with selected hardwood handles. Length 5 feet. Weight about 9½ pounds.76c




RYAN'S POSTHOLE DIGGER.

4-C-7451. The load is cut free from blades and forced out by spreading the handles. Blades are crucible steel. Steel cleaner rods. Built for heavy work. Height 6 feet. Weight about 11½ lbs. Price.\$1.60



VAUGHN'S POST-HOLE AUGERS.

4-C-7455. Solid steel blades which can be replaced if they become broken. Height 44 inches. Weight about 7 lbs.
Size, in. 6 8 10 11
Price.60c 61c
Size, in. 8 9
Price.62c 63c



CROWBARS.

Solid crucible steel, tempered points properly balanced, full size and strength.
Lbs. 12 16 20
Each. 35c 46c 57c

RAILROAD PICKS.

4-C-7461. Best quality cast steel, nicely finished, fully guaranteed. Wt., 5 to 6 lbs.31c
ADZE EYE DRIFTING PICKS.



4-C-7467. Best quality cast steel, nicely finished.
Wt., lbs. 4 4½ 5
Price. 36c 39c 41c

MATTOCKS.

4-C-7463. Cast steel adze eye, long cutter. Wt., 5 to 6 lbs.42c
4-C-7465. Short cutter mattock. Wt., 4½ lbs.41c



ENAMELWARE AT 50 PER CENT SAVING (see pages 202 to 204).

HAY CARRIER OUTFITS



STEEL TRACK OUTFITS COMPLETE.

- 4-C-11201. For 30 foot barn, consisting of:**
1 double swivel Hay Carrier, 30 feet double steel angle track with couplings and bolts, 12 rafter brackets, 12 hanging hooks, 4 floor hooks, 1 short time double harpoon hay fork, 3 steel yoke knot passing pulleys, 100 feet $\frac{1}{2}$ inch Manila Hay Rope, 40 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$10.57**
- 4-C-11203. For 35-foot barn, consisting of:**
1 double swivel Hay Carrier, 35 feet double steel angle track with couplings and bolts, 14 rafter brackets, 14 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 110 feet $\frac{1}{2}$ inch Manila hay rope, 45 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$11.39**
- 4-C-11205. For 40-foot barn, consisting of:**
1 double swivel Hay Carrier, 40 feet double steel angle track with couplings and bolts, 16 rafter brackets, 16 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 120 feet $\frac{1}{2}$ inch Manila hay rope, 50 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$12.21**
- 4-C-11207. For 45-foot barn, consisting of:**
1 double swivel Hay Carrier, 45 feet double steel angle track with couplings and bolts, 18 rafter brackets, 18 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 130 feet $\frac{1}{2}$ inch Manila hay rope, 55 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$13.03**
- 4-C-11209. For 50-foot barn, consisting of:**
One double swivel Hay Carrier, 50 feet double steel angle track with couplings and bolts, 20 rafter brackets, 20 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 140 feet $\frac{1}{2}$ inch Manila hay rope, 60 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$13.85**
- 4-C-11211. For 55-foot barn, consisting of:**
1 double swivel Hay Carrier, 55 feet double steel angle track with couplings and bolts, 22 rafter brackets, 22 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 150 feet $\frac{1}{2}$ inch Manila hay rope, 65 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$14.67**
- 4-C-11213. For 60 foot barn, consisting of:**
1 double swivel Hay Carrier, 60 feet double steel angle track with couplings and bolts, 24 rafter brackets, 24 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 160 feet $\frac{1}{2}$ inch Manila hay rope, 70 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$15.49**
- 4-C-11214. For 65 foot barn, consisting of:**
1 double swivel Hay Carrier, 65 feet double steel angle track with couplings and bolts, 26 rafter brackets, 26 hanging hooks, 4 floor hooks, 1 short time double harpoon Hay Fork, 3 steel yoke knot passing pulleys, 170 feet $\frac{1}{2}$ inch Manila hay rope, 70 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$16.31**

For the convenience of our customers we offer our Hay Carrier Outfits complete. These outfits are such as our experience has taught us to be best adapted for barns of various lengths. Compare our assortment with others and you will find that we furnish a more complete outfit than any other on the market.

The Carriers are extra heavy and have no springs to get out of adjustment and will therefore last for years; in fact, they are practically indestructible. The track is a double steel angle and is furnished in 10 foot lengths. With each outfit we furnish two 5 foot pieces so the joints will not come at the same place, making a stronger and more rigid track than if the lengths were all 10 foot.

The rope is the best quality long fibre pure Manila. We wish to call your particular attention to the fact that we furnish longer lengths than usually supplied with Hay Carrier Outfits.

The outfits as described will meet any requirements in barns of the various lengths specified. To save any delay, we strongly advise ordering any of the assortment just as described; however, if changes must be made be sure and allow sufficient amount to cover any extras and thereby avoid any delay which will be caused through the necessity of writing you regarding such changes.

The Hay Rope furnished is $\frac{1}{2}$ inch diameter. This size is most generally used. $\frac{1}{2}$ inch or 1 inch rope can be used and for which there will be an extra charge as follows:

For $\frac{1}{2}$ inch rope. Price, per foot, extra..... **\$0.01** For 1 inch rope. Price, per foot, extra..... **\$.02**

- 4-C-11215. For 70 foot barn, consisting of:**
1 double swivel Hay Carrier, 70 feet double steel angle track with couplings and bolts, 28 rafter brackets, 28 hanging hooks, 4 floor hooks, 1 short time double harpoon hay fork, 3 steel yoke knot passing pulleys, 180 feet $\frac{1}{2}$ inch Manila hay rope, 75 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$17.13**

WOOD TRACK OUTFITS. (Complete Except Track.)

The Track for these outfits is made from 4x4 inch timbers, which we advise you to furnish.

- 4-C-11217. For 30 foot barn, consisting of:**
1 double swivel Hay Carrier, 12 rafter brackets, 12 hanging hooks, 4 floor hooks, 1 double harpoon short time hay fork, 3 steel yoke knot passing pulleys, 100 feet $\frac{1}{2}$ inch Manila hay rope, 40 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$ 7.92**
- 4-C-11219. For 35 foot barn, consisting of:**
1 double swivel Hay Carrier, 14 rafter brackets, 14 hanging hooks, 4 floor hooks, 1 double harpoon short time Hay Fork, 3 steel yoke knot passing pulleys, 110 feet $\frac{1}{2}$ inch Manila hay rope, 45 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$ 8.34**
- 4-C-11221. For 40 foot barn, consisting of:**
1 double swivel Hay Carrier, 16 rafter brackets, 16 hanging hooks, 4 floor hooks, 1 double harpoon short time Hay Fork, 3 steel yoke knot passing pulleys, 120 feet $\frac{1}{2}$ inch Manila hay rope, 50 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$ 8.76**
- 4-C-11223. For 50 foot barn, consisting of:**
1 double swivel Hay Carrier, 20 rafter brackets, 20 hanging hooks, 4 floor hooks, 1 double harpoon short time Hay Fork, 3 steel yoke knot passing pulleys, 140 feet $\frac{1}{2}$ inch Manila hay rope, 55 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$9.60**
- 4-C-11225. For 55 foot barn, consisting of:**
1 double swivel Hay Carrier, 22 rafter brackets, 22 hanging hooks, 4 floor hooks, 3 steel yoke knot passing pulleys, 150 feet $\frac{1}{2}$ inch Manila hay rope, 60 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$10.00**
- 4-C-11227. For 60 foot barn, consisting of:**
1 double swivel Hay Carrier, 24 rafter brackets, 24 hanging hooks, 4 floor hooks, 1 short time double harpoon hay fork, 3 steel yoke knot passing pulleys, 160 feet $\frac{1}{2}$ inch Manila hay rope, 65 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$10.44**
- 4-C-11229. For 65 foot barn, consisting of:**
1 double swivel Hay Carrier, 26 rafter brackets, 26 hanging hooks, 4 floor hooks, 1 short time double harpoon hay fork, 3 steel yoke knot passing pulleys, 170 feet $\frac{1}{2}$ inch Manila hay rope, 70 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$10.86**

- 4-C-11231. For 70 foot barn, consisting of:**
1 double swivel Hay Carrier, 28 rafter brackets, 28 hanging hooks, 4 floor hooks, 1 short time double harpoon hay fork, 3 steel yoke knot passing pulleys, 180 feet $\frac{1}{2}$ inch Manila hay rope, 75 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$11.28**

WIRE CABLE BARN OUTFITS.

- 4-C-11233. For 30 foot barn, consisting of:**
1 reversible cable carrier, 30 feet $\frac{1}{2}$ inch galvanized wire cable, 2 eye bolts, 2 cable clamps, 3 steel yoke knot passing pulleys, 4 floor hooks, 1 double harpoon short time Hay Fork, 100 feet $\frac{1}{2}$ inch Manila hay rope, 40 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$7.95**
- 4-C-11235. For 40 foot barn, consisting of:**
1 reversible cable carrier, 40 feet $\frac{1}{2}$ inch galvanized wire cable, 2 eye bolts, 2 cable clamps, 3 steel yoke knot passing pulleys, 4 floor hooks, 1 double harpoon short time Hay Fork, 110 feet $\frac{1}{2}$ inch Manila hay rope, 45 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$8.90**
- 4-C-11237. For 50 foot barn, consisting of:**
1 reversible cable carrier, 50 feet $\frac{1}{2}$ inch galvanized wire cable, 2 eye bolts, 2 cable clamps, 3 steel yoke knot passing pulleys, 4 floor hooks, 1 double harpoon short time Hay Fork, 120 feet $\frac{1}{2}$ inch Manila hay rope, 50 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$9.45**
- 4-C-11239. For 60 foot barn, consisting of:**
1 reversible cable carrier, 60 feet galvanized wire cable, 2 eye bolts, 2 cable clamps, 3 steel yoke knot passing pulleys, 4 floor hooks, 1 double harpoon short time Hay Fork, 130 feet $\frac{1}{2}$ inch Manila hay rope, 60 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$10.85**

WIRE CABLE FIELD STACKING OUTFITS.



- 4-C-11241. For 50 foot Field stacking outfits, consisting of:** 1 reversible cable carrier, 1 double harpoon short time Hay Fork, 150 feet $\frac{1}{2}$ inch galvanized wire strand, 2 clamps for making loops around end stakes, 2 collars to prevent posts working inward, 2 long bolts for the top of posts, 3 steel yoke knot passing pulleys, 140 feet $\frac{1}{2}$ inch Manila hay rope, 65 feet $\frac{1}{2}$ inch Manila trip rope. Price..... **\$11.55**
- For $\frac{1}{2}$ inch instead of $\frac{1}{2}$ inch Manila hay rope, add, per foot extra, **.01**
For 1-in. instead of $\frac{1}{2}$ -in. rope add, per ft. **.02**


ADJUSTABLE CATTLE STANCHIONS.

Allows the animal an easy and natural position at all times. Can be immediately adjusted, setting the upright bars 5, 6, 7 and 8 inch apart. Easily locked and only the attendant can open it and release the animal. This is done by merely lifting a steel lock that connects the pivoted bar.

The illustration on the right shows a Stanchion in place locked. The one at the left shows the Stanchion open, held firmly in position by steel guide straps. It is impossible for the animal to turn it and no trouble is experienced by the animal putting its head in the Stanchion.

Made of best quality of hardwood, nicely finished. Height, 4 foot with 64 inch space between upright bars, and can be adjusted very easily by taking out a bolt which makes the spaces $5\frac{1}{2}$ inches, so that it can be used for young stock. The wider spaces are suitable for cattle of any size. The Stanchions are shipped set up for 64 inches between bars. Top and bottom are made of steel and it is the strongest and lightest Stanchion on the market, weighing about 15 pounds each. Sold only in lots of 6 or more. Shipped from factory South-

ern Wisconsin. **4-C-11243. Price for 6..... \$5.75**



HAY CARRIER TOOLS

\$2.97

DOUBLE SWIVEL HAY CARRIERS. With Improved Locking Device.

Has but two pieces, which makes it an absolutely positive lock. No springs or unnecessary parts to get out of order. Will work either way, by changing pulley from one end of the barn to the other, making it unnecessary to untie the ropes from other pulleys. This simple method is a big feature not generally found in other carriers.

4-C-11301. Wood track double swivel Hay Carrier complete with stop and fork pulley. Price, \$2.97
4-C-11303. Steel track double swivel Hay Carrier complete with stop and fork pulley. Price, \$3.00



\$3.00

DOUBLE SWIVEL SLING HAY CARRIER.


Made of the best malleable iron, heavy and durable, simple in construction. The special feature of this swivel carrier is that often when the barn is empty it is not

necessary to raise a load up to the track, for the load can be raised to any point desired, and tripped, thereby saving not only time but half the distance or more for the horses to travel.

Another excellent feature is that it draws the hay or grain direct as the load stands, with no twist in the rope.

4-C-11305. Wood track swivel sling carrier. Price, \$5.87
4-C-11307. Steel track swivel sling carrier. Price, \$5.90

\$5.90



\$5.87

SNATCH PULLEY BLOCK.

4-C-11309. To shorten travel of horse without reducing the power. Horse travels only half the distance hay is carried. Frame is made of malleable iron with iron sheave. For use with manila rope only. Price, each, 42c



IRON YOKE HAY FORK PULLEY.

4-C-11311. With loose hollow pin, hard maple sheave, 5 1/2 inch. Price, each, 16c



DOUBLE ANGLE STEEL TRACK.



4-C-11319. Made only in five and ten foot lengths. Furnished complete with couplings and bolts. Two end bumpers are furnished with track when 30 feet or more are ordered. Price, per foot, 8 1/2c

8 1/2c

STEEL TRACK HANGING HOOKS.

4-C-11321. For double steel angle track. Price, each, 6c




WOOD TRACK HANGING HOOKS.

4-C-11323. 14 inches along the bend. Price, each, 5c




FLOOR HOOKS.

4-C-11325. Used to screw to floor to hold pulleys. Diameter, 1/2 inch. Price, each, 6c



JOINED HANGING HOOKS.



4-C-11327. Used for hanging wood track to beams without using rafter brackets. Price, each, 8c

RAFTER BRACKETS.

4-C-11329. For Hay carrier track. Price, each, 2c



EYE BOLTS.


4-C-11331. For fastening Hay Carrier Cable to end of barn. Has long threads to take up slack. Price, each, 22c




SELF-LOCKING SLING PULLEY.

4-C-11333. Can be used in connection with our Double Swivel Hay Carrier. The simplest and strongest sling pulley ever offered. It has no springs, and regardless of how large or how small the load of hay is in the wagon sling, it will lock at any place.

When the knob of the Sling Pulley enters the Hay Carrier, the entire weight of hay is on this knob and throws the lock against the rope between the two pulleys and when the load is dumped and Hay Carrier is returned and strikes the stop block, the knob drops the sling pulley, is unlocked and is ready for another load. Price, \$1.45



SINGLE HARPOON HAY FORKS.



4-C-11335. Regulation size, made of best materials. Price, each, \$1.35

DOUBLE HARPOON HAY FORKS.

4-C-11337. Short time, Double Harpoon Hay Fork, 25 inch time, 16 inches between points. Made of best quality material. Price, each, 85c

4-C-11339. Long time, Double Harpoon Hay Fork, tines 30 inches long, 16 inches between points. Price, each, \$0.98

4-C-11341. Double Harpoon Hay Fork, 34 inch tines, 22 inches between points. Designed for handling alfalfa and straw. Can be used, however, for handling any kind of hay. Price, each, \$1.81




HAY GRAPPLE FORKS.

The best and strongest Grapple Forks manufactured.

4-C-11343. 4 tine Grapple Fork for regular work. Price, each, \$3.30
4-C-11345. 6 tine Grapple Fork for short hay, loose straw. Price, each, \$3.95



STANDARD ADJUSTABLE WAGON SLINGS.




Made for an 18 foot wagon rack. They can be made shorter for any size wagon by drawing the ropes through the wood bars and tying another knot on each side of wood bars. There is a center trip on all slings and they are fitted with the best and simplest lock.

An outfit generally consists of one sling pulley and three wagon slings, so as to take off an entire load in three lots. The trip rope is of proper length, permitting the sling to be easily tripped. Sling pulleys or sling carriers must be used with wagon slings.

4-C-11347. Length, 4 foot. Price, each, \$1.45
4-C-11349. Length, 5 foot. Price, each, 1.84
4-C-11351. Length, 6 foot. Price, each, 1.95

GALVANIZED HAY CARRIER CABLE.



4-C-11353. 1/2 inch diameter, composed of 7 wires. Price, per foot, 2c

4-C-11355. Clamps for cable Hay carriers. Price, each, 7c

4-C-11357. Collars for Cable Hay carriers. Price, each, 14c

ROPE HITCH WITH SWIVEL HOOK.

4-C-11317. Made of Malleable iron. Will take rope up to 1 inch. Saves cutting or tying the rope. Price, each, 12c



CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Write for Our Plan Book No. 63. It is just out.

GAS CHANDELIERS FOR PARLOR, DINING ROOM AND LIVING ROOM

This Chandelier is very popular for parlor and dining room.

\$1.65

No. 1-E-7731.
Polished Brass Chandeliers, 36 inches long, fluted ball center 3 inches diameter with cup, loop arms, half fluted tubing, canopy and fancy star pattern glass shades, common gas burners and tips.
2 Lt. **\$1.65**
3 Lt. **2.25**



No. 1-E-7733.
Polished Brass Chandelier, 36 inches long, half fluted tubing and loop arms. The center body is beautifully decorated. Complete with common gas burners, tips and glass shades as illustrated.
2 Lt. **\$2.16**
3 Lt. **3.09**
4 Lt. **\$4.05**

For parlor and dining room. The price speaks for itself. A bargain at twice the amount.

\$2.16



All Gas Chandeliers are furnished Complete with common gas burners, shade holders and shades.

No. 1-E-7735. Brushed Brass Chandelier. Square brass tubing. Center body is large square with square cup on top. The square effect carried throughout this fixture is very beautiful and it must be seen to be appreciated. Furnished either with candles as shown or with glass shades, common gas burners and tips.
2 Lt. **\$3.00**
4 Lt. **5.75**

For Parlor and Dining Room, **\$3.00**



CAN'T BE BEAT FOR THE MONEY.
AN ORNAMENT TO ANY PARLOR OR DINING ROOM.

\$3.25



Colonial Design. Very Latest. This is one of the Classiest Fixtures that could be placed in any Parlor or Dining Room.

\$6.00



No. 1-E-7745. Brushed Brass Chandelier. Square Mission design. This is our handsomest and most highly finished gas fixture. Furnished complete as shown, either inverted or regular, with common gas burners and tips.
2 Lt. **\$6.00**
4 Lt. **\$7.50**

No. 1-E-7737. Polished Brass Chandeliers. Large polished brass body with mat gilt band surmounted by a small ball and fluted cup. Fancy cast brass ornaments on the arms and body. Tubing half fluted. This is one of the handsomest fixtures and must be seen to be appreciated. Furnished complete with fancy glass shades, common gas tips and burners.
2 Lt. **\$3.25**
3 Lt. **\$4.37**
4 Lt. **5.50**

A VERY CLASSY FIXTURE FOR **\$2.35**



No. 1-E-7739. Polished Brass Chandelier. Large polished center brass body with rich cast mat gilt ornaments on body and arms. Beaded tubing, canopy and beaded cup. Furnished complete with fancy glass shades. This chandelier, rich and tasteful, would please the most fastidious. Common gas burners and tips.
2 Light, **\$3.45**
3 Lt. **\$4.68**
4 Lt. **5.91**


Very Ornamental. Will Improve the Appearance of Any Parlor or Dining Room.

\$2.15



A WORK OF ART FOR THE BEST OF HOMES.


\$3.45



No. 1-E-7741. Polished Brass Chandelier. Embossed polished brass body and cup, fluted tubing and canopy. Arms fitted with cast brass ornaments. Complete with star pattern glass shades. Common gas burners and tips. This chandelier will improve the appearance of any parlor or dining room.
2 Lt. **\$2.15**
3 Lt. **\$2.90**
4 Lt. **\$4.00**

A Rich and Elegant Fixture for Parlor or Dining Room in the best of Homes.

\$7.25



No. 1-E-7747. This Chandelier is a work of art. Its magnificent appearance will add to the beauty of the best furnished homes. Furnished with inverted glass shades, common gas burners and tips.
2 Lt. **\$7.25**
3 Lt. **\$8.75**

CHICAGO HOUSE WRECKING CO. 35th and Iron Sts., Chicago.

ELECTRIC CHANDELIERS FOR PARLOR, DINING ROOM AND LIVING ROOM

**Best Bargain
for the Money.**

**PRICE
\$248**

No. 1-E-7751.

Polished Brass Chandelier, fluted ball center, 3 inches diameter with cup, loop arms, fluted tubing, canopy and fancy star pattern shades. Wired complete ready to install. Price does not include incandescent lamps.

2 Lt. **\$2.48**
3 Lt. **\$3.45**

No. 1-E-7753.

Brushed Brass Chandeliers. Square brass tubing. Large center body with square cup on top. Anyone wishing to install square fixtures cannot secure a more substantial or beautiful fixture than this one. Furnished with glass shades. Wired complete ready to install. Price does not include incandescent lamps.

2 Lt. **\$4.85**
4 Lt. **\$8.25**

**An
Ornament
to any
Parlor or
Dining
Room.**

**PRICE
\$485**

No. 1-E-7755.

Polished Brass Chandelier. Large polished brass body with mat gilt band surmounted by a small ball and fluted cup. Fancy cast brass ornaments on the arms and body. Fluted tubing. This is one of our handsomest chandeliers and we feel certain our customers would be more than pleased in purchasing this fixture. Furnished with fancy glass shades. Wired complete ready to install. Price does not include incandescent lamps.

2 Lt. **\$4.25**
3 Lt. **\$5.45**
4 Lt. **6.40**

No. 1-E-7757.
Brushed Brass Chandelier. Square Mission design. This is our handsomest and most highly finished electric fixture. Furnished with glass shades. Wired complete, ready to install. Price does not include incandescent lamps.

2 Lt. **\$5.55**
4 Lt. **\$8.10**

**Square
Colonial
Design.
For Par-**

**lor or Dining Room. Is an ornament
in the most beautiful homes.**

**PRICE
\$555**

**OUR
GROCERY CATALOG
IS A MONEY SAVER.
WRITE FOR IT.**

All fixtures wired complete with sockets, shade holders and shades ready to install.

Incandescent lamps for these fixtures are extra. See page 5 for prices on incandescent lamps.

**STOP! LOOK AT THIS
CHANDELIER.
LOOK AT THE PRICE!**

PRICE \$295

No. 1-E-7763.

Polished Brass Chandelier. The center body is large and beautifully decorated, cup is beaded, fluted tubing and loop arms, with fancy glass shades. Wired complete with sockets ready to install. We do not furnish incandescent globes at prices below.

2 Lt. **\$2.95**
3 Lt. **4.15**
4 Lt. **5.40**

No. 1-E-7761.

Polished Brass Chandelier. Large polished center brass body with rich cast mat gilt ornaments on body and arms. Beaded tubing, canopy and beaded cup, with fancy glass shades. This chandelier will improve the appearance of any parlor. Wired complete with sockets ready to install. We do not furnish incandescent globes at these prices.

2 Lt. **\$4.50**
3 Lt. **\$5.75**
4 Lt. **6.80**

**This Chandelier is
a work of art and
cannot be
duplicated
elsewhere
for twice the
price we are
asking.**

**PRICE
\$450**

**This is an ideal
Chandelier for a
parlor or dining
room. The or-
namentation is
exquisite
and very
pleasing to
the eye.**

**PRICE
\$321**

**WRITE FOR OUR
"BOOK OF PLANS"**

**We are headquarters
for Lumber and Mill-
work.**

No. 1-E-7765.

Polished Brass Chandelier, embossed polished brass body and cup, fluted tubing and canopy. Arms fluted with cast brass ornaments. Complete with star pattern glass shades. Wired complete with sockets ready to install.

2 Lt. **\$3.21**
3 Lt. **\$4.38**
4 Lt. **6.46**

**LOOK
At this
Chandelier
for \$248
Worth Double.**

No. 1-E-7769.
Polished Brass Chandeliers. Polished brass ball center and cup. Fluted tubing and canopy. Gracefully curved arms. Furnished with fancy glass shades. Wired complete with sockets ready to install.

2 Lt. **\$2.48**
3 Lt. **\$3.45**

No. 1-E-7767.

Polished Brass Chandelier. Large center body also cup and half the tubing is hexagon in shape. Furnished with glass shades. This chandelier produces a very pleasing effect and will satisfy the most exacting. Wired complete with sockets. We do not furnish incandescent globes at prices below.

2 Lt. **\$3.40**
3 Lt. **\$4.60**
4 Lt. **5.75**

**A very substan-
tial and classy
fixture.**

**PRICE
\$340**

**Write for
Our
ROOFING
BOOK —
a Book of
Bargains**

Write For Our Furniture Catalog.

**CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.**

Write for our General Catalog.

153

IRON BOX BELLS.




Used for door and call bells. Box is made of stamped sheet steel, nickel plated cast gong, German silver contacts. Can be operated and rings clearly with one cell of battery at a distance of 150 feet. Better results can be obtained with two cells of battery, not only increasing the ringing strength but the life of the batteries.

4-C-10501. 3-inch iron box bell.23c
4-inch iron box bell. Used where a louder tone is required.32c

SKELETON BELLS.

Used for fire and burglar alarms, or for other purposes that requires a strong, loud ringing bell, such as mills, shops and factories. The contact points are platinum, thus insuring a uniform penetrating sound.



SKELETON BELL.

4-D-10503. 4-inch Gong.\$1.25
4-D-10505. 5-inch Gong.1.83
4-D-10507. 6-inch Gong.1.95
4-C-10509. 8-inch Gong.3.48
4-D-10511. 10-inch Gong.5.46

IRON BOX BUZZERS.

Used in place of bells for call purposes. Makes a loud buzzing sound.

4-C-10513. Iron box buzzer, Japanned finish.22c
4-C-10515. Iron box buzzer, Nickel plated.35c



IMPROVED MESCO DRY BATTERY.

4-C-10517. Our Mesco Dry Battery. High internal resistance and low in ampereage, ranging from 10 to 12 amperes, 1½ volts. For operating telephone transmitters, call bells, annunciators, burglar alarms, medical batteries and for other similar purposes. The life of this battery is unusually long. Size 2½ inches in diameter; 6½ inches high. Weight 2 pounds.



Per dozen.\$1.60 Each.14c

THIRD RAIL DRY BATTERIES.

4-C-10519. Third rail dry batteries is the best that is manufactured. For any kind of open circuit work, it being a battery of medium internal resistance and long life. It is especially desirable for door bells, telephones, annunciators, medical batteries, call bells and can also be used for ignition work. Current from 18 to 22 amperes. Size 2½ inches in diameter; 6½ inches high. Weight 2 pounds.



Per dozen.\$2.20 Each.19c

"HI-UP" DRY BATTERIES.


"Hi-up" dry batteries designed especially for ignition work. Low internal resistance and intended for the severest work under which an open circuit dry battery will qualify. Suitable for automobiles, motor boats, gasoline engines, lighting small incandescent lights, running small motors, and is guaranteed to stand up equal to any dry battery manufactured for ignition work. Will test from 25 to 30 amperes.



	Size Inches	Price
4-C-10521	2½ x 6½	25c
4-C-10523	3 x 7½	50c
4-C-10525	3½ x 8½	60c

PUSH BUTTONS.

4-C-10527. Wood push buttons. Oak, ash, cherry or walnut. German silver springs, porcelain button. .8c
4-C-10529. Solid cap stamped brass buttons.12c
4-C-10531. Stamped ornamental bronze oxidized copper push buttons. 2½ inches in diameter.13c



WOOD BASE SWITCHES.

For use on telephones, burglar alarms, closed circuit bell systems and battery circuits of all kinds. Hardwood base finished in oak, walnut and cherry.



4-C-10533. Price, 1-point switch.7c
4-C-10535. Price, 2-point switch.8c
4-C-10537. Price, 3-point switch.9c
4-C-10539. Price, 4-point switch.10c

STANDARD WET BATTERIES.



For use on open circuits. For door bells, telephones, etc. Easily re-charged when exhausted. A complete outfit consists of glass jar, round carbon, zinc and one charge of sal ammoniac. Weight 4½ pounds.
4-C-10541. Price complete.28c
4-C-10543. Extra zincs. 3 for.10c
4-C-10545. Sal Ammoniac. Per pound.10c
Per charge.5c

CROWFOOT GRAVITY BATTERIES.

Suitable for closed circuits and used by all of the telegraph companies. Is recognized as a standard for this work. Can also be used in operating bells, small motors, etc. Each battery requires about 3 pounds of blue vitriol to charge it.

4-C-10547. Crowfoot Gravity battery. Size 5x7 inches. Consists of jar, copper and zinc. Weight 5 pounds.42c



4-C-10549. Crowfoot gravity battery. Size 6x8 inches. Consists of jar, copper and zinc. Weight 6 pounds.55c
(Blue vitriol is not furnished with these batteries, it being always sold extra.)

4-C-10551. Battery jar, glass 5x7 inches.13c
4-C-10553. Battery jar, glass 6x8 inches.15c
4-C-10555. Zinc. For 5x7 inch jar.25c
4-C-10557. Zinc. For 6x8 inch jar.34c
4-C-10559. Copper. For 5x7 inch jar.7c
4-C-10561. Copper. For 6x8 inch jar.7c
4-C-10563. Blue vitriol. Per pound.10c

FULLER BATTERY.


4-C-10565. A long life, high grade battery. Recommended for use on long distance telephones, gasoline engines, motors, nickel plating outfits and lavatory work. Also an excellent battery for gasoline engine ignition. Four of these batteries will spark an ordinary gas engine on one charge for a period of eight to ten months.



Per cell complete.\$1.40
4-C-10567. Renewals for Fuller battery. Consists of zinc, can of salt and bi-sulphate of mercury.70c
4-C-10569. Electropion salt for Fuller Battery. Per can. 25c
4-C-10571. Jars for Fuller Battery.18c
4-C-10573. Carbon for Fuller Battery.42c
4-C-10575. Covers for Fuller Battery.9c
4-C-10577. Porous cups for Fuller Battery.18c
4-C-10579. Zinc for Fuller Battery.30c
4-C-10581. Bi-sulphate of mercury. Sufficient for one charge.15c

\$10.65

GASOLINE ENGINE MAGNETO IGNITOR




The most complete and best constructed magneto type of ignitor that has ever been placed on the market. It is constructed with a special 12-section Laminated Armature and solid copper Commutator. The pole pieces are of special soft iron, while the fields or permanent magnets are constructed of the best grade of imported Tungsten steel (are 8 in number). These Magnets are put through a special aging process to insure their giving the highest generating power possible. The bearings are of special bronze metal and the shaft is of turned steel. It is equipped with Compression Grease Cups, and with combination Carbon and Copper Gauze Brushes so arranged that they will not cut the Commutator. Furnished with a Friction Governing Pulley so that all that is necessary to do is to bolt the machine so that the pulley on the ignitor will come in contact with the engine fly wheel. A turn of the engine is all that is necessary to start. But we recommend that dry batteries always be used to start the engine and arrange with a double throw switch so that the battery can be thrown out as soon as the engine is started. It is also recommended that a Spark Coil always be used in conjunction with any type of ignitor, as you can get a much hotter and fatter spark and be sure of your ignition every time.

We guarantee our gasoline ignitor to be absolutely satisfactory or it can be returned to us and the full purchase price refunded.
Shipping weight about 25 pounds.
4-C-10583. Gasoline engine ignitor. For "Make and Break" Ignition.\$10.65
4-D-10585. Gasoline engine ignitor. For Jump Spark Ignition.\$11.45

ELECTRIC BELL OUTFITS.

FOR DOOR AND CALL BELL SERVICE.

4-C-10587. Electric Bell outfit. Consisting of Dry Battery, one bronze push button, one 3-inch iron box bell, 75 feet of annunciator wire and necessary staples.85c
4-C-10589. Electric Bell outfit. Consisting of one cell of Dry Battery, one bronze push button, one 3-inch iron box bell, 75 feet of annunciator wire and necessary staples.75c



VOLT AND AMMETERS.

These instruments are about the same size as a watch and are made with the same care. They are carefully calibrated and are used for battery testing.

4-D-10591. Ever ready voltmeters. Reads 0 to 12 volts.\$1.55
4-D-10593. Ever ready ammeters. Reads 0 to 30 amperes.\$1.32
4-D-10595. Ever ready combined voltmeters. Two scales, registering either voltage or ampereage. Reads 0 to 11½ volts and 0 to 35 amperes.\$1.95



JUMP SPARK COILS.



For stationary and marine engines. Gives a hot, fat spark with very little battery consumption. In connection with these Spark Coils we recommend the use of four cells of battery.
4-C-10597. Jump spark coil.\$4.50

GAS ENGINE "MAKE AND BREAK" SPARK COILS.

4-C-10599. This coil is especially constructed and will give a large, hot, fat spark. Can be operated nicely with four cells of battery. It is particularly adapted to work in conjunction with our Magneto Ignitor, and where the two are used in conjunction the best possible results can be obtained. Dimensions are: 7½ inches long; 3½ inches wide; 2½ inches high. Weight 5 pounds.\$1.57



SPARK PLUGS.

A spark plug is the most important feature in connection with the successful operation of gasoline engines using Jump Spark Coils. The superior features of our Spark Plugs are sure fire, long life and platinum points, insuring perfect explosion. Are suitable for use in automobiles, launches or stationary engines. Each plug is fully guaranteed and is furnished with ½-inch standard iron pipe thread. Simply and strongly constructed and can be quickly taken apart and cleaned. Delivers a good solid spark.
4-C-10596. Porcelain spark plug.48c
4-C-10598. Mica spark plug.53c



OUR LINE OF MECHANICS TOOLS IS COMPLETE AND OF HIGH GRADE

See page 209

ELECTRIC ALARM CLOCK

These outfits are a sure cure for over-sleeping. Electric bell will ring until switch is turned off or connected attachment is disconnected, which means get-up.

The Clock is wound and set at the desired waking hour, the switch is turned on and the electric bell will ring as soon as the time indicated by the alarm hand is reached.

Outfit 4-C-10588 is ready for instant use. Each one is mounted on a polished wood base containing one dry battery. Has electric bell attached on the back.

Outfit 4-C-10588 is arranged so that the clock movement will throw electric bell in circuit which will run until switch is turned off.

We furnish the clock only, the switch and bell can be purchased separately. The switch and bell can be placed near the bed and the clock may remain on the table or elsewhere.

4-C-10588. Electric Alarm Clock outfit complete shipping weight 5½ lbs.\$2.50
4-C-10588. Electric Alarm Clock only, postage 32c. Price.\$1.50



10c

INCANDESCENT LAMPS

10c

Brand new and perfect in every respect representing America's best make. Owing to the great many different styles and makes of incandescent lamps it is impossible to show them all, we, therefore, show and illustrate only the Edison base in the Standard Carbon filament lamps. Our enormous sales in incandescent lamps has placed it in a position to make the most favorable contracts with the largest manufacturers in America. We have sold these lamps to all the largest amusement parks in all of the largest cities in America. People who make tests and know that they are saving money by buying from us. Our contracts on these lamps enable us to offer lamps that are perfect and in every way guaranteed at prices which means a saving to you.

When ordering, be sure and state voltage and candle power required.
EDISON BASE INCANDESCENT LAMPS.

No.	Voltage.	Candle Power.	Price, Case lots of 200 Lamps.	Price, less than Case Lots.
4-C-10655.	100 to 125	16 C. P.	10c	12c
4-C-10656.	104 to 110	8 "	10c	12c
4-C-10660.	200 to 250	16 "	13c	15c
4-C-10661.	200 to 250	8 "	12c	14c

At
Less
Than
Manufact-
urer's Cost

RUBBER COVERED WIRE



Rubber covered, solid conductor Copper Wire. Single braided with standard cotton yarn, which is thoroughly saturated with a pure wax compound, having a high melting power and is smoothly and evenly finished.

Pieces of rubber covered wire are subject to market changes. However, we do not anticipate that there will be any change in price during the life of this catalogue.

	B. & S. Gauge	Price per 1,000 ft.	Price per 100 ft.
4-C-10601	14	\$ 9.80	\$1.10
4-C-10603	12	12.35	1.35
4-C-10605	10	16.30	1.75
4-C-10607	8	22.07	2.30
4-C-10609	6	34.90	3.60

WEATHERPROOF WIRE

Triple Braid, solid conductor; the wires are covered with three closely woven braids of cotton thoroughly saturated with a black weatherproof compound.

Catalog No.	B. & S. Gauge	Price per 1,000 ft.	Price per 100 ft.
4-D-10610.	14	\$ 8.50	\$ 0.95
4-D-10612.	12	9.50	1.05
4-D-10614.	10	14.75	1.55
4-D-10616.	8	20.00	2.20
4-D-10618.	6	30.00	3.30

CIRCULAR LOOM CONDUIT

A flexible conduit of high insulating qualities; used in protection of wires from effects of weather, moisture, heat or abrasion.

Catalog No.	Size	For Wire B. & S. Gauge	Price per foot
4-D-10626.	1/2 inch	8 to 14	4c

LAMP CORD

Cotton Covered Lamp Cord. Composed of two twisted conductors and used for light extensions, drop lights, fans, etc.

	B. & S. Gauge	Price per 1,000 ft.	Price per 100 ft.
4-C-10611	20	\$9.51	\$1.20
4-C-10613	18	11.40	1.40
4-C-10615	16	14.40	1.80

SILK COVERED LAMP CORD

	B. & S. Gauge	Price per 1,000 ft.	Price per 100 ft.
4-C-10617	18	\$16.00	\$1.75
4-C-10619	16	22.00	2.53

WOOD MOULDING AND CAP.

Made to comply with the Board of Fire Underwriters' Rules. Selected hardwood. Price includes moulding and cap.


	Price per 100 feet
4-C-10679. Two Groove for 12 and 14 gauge wire.	\$2.50
4-C-10680. Three Groove for 12 and 14 gauge wire.	\$3.25
4-C-10681. Three Groove for 8 and 10 gauge wire.	\$3.50
4-C-10681. Three Groove for 8 and 10 gauge wire.	\$4.00

PORCELAIN CEILING BUTTONS.

For use in place of ceiling Rosettes. Made in one piece.

4-C-10683. Self-Tying Type.	5c
-----------------------------	----

PORCELAIN TUBES.



Length, Inches Under Head.	4-C-10692. Size of Hole 1/2" For No. 12 and 14 Rubber Covered Wire.	4-C-10694. Size of Hole 3/8" For No. 6, 8, and 10 Rubber Covered Wire.
1 1/2	\$0.45
2	.47	.56
2 1/2	.51	.64
3	.56	.84
4	.98	1.05
5	1.12	1.26
6	1.39	1.63
8	2.52	2.94

4-C-10698. Two Wire Porcelain Cleat. For Nos. 12 and 14 B. & S. Gauge Rubber Covered Wire.

Price, per 100.\$1.50

Price, per dozen.15

4-C-10699. Two Wire Porcelain Cleat. For Nos. 6 to 10 B. & S. Gauge Rubber Covered Wire.

Per 100\$2.98

Per dozen25

WEATHER PROOF PORCELAIN SOCKETS WITH HOOD.

4-C-10676. The Extension Edge or Hood Carries the drip away from the lamp and socket. Method of wiring at the top removes the strain of socket itself and places it on the porcelain. Extra hole in porcelain at top allows extension by cord, if desired. Each socket fitted with 8 inches of No. 14 B. & S. stranded rubber covered wire.....28c

ATTACHMENT PLUGS.

4-C-10677. Attachment Plugs. Will fit any standard Edison Base Socket and are used to run extension light lines from the nearest socket, making it possible to extend light into otherwise inaccessible parts. Also used for connecting electric fans, motors, etc. that can be operated from the lighting circuit. Edison Base, brass cap, fuseless.....13c

EDISON BASE STANDARD SOCKETS.

Polished Brass Shell Fiber Lined. National code standard. 1/2 inch bushing for standard wiring.

4-C-10622 Edison Base Key Socket..19c

4-C-10624. Edison Base Keyless Socket18c

HUBBELL PULL SOCKET.

4-C-10669. Can be used in place of an ordinary socket for outlet by means of pull chain, which is within easy reach and is a decided convenience over the key socket. This is a feature that will be appreciated by those whose chandeliers are too high to be easily reached. They are also especially desirable for use on portable and desk lamps. Furnished only in the Edison base with chain 8 inches long. Price, each.....37c

PORCELAIN BASE WALL SOCKETS.

Edison Base Porcelain Wall Sockets. Brass cap and removable ring.

4-C-10673. Edison Base Key Wall Socket.....26c

4-C-10674. Edison Base Keyless Wall Socket.....26c



EDISON PORCELAIN CLEAT RECEPTACLE.

4-C-10671. Edison Chain Porcelain Receptacle. Price, each.....6c

EDISON PLUG CUT-OUTS

Approved for use of circuits up to 225 volts.

Fitted with screw contacts, requiring no solder.

4-C-10620. 30 Amp. single pole main line Edison plug cut-out.....7c

4-C-10621. 30 Amp. double pole single branch Edison plug cut-out.....13c

4-C-10623. 30 Amp. double pole double branch Edison plug cut-out.....25c

4-C-10625. 30 Amp. 3 wire to 2 wire double branch Edison plug cut-out.....26c

EDISON FUSE PLUGS.

Used in connection with Edison Plug Cutouts.

4-C-10627. 3 Amp. Edison Plug Fuses..4c

4-C-10629. 6 Amp. Edison Plug Fuses..4c

4-C-10631. 10 Amp. Edison Plug Fuses..4c

4-C-10633. 12 Amp. Edison Plug Fuses..4c

4-C-10635. 15 Amp. Edison Plug Fuses..4c

4-C-10637. 20 Amp. Edison Plug Fuses..4c

4-C-10639. 25 Amp. Edison Plug Fuses..4c

4-C-10641. 30 Amp. Edison Plug Fuses..4c

COMBINATION SWITCH AND CUTOUT

The National Board of Fire Underwriters requires that when a surface wire enters a building a main cut-off switch and also a main fuse must be installed in order to be able to cut off all current in the building by throwing the entrance switch in case of fire.

We recommend their use as motor switches. Edison Fuse Plugs up to 30 Amperes can be used in connection with this switch.

4-C-10643. 125 Volt, 25 Amp. Double Pole Combination Switch and Cut-Out.....45c

4-C-10644. 250 Volt, 25 Amp. Double Pole Combination Switch and Cut-Out.....50c

4-C-10645. 250 Volt, 25 Amp. Triple Pole Combination Switch and Cut-Out.....70c

PORCELAIN CEILING ROSETTES.

Used as light outlets in interior wiring

Made in two pieces, based and capped.

4-C-10647. Porcelain Ceiling Rosettes.

Cleat style.....9c

4-C-10648. Porcelain Ceiling Rosettes.

Concealed type. Price, each.....9c

SPLIT PORCELAIN KNOBS.

National Code Standard. 1-inch from groove to base. Saves wire, time and labor of tying.

4-C-10650. For No. 10 B. & S. Gauge Wire and Smaller.

Per 100\$1.95

Per dozen20

4-C-10651. For Nos. 4 to 8 B. & S. gauge wire.

Per 100\$2.70

Per dozen25

PORCELAIN WEATHERPROOF SOCKETS.

4-C-10653. Porcelain Weather Proof Sockets. Plain, without wood. Each socket fitted with 8 inches of No. 14 B. & S. stranded rubber covered wire. Price, each.....14c

PENDANT SWITCH.

4-C-10685. For controlling electrolights, ceiling clusters and other fixtures that are out of reach and not connected with wall switch. This switch is attached by means of lamp cord to the fixture, and the current is shut off and on by pushing button, Underwriters' rating 6 amperes, 125 volts; 3 amperes, 250 volts.

Each.....48c

Price, each, in lots of five or more.....44c

RECEPTACLE PLUG CLUSTERS

Used in connection with Edison Base Sockets, making it possible to increase the number of lights or take off connections for extensions.

For fans, motors, etc.

4-C-10687. Two Light Cluster.....62c

4-C-10688. Three Light Cluster.....79c

4-C-10689. Four Light Cluster.....\$1.10

INDICATING SNAP SWITCHES.

Used in connection with electric lighting work.

4-C-10691. 5-Amp. Single Pole, 220 Volt Indicating Snap Switch.....24c

4-C-10693. 10-Amp. Double Pole, 220 Volt Indicating Snap Switch.....45c

4-C-10695. 20-Amp. Double Pole, 220 Volt Indicating Snap Switch.....72c

4-C-10697. 30-Amp. Double Pole, 220 Volt Indicating Snap Switch.....90c





Harris Woven Wire LAWN FENCING

5 1/4
¢
PER
FOOT

GALVANIZED, METALLIC-PAINTED

This Fencing is Made of the Best Grade of Galvanized Wire.

Painted with an additional coat of specially prepared metallic paint, thereby adding to the wearing quality and life of the fence, as well as making it rust and weather proof. Can be used with either steel or wood posts.

Never in the history of our special offers, have we been in a position to place such remarkably low priced fencing snaps to our customers.

SPECIFICATIONS: Uprights are made of No. 9 heavy galvanized wire, crimped the entire length Cable No. 121, with stays between the uprights, 2 1/2 inches.

Cables are spaced 6 inches apart, except the top wire which is spaced 2 1/2 ins. We can furnish same to you in the following sizes:

Lot No. 2-BM-428. 24 inches high. Per lineal foot.....	5 1/4	Lot No. 2-BM-430. 36 inches high. Per lineal foot.....	6 1/4
Lot No. 2-BM-429. 30 inches high. Per lineal foot.....	5 1/2	Lot No. 2-BM-431. 42 inches high. Per lineal foot.....	6 3/4

The above fencing can be furnished in any continuous lengths up to 300 feet. When ordering please state whether you desire red or slate color. Unless specified, we will always send slate. We can furnish above in galvanized, not painted if desired. We can furnish gates for the above to match fence as listed below.

Lot No. 2-BM-405. 3 foot opening.....	\$1.90	Lot No. 2-BM-408. 4 1/2 foot opening.....	\$2.40
Lot No. 2-BM-406. 3 1/2 foot opening.....	2.10	Lot No. 2-BM-409. 5 foot opening.....	2.60
Lot No. 2-BM-407. 4 foot opening.....	2.25	Lot No. 2-BM-410. 5 1/2 foot opening.....	2.80

\$1.25 For 100 Pounds of Galvanized Wire.

During this sale we are offering our galvanized wire shorts at prices never before heard of and cutting same almost one-half of the regular price of other, and these prices will prevail only during this great sale. The wire offered is suitable for fencing, grape vines and stays and can be used for general purposes. This wire is put up in bundles of 100 lbs. and the lengths run from 50 to 200 feet. We put this together in coils of 100 pounds as near one gauge in a coil as possible.

LOT No. 2-BM-1469. Gauge	Price per 100 lbs.	Gauge	Price per 100 lbs.
9	\$1.25	14	\$1.70
10	1.40	16	1.80
11	1.50	18	1.90
12	1.60		


LOT 2-BM-229. Painted Wire Shorts, per 100 pounds.....\$1.25

Crimped Reinforced Rods, 2 1/2¢ Per Pound

These rods are made of No. 5 Bessemer iron, just the thing for silos, fence posts and general reinforcing. Cut to any length up to 20 feet.
Lot No. 2-BM. 30¢ per 100 lbs.....\$2.25
Write for prices in large quantities.

Barb Wire—Greatest Bargain Ever Offered—Barb Wire

OUR PRICE
\$1.85 Per 100 Pounds



OUR PRICE
\$1.85 Per 100 Pounds

Here is the greatest bargain ever offered in Barb Wire—absolutely the lowest prices ever before made. We quote Barb Wire both galvanized and painted. Some of the galvanized barb wire is not strictly first class, owing to the fact it may have an occasional defect in the galvanizing or the galvanizing may be spotted in places, or part of it may be somewhat black, but for every practical purpose it is just as good as regular galvanized barb wire. The prices offered are for prompt acceptance and subject to change. The barbs are spaced 3 inches and 5 inches apart. When sending us your order be sure to specify which kind you want. The 3 inch is intended for hog wire and the 5 inch for cattle wire.

It is put up in catch weight reels. By that we mean reels containing anywhere from 95 to 120 lbs. to the reel, and therefore it will be billed at the prices quoted per 100 lbs., and not by the rod.

We urge you to get your order in at once, to take advantage of these low prices. It is all 2-pointed Barb Wire. All this material is shipped from our main headquarters at Chicago; and our prices are f. o. b. cars Chicago.

Lot 2-BM-1. Galvanized Barb Wire. 2-Point Barbs 3 In. Apart. Made of No. 12 Wire				Lot 2-BM-3. Painted Barb Wire Barbs. 3-Inches Apart. Made of No. 12 Wire			
In lots of 4000 lbs.	Per 100 lbs.	\$2.00		In Lots of 4,000 lbs.	Per 100 lbs.	\$1.85	
In lots of 3000 lbs.	Per 100 lbs.	\$2.05		In Lots of 3,000 lbs.	Per 100 lbs.	\$1.90	
In lots of 2000 lbs.	Per 100 lbs.	2.10		In Lots of 2,000 lbs.	Per 100 lbs.	1.95	
In lots of 1000 lbs.	Per 100 lbs.	2.15		In Lots of 1,000 lbs.	Per 100 lbs.	2.00	
In lots of 500 lbs.	Per 100 lbs.	2.20		In Lots of 500 lbs.	Per 100 lbs.	2.05	
Less than 500 lbs.	Per 100 lbs.	2.25		Less than 500 lbs.	Per 100 lbs.	2.10	
Lot 2-BM-2. Galvanized Barb Wire. Barbs 5 Inches Apart. Made of No. 12 Wire				Lot 2-BM-4. Painted Barb Wire Barbs. 5-Inches Apart. Made of No. 12 Wire			
In lots of 4000 lbs.	Per 100 lbs.	\$2.00		In lots of 4,000 lbs.	Per 100 lbs.	\$1.85	
In lots of 3000 lbs.	Per 100 lbs.	\$2.05		In lots of 3,000 lbs.	Per 100 lbs.	\$1.90	
In lots of 2000 lbs.	Per 100 lbs.	2.10		In lots of 2,000 lbs.	Per 100 lbs.	1.95	
In lots of 1000 lbs.	Per 100 lbs.	2.15		In lots of 1,000 lbs.	Per 100 lbs.	2.00	
In lots of 500 lbs.	Per 100 lbs.	2.20		In lots of 500 lbs.	Per 100 lbs.	2.05	
Less than 500 lbs.	Per 100 lbs.	2.25		Less than 500 lbs.	Per 100 lbs.	2.10	

REGULAR BARB WIRE


LOT No. 2-F-9. We have in stock at this time several carloads of high grade, full weight Barbed Wire. This is very heavy galvanized material and is put up on reels containing about 100 lbs. It is sold at so much per 100 pounds and not by the reel. This Barbed Wire is made of No. 12 galvanized wire and the Barbs are both 3 inches and 5 inches apart. Our price on this wire, while it lasts, in any quantity, per 100 pounds is.....\$2.36

156.....We have Everything in Wire. Send for complete Catalog

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Write Michaelson For Paint Information—He Knows

26-in. HOG FENCE, 15c Per Rod



Here is a fine, heavy weight, smooth spring wire galvanized Hog Fencing, built and made of the strongest material possible. It is absolutely correct in every

way and the strongest all around Hog Fencing on the market. Do not confuse it with any of the cheap priced fencing made of light wire being offered, as in buying this fence you get weight to the rod.

This fencing weighs practically 6 pounds to the rod which is easily from 10 to 20 per cent heavier than a similar fence, and furthermore, our price that we are offering this fencing at is lower than that asked for the very cheapest kind of fence. Compare our weights with others and you will readily see that you are getting a bargain.

As a matter of fact, if you were to buy the wire in the fence alone, it would cost you more than it would for our fence (besides the cost of manufacture) per rod. The stays on this fence are spaced 6 and 12 inches apart, which makes a first class all around Hog and Field Fence. This is a Fence built for continuous and lasting service, and is the kind of

a fence every up-to-date owner ought to buy.

This Fence is made of 7 line wires, stays spaced 12 inches apart. Top and bottom wires are No. 9, and intermediate wires are No. 11. Stay wires are all No. 12. Put up in 20, 40 and 60-rod rolls.

Lot No. 2-G-1005. Stays spaced 12 inches apart, approximate weight per 100 rods, 680 pounds. Per rod.....

15c

Lot No. 2-G-1009. Stays spaced 6 inches apart, approximate weight per 100 rods, 850 pounds. Per rod.....

21c

We can also furnish this same style of Fencing in the following sizes, constructed with the same size wire as above described:

Lot No. 2-G-1001. 20 inch Hog Fence. 6 Line Wires. Stays spaced 12 inches apart. Approximate weight per 100 rods, 470 pounds. Per rod.....

13c

Lot No. 2-G-1015. 32 inch Sheep Fence. 8 Line Wires. Stays spaced 12 inches apart. Approximate weight per 100 rods, 780 pounds. Per rod.....

20c

Lot No. 2-G-1019. 39 inch Horse and Sheep Fence. 9 Line Wires. Stays spaced 12 inches apart. Approximate weight per 100 rods, 880 lbs. Per rod.....

23c

Lot No. 10-G-1023. 47 inch Stock Fence. 10 Line Wires. Stays spaced 12 inches apart. Approximate weight per 100 rods, 990 pounds. Per rod.....

27c

Lot No. 2-G-1003. 20 inch Hog Fence. 6 Line Wires. Stays spaced 12 inches apart. Approximate weight, per 100 rods, 720 pounds. Per rod.....

17c

Lot No. 2-G-1017. 32 inch Sheep Wire. 8 Line Wires. Stays spaced 6 inches apart. Approximate weight per 100 rods, 980 pounds. Per rod.....

26c

Lot No. 2-G-1021. 39 inch Horse and Sheep Fence. 9 Line Wires. Stays spaced 6 inches apart. Approximate weight per 100 rods, 1,120 lbs. Per rod.....

30c

Lot No. 2-G-1025. 47 inch Stock Fence. 10 Line Wires. Stays spaced 6 inches apart. Approximate weight per 100 rods, 1,270 pounds. Per rod.....

35c

CHICAGO HOUSE WRECKING CO.
35th and Iron Sts., Chicago.

Special Prices on Cemetery Enclosures and Iron Fencing.

157

\$22⁴⁵

BUYS THIS IDEAL OAK CABINET

Perfection seems to be achieved in this cabinet. Of wonderful convenience, utility and attractiveness. A great labor and time economizer.

\$10.00 Saved You. This is a conservative estimate, as many dealers ask \$12.00 and \$15.00 more than our wrecking price. We secured several hundred of these desirable cabinets through a spot cash purchase. You may not be interested in all of the details of this wonderful deal, but you must be interested in the big saving we can now offer you as its direct result.

You are bound to have a good kitchen cabinet sooner or later. Buy now, and get the use of it for each remaining day of your life.

One of the many valuable features is the nickeloid sliding extension table top. This comes out automatically when the front is slightly raised. The metal top is rust and germ resisting; handsome, sanitary, convenient and most easily kept clean. Measures 28 by 42 inches. Bound with oak finishing strips on front and sides.

A Few Good Points.

1. Ventilating cooling cupboard.
2. White enameled interior.
3. Swinging all metal flour bin.
4. Cleanable sifter attachment and glass front.
5. First-class clock.
6. Sanitary tinned wire shelves.
7. Pressed glass tea, coffee and spice jars, also graduating measuring cup.
8. Two compartment metal cake and bread drawer.
9. Frosted glass canopy doors.
10. Figured oak throughout.



Save Time, Steps, Waste, Space & Money

TOP is divided into three sections, the interiors of which are white enameled with four coats of lustrous, hard white enamel. At the right is a roomy cooling cupboard with two sanitary tinned wire shelves. The lower part of door is fitted with an iron ring for holding the glass sugar bin. This sanitary receptacle is fitted with a valve and any desired quantity of sugar can be obtained instantly. Back of the sugar jar is a half width shelf for holding the five pressed glass spice canisters; also furnished. The left hand door has a wire rack to hold the tea and coffee canisters supplied as shown. A graduated glass measuring cup is also supplied. The left hand compartment contains the swinging flour bin. The illustration shows this pulled forward and down ready for filling. Note the simplicity and convenience. This entire flour bin is of metal, white enameled on exterior. Sifter attachment easily removed for cleaning purposes. Glass front enables you to tell at a glance how much flour you have on hand. Capacity about 50 lbs. Center cupboard has three stationary, white enameled shelves. Clock is in plain view and wound from the inside, guaranteed a first class time keeper. Handy open compartment below center cupboard. Canopy when closed measures 12 inches front to back. Doors have neat brass plated spring catches.

BASE is roomy and unusually practical. 28 by 42 inch automatic sliding nickeloid top as described above. Can be removed when desired. Extra top below makes it dust-proof. One reversible sliding chopping board, smoothly finished. Upper drawer is divided into three compartments for knives, forks and spoons, or other articles. Second drawer is not divided. Lower drawer is of full tinned metal with a tight, automatically opening and closing cover to keep out dust and vermin, or prevent bread drying out. The open compartment is exceedingly roomy and has a tinned wire sliding shelf, fitted so it can not tip over when drawn out. Door to this compartment has two plate or cover racks, as shown. Large paneled door, bottom, top and ends are of built-up stock to prevent warping.

General construction is extra good, no details which go to assure satisfactory service being slighted. The finish is a dull waterproof golden, attractive and especially fit for the steam, dampness and excessive heat which alternate in most kitchens. Rounded corners and edges on top, legs, etc. Good casters. Total height, 72 inches. Base height, 34 inches. Shipped from point of purchase in Indiana. Weight, 255 lbs. **\$22.45** I-G-3730. Price, with all articles mentioned in description.



I-G-3730 CLOSED.

Note its compactness and attractiveness.



1913 MODEL-Rounding Corner-White Enamel Lined

SANITAX
OAK REFRIGERATORS

\$4.85
And Upwards



**STYLES,
SIZES AND
PRICES
TO SUIT
EVERY
TASTE,
NEED OR
PURSE**



The 1913 Style "Sanitax" Refrigerator is shown in the above illustrations. Special attention is called to the new, artistic, rounding corner design. This gives a trim, solid, compact and graceful effect which cannot be shown in any illustration. Nothing is spared which will give it a handsome appearance, extreme solidity and long life. The case is made of **Solid Oak**, attractively paneled as shown. Being made of thoroughly seasoned and kiln-dried stock it cannot warp, twist, or get out of shape. The case is tongued and grooved at every joint, and an air-tight fit and absolute insulation are thereby assured. The oak used is figured white oak, given the new golden tint by means of two coats of extra quality coach varnish, finished a high gloss furniture finish.

White Enamel Interior Be sure to order a "Sanitax" Refrigerator with a white enameled provision chamber. This white enamel consists of three thick coats, smoothly applied and baked to a hard, flinty consistency. The purity, the cleanliness, the economy, and the beauty of this will appeal strongly to every housewife. Not only are the bottom, sides and back of the provision chamber white enameled, but so are the door lining, drip trap and removable drain pipe. The enamel is applied by a special European process and is entirely different from white paint and cold water enamels which are bound to chip and crack. This white enamel is clear, dazzling white, elegant to behold, and is guaranteed to keep its color. It is entirely without odor and is not absorbent, consequently is germ-proof and cannot catch or retain any odor. It contains no poisonous substances. It is applied with extreme care over heavy sheet steel and is guaranteed in every way. All white enameled boxes have the new non-rusting wire shelves.

The Circulation is fully explained on the Introductory page of Refrigerators. Be sure and read this carefully, as nothing is of more importance than free, unimpeded circulation between the ice and food compartments. The fact that pure cold air from the ice reaches every part of the food chamber assures an extremely cold, even temperature. The ventilation is scarcely more important than the condensation by means of which the impurities, foul odors, etc., are thrown off and carried out. All condensing surfaces are located inside of the ice chamber and the result is that the stream of air passing from the ice is at all times dry. This means that your fruits will be luscious and your milk sweet, pure and free from taint at all times.

30-Day Trial Privilege Our "Sanitax" refrigerators are all sold with the understanding that, if after using one for 30 days, you find it imperfect in materials, construction or workmanship, it may be returned to us at our expense and your money will be refunded.

Every Refrigerator Needs a thorough cleansing once in a while, and the Sanitax is no exception. The illustration above shows how readily and thoroughly this can be done. Everything in the provision chamber can be removed instantly and easily. The shelves are of transversely woven wire, retinned and rust-resisting. Do not retard free circulation. There are no crevices or cracks difficult to get at or clean and there are no places for foodstuffs or germs to lodge. The drain pipe is shown on the floor in front of the refrigerator. The lower end of this is fitted with a removable cap which catches impurities which might not pass the trap below. The handsome galvanized steel lining of the ice compartment is well shown on the illustration of the top door, which is shown open. The heavy ice rack is of the same material, deeply corrugated for condensing purposes. The food and ice compartments are connected with ample air space to permit absolutely free circulation.

Absolute Insulation is derived from the perfect combination of scientifically approved non-conducting materials, which are fully described on the first refrigerator page. The ice-saving properties of these refrigerators have been tested in thousands of homes and is not merely theoretical, but practical. The top opening, one provision door model shown above, is one of the time-tried, very satisfactory styles suitable for most ordinary requirements. We especially urge the purchase of a large size refrigerator, as tests prove these to be the most economical in the use of ice.

The Hardware, hinges, lock, name plate, door catch and lid lifter, are made of solid cast brass, finished with a lasting Roman gold finish, which harmonizes beautifully with the golden oak. Faucet and tumbler holder (with which all models having water coolers are equipped) are nickel plated. The waste pipe is fitted below with a patent drip cap, which is described and illustrated on the first refrigerator page. The baseboard is hinged at the top and swings upwards to permit the removal of waste water pan. The casters are of a patent "grip-neck" style, they revolve and slide easily and will not fall out when the refrigerator is lifted. Extra strength and attractiveness is afforded by the moulding extending around the base. This is ordinarily found only in very high priced refrigerators.

Immediate Shipment We carry a large stock of these refrigerators in Chicago, and are at all times in position to make immediate shipment from here as well as from our Southern and Eastern warehouses. Each refrigerator is inspected three times, carefully crated, and is guaranteed to reach you in the same perfect condition as it leaves the factory. Refrigerators take second class rate of freight, and as we give all shipping weights, you can readily figure what the style you wish will cost laid down at a point near you.

Catalogue Number.	OUTSIDE MEASUREMENTS.			INSIDE MEASUREMENTS.		Ice Capacity	Shipping Weight.	Price Galvanized Lining and Shelves	Price White Enameled, Wire Shelves
	Height.	Width.	Depth.	Ice Chamber	Food Chamber.				
1-G-4961.	38 in.	20 in.	13½ in.			25 lbs.	85 lbs.	\$ 4.85	
1-G-4962.	39 in.	23 in.	15 in.	15x10x8½ in.	18x10x15 in.	40 lbs.	110 lbs.	6.15	\$6.85
1-G-4963.	40 in.	24 in.	16 in.	16x11x9 in.	19x11x16 in.	50 lbs.	120 lbs.	8.05	8.85
1-G-4964.	41 in.	26 in.	17 in.	18x12x9½ in.	21x12x16 in.	65 lbs.	125 lbs.	9.85	10.55
1-G-4965.	43 in.	28 in.	17½ in.	20x13x9½ in.	23x13x18 in.	80 lbs.	140 lbs.	10.30	11.15
1-G-4966.	46 in.	31 in.	18½ in.	23x14x12 in.	25x14x18 in.	100 lbs.	175 lbs.	11.95	12.75
1-G-4967.	48 in.	33 in.	20 in.	25x15x12 in.	27x15x21 in.	140 lbs.	210 lbs.	13.50	14.45
1-G-4960.	48 in.	36 in.	20 in.	28x15x12 in.	30x15x21 in.	160 lbs.	220 lbs.	15.90	16.85


Porcelain Lined Water Coolers can be supplied in any top opening, white enamel lined refrigerators. The additional cost for these water coolers together with the nickel plated faucet, tumbler holder, etc., on the outside is \$2.00 additional for the numbers 1-G-4962, 3 and 4;

\$2.20 additional for the four largest sizes. The ice capacity is reduced from 10 to 20 lbs. when water cooler is inserted. For further information see the more complete description on the preceding page. Be sure to get a refrigerator large enough. No. 1-G-4960 has two doors to the food chamber.



24⁷⁵ BUYS 1¹/₂ HORSE POWER HUMMER

**Strong—
Compact**



GASOLINE ENGINE Complete Ready To Run

"Will Outpump Any Windmill"
"Ideal to Run a Washing Machine"
"Just the Power to Run a Sprayer"
"Easily Pulls your Fanning Mill"
"Will Turn a Grindstone all Day"
"Often Used to Run Horse Clippers"
"Splendid for Printing Office"
Will operate any Hand Power or Foot Power Machine Made

What could be more convenient than to have a small engine that can be easily moved around to do the many jobs you have? You cannot afford to be without a gasoline engine when you can get one at such a low price.

Order one today at this unheard-of price It will put your farm on a business basis and save you time and money.

Let "The HUMMER" do your work. It will run the cream separator and washing machine, as well as pump water and all other light chores around the house and barn. It is always ready and will run all day with little attention. Sold on thirty days' trial and a five-year guarantee on material and workmanship.

We can furnish any size engine needed for your work. If there is any doubt in your mind as to just what size gasoline engine to buy, write us just what machinery you want to run, what work you have to do, giving full particulars, and we will tell you just what engine you should buy to get the best results.

Ideal for Pumping

The "Old Oaken Bucket" is no more. It was replaced years ago by the pump and windmill and now the windmill is a thing of the past, the gasoline engine is taking its place. A windmill without wind may be a "thing of beauty" but it is of very little help to the farmer during the hot, sultry summer day when his stock is panting for water and he finds it necessary to stand an hour or two daily to quench their thirst. A Gasoline Engine, however, is always ready in any kind of weather, rain or shine, wind or calm.

Our Binding Guarantee

THIS GUARANTEE means that every engine we send out is guaranteed for FIVE years. Should at any time within the first five years you use this "Hummer" engine, you find any flaw in the material used in its construction, or if you find a defect in any part on account of improper construction, we will replace this part free of charge at our factory. We will also allow you to try this engine out on your own place, on your own work, for 30 days. If at the end of this trial period you do not find it just as represented and in perfect working order, notify us at once and we will gladly send you shipping instructions for its return. We will cheerfully refund money and pay freight both ways on any engine not satisfactory.

Starts Easy

In putting this engine on the market, we have had two distinct points in view; first, simplicity; second, easy starting. For this reason we have made this engine of small bore and stroke. It is very often the case when the men folks are away, then the women and children must take care of the stock, and the heavy cumbersome engines are not fit for such use, no matter how reliable they are; it is absolutely impossible for a woman or a ten year old boy to swing a large heavy gasoline engine against the compression.

No. 8-E-2128 — 1¹/₂ H. P. "Hummer" Water-Cooled Gasoline Engine \$24.75

General Specifications of 1¹/₂ H. P. Gasoline Engine

Hummer—Is a four cycle 1¹/₂ H. P. self-contained horizontal, hopper cooled, mounted on heavy wood skids, with battery box.

Cylinder—3¹/₄ bore by 4-in. stroke.

Valves—Are large, easily accessible and operate by a very simple valve gear.

Ignition—Jump spark, hit and miss type. We use a standard automobile spark plug.

Pulley—4-inch flat face, 4¹/₂-inch diameter, iron.

Automatic Governor—Takes care of any variation in the load quickly and automatically. This governor automatically cuts

off the supply of gas and electric current when engine is on light load, and this is why it is the most economical one to run.

Muffler—Deadens the noise of the engine without loss of power or back pressure.

Fly Wheels—Weight 40 pounds. Carefully counterbalanced, no vibration.

Speed—Normal, 400 revolutions per minute; can be decreased to 300 or increased to 600 revolutions per minute.

Weight—Engine complete weighs 230 pounds. No unnecessary weight. Light, strong, compact and durable.

Instantaneous Automatic Water Heater

\$37⁵⁰

The "HARRIS" Gas Heater GREATEST OF MODERN INVENTIONS

\$37⁵⁰

Works automatically—just open faucet and gas is turned on—close faucet and gas is turned off.

Furnishes hot water instantaneously—open your faucet and you have hot water. No waste of gas—no waste of hot water. Always ready—hot water on tap day and night, winter and summer.

Price Within Your Reach

There is now no excuse for your not having a constant and inexhaustible supply of hot water day and night, winter and summer, by the simple act of turning a faucet. Hot water is not a luxury but a necessity. Not an inch of gas is wasted. Every bit of gas consumed actually goes into the water.

WHAT THE "HARRIS" HEATER MEANS TO YOU

One by one, modern improvements have been supplied to you. This heater is the last word. You have thrown away your kerosene lamp and now read by gas or electricity. You have furnace or hot water heat in place of coal stoves. You have a modern bathroom outfit with sanitary plumbing. Now add this latest improvement and you will truly have all modern conveniences.

There is no gas wasted with our heater. All the heat in every foot of gas goes into the water. None is lost by radiation from the sides of the heater. The jacket is made double with an intermediate layer of asbestos so that you can place your hand on the jacket at any time and it can hardly be warmed.

Only the Water Needed is Heated

You only heat the water you actually need. You are not wasting gas by keeping water in a storage tank hot all the time.

You want hot water, but you do not want to waste your money. This heater will pay for itself within a year's time by the actual saving in the amount of gas consumed.

You can also place your hand on top of the exhaust pipe and it will not burn, which shows that all the gas you are burning is actually being used and no heat is being wasted through the flue.

The pilot light of our heater is the smallest in the world, consuming less than one thousand feet of gas per year. We guarantee this heater to furnish two gallons of water, raised 70 degrees in temperature in one minute, and we also guarantee that our heater furnishes a gallon of water to every foot of gas used! With gas at \$1.00 per thousand this would mean 10 gallons of hot water for one cent. Where gas is cheaper the cost of operation is still further reduced.

Easy to Connect

No expert mechanic or professional plumber required for installing our heater. Nothing to do but connect a few pipes. Heater furnished with unions already in place. Simply place the heater in basement, kitchen or bathroom, wherever preferred, and connect water and gas pipes to the heater. Heater can be placed anywhere, regardless of present heating arrangements. If you already have hot water connections to furnace, boiler, kitchen range, gas range or range boiler, our heater is coupled up without disturbing your present piping. Full instructions furnished. No chance for mistake.

Every part of our heater is jig made. Each part of heater is positively standard and interchangeable. All parts guaranteed to fit all our heaters. This positively protects you in case of accident of any kind requiring repair to heater. We can replace any part of heater such as valve, burner, jacket, etc., and guarantee that the new part will fit accurately. We cannot too strongly impress upon you the importance of this feature. Repairs on higher priced heaters now in vogue, are exceedingly troublesome, but on our heater, you are fully protected.

CAUTION

The capacity of our heater is guaranteed to be two gallons of water per minute. It is therefore adequate for all requirements of an ordinary residence, and for one family. We recommend a separate heater for each family where there are several apartments in one building.

Simple in Construction

In order to be really useful, a heater of this kind must be simple—so simple that the average person can install it, operate it and repair it in case of accident. No complicated mechanism, delicate valves or intricate contrivances can be allowed. Our heater is reduced to bedrock simplicity. There is only one valve. This is the valve which controls the water supply and the gas supply. When the faucet is opened the water enters through the top compartment and its pressure forces down the piston rod to which the gas valve is attached. The water valve and the gas valve operate together. They open and close together. This in a nutshell, represents the operation of our heater. Nothing could be simpler. Adaptable for all kinds of pressure. City pressure from 5 to 50 pounds and even gravity pressure. Valve is adjustable to varying pressure by simple turning of screw in the rod connecting the water and gas shut-off valves.

Our heater is guaranteed to act instantaneously and to secure a greater amount of heat units out of the flame, than any kind of gas heater ever manufactured. This has been demonstrated by actual test. You can prove it by holding your hand over the flue. It will not burn, showing conclusively that practically every bit of heat goes into the water. Our heater has 90 feet of copper coil, tested under 350 pounds hydrostatic pressure. The current of the water being downwards, protects these coils from being clogged up by sediment. An aluminum baffle pan placed under these coils protects the burners from moisture or condensation dripping into the flame. Every point of possible difficulty in connection with heaters of this kind has been taken into consideration and fully provided against.

HOT WATER

Our Binding Guarantee Covers This Heater





You make no mistake buying our "Harris" Heater. Our Two Million Dollar Capital stands back of it. Guaranteed the cheapest, simplest and most efficient automatic instantaneous gas heater on the market. We replace free of charge any part of heater within one year from date of purchase. You are fully protected.

When ordering heater be sure and answer the following questions.

- First. Have you natural or artificial gas?
- Second. Have you direct or gravity pressure?
- Third. If gravity pressure, state the fall in feet from bottom of tank to highest faucet.
- Fourth. How many fixtures (bathtub, lavatory, sink, laundry tub) are to be supplied?
- Fifth. State distance of each fixture from heater.

Careful reply to these questions will enable us to adjust our heater to your conditions and guarantee greatest efficiency and most satisfactory results.

Order by Lot No. 5F10; Price \$37.50




OUR GREAT LUMBER DEPARTMENT

Here are pictures of interesting points about our great Lumber Department. Every single article in both Lumber and Mill Work is guaranteed absolutely brand new. There is not a stick of used Lumber in our stock. It is all guaranteed first class and cannot be equaled at the price by any dealer in lumber and building material anywhere.


**MILLIONS OF FEET
OF BRAND NEW
LUMBER.**




**CAPACITY
50 CARS PER DAY.**




**OUR PRICES SAVE
YOU 35 to 50
PER CENT.**




**Yard scene showing
dry sheds in distance.**






Storage Yards.




**An alley way in our
mammoth lumber yards.**



In our Lumber Dept. Office we employ a vast staff of estimators & Salesmen. This picture shows just a small portion of the office.

**Interior view of one
of our Dry Sheds.**



**EVERY PIECE OF STOCK IS
GUARANTEED BRAND NEW.**

**NO WRECKED OR SECOND
HAND LUMBER FOR SALE.**

The above views will give you an idea of the magnitude of our Lumber and Building Material Departments where we employ in the office and yards—hundreds of people. It is the largest Department of its kind in the world, and is a pleasant surprise to visitors, many of whom expressed the opinion that while they expected to see a large Department, they were much surprised at the immensity of our Lumber and Millwork stocks.

CHICAGO HOUSE WRECKING CO., 35th & IRON STREETS, CHICAGO.